



October 1, 2018

Tree of Knowledge
622 Buffalo Lake Rd.
Sanford, NC

Harnett County Government Complex
307 Cornelius Harnett Boulevard
Lillington, NC 27546

ph: 910-893-7550
fax: 910-893-9429

Mr. and Mrs. Hicks,

I have received the application for your proposed child care center. The application has been approved with the following conditions:

1. The hand sink in the food preparation area in the 0-12 month old room will be used for the staff handwashing prior to food preparation or food service. This sink will not be used for general hand washing or washing utensils, toys or other objects.
2. The hand sinks in the diaper changing area in the 0-12 month old room and the 2-3 year old room will be used for hand washing of the staff and the children after diaper changing. This sink will not be used for general hand washing or washing utensils, toys or other objects.
3. Provide a splashguard between the food prep hand washing sink and the counter top.
4. Only single-use and single-service utensils only.
5. Because domestic refrigeration is used, potentially hazardous foods may not be prepared more than 12 hours in advance or be heated and re-served on another day.
6. Decks, fences, playground equipment, and other products constructed or installed after September 1, 2006 shall not be made from chromated copper arsenate (CCA) pressure-treated wood unless the use of CCA-treated wood is for an approved use listed on the CCA product label and allowed under the US EPA Supplemental Guidance on Interpretation of Revised Chromated Copper Arsenate (CCA) Wood Preservative Label, as amended. In areas accessible to children, CCA-treated wood decks, playground and recreational equipment, and structures installed or constructed: (1) prior to January 1, 2005; or (2) where EPA allows the use of CCA-treated wood, shall be sealed using an oil-based, semi-transparent sealant; oil-based clear stain; or a water-based clear stain applied at least once every two years. At the time of the initial sealant or stain application and whenever more than two years has passed since the previous sealant application, soil under such wood shall be: (1) removed and replaced with similar material; (2) covered with at least four inches of soil, gravel, sand, sod, or other vegetation; or (3) otherwise made inaccessible.

The review of this facility was made using 15 A NCAC 18A .2800, "Rules Governing the Sanitation of Child Care Centers." This review does not cover any other aspects of construction regulated by other jurisdictions.

Sincerely,

Gale Violette Greene, REHS
Food and Lodging Program Specialist
Environmental Health Section
Harnett County Health Dept.