

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

**PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET**

**SUBDIVISION: DOLLAR GENERAL**

**LOT US HWY. 401**

**INITIAL SYSTEM: APPROVED 25% REDUCTION**

**REPAIR: APPROVED 25% REDUCTIO**

**DISTRIBUTION: SERIAL**

**DISTRIBUTION: SERIAL**

**BENCHMARK: 100.0**

**LOCATION: TOP FIRE HYDRANT**

**DAILY FLOW: 200 GPD**

**LTAR: 0.4 GPD/FT2**

<u>LINE</u>	<u>FLAG COLOR</u>	<u>ELEVATION</u>	<u>LENGTH</u>
1	B	106.17	42'
2	W	105.92	42'
3	P	105.08	42'
4	B	105.00	42'
5	W	104.67	42'
6	P	104.50	42'

**BY M. EAKER**

**DATE 8/6/18**

**TYPICAL PROFILE**

**THERE SHALL BE NO GRADING,**

**0-12 LS (VFR, WGR)**

**CUTTING, LOGGING OR OTHER SOIL**

**12-48 SCL (VFR, WGR)**

**DISTURBANCE IN SEPTIC AREA**

**CR2>26". Install drainfield at 12 inches**

**ADD 6" APPROVED FILL COVER**

