

DAVID MILLER, PE

6300 Creedmoor Rd, STE 170#363

Raleigh, NC 27612

(919) 422-8932 (Office); DAVE@DMA-PA.COM

January 8, 2020

Anderson Creek Partners LP

Attn.: Andy Barr and Eric Linn (910)813-0662

919-454-4680

Anderson Creek, NC

E-mailed: andybarr40@yahoo.com

RE: Engineering - Site Observations - Fill Testing
Anderson Creek Subdivision - 6755 Overhills Road
Spring Lake, Harnett County, NC
Project No.: 19DDM-1212G

To Whom It May Concern:

Representatives of the undersigned's arrived on-site from 12-19-19 to 1-6-20 to perform density testing for the backfill behind the wall at the above referenced site. Based on the field and laboratory testing the fill soils were adequately compacted at the tested locations (at least 95% of the Standard Proctor Dry Density). The American Standard Test Methods (ASTM) 698 and Special Publication 399 testing were performed in general accordance with these requirements.

Sincerely,

David Miller, PE

DEM/19DDM-1212G

