

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: MF1900143-B
10 Unit-3rd Floor
Fairway Pointe Condos
Building 17
Unit 201

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Pages or sheets covered by this seal: I44485509 thru I44485509

My license renewal date for the state of North Carolina is December 31, 2021.

North Carolina COA: C-0844




January 25, 2021

Sevier, Scott

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.


Job MF1900143-B	Truss F19	Truss Type Floor	Qty 4	Ply 1	10 Unit-3rd Floor	1 UNIT JV 1 OF 1	I44485509
--------------------	--------------	---------------------	----------	----------	-------------------	---------------------	-----------

Carter Components (Sanford), Sanford, NC - 27332, 8.430 s Nov 30 2020 MiTek Industries, Inc. Thu Jan 21 16:17:02 2021 Page 1
 ID:VEQ8yXJsehX_YGARpJvWvzB?VO-SoOzeB8QnbHb6yu6JjrT0pOnoz7Rj8U3iqg5H9zt4WV



1" DEEP X 3" WIDE NOTCH IN TOP CHORD, WEB 5-17, AND BOTTOM CHORD STARTING AT 6" FROM THE RIGHT END OF TRUSS AS SHOWN

SCAB AND TRUSS TO FIT IN 5" HANGER SEAT



SHOP FABRICATE SCAB TRUSS AS SHOWN ON SHEET (2 OF 2). ATTACH SCAB TRUSS TO ONE FACE OF EXISTING TRUSS WITH ONE ROW OF (0.131" X 3") NAILS SPACED 3" O.C. IN ALL ALIGNING MEMBERS UNLESS OTHERWISE INDICATED.

Plate Offsets (X,Y)--	[4:0-1-8,Edge], [5:0-1-8,Edge], [12:0-1-8,Edge], [13:0-1-8,Edge]
-----------------------	--

LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 40.0	1-7-3	TC 0.76	in (loc) l/defl L/d	MT20	244/190
TCDL 10.0	Plate Grip DOL 1.00	BC 0.89	Vert(LL) -0.14 19-20 >999 480		
BCLL 0.0	Lumber DOL 1.00	WB 0.42	Vert(CT) -0.19 19-20 >976 360		
BCDL 5.0	Rep Stress Incr YES	Matrix-S	Horz(CT) 0.04 17 n/a n/a		
	Code IBC2015/TPI2014			Weight: 151 lb	FT = 20%F, 11%E

LUMBER-	BRACING-
TOP CHORD 2x4 SP No.2(flat)	TOP CHORD Sheathed or 6-0-0 oc purlins, except end verticals.
BOT CHORD 2x4 SP No.1(flat)	BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
WEBS 2x4 SP No.3(flat)	6-0-0 oc bracing: 26-27,24-26,23-24,22-23.

REACTIONS. (size) 32=0-3-8, 24=0-3-8, 17=Mechanical
 Max Grav 32=586(LC 3), 24=1578(LC 1), 17=597(LC 4)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD 1-32=-269/32, 16-17=-269/28, 2-3=-1225/0, 3-4=-1785/0, 4-5=-1847/0, 5-6=-1419/150, 6-7=-461/549, 7-8=0/1713, 8-10=0/1713, 10-11=-526/496, 11-12=-1472/109, 12-13=-1890/0, 13-14=-1816/0, 14-15=-1244/0
BOT CHORD 31-32=0/783, 30-31=0/1645, 29-30=0/1847, 28-29=0/1847, 27-28=0/1847, 26-27=-335/1056, 24-26=-852/0, 23-24=-758/11, 22-23=-288/1116, 21-22=0/1890, 20-21=0/1890, 19-20=0/1890, 18-19=0/1669, 17-18=0/797
WEBS 8-24=-279/48, 2-32=-946/0, 2-31=0/575, 3-31=-547/0, 7-24=-1210/0, 7-26=0/878, 6-26=-837/0, 6-27=0/552, 5-27=-730/0, 10-24=-1291/0, 10-23=0/868, 11-23=-826/0, 11-22=0/539, 12-22=-716/0, 15-17=-964/0, 15-18=0/582, 14-18=-553/0

- NOTES-**
- Unbalanced floor live loads have been considered for this design.
 - All plates are 3x5 MT20 unless otherwise indicated.
 - Refer to girder(s) for truss to truss connections.
 - This truss has been designed for a moving concentrated load of 250.0lb live and 10.0lb dead located at all mid panels and at all panel points along the Top Chord, nonconcurrent with any other live loads.
 - Recommend 2x6 strongbacks, on edge, spaced at 10-0-0 oc and fastened to each truss with 3-10d (0.131" X 3") nails. Strongbacks to be attached to walls at their outer ends or restrained by other means.
 - CAUTION, Do not erect truss backwards.



January 25, 2021

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.
 Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601



818 Soundside Road
 Edenton, NC 27932


Job MF1900143-B	Truss F19	Truss Type Floor	Qty 4	Ply 1	10 Unit-3rd Floor	I44485509
--------------------	--------------	---------------------	----------	----------	-------------------	-----------

Carter Components (Sanford),

Sanford, NC - 27332,

8.430 s Nov 30 2020 MiTek Industries, Inc. Thu Jan 21 16:17:02 2021 Page 2
ID:vEQ8yXJsehX_YGARPbjvWvzB?VO-SoOzeB8QnbHb6yu6JjrT0pONoz7RJ8U3iqg5H9zt4WV

FIELD SPLICE DETAIL



LUMBER-
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

- 1) All plates are 3x5 MT20 unless otherwise indicated.
- 2) The Fabrication Tolerance at joint 9 = 11%, joint 21 = 11%, joint 14 = 11%

PLATES **GRIP**
MT20 244/190

FT = 11%

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 5/19/2020 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see


ANSI/TPI1 Quality Criteria, DSB-89 and BCSI Building Component

Safety Information available from Truss Plate Institute, 2670 Crain Highway, Suite 203 Waldorf, MD 20601

ENGINEERING BY
TRENCO
A MiTek Affiliate

818 Soundside Road
Edenton, NC 27932

Job MF1900143-B	Truss F19X	Truss Type FLOOR	Qty 4	Ply 1	10 Unit-3rd Floor
--------------------	---------------	---------------------	----------	----------	-------------------




LUMBER- TOP CHORD 2x4 SP No.2 BOT CHORD 2x4 SP No.2 WEBS 2x4 SP No.3	1) All plates are 3x5 MT20 unless otherwise indicated. 2) The Fabrication Tolerance at joint 9 = 11%, joint 21 = 11%, joint 14 = 11%	PLATES MT20 GRIP 244/190 FT = 11%
--	---	---




Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.



This symbol indicates the required direction of slots in connector plates.

* Plate location details available in **MITek 20/20 software** or upon request.

PLATE SIZE

4 X 4


The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING




Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI 1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System

6-4-8
dimensions shown in ft-in-sixteenths
(Drawings not to scale)



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITteK® All Rights Reserved



MITek Engineering Reference Sheet: Mill-7473 rev. 5/19/2020



General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Rewriting pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.