

14. Do all doors have a minimum clear opening width of 32" (min. door width of 36") in the following locations:
- a. between occupied rooms and required exits? Yes No
 - b. exit doors leading to the exterior? Yes No

15. Are all doors in the line of exit travel a swinging door (side hinged)? Yes No

16. Do doors to rooms that accommodate more than 50 people swing in the direction of travel? (N/A applies if room accommodates less than 50 people) N/A Yes No

17.a Do all required egress and exit doors have single motion, self-unlocking type handle, lever, push pad, or panic hardware? Yes No

b. If room accomdates 100 or more people, do all required egress and exit doors have push pads or panic hardware? N/A Yes No

STAIRS (NOTE: If no stairs, interior or exterior, check N/A and go to Question 22. If applicable, all questions must be answered)

18.a Are all stairs serving 50 or more occupants at least 44 inches in width? N/A Yes No

b Are all stairs serving less than 50 occupants, at least 36" in width? N/A Yes No

19. Are all stairs with four or more steps provided with proper handrails and guardrails? Yes No

20. Are all interior stairs enclosed with 1-hour rated walls and 1-hour rated "B" labeled doors that are at least 36" wide? Yes No

21. Are the stair enclosure doors self-closing? Yes No

WALLS AND CEILINGS

22. a. Are all wall and ceiling coverings throughout building non-combustible? (Use of untreated combustible fiber boards, wood, and other combustible fiber boards, wood and other combustible finishes is prohibited). Yes No

b. Do interior wall and ceiling finish materials meet the flame spread ratings as required by the Minimum Interior Finish Classification Table, NCBC Yes No

23. Do ceilings in habitable rooms have a minimum of 7'-6" clear height? Yes No

HEATING SYSTEMS/MECHANICAL

24. Is the building free of unvented fuel burning or portable electric space heaters? Yes No

25. Have air conditioning, ventilation, heating, cooking, and other service equipment been inspected and approved by the appropriate inspectors? Yes No
Date Inspected 7-22-20

26. a. Is combustion and ventilation air for boiler or heater rooms taken directly from and discharged to the outside of the building? (N/A if electric heat is installed) N/A Yes No

b. If inside air is used for fuel-burning appliance does it meet the requirements of Chapter 7 of the North Carolina Mechanical Code. (N/A if inside air is not used) N/A Yes No

PLUMBING

27. Does the number of waterclosets and lavatories comply with the Plumbing Code as determined by the appropriate inspector? (1 watercloset per 15 children, 1 lavatory per 25 children) Yes No

Maximum # of persons allowed by plumbing facilities? 45
Date Inspected 7-22-20 30 R.H.