FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO: G20V36 CALC BY: A.R. 1/8/2021 DATE:

REVISED BY:

REVISION DATE:

FILE: bldg-v-1642-30-115-NC

STRUCTURAL CALCULATIONS

DESIGN LOADS

ROOF LIVE LOAD =

30 psf (Ground Snow Load = 5 psf)

ROOF DEAD LOAD =

6 psf

FLOOR LIVE LOAD =

100 psf

FLOOR DEAD LOAD BAY = 45 psf

C.H. MOSS, P.E. P.O. BOX 28

FLOOR DEAD LOAD EQUIPMENT = 30 psf

COVINGTON, GA 30015

POINT LOAD FROM VEHICLE = 2.25 kips

WIND SPEED =

115 mph Vult

(89 mph Vasd

EXPOSURE =

C

SITE CLASS =

D

SEISMIC DESIGN

CATEGORY =

STRUCTURAL MATERIAL

STRUCTURAL STEEL ASTM A-36-05 Fy = 36 ksi W-SHAPE STEEL ASTM A-992-06a Fy = 50 ksi

TUBULAR STEEL ASTM A-500-07 GRADE B Fy = 46 ksi

ROOF DECK ASTM A-653-07 Fy = 50 ksi

BOLTS ASTM A-307-04e01 Ft = 20 ksi Fv = 10 ksi

ANCHOR BOLTS A-307 -04e01 Fu = 58 ksi

REFERENCES

MANUAL OF STEEL CONSTRUCTION AISC (ASD) 15th Edition **INCLUDING - AISI/AISC 360-10** SPECIFICATION FOR THE DESIGN OF COLD-FORMED STEEL MEMBERS - AISI S100-12 2015 INTERNATIONAL BUILDING CODE **ASCE 7-10**

FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

ROOF DECK CALCULATION

CEILING DECK CALCULATION::

Note: Ceiling deck supports 24 GA Roof Decking

LL= **30**

DL= **6**

w= **42.0** #/ft (per (1) 14" panels)

psf

psf

try 20 ga roof deck w/4" deep deck ribs


Mmax(+)= 14.33 in-kips

Mmax(-)= **0.00** in-kips

fb= 21.89 ksi < allowable=30 ksi o.k

use 20 ga roof deck w/4" deep deck ribs

see last sheets of calculations for panel properties.



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36
CALC BY: A.R.
DATE: 1/8/2021

ROOF DECK CALCULATION

CEILING DECK CALCULATION::

Note: Ceiling deck supports 20 GA Roof Decking


LL= **30** psf DL= **6** psf

w= **47.9** #/ft(per 16" panel)

Mmax(+)= **4.32** in-kips Mmax(-)= **0.00** in-kips

fb= 13.92 ksi < allowable=30 ksi o.k

** use **20 ga** roof deck ** see next to last sheet for panel properties.



FREY-MOSS STRUCTURES

Sheetz's Inc.
Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

CAR WASH ROOF BEAM

RB1

dead load =	6	psf	end L=	0.00	ft
live load =	30	psf	span L=	13	ft

target end
$$Ix= defl(180)(100)/(Lx12) = 0$$
 in⁴ target span $Ix= defl(240)(100)/(Lx12) = 1$ in⁴

try	C5x6.7	lx (in^4)= 7.49	S (in^3)=	: 3	R1=1.87k
	unbraced -L (in) =	16	unbraced -L (in) =	16	
	(-)Mmax (k-in) =	25.83	(+)Mmax (k-in) =	13.16	R2=3.23k
	(-)Fb(ksi)=	23.8	(+)Fb(ksi)=	23.8	
	(-)fb(ksi)=	8.6	(+)fb(ksi)=	4.4	


target deflections:(in)

end due to DL+LL =L/180=	0.00	span due to DL+LL =L/240=	0.65
end due to DL =L/540=	0.00	span due to DL =L/720=	0.22

actual deflections:(in)

end due to DL+LL =	0.00	span due to DL+LL =	0.05
end due to DL =	0.00	span due to DL =	0.01

Use C5x6.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

G20V36 JOB NO: A.R. CALC BY: 1/8/2021 DATE:

CAR WASH ROOF BEAM

RB2

dead load =

6 psf end L=

0.00

ft ft

live load =

30 psf span L=

10

beam carries

1.3

ft tributary width w=

48 # / ft

end defl=

0 in/ 100^4

span defl= 0.00113 in/ 100⁴

target end Ix = defl(180)(100)/(Lx12) =

0 in⁴

target span Ix= defl(240)(100)/(Lx12) =

in⁴ 0

try **C5X6.7**

 $Ix (in^4) = 7.49$

 $S (in^3) = 3$

R1=1.73k

unbraced -L (in) =

16 4.18 unbraced -L (in) = 16

(-)Mmax(k-in) =(-)Fb(ksi)=

23.8

(+)Mmax (k-in) =(+)Fb(ksi)=

3.02 23.8

(-)fb(ksi)=

1.4

(+)fb(ksi)=

1.0

target deflections:(in)

end due to DL+LL =L/180=

0.00

span due to DL+LL =L/240=

0.50

end due to DL =L/540=

0.00

span due to DL =L/720=

0.17

actual deflections:(in)


end due to DL+LL = end due to DL =

0.00 0.00 span due to DL+LL =

span due to DL =

0.02 0.00

Use C5X6.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

EQUIPMENT ROOF BEAM:

RB3

dead load = 6 psf live load = 30 psf

end L= **0.00** ft span L= **11** ft

beam carries 4.0 ft tributary width w= 144 #/ft

end defl= **0** in/ 100^4

span defl= **0.002** in/ 100^4

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 0 in⁴

 $S(in^3) = 3$ R = 1.37ktry C5X6.7 $Ix (in^4) = 7.49$ unbraced -L (in) = 16unbraced -L (in) = 16 (+)Mmax (k-in) =13.1 (-)Mmax (k-in) =0 (-)Fb(ksi)= 23.8 (+)Fb(ksi)=23.8 (-)fb(ksi)= 0.0 (+)fb(ksi)=4.4


target deflections:(in)

end due to DL+LL =L/180= 0.00 span due to DL+LL =L/240= 0.55 end due to DL =L/540= 0.00 span due to DL =L/720= 0.18

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.03 end due to DL = 0.00 span due to DL = 0.00

Use C5X6.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

EQUIPMENT ROOF BEAM:

RB4

dead load = 6 psf end L= 0.00 ft live load = 30 psf span L= 7.75 ft

beam carries 2.0 ft tributary width w= 72 #/ft

end defl= **0** in/ 100⁴ span defl= **0.002** in/ 100⁴

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 1 in⁴

try **C5X6.7** $lx (in^4) = 7.49$ $S(in^3) = 3$ R1=0.22k unbraced -L (in) = 16 unbraced -L (in) = 16(-)Mmax (k-in) =(+)Mmax (k-in) =6.49 (-)Fb(ksi)= 23.8 (+)Fb(ksi)= 23.8 (-)fb(ksi)= 0.0 (+)fb(ksi)=2.2


target deflections:(in)

end due to DL+LL =L/180= 0.00 span due to DL+LL =L/240= 0.39 end due to DL =L/540= 0.00 span due to DL =L/720= 0.13

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.03 end due to DL = 0.00 span due to DL = 0.00

Use C5X6.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36

CALC BY: A.R.

DATE: 1/8/2021


FLOOR DECK CALCULATION

FLOOR DECK CALCULATION::

LL= 100 psf DL= 45 psf TL= 145.0 psf

Maximum Load Allowed = 153 psf o.k
Per F-Deck Properites Chart
22 GA with 3-Span Min.

Use 22 GA F-Deck



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

CAR WASH FLOOR PURLIN:

FP1

dead load =	45	psf	end L=	0.00	ft
live load =	100	psf	span L=	15.1	ft

target end
$$Ix= defl(180)(100)/(Lx12) = 0$$
 in⁴ target span $Ix= defl(360)(100)/(Lx12) = 16$ in⁴

try W6 x 15	lx (in^4)= 29.1	S (in^3)=	9.72	R1=3.26k
unbraced -L (in) =	16	unbraced -L (in) =	16	
(-)Mmax (k-in) =	0	(+)Mmax (k-in) =	164	
(-)Fb(ksi)=	23.8	(+)Fb(ksi)=	23.8	
(-)fb(ksi)=	0.0	(+)fb(ksi)=	16.8	


target deflections:(in)

end due to DL+LL =L/180=	0.00	span due to DL+LL =L/360=	0.50
end due to DL =L/540=	0.00	span due to DL =L/720=	0.25

actual deflections:(in)

end due to DL+LL =	0.00	span due to DL+LL =	0.28
end due to DL =	0.00	span due to DL =	0.09

Use W6 x 15 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

CAR WASH FLOOR PURLIN:

FP1

dead load =	45	psf	P1 =	2.25	kips
live load =	0	psf	span L=	15.1	ft

target end
$$Ix = defl(180)(100)/(Lx12) = 0$$
 in⁴ target span $Ix = defl(240)(100)/(Lx12) = 10$ in⁴


target deflections:(in)

end due to DL+LL =L/180=	0.15	span due to DL+LL =L/360=	0.50
end due to DL =L/540=	0.05	span due to DL =L/720=	0.25

actual deflections:(in)

end due to DL+LL =	0.00	span due to DL+LL =	0.27
end due to DL =	0.00	span due to DL =	0.27

Use W6 x 15 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36

CALC BY: A.R.

DATE: 1/8/2021

EQUIPMENT FLOOR PURLIN: FP2

The purlins calculated using the vehicle point loads are slightly higher than with just the 100 psf live load. If all purlins are loaded with 100 psf live load this will put much more load into side channels

dead load = 30 psf end L= 0.00 ft live load = 7.75 ft 100 psf span L= beam carries 4.0 ft tributary width w= 520 # / ft

end defl= **0** in/ 100^4 span defl= **0.015** in/ 100^4

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 4 in⁴

try W6 x 9 Ix (in^4)= 16.4 S (in³)= **5.56** R1=1.73k unbraced -L (in) = 16 unbraced -L (in) = 16 0.00 (+)Mmax (k-in) =(-)Mmax (k-in) =46.85 23.8 (+)Fb(ksi)= 23.8 (-)Fb(ksi)= 0.0 (-)fb(ksi)= (+)fb(ksi)=8.4


target deflections:(in)

end due to DL+LL =L/180= 0.00 span due to DL+LL =L/360= 0.26 end due to DL =L/540= 0.00 span due to DL =L/720= 0.13

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.09 end due to DL = 0.00 span due to DL = 0.02

Use W6 x 9 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

CAR WASH FLOOR BEAM:

FB₁

dead load = 45 psf end L= 0.00 ft live load = 100 psf span L= 11 ft

beam carries 8.0 ft tributary width w= 1160 #/ft

end defl= **0** in/ 100⁴ span defl= **0.066** in/ 100⁴

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 12 in⁴

lx (in⁴)= **129** S (in³)= 21.5 R = 14.4ktry C12X20.7 unbraced -L (in) = 48 unbraced -L (in) = 48(-)Mmax(k-in) =176 (+)Mmax (k-in) =123 (-)Fb(ksi)= 23.8 23.8 (+)Fb(ksi)= 5.7 (-)fb(ksi)= 8.2 (+)fb(ksi)=


target deflections:(in)

end due to DL+LL =L/180= **0.00** span due to DL+LL =L/360= **0.37** end due to DL =L/540= **0.00** span due to DL =L/720= **0.18**

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.05 end due to DL = 0.00 span due to DL = 0.02

Use C12X20.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

EQUIPMENT FLOOR BEAM:

FB₂

dead load =	30	psf	end L=	2.00	ft
live load =	100	psf	span L=	11	ft

beam carries 4.0 ft tributary width w= 520 #/ft

end defl= **0** in/ 100⁴ span defl= **0.024** in/ 100⁴

target end Ix = defl(180)(100)/(Lx12) = 0 in⁴ target span Ix = defl(240)(100)/(Lx12) = 4 in⁴

try **C12X20.7** $Ix (in^4) = 129$ S (in³)= **21.5** R1 = 2.16 kunbraced -L (in) = 16 unbraced -L (in) = 48 R2 = 6.16 k(-)Mmax(k-in) =72 (+)Mmax (k-in) =50 (+)Fb(ksi)= (-)Fb(ksi)= 23.8 23.8 (-)fb(ksi)= (+)fb(ksi)=2.3 3.3


target deflections:(in)

end due to DL+LL =L/360= 0.07 span due to DL+LL =L/360= 0.37 end due to DL =L/540= 0.04 span due to DL =L/720= 0.18

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.02 end due to DL = 0.00 span due to DL = 0.00

Use C12X20.7 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36	
CALC BY:	A.R.	
DATE:	1/8/2021	

FB3

CARWASH FLOOR BEAM:

dead load = 45 psf end L= 0.00 ft live load = 100 psf span L= 15.1 ft

beam carries 2.0 ft tributary width w= 290 #/ft

end defl= **0** in/ 100⁴ span defl= **0.116974** in/ 100⁴

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 15 in⁴


Ix (in^4)= **129** $S (in^3) = 21.5$ R1=2.18k try C12X20.7 unbraced -L (in) = 16 unbraced -L (in) = 1299.18 (+)Mmax (k-in) =(-)Mmax (k-in) =0 23.8 (+)Fb(ksi)= 23.8 (-)Fb(ksi)= 4.6 0.0 (+)fb(ksi)=(-)fb(ksi)=

target deflections:(in)

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.09 end due to DL = 0.00 span due to DL = 0.03

Use C12X20.7



FREY-MOSS STRUCTURES

Sheetz's Inc. **Modular Car Wash**

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

CARWASH FLOOR BEAM:

FB3

dead load = 45 psf live load = 0

P1 = 2.25

kips 15.1 span L= ft

beam carries

2.0 ft tributary width w= 90 # / ft

end defl=

in/ 100⁴ 0

psf

span defl=

in/ 100⁴ 0.17

target end Ix = defl(180)(100)/(Lx12) =target span Ix= defl(240)(100)/(Lx12) = 0 in^4 in⁴

23

try C12X20.7

Ix (in^4)= **129**

0

23.8

S (in³)= **21.5**

R1=2.91k

unbraced -L (in) = (-)Mmax(k-in) =

unbraced -L (in) = 1216 (+)Mmax (k-in) =

147.00

(-)Fb(ksi)=

(+)Fb(ksi)=

23.8

(-)fb(ksi)=

0.0

(+)fb(ksi)=

6.8

target deflections:(in)

end due to DL+LL =L/180=

0.15

span due to DL+LL =L/360=

0.50

end due to DL =L/540=

0.05

span due to DL =L/720=

0.25

actual deflections:(in)

end due to DL+LL =

0.00

span due to DL+LL =

0.13


end due to DL =

0.00

span due to DL =

0.13

Use C12X20.7



FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

EQUIPMENT FLOOR BEAM:

FB4

dead load = 45 psf end L= 0.00 ft live load = 100 psf span L= 7.75 ft

beam carries 2.0 ft tributary width w= 290 #/ft

end defl= **0** in/ 100⁴ span defl= **0.008** in/ 100⁴

target end Ix= defl(180)(100)/(Lx12) = 0 in⁴ target span Ix= defl(240)(100)/(Lx12) = 2 in⁴

try C7 x 9.8 $lx (in^4) = 21.3$ $S (in^3) = 6.08$ R1 = .87kunbraced -L (in) = 16 unbraced -L (in) = 16 (+)Mmax (k-in) =(-)Mmax (k-in) =0 26.13 23.8 (+)Fb(ksi)= 23.8 (-)Fb(ksi)= (+)fb(ksi)=4.3 (-)fb(ksi)=0.0


target deflections:(in)

end due to DL+LL =L/180= 0.00 span due to DL+LL =L/240= 0.39 end due to DL =L/540= 0.00 span due to DL =L/720= 0.13

actual deflections:(in)

end due to DL+LL = 0.00 span due to DL+LL = 0.04 end due to DL = 0.00 span due to DL = 0.01

Use C7 x 9.8 with Zero Flange Brace(s) per Span



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36

CALC BY: A.R.

DATE: 1/8/2021

WIND & SEISMIC ANALYSIS

wind analysis:

refer 2015 INTERNATIONAL BUILDING CODE

height to top of structure = 11.83 ft

wind speed = 115 mph

Importance factor, I = 1.00

Adjustment Factor (λ) for exposure C = 1.21

Per figure 28.6-1 Zone A = 21 psf

Per figure 28.6-1 Zone C = 13.9 psf

Load Factor from ASCE 2.4.1 for all cases = 0.6

design wind force (zone A) = Wind Load X $1.0 \times 1.21 \times 0.6 =$ 15.25 psf design wind force (zone C) = Wind Load X $1.0 \times 1.21 \times 0.6 =$ 10.09 psf

Wind Load on the Side of Building = 11.07 psf

Use Minimum Wind Speed per code = 16.00 psf

seismic analysis:

refer 2015 INTERNATIONAL BUILDING CODE

From Figure 22-1 Ss = 0.062 g

From Figure 22-2 S1 = 0.034 g

From Section 11.4.2 The Site Class D has been selected

From table 11.4-1 Fa = 1.6

From table 11.4-2 Fv = 2.4

Seismic Occupancy Catagory from Table 1-1 1

 $SMS = Fa \times Ss = 0.0992$

 $SM1 = Fv \times S1 = 0.08$

SDS = 2/3 SMS = 0.07

SD1 = 2/3 SM1 = 0.0544

Seismic Design Category A

Response Modification Factor from Table 12.2-1.G.1 2.5

FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36

CALC BY: A.R.

DATE: 1/8/2021

WIND & SEISMIC ANALYSIS

seismic analysis continued:

Per Section 12.14.8 the Simplified Analysis has been selected

Equation 12.14-11 shows $V = 1.2 \times S_{DS} / R \times W$

W = (12 psf dead load + 42' Length X 24' Width

6.05 kips

Reaction from Seismic at top of building = V = 0.192

.**192** kips

moment from wind load:

Tributary height of wall for wind = 6.33 ft

Reaction from wind (Rw) = Tribuatry height (L) (F) = 4.25 kips

Reaction from Wind is greater than from Seismic - Use 4.25 kips

Force taken by shear wall (Fs) = Length of Wall X 181 #/ft = 4.34 kips

Force per Column = (Rw - Fs) / # Columns = 0.00 kips

Moment in column = Force X Height = 0.00 ft-kips

FREY-MOSS STRUCTURES

Sheetz's Inc. **Modular Car Wash**

G20V36 JOB NO: A.R. CALC BY: 1/8/2021 DATE:

COLUMN CALCULATION

Column Selection:

Try **TS** 3 x 3 x 3/16" Columns

Sx = 1.73 in^3

Ix = 2.6 in^4

KH/r = 140.18

K = 1.2 Fa = 7.60 ksi

A =

Fb = 27.6 ksi

1.13 in r =

11 ft Height =

> Fe= 7.60 ksi

Column Calculation at Rigid Frame:

Wind Moment is Greater

Load Combination: DL + LL + WL

3.23 kips

P = DL + LL =fa=P/A =

1.60 ksi

fa/Fa= 0.21

2.02 in^2

AISC EQ.H1-1 APPLIED

Maximum Moment=

0.00 ft-kips

fb = Moment*12/Sx =

0.00

Use Equation H1-1 = Cm (fb) / [Fb (1-fa/Fe)] = 0.00 ksi


fa/Fa + fb/Fb =

< 1.00 0.k. 0.21

***USE

TS 3 x 3 x 3/16"

FOR COLUMN ***



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36
CALC BY: A.R.
DATE: 1/8/2021

OPTIONAL COLUMN CALCULATION

Column Selection:

Try TS 3 x 3 x 14 GA Columns

Sx = 0.9 in³ A = 0.95 in^2 r = 1.18 in 1.2 11 ft 1.33 in⁴ K = Height = |x| =7.60 ksi 7.60 ksi Fe= KH/r = 140.18Fa =

Fb = 27.6 ksi

Column Calculation at Rigid Frame:

Wind Moment is Greater

Load Combination : DL + LL + WL

P = DL + LL =

3.23 kips

fa=P/A =

3.40 ksi

fa/Fa= 0.41

AISC EQ.H1-1 APPLIED

Maximum Moment=

0.00 ft-kips


fb = Moment*12/Sx =

0.00

Use Equation H1-1 = Cm (fb) / [Fb (1-fa/Fe)] = 0.00 ksi

fa/Fa + fb/Fb = 0.41 < 1.00 0.k.

***USE TS 3 x 3 x 14 GA FOR COLUMN ***



FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

G20V36 JOB NO: **CALC BY:** A.R. 1/8/2021 DATE:

OPTIONAL COLUMN CALCULATION

Column Selection:

lx =

Try TS 3 x 2 x 14 GA Columns

Sx = 0.65 in³

0.98 in^4

KH/r = 140.18

K = 1.2

A =

Fa = 7.60 ksi

r = 1.12 in Height = 11 ft

7.60 ksi Fe=

Fb= 27.6 ksi

Column Calculation at Rigid Frame:

Wind Moment is Greater

Load Combination: DL + LL + WL

P = DL + LL =

3.23 kips

fa=P/A =

4.14 ksi fa/Fa= 0.55

0.78 in^2

AISC EQ.H1-1 APPLIED

Maximum Moment=

0.00 ft-kips

fb = Moment*12/Sx =

0.00

Use Equation H1-1 = Cm (fb) / [Fb (1-fa/Fe)] = 0.00 ksi


fa/Fa + fb/Fb =

0.55 < 1.00 0.k.

***USE

TS 3 x 2 x 14 GA

FOR COLUMN ***




FREY-MOSS STRUCTURES


Sheetz's Inc. Modular Car Wash JOB NO: G20V36
CALC BY: A.R.
DATE: 1/8/2021

F-DECK FOR FLOOR

SECTION PROPERTIES TABLE

	22 GAGE	20 GAGE	18 GAGE	16 GAGE
DESIGN THICKNESS	.0299	.0359	.0478	.0598
WEIGHT — ptd.	1.6	1.9	2.6	3.2
WEIGHT — galv.	1.7	2.0	2.7	3.3
I _p in ⁴	.133	.170	.246	.316
S _p in ³	.136	.167	.231	.294
I _n in ⁴	.158	.189	.252	.316
S _n in ³	.147	.178	.238	.298





UNIFORM LOAD TABLE (lbs/ft^2)

		SINGLE	SPAN			DOUBL	E SPAN			TRIPLE	SPAN	
	22 GAGE	20 GAGE	18 GAGE	16 GAGE	22 GAGE	20 GAGE	18 GAGE	16 GAGE	22 GAGE	20 GAGE	18 GAGE	16 GAGE
4'-0"	113	139	193	245	123	148	198	248	153	185	248	310
4'-6"	90	110	152	194	97	117	157	196	121	147	196	245
5'-0"	73	89	123	157	78	95	127	159	98	119	159	199
5'-6"	60	74	102	130	65	78	105	131	81	98	131	164
6'-0"	50	62	85	106	54	66	88	110	68	82	110	138
6'-6"	42	51	69	86	46	56	75	94	58	70	94	118
7'-0"	35	43	5.7	70	40	48	65	81	50	61	81	101
7'-6"	31	36	48	59	35	42	56	71	44	53	71	88
8'-0"	27	32	42	51	31	37	50	62	38	46	62	78
8'-6"		28	36	44	27	33	44	55	34	41	55	69
9'-0"		25	32	38		29	39	49	30	37	49	61
9'-6"			29	34		26	35	44	27	33	44	55
10'-0"			26	31			32	40		30	40	49
10'-6"				28			29	36		27	36	44
11'-0"				26			26	33		25	33	39
١	/aximu	m Spa	ns and	Cantil	evers	or Cor	structi	on Mai	ntenan	ce Loa	ds	
SPAN	4'-6"	5'-6"	7'-1"	8'-0"	5'-6"	6'-8"	8'-3"	9'-4"	5'-7"	6'-10"	8'-4"	9'-6"
CANT.	1'-1"	1'-4"	1'-9"	2'-3"	1'-1"	1'-4"	1'-9"	2'-3"	1'-1"	1'-4"	1'-9"	2'-3"


FREY-MOSS STRUCTURES

Sheetz's Inc.

Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

20 GA. CARWASH CEILING DECK



Fy = 50,000 PSI Fb = 30,000 PSIt = .036 in

Calculation Taken from From "AISI Cold Formed Steel Design" 2007 Edition - Section 3.5 & 3.6

POSITIVE BENDING

NEGATIVE BENDING

Member	Α	Υ	AY	AY2	I	Α	Υ	AY	AY2	ı
1	0.50	3.75	1.88	7.03	0.01	0.50	3.75	1.88	7.03	0.01
2	0.99	3.98	3.94	15.70	0.00	0.99	3.98	3.94	15.70	0.00
3	4.00	2.00	8.00	16.00	5.33	4.00	2.00	8.00	16.00	5.33
4	13.93	0.02	0.25	0.00	0.00	1.61	0.02	0.03	0.00	0.00
5	3.94	1.97	7.75	15.27	5.09	3.94	1.97	7.75	15.27	5.09
6	0.80	3.92	3.15	12.34	0.00	0.80	3.92	3.15	12.34	0.00
7	0.31	3.78	1.18	4.46	0.00	0.31	3.78	1.18	4.46	0.00
Totals	24.47		26.15	70.80	10.44	12.15		25.93	70.80	10.44

Determine Effective Width Using Equation B2.1-1 through B2.1-5

Check Compression Members w/t = 0.990/0.036 = 28 < 30 OK

w/t = 13.928/0.036 = 387 > 30

Calculate Effective Width of Compression Flange b = p X w = 0.101 X 0.036 = 1.611 in

Ybar = 26.150/24.471 = 1.069

C = 4.000 - 1.069 = 2.931

 $I = 10.437 + 70.803 - 24.471(1.069)^2$

 $I = 53.297 \times t = 53.297 \times 0.036$

 $I = 1.919 \text{ in}^4$

S = 1.919 / 2.931

 $S = 0.655 \text{ in}^3$

Ybar = 25.928/12.154 = 2.133

C = 4.000 - 2.133 = 1.867

I = 10.436 + 70.799 - 12.154(2.133)²

 $I = 25.923 \times t = 25.923 \times 0.036$

 $I = 0.933 \text{ in}^4$

S = 0.933 / 1.867

 $S = 0.500 \text{ in}^3$


FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash JOB NO: G20V36

CALC BY: A.R.

DATE: 1/8/2021

20 GA Equipment Ceiling/All Wall Deck - 3" Tall



Fy = 50,000 Fb = 30,000t = .036 in

Calculation Taken from From "AISI Cold Formed Steel Design" 2007 Edition - Section 3.5 & 3.6

POSITIVE BENDING

NEGATIVE BENDING

							i de la constantina della cons			
Member	Α	Υ	AY	AY2		Α	Υ	AY	AY2	1
1	0.500	2.750	1.375	3.781	0.010	0.500	2.750	1.375	3.781	0.010
2	0.990	2.982	2.952	8.803	0.000	0.990	2.982	2.952	8.803	0.000
3	3.000	1.500	4.500	6.750	2.250	3.000	1.500	4.500	6.750	2.250
4	15.928	0.018	0.287	0.005	0.002	1.611	0.018	0.029	0.001	0.000
5	2.938	1.469	4.316	6.340	2.113	2.938	1.469	4.316	6.340	2.113
6	0.803	2.920	2.345	6.847	0.000	0.803	2.920	2.345	6.847	0.000
7	0.312	2.782	0.868	2.415	0.003	0.312	2.782	0.868	2.415	0.003
Totals	24.471		16.643	34.941	4.378	10.154		16.385	34.937	4.377

Determine Effective Width Using Equation B2.1-1 through B2.1-5 From 2001 AISI Standard with 2004 Supplement

Check Compression Members w/t = 0.990/0.036 = 28 < 30 OK

w/t = 15.928/0.036 = 442 > 30

Calculate Effective Width of Compression Flange b = p X w = 0.101 X 0.036 = 1.611 in

Ybar = 16.643/24.471 = 0.680

C = 3.000 - 0.680 = 2.320

 $I = 4.378 + 34.941 - 24.471(0.680)^2$

 $I = 28.001 \times t = 28.001 \times 0.036$

 $I = 1.008 \text{ in}^4$

S = 1.008 / 2.320

 $S = 0.435 \text{ in}^3$

Ybar = 16.385/10.154 = 1.614

C = 3.000 - 1.614 = 1.386

 $I = 4.377 + 34.937 - 10.154(1.614)^2$

 $I = 12.874 \times t = 12.874 \times 0.036$

 $I = 0.463 \text{ in}^4$


S = 0.463 / 1.386

 $S = 0.334 \text{ in}^3$

FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

JOB NO: G20V36
CALC BY: A.R.
DATE: 1/8/2021



(3.4.1) SHEAR STRESS IN WEBS

$$h/t = 16/.036 = 444$$

$$547/\sqrt{33} = 95$$
 95 < 444

$$Fv = 83.200/(444)^2 = .422 \text{ KSI}$$

$$V = .422 \text{ KSI}$$

MAX. SHEAR PER FOOT = .422 (12 in) (.036) = 182 #/FT

USE #10 S.M. SCREWS IN PANEL RIBS AND COLUMNS — SEE SPACING BELOW

USE 2) #10 S.M. SCREWS

AT TOP AND BOTTOM OF PANELS

SHEAR WALL FASTENER SPACING

#10 S.M. Screw (Minor Diameter = .18 in)

Value in Shear per Screw = 250# per AISI

Cold Formed Steel Design Table IV

Using Spacing of 22 inches

Max. Shear per Foot in Shear Wall = 250 (1.33) (12 in/ft) / 22 in = 181 #/ft

Use Value of 181 #/ft for Max. Shear per Foot in Shear Wall

FREY-MOSS STRUCTURES

Sheetz's Inc. Modular Car Wash

JOB NO:	G20V36
CALC BY:	A.R.
DATE:	1/8/2021

Check Wall Deck against Wind Load

From Table 30.7-2 from ASCE 7-10 Zone 5 Pressure = 48.4 psf

Distributed Load on Wall = 48.4 psf X 1.21 X 4/3 ft = 78.1 #/ft

Moment in Panel = 78.1 #/ft X 11 ft^2 / 12 = 787 ft-lbs = 9.45 in-kips

9.45 in-kips / 0.334 in³ = 28.29 ksi < 30 ksi OK

Calculation for Fastening Roof Flashing

From Table 30.7-2 from ASCE 7-10 Zone 3 Pressure = 82.6 psf

Maximum Wind Load = -82.6 psf X 1.21 = 99.9 psf

Panels are 1.0 ft wide and fasteners are 3'-0" O/C Max

Load in each fastener = 99.9 psf X 1.0 ft X 3 ft = 300 lbs

#10 Teks are good for 302 # Pullout, 1125 # Pullover and 731 # Shear OK

Envelope Compliance Certificate

Project Information

Energy Code: 90.1 (2013) Standard
Project Title: Sheetz Automatic Carwash
Location: Cameron, North Carolina

Climate Zone: 3a

Project Type: New Construction

Performance Sim. Specs: EnergyPlus 8.1.0.009 (EPW: USA_NC_Charlotte-Douglas.Intl.AP.723140_TMY3.epw)

Construction Site: Sawyer Rd. & NC 24-87 Cameron, NC 28326 Owner/Agent:

Designer/Contractor:
Andy Rape
Frey-Moss Structures
1801 Rockdale Industrial Blvd.
Conyers, GA 30012
770-483-7543
fms@frey-moss.com

Building Area Floor Area

1-Transportation : Nonresidential 923

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor _(a)
Roof 1: Metal Building, Standing Seam, Double Insulation Layer with Thermal Blocks (c), [Bldg. Use 1 - Transportation]	268	11.0	17.0	0.038	0.041
Floor 1: Steel Joist, [Bldg. Use 1 - Transportation]	268	19.0	5.6	0.040	0.038
NORTHEAST Exterior Wall 1: Other Steel Framed Wall, [Bldg. Use 1 - Transportation] (b)	325			0.052	0.077
SOUTHEAST Exterior Wall 2: Other Steel Framed Wall, [Bldg. Use 1 - Transportation] (b)	83			0.052	0.077
SOUTHWEST Semi-Exterior Wall 1: Other Steel Framed Wall, [Bldg. Use 1 - Transportation] (b)	325			0.089	0.124
NORTHWEST Exterior Wall 3: Other Steel Framed Wall, [Bldg. Use 1 - Transportation] (b)	83			0.052	0.077
Door 1: Insulated Metal, Swinging, [Bldg. Use 1 - Transportation]	28			0.350	0.700

- (a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.
- (b) 'Other' components require supporting documentation for proposed U-factors.
- (c) Thermal spacer block with minimum R-3.5 must be installed above the purlin/batt, and the roof deck secured to the purlins.

Project Notes

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 1 of 18

Envelope PASSES: Design 2% better than code

Envelope Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed envelope systems have been designed to meet the 90.1 (2013) Standard requirements in COMcheck Version 4.1.5.1 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Robert B. Smith - PE

Name - Title

Signature

01/25/2021

Date

Exterior Wall - Rs = 0.17 (Exterior Air Film) + 13.0 (2" Redmax) + 0.39 (Durock) + 0.0 (Metal Panel) + 0.68 (Interior Air Film) = 14.24

ER = 11.1 (3.5" R-13 Batt Insulation) \times 0.46 (Correction Factor "Fc" from table C402.1.4.1) = 5.11

Uo = 1/(Rs + ER) = 1/(14.24 + 5.11) = 0.052

Semi-Exterior Wall - Uo = $1/(Rs + ER) = 1/(1 + 5.11 \times 2) = 0.089$

SEAL
048412

SEAL
048412

P-1359

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 2 of 18

COMcheck Software Version 4.1.5.1



Interior Lighting Compliance Certificate

Project Information

Energy Code: 90.1 (2013) Standard **Project Title:** Sheetz Automatic Carwash

Project Type: **New Construction**

Construction Site: Sawyer Rd. & NC 24-87 Cameron, NC 28326

Owner/Agent:

Designer/Contractor: Andy Rape Frey-Moss Structures 1801 Rockdale Industrial Blvd. Conyers, GA 30012 770-483-7543 fms@frey-moss.com

Allowed Interior Lighting Power

	A Area Category	B Floor Area (ft2)	C Allowed Watts / ft2	D Allowed Watts (B X C)
1-Transportation		923	0.70	646
			Total Allowed Watts =	= 646

Proposed Interior Lighting Power

A Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	B Lamps/ Fixture	C # of Fixtures	D Fixture Watt.	(C X D)
1-Transportation				
LED 1: 1: LED: Other:	1	6	80	480
LED 2: 1: LED: Other:	1	4	40	160
		Total Propos	e atteW has	640

Interior Lighting PASSES: Design 1% better than code

Interior Lighting Compliance Statement

Compliance Statement: The proposed interior lighting design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed interior lighting systems have been designed to meet the 90.1 (2013) Standard requirements in COMcheck Version 4.1.5.1 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

01/25/2021 Floyd Keels - PE Date

Name - Title Signature



Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 3 of 18

COMcheck Software Version 4.1.5.1



Exterior Lighting Compliance Certificate

Project Information

Energy Code: 90.1 (2013) Standard **Project Title:** Sheetz Automatic Carwash Project Type: **New Construction**

Exterior Lighting Zone 2 (Neighborhood business district)

Construction Site: Sawyer Rd. & NC 24-87 Cameron, NC 28326

Owner/Agent:

Designer/Contractor: Andy Rape Frey-Moss Structures 1801 Rockdale Industrial Blvd. Conyers, GA 30012 770-483-7543 fms@frey-moss.com

Allowed Exterior Lighting Power

A Area/Surface Category	B Quantity	C Allowed Watts / Unit	D Tradable Wattage	E Allowed Watts (B X C)
Illuminated length of facade wall or surface	16 ft	2.5	No	40
		Total Tradab	ole Watts (a) =	0
		Total All	owed Watts =	40
	Total All	owed Supplement	tal Watts (b) =	600

- (a) Wattage tradeoffs are only allowed between tradable areas/surfaces.
- (b) A supplemental allowance equal to 600 watts may be applied toward compliance of both non-tradable and tradable areas/surfaces.

Proposed Exterior Lighting Power

A	В	С	D	E
Fixture ID : Description / Lamp / Wattage Per Lamp / Ballast	Lamps/ Fixture	# of Fixtures	Fixture Watt.	(C X D)
Illuminated length of facade wall or surface (16 ft): Non-tradable Wattage				
LED 1: 3: Wallpack: Other:	1	2	91	182
	Total Trac	dable Propos	sed Watts =	0

Exterior Lighting PASSES: Design 0.0% better than code

Exterior Lighting Compliance Statement

Compliance Statement: The proposed exterior lighting design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed exterior lighting systems have been designed to meet the 90.1 (2013) Standard requirements in COMcheck Version 4.1.5.1 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Floyd Keels - PE Name - Title Signature

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page Data filename: 4 of 18

COMcheck Software Version 4.1.5.1 Mechanical Compliance Certificate

Project Information

Energy Code: 90.1 (2013) Standard
Project Title: Sheetz Automatic Carwash
Location: Cameron, North Carolina

Climate Zone: 3a

Project Type: New Construction

Construction Site: Sawyer Rd. & NC 24-87 Cameron, NC 28326 Owner/Agent:

Designer/Contractor:
Andy Rape
Frey-Moss Structures
1801 Rockdale Industrial Blvd.
Conyers, GA 30012
770-483-7543
fms@frey-moss.com

Mechanical Systems List

Quantity System Type & Description

1 HVAC System - Item #18 (Single Zone):

Heating: 1 each - Hydronic or Steam Coil, Hot Water, Capacity = 175 kBtu/h No minimum efficiency requirement applies

Fan System: None

I Water Heater - Item #D:

Electric Instantaneous Water Heater, Capacity: 0 gallons No minimum efficiency requirement applies

Mechanical Compliance Statement

Compliance Statement: The proposed mechanical design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed mechanical systems have been designed to meet the 90.1 (2013) Standard requirements in COMcheck Version 4.1.5.1 and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Robert B. Smith - PE

Name - Title Signature

01/25/2021

5 of 18

Date

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page

COMcheck Software Version 4.1.5.1 Inspection Checklist

Energy Code: 90.1 (2013) Standard

Requirements: 100.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section #	Plan Review	Complies?	Comments/Assumptions
& Req.ID			
4.2.2, 5.4.3.1.1, 5.7 [PR1] ¹	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
4.2.2, 6.4.4.2.1, 6.7.2 [PR2] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the mechanical systems and equipment and document where exceptions to the standard are claimed. Load calculations per acceptable engineering standards and handbooks.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
4.2.2, 7.7.1, 10.4.2 [PR3] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the service water heating systems and equipment and document where exceptions to the standard are claimed. Hot water system sized per manufacturer's sizing guide.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
4.2.2, 8.4.1.1, 8.4.1.2, 8.7 [PR6] ²	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the electrical systems and equipment and document where exceptions are claimed. Feeder connectors sized in accordance with approved plans and branch circuits sized for maximum drop of 3%.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E1
4.2.2, 9.4.3, 9.7 [PR4] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the interior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided should include interior lighting power calculations, wattage of bulbs and ballasts, transformers and control devices.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2

High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)	1 High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
---	------------------------	---	------------------------	---	---------------------

Project Title: Sheetz Automatic Carwash Report date: 01/09/21 6 of 18

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
9.7 [PR8] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the exterior lighting and electrical systems and equipment and document where exceptions to the standard are claimed. Information provided should include exterior lighting power calculations, wattage of bulbs and ballasts, transformers and control devices.	□Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
6.7.2.4 [PR5] ¹	Detailed instructions for HVAC systems commissioning included on the plans or specifications for projects >=50,000 ft2.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21 Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 7 of 18

Section # & Req.ID	Footing / Foundation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
4.2.4 [FO1] ²	Installed below-grade wall insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R	R	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
4.2.4 [FO3] ²	Installed slab-on-grade insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R Unheated Heated	R Unheated Heated	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.5.3.5 [FO5] ²	Slab edge insulation depth/length.	ft	ft	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.7 [FO6] ¹	Exterior insulation protected against damage, sunlight, moisture, wind, landscaping and equipment maintenance activities.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
5.8.1.7.3 [FO7] ¹	Insulation in contact with the ground has <=0.3% water absorption rate per ASTM C272.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
6.4.3.7 [FO9] ³	Freeze protection and snow/ice melting system sensors for future connection to controls.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
6.4.4.1.5 [FO11] ³	Bottom surface of floor structures incorporating radiant heating insulated to >=R-3.5.	R	R	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6 See the Envelope Assemblies table for values.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21
Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 8 of 18

Section # & Req.ID	Framing / Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
5.4.3.2 [FR1] ³	Factory-built and site-assembled fenestration and doors are labeled or certified as meeting air leakage requirements.			☐Complies ☐Does Not ☐Not Observable	Requirement will be met.
	leakage requirements.		 	□Not Applicable	1
5.5.4.3a [FR8] ¹	Vertical fenestration U-Factor.	U	U	\square Complies \square Does Not	See the Envelope Assemblies table for values.
			 	□Not Observable □Not Applicable	
5.5.4.3b [FR9] ¹	Skylight fenestration U-Factor.	U	U	□Complies □Does Not	See the Envelope Assemblies table for values.
			 	□Not Observable □Not Applicable	1 1 1 1 1
5.5.4.4.1 [FR10] ¹	Vertical fenestration SHGC value.	SHGC:	SHGC:	□Complies □Does Not	See the Envelope Assemblies table for values.
			 	□Not Observable □Not Applicable	1 1 1 1
5.5.4.4.2 [FR11] ¹	Skylight SHGC value.	SHGC:	SHGC:	□Complies □Does Not	See the Envelope Assemblies table for values.
			 	□Not Observable □Not Applicable	
5.8.2.1, 5.8.2.3,	Fenestration products rated (U-factor, SHGC, and VT) in			□Complies □Does Not	Requirement will be met.
5.8.2.4, 5.8.2.5 [FR12] ²	accordance with NFRC or energy code defaults are used.			□Not Observable □Not Applicable	Location on plans/spec: A2
5.8.2.2 [FR13] ¹	Fenestration and door products are labeled, or a signed and			□Complies □Does Not	Requirement will be met.
	dated certificate listing the U- factor, SHGC, VT, and air leakage rate has been provided by the manufacturer.			□Not Observable □Not Applicable	Location on plans/spec: A2
5.5.3.6 [FR14] ²	U-factor of opaque doors associated with the building	U Swinging	U Swinging	□Complies □Does Not	See the Envelope Assemblies table for values.
	thermal envelope meets requirements.	Nonswinging	Nonswinging	□Not Observable □Not Applicable	
5.4.3.1 [FR15] ¹	Continuous air barrier is wrapped, sealed, caulked,			□Complies □Does Not	Requirement will be met.
	gasketed, and/or taped in an approved manner, except in semiheated spaces in climate zones 1-6.			□Not Observable □Not Applicable	Location on plans/spec: S4-S6

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
--	----------------------	---	------------------------	---	---------------------

Project Title: Sheetz Automatic Carwash Report date: 01/09/21 Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 9 of 18

Section # & Req.ID	Mechanical Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
6.4.1.4, 6.4.1.5 [ME1] ²	HVAC equipment efficiency verified. Non-NAECA HVAC equipment labeled as meeting 90.1.	Efficiency:	Efficiency:	□Complies □Does Not □Not Observable □Not Applicable	See the Mechanical Systems list for values.
6.4.3.4.1 [ME3] ³	Stair and elevator shaft vents have motorized dampers that automatically close.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Exception: Requirement does not apply.
6.4.3.4.5 [ME39] ³	Enclosed parking garage ventilation has automatic contaminant detection and capacity to stage or modulate fans to 50% or less of design capacity.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.4.3.4.4 [ME5] ³	Ventilation fans >0.75 hp have automatic controls to shut off fan when not required.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
6.4.3.8 [ME6] ¹	Demand control ventilation provided for spaces >500 ft2 and >25 people/1000 ft2 occupant density and served by systems with air side economizer, auto modulating outside air damper control, or design airflow >3,000 cfm.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Systems with a design outdoor airflow less than 1200 cfm.
6.5.3.2.1 [ME40] ²	DX cooling systems >= 75 kBtu/h (>= 65 kBtu/h effective 1/2016) and chilled-water and evaporative cooling fan motor hp >= ½ designed to vary indoor fan airflow as a function of load and comply with operational requirements.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply. See the Mechanical Systems list for values.
6.4.4.1.1 [ME7] ³	Insulation exposed to weather protected from damage. Insulation outside of the conditioned space and associated with cooling systems is vapor retardant.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
6.4.4.1.2 [ME8] ²	HVAC ducts and plenums insulated. Where ducts or plenums are installed in or under a slab, verification may need to occur during Foundation Inspection.	R	R	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
6.4.4.1.3 [ME9] ²	HVAC piping insulation thickness. Where piping is installed in or under a slab, verification may need to occur during Foundation Inspection.	in.	in.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.4.4.1.4 [ME41] ³	Thermally ineffective panel surfaces of sensible heating panels have insulation >= R-3.5.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.4.4.2.1 [ME10] ²	Ducts and plenums sealed based on static pressure and location.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
	1 High Impact (Tier	1) 2 Medium	Impact (Tier 2)	3 Low Impact (Ti	ier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21 Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 10 of 18

Section # & Req.ID	Mechanical Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
6.4.4.2.2 [ME11] ³	Ductwork operating >3 in. water column requires air leakage testing.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.2.2.1 [ME50] ²	Three-pipe hydronic systems using a common return for hot and chilled water are not used.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
6.5.2.3 [ME19] ³	Dehumidification controls provided to prevent reheating, recooling, mixing of hot and cold airstreams or concurrent heating and cooling of the same airstream.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Cooling capacity 40 kBtu/h.
6.5.2.4.1 [ME68] ³	Humidifiers with airstream mounted preheating jackets have preheat auto-shutoff value set to activate when humidification is not required.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.2.4.2 [ME69] ³	Humidification system dispersion tube hot surfaces in the airstreams of ducts or airhandling units insulated >= R-0.5.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.2.5 [ME70] ³	Preheat coils controlled to stop heat output whenever mechanical cooling, including economizer operation, is active.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
6.5.3.3 [ME42] ³	Multiple zone VAV systems with DDC of individual zone boxes have static pressure setpoint reset controls.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply. See the Mechanical Systems list for values.
6.5.4.2 [ME25] ³	HVAC pumping systems >10 hp designed for variable fluid flow.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Minimum flow is less than required for proper operation and pump power =75 hp.
6.5.4.3, 6.5.4.3.1, 6.5.4.3.2 [ME26] ³	Fluid flow shutdown in pumping systems to multiple chillers or boilers when systems are shut down.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
6.5.6.1 [ME56] ¹	Exhaust air energy recovery on systems meeting Tables 6.5.6.1-1, and 6.5.6.1-2.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.6.2 [ME31] ³	Condenser heat recovery system that can heat water to 85 °F or provide 60% of peak heat rejection is installed for preheating of service hot water.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
6.5.7.1.1 [ME32] ²	Kitchen hoods >5,000 cfm have make up air >=50% of exhaust air volume.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash

Report date: 01/09/21 Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs
Page 11 of 18 90.1 2013.cck

Section # & Req.ID	Mechanical Rough-In Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
6.5.7.1.5 [ME49] ³	Approved field test used to evaluate design air flow rates and demonstrate proper capture and containment of kitchen exhaust systems.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.8.1 [ME34] ²	Unenclosed spaces that are heated use only radiant heat.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
7.4.2 [ME36] ²	Service water heating equipment meets efficiency requirements.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
6.4.3.9 [ME63] ²	Heating for vestibules and air curtains include automatic controls that shut off the heating system when outdoor air temperatures > 45F. Vestibule heating systems controlled by a thermostat in the vestibule with setpoint <= 60F.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.5.10 [ME73] ³	Doors separating conditioned space from the outdoors have controls that disable/reset heating and cooling system when open.			□Complies □Does Not □Not Observable □Not Applicable	Exception: Building entrances have automatic closing devices. Location on plans/spec: A2

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 12 of 18 90.1 2013.cck

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
8.4.2 [EL10] ²	20-Amp receptacles are controlled by an automatic control device.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Space type is not private office, open office, or computer classroom.
9.4.1.1 [EL1] ²		□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
9.4.1.1 [EL2] ²	Independent lighting controls installed per approved lighting plans and all manual controls readily accessible and visible to occupants.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
9.4.1.2 [EL11] ²	with required lighting controls and daylight transition zone lighting.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
9.4.1.1f [EL13] ¹	roof monitors that have more than 150 W combined input power for general lighting are controlled by	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
9.4.1.4 [EL3] ²	Automatic lighting controls for exterior lighting installed.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
9.4.1.3 [EL4] ¹	specific uses installed per approved lighting plans.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
9.6.2 [EL8] ¹		□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: E2
10.4.1 [EL9] ²	Electric motors meet requirements where applicable.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)	1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)	
---	---	----------------------	---	------------------------	---	---------------------	--

Report date: 01/09/21 Project Title: Sheetz Automatic Carwash Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs
Page 13 of 18 90.1 2013.cck

Section # & Req.ID	Insulation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
4.2.4 [IN2] ¹	Installed roof insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports. For some ceiling systems, verification may need to occur during Framing Inspection.	R Above deck Metal Attic	R Above deck Metal Attic	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.2, 5.8.1.3 [IN3] ¹	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the ceiling slope is <= 3:12.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
4.2.4 [IN6] ¹	Installed above-grade wall insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R Mass Metal Steel Wood	R Mass Metal Steel Wood	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.2 [IN7] ¹	Above-grade wall insulation installed per manufacturer's instructions.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
4.2.4 [IN8] ²	Installed floor insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	R Mass Steel Wood	R Mass Steel Wood	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
5.8.1.2 [IN9] ²	Floor insulation installed per manufacturer's instructions.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
5.8.1.1 [IN10] ²	Building envelope insulation is labeled with R-value or insulation certificate has been provided listing R-value and other relevant data.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
5.8.1.9 [IN18] ²	Building envelope insulation extends over the full area of the component at the proposed rated R or U value.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
5.8.1.4 [IN11] ²	Eaves are baffled to deflect air to above the insulation.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
5.8.1.5 [IN12] ²	Insulation is installed in substantial contact with the inside surface separating conditioned space from unconditional space.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
5.8.1.6 [IN13] ²	Recessed equipment installed in building envelope assemblies does not compress the adjacent insulation.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Section # & Req.ID	Insulation Inspection	Plans Verified Value	Field Verified Value	Complies?	Comments/Assumptions
5.8.1.7.1 [IN15] ²	Attics and mechanical rooms have insulation protected where adjacent to attic or equipment access.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: S4-S6
5.8.1.7.2 [IN16] ²	Foundation vents do not interfere with insulation.			□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
5.8.1.8 [IN17] ³	Insulation intended to meet the roof insulation requirements cannot be installed on top of a suspended ceiling. Mark this requirement compliant if insulation is installed accordingly.			☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	Requirement will be met. Location on plans/spec: S4-S6

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21 Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 15 of 18

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
5.4.3.3 [FI1] ¹	dock cargo doors in Climate Zones 4-	□Complies □Does Not	Requirement will be met.
	8.	□Not Observable □Not Applicable	Location on plans/spec: A2
6.4.3.1.2 [FI3] ³	Thermostatic controls have a 5 °F deadband.	□Complies □Does Not	Exception: having jurisdiction.
		□Not Observable □Not Applicable	
6.4.3.2 [FI20] ³	Temperature controls have setpoint overlap restrictions.	□Complies □Does Not	Requirement will be met.
		□Not Observable □Not Applicable	
6.4.3.3.1 [FI21] ³	HVAC systems equipped with at least one automatic shutdown control.	□Complies □Does Not	Requirement will be met.
		□Not Observable □Not Applicable	Location on plans/spec: P5
6.4.3.3.2 [FI22] ³		□Complies □Does Not	Requirement will be met.
	required for maintenance.	□Not Observable □Not Applicable	Location on plans/spec: P5
6.4.3.6 [FI6] ³	When humidification and dehumidification are provided to a zone, simultaneous operation is prohibited. Humidity control prohibits the use of fossil fuel or electricity to produce RH > 30% in the warmest zone humidified and RH < 60% in the coldest zone dehumidified.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
6.7.2.1 [FI7] ³	Furnished HVAC as-built drawings submitted within 90 days of system acceptance.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
6.7.2.2 [FI8] ³	Furnished O&M manuals for HVAC systems within 90 days of system acceptance.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met.
6.7.2.3 [FI9] ¹	systems serving zones >5,000 ft2 of conditioned area.	□Complies □Does Not □Not Observable □Not Applicable	Exception: Requirement does not apply.
6.7.2.4 [FI10] ¹	calibration and adjustment of controls.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P5
7.4.4.3 [FI11] ³	Public lavatory faucet water temperature <=110°F.	□Complies □Does Not □Not Observable □Not Applicable	Requirement will be met. Location on plans/spec: P1
8.7.1 [FI16] ³		□Complies □Does Not □Not Observable	Requirement will be met.
		□Not Applicable	

1 High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash

Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs
Page 16 of 18 90.1 2013.cck

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
8.7.2 [FI17] ³	Furnished O&M instructions for systems and equipment to the	\square Complies \square Does Not	Requirement will be met.
	building owner or designated representative.	□Not Observable □Not Applicable	
9.2.2.3 [FI18] ¹	Interior installed lamp and fixture lighting power is consistent with what is shown on the approved lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	\square Complies \square Does Not	See the Interior Lighting fixture schedule for values.
		□Not Observable □Not Applicable	
9.4.2 [FI19] ¹	Exterior lighting power is consistent with what is shown on the approved	□Complies □Does Not	See the Exterior Lighting fixture schedule for values.
	lighting plans, demonstrating proposed watts are less than or equal to allowed watts.	□Not Observable □Not Applicable	
10.4.3 [FI24] ²	Elevators are designed with the proper lighting, ventilation power, and	\square Complies \square Does Not	Exception: Requirement does not apply.
	standby mode.	□Not Observable □Not Applicable	
7.4.3 [FI45] ²	First 8 ft of outlet piping is insulated	□Complies □Does Not	Exception: Requirement does not apply.
		□Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: Sheetz Automatic Carwash Report date: 01/09/21

Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs Page 17 of 18 90.1 2013.cck

Project Title: Report date: 01/09/21 Sheetz Automatic Carwash Data filename: J:\AA-GEORGIA JOBS\Drawings-2020\V\G20V36 - Cameron, NC - Sheetz Eng\Calcs\Energy Calcs
Page 18 of 18 90.1 2013.cck

Report Prepared By:

Frey-Moss Structures

For: Sheetz Carwash North Carolina

Sawyer Rd. & NC 24-87

Cameron, North Carolina 28326

Design Conditions: Fayetteville, Pope; Latitude: 35; Time 4:00 PM

Indoor: Outdoor:

Summer temperature: 75
Winter temperature: 72
Winter temperature: 20
Relative humidity: 50
Summer grains of moisture: 111
Daily temperature range: 20

Building Component			Sensible Gain (BTUH)	Latent Gain (BTUH)	Total Heat Gain (BTUH)	Total Heat Loss (BTUH)
Floor	268.1	sg.ft.	0	0	0	3,437
NE Wall		sq.ft.	439	0	439	1,352
SW Wall		sq.ft.	406	0	406	1,352
NW Wall	62.5	sq.ft.	52	0	52	260
Door Leakage Summer Leakage Winter		sq.ft. cfm cfm	190 262 0	0 447 0	190 709 0	582 0 1,544
SE Wall		sq.ft.	159	0	159	343
Ceiling	268.1	•	680	0	680	697
People/Vent Ventilation		people cfm	0 1,870	0 3,196	0 5,066	0 5,720
Infiltration Summer Infiltration Winter	167.8733 176.81		3,139 0	5,365 0	8,504 0	0 10,114
Lights	360	watts	1,476	0	1,476	0
Whole Building - All Components			8,673	9,008	17,681 (1.5 tons)	25,401

HVAC-Calc Commercial 4.0

by HVAC Computer Systems Ltd.