

# Proposed "Concrete Batch Plant" Dispatch Office Building for


# Crete Solutions LLC

239 Raleigh Street  
Wilmington, North Carolina

CONTRACT DOCUMENTS: SUBMITTAL 3/30/18 (Issued for Code Enforcement Permit Review Approval )  
Occupancy Group Use: " Business (B) "

APPROXIMATE VICINITY OF  
PROPOSED PROJECT  
SEE LOCATION MAP


VICINITY MAP  
NTS



APPROXIMATE AREA OF  
EXISTING BUILDING FACILITY  
NEW CONSTRUCTION

LOCATION MAP  
NTS

1  
A100




KEY PLAN

NOT TO SCALE

SHEET TITLES

G100	COVER SHEET	A5100	FOUNDATION PLAN
G100	BUILDING CODE & LIFE SAFETY PLANS	A100	DIMENSIONAL FLOOR PLAN
N100	ACCESSIBILITY DETAILS	A101	REFLECTED CEILING PLAN
N101	GENERAL CONSTRUCTION NOTES	A200	EXTERIOR BUILDING ELEVATIONS BUILDING CROSS SECTION
C0.0	GENERAL COVER SHEET	A300	TYPICAL WALL SECTIONS
C1.0	GENERAL NOTES	A400	ENLARGED PLANS, ELEVATIONS & DETAILS
C2.0	SITE PLAN	A500	DOOR/WINDOW SCHEDULES, ELEVATIONS & DETAILS
C2.1	SITE INVENTORY MAP	P100	PLUMBING SCHEDULES, NOTES & DETAILS
C3.0	EROSION CONTROL PLAN	P101	FLOOR PLAN - PLUMBING - WASTE
C3.1	GRADING & DRAINAGE PLAN	P102	FLOOR PLAN - PLUMBING - WATER
C4.0	UTILITY PLAN	M100	MECHANICAL SCHEDULES NOTES & DETAILS
C5.0-5.4	DETAILS	M101	FLOOR PLAN - MECHANICAL
L1.0	LANDSCAPING PLAN	E100	ELECTRICAL SCHEDULES, NOTES & DETAILS
S1.0	FOUNDATION AND SLAB PLAN	E101	FLOOR PLAN - ELECTRICAL - POWER
S2.0	ROOF FRAMING PLAN	E102	FLOOR PLAN - ELECTRICAL - LIGHTING

ARCHITECTURAL FIRM OF RECORD:




**Design  
Elements**

Michael L. Saieed, Jr., AIA, LEED-AP  
Architect

ENGINEERING FIRM


(MECHANICAL, ELECTRICAL, PLUMBING) OF RECORD:



**McDOWELL CONSULTING  
ENGINEERS, INC**

P.O. BOX 367  
HAMPSTEAD, NC 28443  
TEL.(910) 270-3747 FAX.270-3779

ENGINEERING FIRM STRUCTURAL OF RECORD:



**DAVID TERKELTOUB AND ASSOCIATES  
CONSULTING ENGINEERS**

902 PINE GROVE DRIVE  
WILMINGTON, NC 28409  
PHONE: (910) 794-3070 FAX: (910) 794-3090

2012 APPENDIX B BUILDING CODE SUMMARY FOR ALL COMMERCIAL PROJECTS

Project information form including Name of Project, Address, Designer, and Construction details.

Table with columns for Building Data, Allowable Area, and Occupancy, detailing various building specifications.

Table for Design Loads Summary, including columns for Description and Allowable Area.

Table for Electrical System and Equipment, detailing requirements for various electrical components.

Table for Mechanical Summary, detailing requirements for mechanical systems.

Table for Energy Requirements, detailing requirements for energy efficiency.

Table for Allowable Area, detailing requirements for building area.

Life Safety System Requirements section, including checkboxes for various safety features.

Table for Exit Requirements, detailing requirements for exits and egress paths.

Table for Plumbing Fixture Requirements, detailing requirements for plumbing fixtures.

Table for Design Loads Summary, detailing requirements for design loads.

Table for Electrical System and Equipment, detailing requirements for electrical systems.

Table for Mechanical Summary, detailing requirements for mechanical systems.

Table for Energy Requirements, detailing requirements for energy efficiency.

Table for Allowable Area, detailing requirements for building area.

Table for Fire Protection Requirements, detailing requirements for fire protection.

Table for Allowable Area, detailing requirements for building area.

COMcheck Software Version 4.0.5.1 Envelope Compliance Certificate

Section 1: Project Information

Form for Section 1: Project Information, including Construction Site, Owner/Agent, and Designer/Contractor details.

Section 2: Envelope Assemblies and Requirements Checklist

Table for Section 2: Envelope Assemblies and Requirements Checklist, detailing requirements for various envelope assemblies.

Air Leakage, Component Certification, and Vapor Retarder Requirements


- List of requirements for Air Leakage, Component Certification, and Vapor Retarder.

- List of requirements for Additional Efficiency Package Requirements.


Section 3: Compliance Statement

Compliance Statement text regarding the project's adherence to building codes.

Table for Section 3: Compliance Statement, detailing compliance with various codes.



GENERAL ARRANGEMENT LIFE SAFETY PLANS



LEGEND (LIFE SAFETY PLAN)

- Legend defining symbols for fire extinguishers, exit signs, exits, no exit, egress means, and travel paths.

Vertical text on the left margin: 0 3/28/18 ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL

Vertical text on the right margin: THIS SHEET SHOWS BASIC DRAFTING STANDARDS. THIS DRAWING AND THE DESIGNS SHOWN ARE THE PROPERTY OF MICHAEL L. SAIEED, ARCHITECT & DESIGN ELEMENT, INC.

Design Elements logo and contact information for Michael L. Saieed, RA, AIA, LEED-AP.

Proposed Dispatch Office Building for Crete Solutions, LLC logo and contact information for Michael L. Saieed, RA, AIA, LEED-AP.

**Design Elements**  
 M. L. Saeed (Michael), AIA, LEED-AP  
 Architect / President  
 239 Raleigh Street  
 Wilmington, North Carolina 28405  
 910.597.3131

**Proposed Dispatch Office Building for  
 Crete Solutions, LLC**  
 ACCESSIBILITY DETAILS, SYMBOLS AND LEGENDS  
 Contract Documents - Issued for Construction


30/2018  
 THE PROFESSIONAL SEAL OF MICHAEL L. SAEED, ARCHITECT

date 2/15/18  
 job no. CRETE/BUS  
 drawn by MSAIEED  
 checked by MSAIEED  
 drawing no. N100  
 revision no. 0


**FLOOR PLAN LEGEND**

- SIGN-** WALL MOUNTED (DOOR MOUNTED IF NOT APPLICABLE) IDENTIFICATION SIGNAGE (SEE SIGNAGE DETAIL SHEET B/N100)
- 1** DESIGNATES WALL TYPE CONSTRUCTION; (SEE SHEET 1/N102 FOR TYPICAL WALL TYPES)
- FE** FIRE EXTINGUISHER WALL MOUNT UNIT W/ LEVER HT. @ 42" AFF (MULTI-PURPOSE CARBON DIOXIDE (MIN.10lb) CLASS TYPE ABC)
- FEC** FIRE EXTINGUISHER & SEMI-RECESS METAL CABINET; IN-WALL MOUNTED 42" AFF FROM TOP LEVER/HANDLE (MIN.10lb) CLASS TYPE ABC; FACE FINISHED CABINET SHALL NOT EXTEND > 4" INTO ANY PATH OF CIRCULATION; PROVIDE RATED CABINET WHERE INSTALLED IN RATED WALL.
- #** INDICATES DOOR IDENTIFICATION NUMBER; SEE ARCH SHT XXX FOR INFORMATION ON NOM. DOOR/FRAME SIZES, DESIGNATION TYPES & HARDWARE (REFERENCE ARCH XXXX FOR DETAILED INFORN)
- A** INDICATES WINDOW IDENTIFICATION NUMBER; REF. SEE SHEET D/A201 FOR DETAILED INFORMATION FOR WINDOW FRAME DIMENSIONS AND NOTES
- SWC/HM** (WIDTH) x (HEIGHT) DESIGNATES SIZES AND DOOR - SOLID WOOD CORE (SWC) AND FRAME - METAL FRAME (HM) HOLLOW METAL OR METAL KNOCK DOWN FRAME
- M.T.** DESIGNATES EXTRUDED (SOLID) ALUMINUM FLOOR FINISH FLUSH TRANSITION THRESHOLD; ADAAG/HC "BARRIER FREE" ACCESSIBLE CROSS-OVER (MAX. 1/2" THK'N)
- E.U.** EXPANSION CONSTRUCTION JOINT EXTERIOR (NOM. 1/2"); TRAFFIC GRADE BITUMINOUS MATERIAL; PERIMETER CONCRETE SLAB TO WALL
- M.T.S.** ALUM. EXTRUDED THRESHOLD TRANSITION STRIP; APPROPRIATE FINISH STRIP, JOINT SYSTEM AT FINISHED FLOORING CHANGES FROM ONE MATERIAL TO ANOTHER; TYPICAL FINISHED CARPET TO TAPERED TO FINISHED CONCRETE SLAB; DISABILITY ACCESSIBLE (ANSI/ADAAG)
- C.T.J.** CONCRETE FLAT SLAB CONTROL JOINT; PER-FORMED "T-SHAPE" PLASTIC CRACK CONTROL STRIP (OPTIONAL: SAW CUT CONTROL JOINT; SAW CUT TOP SURFACE)
- C.J.** CONSTRUCTION JOINT; SEPARATE FLOOR SLAB POUR W/ FORMED CONT. (SHEAR) KEYWAY AT ABUTTING PERIMETER SLAB EDGES
- C.S.** CONCRETE SLAB CONTROL JOINT; TOOLED JOINT
- +** ARCHITECTURAL VERTICAL CONTROL; SURFACE FINISHED ELEVATION POINT
- FD** FLOOR DRAIN, APPROXIMATE LOCATION CAST-IN-SLAB RECESS AND SLOPE FOR DRAINAGE (MIN 16" SQ. FLOOR SLAB TAPERED TO DROPPED INLET WASTE DRAIN) REFERENCE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION
- DESIGNATES PROPOSED (NEW WORK) WOOD STUD WALL FRAMING LOCATIONS (REFERENCE A/XXX FOR TYPICAL WALL TYPE CONSTRUCTION ASSEMBLY)
- (HC)** DESIGNATED AS HANDICAPPED ACCESSIBILITY "ARCHITECTURAL BARRIER FREE" (CLEAR FLOOR AREA: 60" DIAMETER TURNING AND 60"x60" SQUARE SPACE DENOTED ADA/ANSI) (OR) 30"x48" FORWARD AND SIDE APPROACHES

**SYMBOL KEY**



**BUILDING LINE DEFINITION**



**VERTICAL CONTROL EQUIVALENTS:**

- FF** - ARCHITECTURAL (DENOTED FOR SIMPLISTIC DESIGNS) FINISHED FIRST FLOOR ELEVATION (EL) = 0'-00" (0.00' A.F.F.))
- FG** - ARCHITECTURAL FINISHED GRADE ELEVATION (EL) = (-)3.000' A.F.F. (EST. 5'-0" FROM DESIGNATED BUILDING LINE)
- EL FF** - CIVIL SITE PLAN = FINISHED SLAB ELEVATION (MHSL)
- FG** - FINISH GRADE (BUILDING GRADE PERIMETER) = EL. (T.B.D.) MSL (EST. 12'-0" FROM DESIGNATED BUILDING LINE) (SEE CIVIL SITE DWG'S FOR ACTUAL FINISH GRADE (DECIMAL (FT) DESIGNATION))


**CONVERSION CHART**

US STANDARD STEEL GAUGE EQUIVALENTS IN NOMINAL DIMENSIONS







MINIMUM DELIVERED THICKNESS (mils)	REFERENCE GAUGE STEEL SHEET (ga)	REFERENCE THICKNESS ALUMINUM 3003 (mils)
18	25	0.018"-0.021"
27	22	0.027"-0.031"
33	20	0.035"-0.040"
43	18	0.042"-0.045"
54	16	0.050"-0.055"
68	14	0.064"-0.071"
97	12	0.080"-0.102"

**GENERAL ABBREVIATIONS**

- ADA AMERICAN/DISABILITY ACT  
 ADAAG ADA ACCESSIBLE GUIDELINES  
 AFF ABOVE FINISHED FLOOR\*  
 AFG ABOVE FINISHED GRADE\*  
 AGDR AGGREGATE  
 AIR ANCHOR  
 AHU AIR HANDLING UNIT\*  
 ALUM ALUMINUM  
 ALT ALTERNATE  
 ANOD ANODIZED  
 ASSY ASSEMBLY  
 ATACH ATTACHMENT  
 AVG AVERAGE  
 AUTH AUTHORITY HAVING JURISDICTION  
 BRD BOARD  
 BTUM BITUMINOUS  
 BL BUILDING LINE  
 BLDG BUILDING  
 BLK BLOCK  
 BM BEAM  
 BOT BOTTOM  
 BRG BEARING  
 C/C CENTER TO CENTER\*  
 CAB CABINET  
 CPT CARPET  
 CAV CAVITY  
 CD CORNER GUARD\*  
 CEMT CEMENT  
 CER CERAMIC  
 CHAN CHANNEL  
 CHRF CHAIR\*  
 CJ CONSTRUCTION JOINT  
 CL CENTER LINE  
 CLG CEILING  
 CJ CONTROL JOINT  
 CLR CLEAR  
 CMU CONCRETE MASONRY UNIT\*  
 CO CASED OPENING\*  
 COL COLUMN  
 CONC CONCRETE  
 CONN CONNECTION  
 CONST CONSTRUCTION  
 CONT CONTINUOUS (ACTION)  
 DBL DOUBLE  
 DEMO DEMOLITION\*  
 DET DETAIL  
 DIF DRINKING FOUNTAIN  
 DIM DIMENSION  
 DIST DISTANCE  
 DN DOWN  
 DS DOWNSPOUT  
 DWG DRAWING  
 EL ELEVATION  
 EMER EMERGENCY  
 EQ EQUALLY SPACED  
 EQUIP EQUIPMENT  
 EST ESTIMATE  
 EW EACH WAY  
 EWC ELECTRICAL WATER COOLER  
 EWH ELECTRICAL WATER HEATER\*  
 EXHT EXHAUST FAN\*  
 EXP EXPANSION  
 EJ EXPANSION JOINT  
 EXST EXISTING  
 EXT EXTERIOR  
 FAOP FIRE ALARM UNIT\*  
 FLD FLOOR DRAIN  
 FDN FOUNDATION  
 FEC FIRE EXTINGUISHER CABINET\*  
 FRIP FIRE/RIBRIG/ASS\*  
 FIN FINISH\*  
 FM FL FINISH FLOOR\*  
 FSR FINISH PER SQUARE FOOT  
 FLR FINISH GRADE\*  
 FLD FLOORING\*  
 FT FOOTING  
 GA GAGE  
 GALV GALVANIZED  
 GND GROUND  
 GYP BD GYPSUM BOARD\*  
 H PLAM HIGH PRESSURE LAMINATE\*  
 HC HOLLOW CORE\*  
 HDBR HARDWARE\*  
 HGT HEIGHT  
 HDRE HORIZONTAL  
 HPT HIGH POINT  
 HVAC HEATING, VENTILATION, AIR CONDITIONING\*  
 HWH HOT WATER HEATER  
 INSUL INSULATION  
 INTR INTERIOR  
 JST JOIST\*  
 JNT JOINT  
 LAM LAMINATION  
 LAV LAVATORY  
 LONG LONGITUDINAL  
 LPT LOW POINT\*  
 LT WT LIGHT WEIGHT\*  
 LTD LFL LIGHTING PANEL\*  
 LV LAMINATED VENEER LUMBER  
 MASO MASONRY\*  
 MATL MATERIAL  
 MAX MAXIMUM  
 MECH MECHANICAL  
 MET METAL  
 MFG MANUFACTURING  
 MIN MINIMUM  
 MISG MISCELLANEOUS  
 MO MASONRY OPENING  
 MR MOISTURE RESISTANT  
 MTD MOUNTED  
 NA NOT APPLICABLE  
 NIC NOT IN CONTRACT  
 NO NOT IN CONTRACT  
 NOM NOMINAL  
 NTS NOT TO SCALE  
 O/C ON CENTER  
 OD OUTSIDE DIAMETER  
 OPP OPPOSITE  
 OVHD OVERHEAD  
 PEMP PRE-ENGINEERED METAL (MFR) BUILDING PERP PERPENDICULAR  
 PLYWD PLYWOOD  
 PR PAIR  
 PREFAB PREFABRICATED  
 PREFIN PREFINISHED\*  
 PRELUM PRELUMINARY\*  
 PSI POUNDS PER SQUARE FOOT  
 PFI POUNDS PER SQUARE INCH  
 PTD PRESSURE TREATED  
 PTD PAINTED  
 REF REFERENCE  
 REINF REINFORCE(D)(ING)(MENT)  
 REQ REQUIRED  
 RO ROUGH OPENING  
 SCHED SCHEDULE  
 SHT SHEETING\*  
 SIM SIMILAR  
 SPEC SPECIAL  
 SPEC SPECIFICATION  
 SF (SqFt) SQUARE FOOT  
 SS STAINLESS STEEL  
 STC SOUND TRANSMISSION CLASS\*  
 STD STANDARD  
 STL STEEL  
 STOR STORAGE  
 STRUCT STRUCTURAL\*  
 TAB TOP AND BOTTOM  
 TAG TAGS AND GROOVE  
 TIC TOP OF (CONSTRUCTED ELEMENT)  
 THK THICKNESS\*  
 TRIP THROUGH  
 TEMP TEMPERED GLASS\*  
 TOL TOTAL  
 TV TELEVISION  
 TYP TYPICAL  
 TEL TELEPHONE CABINET\*  
 TYP TYPICAL  
 TBD TO BE DETERMINE  
 UNO UNLESS OTHERWISE NOTED\*  
 VCT VVVV COMPOSITION TILE\*  
 VERT VERTICAL  
 W/ WITH  
 W/O WITHOUT  
 W/W WALL TO WALL\*  
 WC WATER CLOSET  
 WCO WALL CLEANOUT\*  
 WD WOOD  
 WFE WELDED WIRE FABRIC\*  
 WFMW TRANSFORMER




**TACTILE SIGN DETAILS** NOT TO SCALE:







no.	date	revision	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL
A	2/19/18		SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18		DESIGN DEVELOPMENT PROGRESS REVIEW
0	3/28/18		ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL



### FOUNDATION PLAN

SCALE: 1/4" = 1'-0"



### GENERAL FOUNDATION PLAN NOTES

**PRE-CONSTRUCTION SITE PREP** REMOVE REQUIRED LAYERS OF EXISTING TOPSOIL (ORGANIC SOIL) GRADES OF SOFT CLAY AND OTHER UNSUITABLE MATERIALS UNDER ALL FLOOR SLABS, RIBBON SLABS, FOOTINGS, AND 5'-0" BEYOND BUILDING FOOTPRINT EXTERIOR WALLS. REFERENCE GEO-TECHNICAL SOIL ENGINEERING REPORT OF SUBSURFACE INVESTIGATION FOR PROPER SOIL BEARING CONDITIONS FOR RECOMMENDATIONS TO STRUCTURALLY SITE PREP AND CONDITION TO IMPROVE EXISTING GRADES AT DEPTHS (DENSIFY THE SOIL) TO ACHIEVE PROPER SOIL BEARING CAPACITIES AND (IF REQUIRED) SEISMIC RESISTANCE. PREPARED SOILS SHALL BE CLEANED OF ALL VEGETATION AND ORGANIC MATERIAL. **TERMITE TREAT BEFORE CONSTRUCTING BUILDING PAD, PERIMETER SLABS AND FOUNDATIONS.** GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO REFERENCE STRUCTURAL DRAWINGS AND BUILDING OWNER PROVIDED PROFESSIONAL SOIL ENGINEER'S SUBSURFACE GEO-TECHNICAL SOIL REPORT (OPTIONAL: REMOVED ORGANIC SOILS TO BE STORED AND REUSED FOR LANDSCAPING)

ALL FOUNDATIONS (FOOTINGS) SHALL BEAR ON UNDISTURBED (WITHOUT ORGANIC) SOIL (OR) SELECT FILL CAPABLE OF SUPPORTING A DESIGN BEARING PRESSURE OR 1500 PSF; WHERE THE BOTTOM OF FOUNDATION ELEVATION DOES NOT EXTEND TO SUITABLE UNDISTURBED SUBSOIL, ALL UNSUITABLE MATERIAL SHALL BE REMOVED AND THE BUILDING FOOTPRINT PAD SHALL BE FILLED WITH CLEAN MATERIAL SELECT AND COMPACTED TO 95% DENSITY (COMPACTION PROCEDURE PER ASTM D698 RECOMMENDATIONS) FILL FOR BUILDING PAD SHALL BE TESTED FOR COMPACTION BY A CERTIFIED GEO-TECHNICAL SOIL ENGINEERING TESTING FIRM. TEST SHALL BE CONDUCTED IN AN AREA OF PROPOSED TRENCHED FOOTING, ONE TEST PER 25 LINEAR FEET OF FOOTING. FOOTING SUB GRADE WILL NOT BE ACCEPTABLE UNIT TESTS HAVE BEEN PASSED (OR) GENERAL CONTRACTOR ACCEPTS SURETIES AND RESPONSIBILITIES FOR EXISTING SOIL CONDITIONS TO RESIST BUILDING SETTLEMENT ISSUES.

REFERENCE ARCHITECTURAL (TYP) WALL SECTIONS (AND IF PROVIDED AS SUPPLEMENT; STRUCTURAL DRAWINGS TAKES PRECEDENCE OVER ARCHITECTURAL)

### GENERAL CONDITIONS AND NOTES

PLAN DIMENSIONS OF INTERIOR WALLS ARE MEASURED FROM FACE TO FACE OF WALL STUD END FACE EDGE AND FACE OF MASONRY, FACE OF FLOOR SLAB/MASONRY FOUNDATION WALL, UNLESS NOTED OTHERWISE; REFERENCE ARCHITECTURAL SHEET A100 FOR DIMENSIONAL LOCATIONS OF WALLS AND PLUMBING FIXTURES LOCATIONS; GENERAL CONTRACTOR SHALL PROVIDE (AND CHECK REFERENCE WITH PROPRIETARY VENDOR SPECIFICATIONS AND SPECIALITY EQUIPMENT DRAWINGS) ALL LAYOUTS (AND UNDER SLAB (COMMON AND SPECIALITY) SERVICES) REQUIRED BEFORE CONSTRUCTION BEGINS

ALL CONCRETE FLOOR SLABS OVER EXCAVATION TRENCHING FOR BUILDING UNDER SLAB OPERATIONAL SERVICES SHALL BEAR ON UNDISTURBED (WITHOUT ORGANIC) SOIL (OR) SELECT FILL CAPABLE OF SUPPORTING A DESIGN BEARING PRESSURE OR 1500 PSF IF GEO-TECH WHERE BACKFILLING (SUB-GRADE) SOIL IS REQUIRED WITHIN EXCAVATED TRENCHED AREAS THE SUB-GRADE SOIL MATERIAL SHALL BE CLEAN SELECTED AND COMPACTED IN 8-INCH LAYERS TO A (MINIMUM) 95% STANDARD PROTECTOR DRY DENSITY (COMPACTION PROCEDURES SHALL FOLLOW ASTM D698 RECOMMENDATIONS); TEST SHALL BE CONDUCTED IN AN AREA OF PROPOSED TRENCHING, ONE TEST PER 25 LINEAR FEET OF FOOTING. FOOTING SUB GRADE WILL NOT BE ACCEPTABLE UNIT TESTS HAVE BEEN PASSED (OR) GENERAL CONTRACTOR ACCEPTS SURETIES AND RESPONSIBILITIES FOR EXISTING SOIL CONDITIONS TO RESIST BUILDING SETTLEMENT ISSUES.

FINAL SUB-GRADE BACKFILL SHALL BE FINISHED FLUSH AND LEVEL TO EXISTING BASE SOIL (UNDER SLAB) SUB-GRADE AS NOT TO CAUSE ANY UN-INFORMED THICKNESS OF CONCRETE FLOOR SLAB CONSTRUCTION. GENERAL CONTRACTOR ACCEPTS SURETIES AND RESPONSIBILITIES FOR EXISTING SOIL CONDITIONS AND SUB-GRADE SOIL BACKFILL TO RESIST FLOOR SLAB SETTLEMENT ISSUES. (ONLY IF PROVIDED AS A SUPPLEMENT; REFERENCE STRUCTURAL DRAWINGS FOR ADDITIONAL INFORMATION TO TAKE PRECEDENCE)

ALL CONCRETE FOOTINGS, INCLUDING FLOOR (IF PROVIDED CUSTOM COLORED) SLAB-ON-GRADE SHALL OBTAIN A COMPRESSIVE STRENGTH OF (MIN) 3,500 psi AT AN AGE OF 28 DAYS AND A MAXIMUM SLUMP OF 5 INCHES, UNLESS NOTED OTHERWISE. (DO NOT AIR ENTRAIN CONCRETE) (ONLY IF PROVIDED AS A SUPPLEMENT; REFERENCE STRUCTURAL DRAWINGS FOR ADDITIONAL INFORMATION TO TAKE PRECEDENCE)

ALL REINFORCING STEEL SHALL BE IN ACCORDANCE WITH ASTM A615, GRADE 60 ksi; PLACEMENT AND PROTECTION (AND CLEAN FROM SURFACE RUST) OF STEEL REINFORCING SHALL BE IN ACCORDANCE WITH THE LATEST EDITION OF A.C.I. 318; WHERE CONTINUOUS REINFORCING BARS ARE REQUIRED THERE SHALL BE A MIN. 3/8" (X) BAR DIAMETER AT END LAPPED SPLICES

MINIMUM CLEAR COVER ON REINFORCING: PER ACI 318 (LATEST EDITION) CONCRETE CAST AGAINST AND PERMANENTLY EXPOSED TO SOILS: 3" CONCRETE OVER EXPOSED TO SOIL; WELD WIRE FIBER (W.W.F.) MID-POINT (CENTER) PLACEMENT WITHIN CONCRETE FLOOR SLAB

ALL CONCRETE MASONRY UNITS (CMU) SHALL BE IN ACCORDANCE WITH ASTM C-90 TYPE I GRADE N-1 (FM 1350psi); GROUT FOR MASONRY WALL SHALL COMPLY WITH ASTM C-476, AND SHALL BE PROPORTIONED TO OBTAIN A 28 DAY COMPRESSIVE STRENGTH OF 2500psi; ALL MORTAR SHALL BE ASTM C-270, TYPE M OR S.

### LEGEND

- FLOOR DRAIN, APPROXIMATE LOCATION CAST-IN-SLAB RECESS AND SLOPE FOR DRAINAGE (MIN 18" SQ. FLOOR SLAB TAPERED TO DROPPED INLET WASTE DRAIN) REFERENCE PLUMBING DRAWINGS FOR ADDITIONAL INFORMATION
  - C.S. CONCRETE FLAT SLAB CONTROL JOINT (APPROXIMATE LOCATION) WHERE APPLICABLE PLACE UNDER PARTITION WALLS; PRE-FORMED "T-SHAPE" PLASTIC CRACK CONTROL STRIP (OPTIONAL: SAW CUT CONTROL JOINT; SAW CUT TOP SURFACE)
  - E.J. EXPANSION CONSTRUCTION JOINT, (NOM. 1/2" WIDTH) EXTERIOR TRAFFIC GRADE BITUMINOUS MATERIAL; PERIMETER FOUNDATION TO SLAB EDGE; WEATHER TIGHT JOINT SEAL W/ POUR-ABLE SELF LEVELING SEALANT (SIMILAR MFR: SIKAFLEX)
  - UNDERGROUND PVC CONDUIT STUB UP FOR MULTIPLE CIRCUITED ELECTRICAL JUNCTION BOX(S) (ELECTRICAL OUTLET(S) COMBINATION; REFERENCE ELECTRICAL DRAWINGS; VERIFY LOCATION WITH GENERAL ARRANGEMENT FLOOR PLAN, CAP ALL CONDUITS/PIPING DURING CONSTRUCTION. PVC CONDUIT ONLY AT UNDERGROUND LOCATIONS. (SCHEDULE 20 PVC, UTILIZE 45° BENDS ONLY); COORDINATE FINIAL LOCATIONS WITH BUILDING OWNER.
  - NOM. 8" CONCRETE MASONRY UNIT FOUNDATION WALL (REFERENCE ARCHITECTURAL WALL SECTION FOR ADDITION INFORMATION) SEE STRUCTURAL WORKING DRAWINGS FOR CONSTRUCTION DETAILS AND SPECIFICATION NOTES
- (TYPICAL; UNLESS NOTED OTHERWISE) CONCRETE MASONRY UNITS SHALL BE IN ACCORDANCE WITH ASTM C-90 TYPE I GRADE N-1 (FM 1350psi); GROUT FOR MASONRY WALL SHALL COMPLY WITH ASTM C-476, AND SHALL BE PROPORTIONED TO OBTAIN A 28 DAY COMPRESSIVE STRENGTH OF 2500psi; ALL MORTAR SHALL BE ASTM C-270, TYPE M OR S.

### PLAN KEYNOTES

- REMOVE REQUIRED LAYERS OF EXISTING (ORGANIC SOIL) FINISHED TOPSOIL GRADE TO VIRGIN GRADE SOIL LEVEL; (IF PROVIDED AS NECESSARY, REMOVE TOPSOIL AT DEPTHS DENOTED IN GEO-TECHNICAL SOIL ENGINEERING REPORT). PREPARED BUILDING FOOTPRINT BEARING SOIL SHALL BE CLEANED OF ALL VEGETATION AND ORGANIC MATERIAL (OPTIONAL: REMOVED ORGANIC SOILS TO BE STORED AND REUSED FOR LANDSCAPING)
- BACK-FILL SUB-GRADE FOR ELEVATED FLOOR SLAB AND SPREAD FOOTING BEARING; PROVIDE CLEAN SANDY/CLAY SOIL (IF REQUIRED BY GEO-TEC SOIL ENGINEER'S REPORT; #57 AGGREGATE) IN COMPACTED "LIFT GRADE" 8 INCH LAYERS (MIN. 95% COMPACTION (MECHANICAL ACTION) OF EACH LAYER) IF PROVIDED AS NECESSARY GENERAL CONTRACTOR TO REVIEW BUILDING OWNER'S PROVIDED "SOIL ENGINEER'S" REPORT OF SUBSURFACE INVESTIGATION FOR PROPER SOIL BEARING CONDITIONS
- "VAPOR BARRIER (VB)" UNDER CONDITIONED SPACES ONLY (MIN. 15mil) UNDER CONCRETE FLOOR SLAB (OVER CLEAN COMPACTED/ELEVATED GRADE LIFT SUB-BASE SOIL) MOISTURE PROTECTION-PUNCTURE RESISTANT PLASTIC SHEETING (METALLOCENE POLYOLEFIN); PROVIDE MIN. 6" SEAL LAPPED JOINTS WITH TAPED SEAMS INSTALLATION; THRU BARRIER/SLAB PIPE PENETRATIONS (w/ PLUMBING AND ELECTRICAL SERVICES) SHALL BE TAPED (OR) MASTIC (MFR: "STEGO INDUSTRIES-15MIL," ASTM E1745 CLASS A; WITH 0.01 PERMANENCE)
- CONTINUOUS 8" CONCRETE MASONRY UNIT FOUNDATION WALL; REINFORCED W/ #5 HOOKED VERT. DOWELS TO FOOTING, TYPICAL 2'-0" O/C. AND MAX. 16" FROM INSIDE/OUTSIDE BUILDING CORNERS; STAGGER PLACEMENT 24" FROM TRAVERSE BARS; PROVIDE HORZ MASONRY "TRUSS TYPE" REINF. @ 8" VERT. O.C.; CONCRETE GROUT (PEA GRAVEL (MAX. 3/8" DIA) AGGREGATE) FILL ALL CMU CELLS SOLID.
- MIN. 4" THK CONCRETE SLAB ON GRADE; REINFORCED W/ 6x6 W2.1-W2.1 (FLAT SHEETS) W.W.F. ON VAPOR BARRIER OVER CLEAN COMPACTED DRAINAGE SUB-BASE AGGREGATE (CONC Fy 3500 psi; STL. TROWEL SURFACE FINISH)
- EXTERIOR CONCRETE SLAB ON ELEVATE GRADE; NOM. 4" THK'N REINFORCED W/ 6x6 1.4-1.4 W.W.F. OVER CLEAN COMPACTED GRANULAR SUBFILL (CONC 2800 psi; LIGHT BROOM SURFACE FINISH) SITE-VERIFY AND MODIFY TO MATCH EXISTING GRADE CONDITIONS. HORIZONTAL RUNS SHALL NOT EXCEED VERTICAL GRADIENT FOR: WALKWAY 1:20; SLOPE ACCESSIBLE RAMPS: 1:12; MAX. (FIXED) CROSS SLOPE (FROM CENTER) SIDE DRAINAGE 1/4" PER FOOT
- PROPOSED ELECTRICAL POWER AND LIGHTING PANELS; PROVIDE (2) ADDITIONAL UNDER SLAB 2" DIA. PVC SPARE CONDUITS "STUB-UP" (MIN. 6" AFF) AND CAP UNDER ELEC PANEL (SEE ELECTRICAL DRAWINGS FOR ADDITIONAL DETAILED SERVICES & "MD" PNL LOCATIONS)

COPYRIGHT: DESIGN ELEMENTS 2018 THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAEGE, ARCHITECT & DESIGN ELEMENTS INC. THE REPRODUCTION, COPYING OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND IMPROPER. THIS SHEET SHOWS BASIC DRAFTING STANDARDS WILL BE SUBJECT TO LEGAL ACTION.

Proposed Dispatch Office Building for  
**Crete Solutions, LLC**

239 Raleigh Street  
Wilmington, North Carolina 28401

ARCHITECTURAL FOUNDATION PLAN  
Contract Documents - Issued for Construction

M. L. Saegge (Michael), AIA, LEED-AP  
Architect / President  
Wilmington, North Carolina 28405  
910.309.3131

DATE: 2/15/18  
JOB NO.: CRETE/BUS  
DRAWN BY: MSAIEED  
CHECKED BY: MSAIEED  
DRAWING NO.: AS100  
REVISION NO.: 0

**STRUCTURAL NOTES**

**GENERAL**

1. DESIGN LOADS:
- |        |           |         |
|--------|-----------|---------|
| ROOF:  | LIVE LOAD | 20 PSF  |
| FLOOR: | LIVE LOAD | 150 PSF |

BASIC WIND DESIGN VELOCITY: 130 MPH (N.C. STATE BUILDING CODE LATEST EDITION).  
 DESIGN PRESSURES PER ASCE 7-05 EXPOSURE C  
 NET UPLIFT:  $a = 5.0$  FT.  
 ZONE 1: 35 PSF ZONE 2 & 3: 45 PSF

IMPORTANCE FACTORS: Wind ( $I_w$ ) 1.0  
 Snow ( $I_s$ ) 1.0  
 Seismic ( $I_e$ ) 1.0

COLLATERAL LOAD: 5.0 psf  
 GROUND SNOW LOAD: 10.0 psf  
 WIND LOAD: Basic Wind Speed 130 MPH (ASCE-7-05)  
 Exposure Category C

Wind Base Shears (for MWFRS)  $V_x = 56.0K$   $V_y = 48.0K$

SEISMIC DESIGN CATEGORY A  
 Compliance with Section 1616.4 only?  Yes  No  
 SEISMIC DESIGN CATEGORY  B  C  D  
 Provide the following Seismic Design Parameters:  
 Seismic Use Group \_\_\_\_\_  
 Spectral Response Acceleration  $S_S = 29.24\%$   $S_1 = 9.7\%$   
 Site Classification E  Field Test  Presumptive  Historical Data  
 Basic Structural System (check one)  
 Bearing Wall  Dual w/Special Moment Frame  
 Building Frame  Dual w/Intermediate R/C or Special Steel  
 Moment Frame  Inverted Pendulum

Seismic base shear  $V_x = 31.6$   $V_y = 31.6$   
 Analysis Procedure  Simplified  Equivalent Lateral Force  Modal  
 Architectural, Mechanical, Components anchored? \_\_\_\_\_

LATERAL DESIGN CONTROL: Earthquake \_\_\_\_\_ Wind

SOIL BEARING CAPACITIES:  
 Field Test (provide copy of test report) \_\_\_\_\_ psf  
 Presumptive Bearing Capacity 2000 psf  
 Pile size, type, and capacity \_\_\_\_\_

2. STRUCTURE SHALL BE BRACED UNTIL CONSTRUCTION IS COMPLETE.

**LAYOUT**

1. THE CONTRACTOR SHALL PROVIDE ALL LAYOUT REQUIRED TO CONSTRUCT HIS WORK.

**FOUNDATION**

1. FOOTING DESIGN IS BASED ON AN ALLOWABLE SOIL BEARING PRESSURE OF 2000 PSF.  
 2. REMOVE TOPSOIL, ORGANICS, SOFT CLAY AND OTHER UNSUITABLE MATERIALS UNDER ALL FLOOR SLABS, FOOTINGS, AND 5'-0" BEYOND BUILDING WALLS. BACKFILL AS REQUIRED WITH CLEAN SELECT FILL COMPACTED IN 8-INCH LAYERS TO A MINIMUM OF 95% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY. AT OPTIMUM MOISTURE CONTENT IN ALL LAYERS UP TO THE UPPER ONE FOOT. FILL TO BE PLACED WITHIN 12-INCHES OF THE DESIGN SUBGRADE ELEVATION SHALL BE COMPACTED TO 98% OF THE STANDARD PROCTOR MAXIMUM DRY DENSITY AT OPTIMUM MOISTURE CONTENT.

**CAST-IN-PLACE CONCRETE**

1. CONCRETE COMPRESSIVE STRENGTH AT 28 DAYS: 4000 PSI  
 2. REINFORCING STEEL: ASTM A615, GRADE 60  
 3. WELDED WIRE MESH: ASTM A185  
 4. MINIMUM CLEAR COVER ON REINFORCING: PER ACI 318 (LATEST EDITION)  
 5. DOWELS AND CONTINUOUS REINFORCING SHALL HAVE A MINIMUM LAP OF 30 BAR DIAMETERS, BUT SHALL NOT BE LESS THAN 24 INCHES.  
 6. PROVIDE AIR ENTRAINMENT OF 4 TO 6 PERCENT IN EXTERIOR CONCRETE.

**MASONRY**


1. COMPRESSIVE STRENGTH OF CONCRETE MASONRY UNITS: GRADE N, TYPE I, ASTM C90, FM=1500 PSI MINIMUM.  
 2. COMPRESSIVE STRENGTH OF MORTAR AT 28 DAYS SHALL BE 1800 PSI MIN., TYPE M OR S.  
 3. TIE WYTHES WITH HORIZONTAL REINFORCING AS SPECIFIED.

**STRUCTURAL TIMBER**


1. LUMBER SHALL BE SOUTHERN YELLOW PINE OR SPF GRADE 2 MINIMUM.  
 2. ALL WORK SHALL COMPLY WITH THE N.C. STATE BUILDING CODE (LATEST EDITION). WOOD CONNECTIONS AND DETAILS NOT SHOWN ON THE DRAWINGS SHALL BE IN ACCORDANCE WITH THE "WOOD CONSTRUCTION" CHAPTER AND THE FASTENING SCHEDULES OF THE N.C. STATE BUILDING CODE.  
 3. LUMBER IN CONTACT WITH MASONRY OR CONCRETE SHALL BE PRESSURE TREATED WITH ACQ TO 0.25 PCF RETENTION.  
 4. LUMBER ABOVE GROUND AND EXPOSED TO WEATHER SHALL BE PRESSURE TREATED WITH ACQ TO 0.25 PCF RETENTION.

**WOOD TRUSS GENERAL NOTES**


1. TRUSS AND DETAILS ON THESE DRAWINGS ARE FOR ESTIMATING PURPOSES ONLY AND SUBJECT TO MODIFICATION DEPENDING ON THE PARTICULAR TRUSS USED.  
 2. TRUSS MANUFACTURER SHALL SUBMIT SHOP DRAWINGS AND DESIGN CALCULATIONS TO THE ENGINEER OF RECORD FOR APPROVAL BASED ON THE INFORMATION PROVIDED.  
 3. THE DRAWINGS AND CALCULATIONS SHALL BE SEALED BY AN ENGINEER LICENSED IN THE STATE OF NORTH CAROLINA.  
 4. DURING CONSTRUCTION AND ERECTION, THE CONTRACTOR SHALL ADEQUATELY BRACE AND SUPPORT ALL TRUSSES UNTIL ALL CONNECTIONS, PERMANENT BRACING, AND ROOF DECK ARE IN PLACE.  
 5. TRUSS LOADING:  
 ROOF TRUSSES  
 TOP CHORD DL = 10 PSF LL = 20 PSF WIND = 130 MPH  
 BOTTOM CHORD DL = 10 PSF LL = 10 PSF (NON-STORAGE)




**1 FOUNDATION AND SLAB PLAN**  
 S1.0 SCALE: 1/4" = 1'-0"



**2 SECTION**  
 S1.0 SCALE: 3/4" = 1'-0"



**3 SAWED CONST. JT.**  
 S1.0 SCALE: 1" = 1'-0"



**4 KEYED CONST. JT.**  
 S1.0 SCALE: 1" = 1'-0"

no.	date	revision
A	2/19/18	SCHEMATIC DESIGN, PROGRESS REVIEW, AND APPROVAL
B	3/7/18	DESIGN DEVELOPMENT, PROGRESS REVIEW

THIS SHEET SHOWS BASIC DRAFTING STANDARDS. THIS SHEET SHALL BE SUBJECT TO LEGAL ACTION.  
 COPYRIGHT © DESIGN ELEMENTS 2018. THE DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.

DAVID TERKELTOUB AND ASSOCIATES, P.C.  
 CONSULTING ENGINEERS  
 802 PINE GROVE DRIVE  
 WILMINGTON, NC 28409  
 PHONE: (910) 794-3070 FAX: (910) 794-3090  
 DT PROJECT NO. 16036  
 FIRM LICENSE NO.: C-2874  
THIS DRAWING IS THE PROPERTY OF DAVID TERKELTOUB AND ASSOCIATES, P.C. AND IS NOT TO BE REPRODUCED OR TRANSMITTED IN ANY FORM OR BY ANY MEANS, ELECTRONIC OR MECHANICAL, INCLUDING PHOTOCOPYING, RECORDING, OR BY ANY INFORMATION STORAGE AND RETRIEVAL SYSTEM, WITHOUT THE WRITTEN PERMISSION OF THE ENGINEER. © 2018

**Design Elements**  
 M. L. Saeed (Principal), AIA, LEED-AP  
 1312 Calhoun Drive, Suite 142  
 Wilmington, North Carolina 28405  
 P.O. Box 3131


**Proposed Office Building for Concrete Batching Plant**

239 Raleigh Street  
 Wilmington, North Carolina 28401

job status **Contract Documents - Issued for Construction**


date	2/15/18
job no.	CRETE/BUS
drawn by	DERKELTOUB
checked by	DERKELTOUB
drawing no.	S1.0
revision no.	B

no.	date	revision
A	2/19/18	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18	DESIGN DEVELOPMENT PROGRESS REVIEW



ALL HEADERS IN EXTERIOR WALLS SHALL BE  
 (3) 2X10s W/1/2" PLYWOOD FILLER PLATES  
 BETWEEN THE 2X10s

**1** ROOF FRAMING PLAN  
 S2.0 SCALE: 1/4" = 1'-0"




**2** SECTION  
 S2.0 SCALE: 3/4" = 1'-0"

Copyright: DESIGN ELEMENTS 2018

THIS SHEET SHOWS BASIC DRAFTING STANDARDS

THE DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAIEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.

**DAVID TERKELTOUB AND ASSOCIATES, P.C.**  
 CONSULTING ENGINEERS  
 802 PINE DRIVE DRIVE  
 WILMINGTON, NC 28409  
 PHONE: (910) 794-0700 FAX: (910) 794-3090  
 DT PROJECT NO. 18034  
 FIRM LICENSE NO.: C-2874  
THIS DRAWING IS THE PROPERTY OF DAVID TERKELTOUB AND ASSOCIATES  
 MADE OR IN PART MADE BY THE FLOORING OF B. FLOORING




**Design Elements**  
 M. L. Saieed (Michael), AIA, LEED-AP  
 Architect / President  
 Suite 142  
 239 Raleigh Street  
 Wilmington, North Carolina 28401  
 P.O. BOX 3131

**Proposed Office Building for  
 Concrete Batching Plant**



239 Raleigh Street  
 Wilmington, North Carolina 28401  
 job status **Contract Documents - Issued for Construction**

date	2/15/18
job no.	CRETE/BUS
drawn by	DTERKELTOUB
checked by	DTERKELTOUB
drawing no.	S2.0

no.	date	revision
A	2/19/18	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18	DESIGN DEVELOPMENT PROGRESS REVIEW
0	3/28/18	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL



### PROPOSED FLOOR PLAN



SCALE: 1/4" = 1'-0"

### GENERAL KEYNOTES

FOR THIS SHEET ONLY

- 01 HEATING/AIR CONDITIONING (HVAC) EXTERIOR COMPRESSOR UNIT W/ ON-GRADE CONCRETE MAINTENANCE PAD (EPOXY ADHESIVE ANCHORED BOLT UNIT IN-PLACE); (MIN. 4" THK CONC PAD); HVAC UNIT ZONED PER SINGLE FLOOR LEVEL (OCCUPIED SPACES); MECHANICAL UNIT ELECTRICAL DISCONNECT SWITCH EXTERIOR SURFACE WALL MOUNTED ABOVE GRADE (MIN. 36"); MIN. HORIZONTAL DISTANCE 36" AWAY FROM ANY UNIT; (REFERENCE MECHANICAL DRAWINGS FOR DETAILS)
- 02 ELECTRICAL MAIN DISTRIBUTION (CENTER) PANEL AND METER BASE; APPROXIMATE LOCATION (REFERENCE ELECTRICAL DRAWINGS)
- 03 PROPOSED RECESSED INTERIOR WALL MOUNTED ELECTRICAL (POWER AND LIGHTING) PANEL (APPROXIMATE CENTERLINE LOCATION); PROVIDED THRU WALL ABOVE (OR CENTERED) ELECTRICAL PANEL PVC CONDUIT, NOTE PROVIDE; (2) ADDITIONAL UNDER SLAB 2" DIA. PVC SPARE CONDUITS AND (1) 1" PVC SPARE CONDUIT "STUB-UPS" (MIN. 6" A.F.F. AND CAP) UNDER ELECTRICAL PANEL (ELECTRICAL PANEL AMPERAGE AND ITS DESIGNATED SERVICE ASSIGNED SPACES, SHALL BE COORDINATED WITH BUILDING OWNER AND BATCH-PLANT SPECIALIZE ELECTRICAL EQUIPMENT AND VERIFIED WITH ELECTRICAL CONTRACTOR) REFERENCE ELECTRICAL ENGINEER DRAWINGS FOR ADDITIONAL DETAIL INFORMATION)
- 04 EXTERIOR HOSE BIB; THRU WALL WALL SECUREMENT; PROVIDE FREEZE PROTECTION
- 05 (TYPICAL) ACCESSIBLE CONCRETE (FRONT EGRESS/ENTRY) WALKWAY/PARKING CURB STEP DOWN; (MIN. 5'-0" WIDTH U.N.O.) MIN. 4" THICKNESS EXTERIOR CONCRETE "SLAB/CURB ON GRADE" w/ TURN-DOWN PERIMETER THICK EDGES; REINFORCED SLAB/CURB W/ 6x6 1.4-1.4 W.W.F. (MESH SHEETS) OVER CLEAN COMPACTED GRANULAR SUBFILL (CONC 3000 psi); PROVIDE TOP/BOTTOM No.4 NOSING BARS AT TURN-DN EDGES;
- FINISHED WALKWAY/CURBING: HIGH POINT (HP) ELEVATION (-) 0.25" DROP FROM FINISHED CONCRETE FLOOR SLAB; LOW POINT (LP) MAX. 6" ELEVATED WALKWAY/CURBING ABOVE FINISH PAVEMENT; SLOPE WALKWAY/CURBING CROSS-SECTION FOR DRAINAGE (MAX. 1/4" IN 12"); LT. BROOM SURFACE TEXTURE FINISH PROVIDED W/ ADEQUATE CONTROL JOINT ON-CENTER MIN. NOMINAL SPACING EQUAL TO WIDTH OF WALKWAY/CURBING; OVERALL WALKWAY "RUN" SHALL NOT EXCEED 5% SLOPE; OFFSET EGRESS/ENTRY STOOP TO PROVIDE MIN. 18" WIDE (FLAT SURFACE) "ARCHITECTURAL BARRIER FREE" FORWARD APPROACH TO DOOR STRIKE SIDE
- SEE CIVIL/SITE PLANS FOR "ARCHITECTURAL BARRIER FREE" ACCESSIBLE ACCESS POINTS "CURB CUTS," LOCATIONS AND CONSTRUCTION DETAILS
- 06 (TYP) ACCESSIBLE SLOPED CONCRETE SIDEWALK AND APRON; SLOPE TO FINISHED WALKWAY (OR) FOR DRAINAGE (MAX. NOT TO EXCEED 6'-0" RUN LENGTH @ 1" IN 12" SLOPE; FLUSH TO FINISHED GRADE; MAX. 1/2" ELEVATION GRADE DIFFERENCE) SLOPE CROSS-SXN FOR DRAINAGE (MAX. 1/4" IN 12"); SITE VERIFY/ADJUST FOR WIDTH; REINF. W/ 1.4x1.4-6x6 W.W.F.; LIGHT BROOM TEXTURE FINISH;
- 07 (TYP) ACCESSIBLE CONCRETE STOOP ENTRY/EXIT ACCESS POINT; STOOP (NOMINAL FLAT) FLUSH TO FINISHED BUILDING FLOOR SLAB AT ACCESS POINT; SLOPE TO FINISHED WALKWAY (OR) ACCESSIBLE RAMP AT CROSS-SXN FOR DRAINAGE (MAX. 1/4" IN 12"); (REFERENCE KEYNOTE [05] FOR CONSTRUCTION)
- 08 PROPOSED TELEPHONE BACKBOARD (APPROXIMATE LOCATIONS; SEE PLAN) FOR EQUIPMENT SERVICE; MIN. 24"(W)x48"(H)-3/4"; SURFACE WALL MOUNTED (BOTTOM 30" A.F.F.) RATED PLYWOOD (FRTW) BACKER (BLUE) BOARD (UL-LISTED); PROVIDE DOUBLE GANG ELECTRICAL OUTLET (IF NOT DENOTE ON ELECTRICAL DRAWINGS)
- 09 NOM. 12"(W) x 30"(L) PRE-CAST CONCRETE SPLASH (GUARD) BLOCKS; PLACED DIRECTLY UNDER DOWNSPOUT DISCHARGE; LOCATIONS AS DENOTED; (OPTIONAL: DOWNSPOUTS SHALL CONNECT DIRECTLY TO UNDERGROUND STORM DRAINAGE)
- 10 ATTIC ACCESS "CEILING RECESS FOLDING PULL-DOWN" LADDER, ALUM EXTRUDED COMMERCIAL GRADE FRAMING; (MIN. 300lb CAP.) VERIFY R.O. DIMENSION W/PROPRIARY ACCESS STAIR MFR. AND COORDINATE W/ TRUSS VENDOR/SUPPLIER) PROVIDE MIN. 36"x36" CLEAR FLOOR AREA AT PULL-DOWN (RECESS FOLDING NOM. SIZE 22"x54" SITE VERIFY ACCESSIBILITY BEFORE ROUGH OPENING CONSTRUCTION)
- 11 (FUTURE) PROPOSED LOCATION FOR COIN/CURRENCY OPERATED VENDING MACHINE (COLD SOFT DRINKS/BOTTLE WATER AND SNACK/CANDY) PROVIDED BY BUILDING OWNER. GENERAL CONTRACTOR SHALL PROVIDE ELECTRICAL SERVICES TO FUTURE INSTALLATION.

### FLOOR PLAN LEGEND

FOR THIS SHEET ONLY

- # INDICATES DOOR IDENTIFICATION NUMBER; SEE ARCH SHT A6XX FOR INFORMATION ON NOM. DOOR/FRAME SIZES, DESIGNATION TYPES & HARDWARE
- X INDICATES WINDOW IDENTIFICATION LETTER; REFERENCE SEE SHEET A6XX FOR DETAILED INFORMATION FOR WINDOW FRAME DIMENSIONS AND NOTES
- E.J. EXPANSION CONSTRUCTION JOINT, (NOM. 1/2" WIDTH) EXTERIOR TRAFFIC GRADE BITUMINOUS MATERIAL; PERIMETER FOUNDATION TO SLAB EDGE; WEATHER TIGHT JOINT SEAL W/ POUR-ABLE SELF LEVELING SEALANT (SIMILAR MFR: SIKAFLEX)
- T DESIGNATES FREEZE-PROOF ENCLOSED COMMERCIAL WALL "HOSE BIB" WITH VACUUM BREAKER & "TEE" KEY
- DS PRE-FINISHED NOM. 4x2 DOWN SPOUT (DS) (MIN. 26ga) FROM CONTINUOUS GEE GUTTER, (MIN. 26ga); PROVIDE (DS) CONNECTION WALL STRAPS AT EACH 1/3 POINT VERTICAL WALL HEIGHT; PROVIDE EACH W/ PRE-CAST CONCRETE SLASH BLOCK; SURFACE SHEET STORM-WATER DRAINAGE MANAGEMENT SYSTEM, REFERENCE CIVIL SITE DWG'S
- C.S. CONCRETE SLAB CONTROL JOINT; TOOLED JOINT
- MTS APPROPRIATE ALUMINUM SOLID EXTRUDED TRANSITION STRIPS, JOINT SYSTEM AT FINISHED FLOORING CHANGES FROM ONE MATERIAL TO ANOTHER
- M.T. DESIGNATES EXTRUDED ALUMINUM FLOOR FINISH FLUSH TRANSITION THRESHOLD; ADAAG/HC "BARRIER FREE" ACCESSIBLE CROSS-OVER (MAX. 1/2" THKN.)
- SIGN-- WALL MOUNTED IDENTIFICATION SIGNAGE (SEE SIGNAGE DETAIL A/N100)

### ROOM FINISH LEGEND

FOR BUILDING OWNER REVIEWS AND FINAL APPROVALS, GENERAL CONTRACTOR SHALL PROVIDE SELECTED FINISHING (FLOOR, WALL & CEILING AND RESTROOM ACCESSORIES) MATERIALS AND COLOR SAMPLES FOR ALL INTERIOR SURFACE FINISHES. ADDITIONAL SUBMITTALS FOR BUILDING OWNER APPROVALS SHALL INCLUDE ELECTRICAL LIGHTING AND PLUMBING FIXTURES AND MECHANICAL APPLIANCES FROM PROPRIETARY VENDORS.

NAME	ROOM IDENTIFICATION NAME
A1111	CEILING HEIGHT ABOVE FIN FLOOR
CEILING	
1	2x2 SUSPENDED CEILING ACoustICAL LAY-IN SYSTEM; COLOR: WHITE TILE/CEILING GRID; (USG: "MARS" (HIGH-NRC/HIGH-CAC); REGULAR TILES 7/8"(0) (SLT) EDGES; ACoustICAL SUSPENSION SYSTEM: DOWN DX/DXL 15/16" GRID)
2	PAINTED GYPSUM SOFFIT/CEILING BOARD (GA214-LEVEL 5 SURFACE TEXTURE FINISH) (OPTIONAL: USG: "TUFF-HIDE") SMOOTH SURFACE FINISHED
WALLS	
1	PAINTED GYPSUM BOARD PARTITION; (GA214-LEVEL 4 SURFACE FINISH) (WASHABLE, AND MILDEW/MOISTURE RESISTANCE PAINT REQUIRED); (PRE-PRIMED PAINTED) SEMI-GLOSS ACRYLIC LATEX; COLOR: T.B.D.
2	PAINTED GYPSUM BOARD PARTITION; (GA214-LEVEL 4 SURFACE FINISH); (PRE-PRIMED PAINTED) EGG-SHELL SHEEN FINISH, ACRYLIC LATEX PAINT; COLOR: T.B.D.
BASE	
0	NONE
1	RUBBER/VINYL BASE (NOM 4" HEIGHT); COLOR: T.B.D.
2	5.5" WOOD BASE W/ BEVEL COVE (PAINT GRADE) (OWNER SPECIFIED)
FLOOR	
A	SEALED CONCRETE FINISH; MULTI-APPLIED "PENETRATING" CONCRETE MOISTURE BARRIER SEALER (PROPRIETARY MFR.: "AQUAFIN INC.")
B	12"x12" VINYL COMPOSITE TILE (OWNER SPECIFIED)
C	24"x24" (OR) 12"x36" COMPOSITE CARPET TILE; DIRECT GLUED-DOWN (FLEECE BACKER (OR) NEOPRENE FOAM BACKER)

THIS SHEET SHOWS BASIC DRAFTING STANDARDS. THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.

Copyright © Design Elements 2018

THIS SHEET SHOWS BASIC DRAFTING STANDARDS

Proposed Dispatch Office Building for  
**Crete Solutions, LLC**

239 Raleigh Street  
Wilmington, North Carolina 28401

**FLOOR PLAN**  
Contract Documents - Issued for Construction

date: 2/15/18

job no.: CRETE/BUS

drawn by: MSAIEED

checked by: MSAIEED

drawing no.:

no. revision

date

revision

no. date revision

0 3/28/18 ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL

1 2/19/18 SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL

2 3/7/18 DESIGN DEVELOPMENT PROGRESS REVIEW

job status


job status

no. revision





0



NO.	DATE	REVISION
A	2/19/18	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18	DESIGN DEVELOPMENT PROGRESS REVIEW
0	3/28/18	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL



**PROPOSED REFLECTED CEILING PLAN**



- GENERAL SUSPENDED CEILING NOTE:**
- SEISMIC SPLAY WIRE BRACING AND COMPRESSION POSTS/STRUTS ARE ONLY REQUIRED IN HIGH SEISMIC ZONE AREAS DESIGNED FOR: CATEGORIES D, E, F.
  - AREAS SMALLER THAN 1000 SQ. FT. AND WITH WALLS ON FOUR SIDES EXTENDING TO THE STRUCTURE NEED NOT HAVE SEISMIC SPLAY WIRE REINFORCING. BOUNDARY WALLS MUST BE BRACED TOP AND BOTTOM INDEPENDENT OF CEILING TO QUALIFY.
  - SEISMIC CLIPS ARE REQUIRED IN SEISMIC DESIGN CATEGORIES D, E AND F.
  - NOMINAL 2" HORIZONTAL LEG ON WALL MOLDING IS REQUIRED ONLY IN SEISMIC DESIGN CATEGORIES D, E AND F. WITH CC-ES EVALUATION REPORT, A 7/8" LEG WOULD BE ACCEPTABLE WITH PROPER SEISMIC CLIPS.
- TYPICAL FINISHED ACOUSTICAL METAL LAY-IN SUSPENSION SYSTEM ASSEMBLIES SHALL BE SIMILAR AS METAL SUSPENSION SYSTEM WITH GYPSUM PANEL SHEATHING (HARD CEILINGS)

**(TYP) SCHEMATIC SUSPENDED CEILING GRID SYSTEM NOT TO SCALE**

**REFLECTED SUSPENDED CEILING NOTES**

REFERENCE ELECTRICAL AND MECHANICAL DRAWINGS FOR 2x2 FINISHED CEILING GRID LAYOUTS WITH SPECIFIED LIGHTING FIXTURE TYPES AND ACTUAL MECHANICAL (SUPPLY AND RETURN) DIFFUSERS CONFIGURATIONS.

GENERAL CONTRACTOR SHALL BE RESPONSIBLE TO SITE VERIFY ALL OVERHEAD EXISTING CONDITIONS (STRUCTURAL WOOD FRAMING, AND MECHANICAL DUCTWORK SYSTEM, BUT NOT LIMITED TO), FOR ALL THEIR LOCATIONS OF VERTICAL HEIGHTS ABOVE FINISHED FLOOR, AND CONFIRMING THAT THE PROPOSED FINISHED CEILING ASSEMBLIES ARE BUILD-ABLE AS SHOWN BEFORE PROCEEDING WITH CONSTRUCTION. IF THERE ARE ANY QUESTIONS REGARDING THESE OR OTHER COORDINATION ISSUES, THE GENERAL CONTRACTOR IS RESPONSIBLE FOR OBTAINING A CLARIFICATION FROM THE LEASE TENANT OWNER (OR) DESIGNER BEFORE PROCEEDING WITH CONSTRUCTION IN QUESTION.

POSITION 2x2 LAY-IN GRID ASSEMBLY TO PROVIDE THE OPTIMUM USAGE OF FULL TILES WITH MINIMUM REQUIRED FIELD CUTTING TO FIT. "ABSOLUTELY NO CEILING TILE SLIVERS ALLOWED" WHERE PERIMETER 2x2 GRID LAYOUT MEETS HEAD WALLS, THE MIN. ALLOWED FINISHED TILE WIDTH SHALL NOT BE LESS THAN 6". CONTRACTOR SHALL MODIFY ONLY ADJACENT PERIMETER 2x2 GRIDS INTO 2x4 GRIDS TO ELIMINATE TILE SLIVERS. (CONTRACTOR SHALL ORDER AN EXTRA BOX (10 PERCENT) MATCHING CEILING TILES AS NECESSARY FOR DAMAGE REPLACEMENTS)

(BUILDING OWNER) SHALL SPECIFY SELECTED LIGHTING FIXTURE ARCHITECTURAL STYLE/TYPES (ELECTRICAL DRAWING DENOTING ONLY RECOMMENDED FIXTURE STYLE/TYPE); GENERAL CONTRACTOR SHALL PROVIDE (UNLESS NOTED OTHERWISE); REFERENCE ELECTRICAL DRAWINGS FOR ALLOWABLE WATTAGE PER FIXTURE AS DENOTED AND REQUIRED TO MEET NCBC/ECC-2012

GENERAL CONTRACTOR SHALL REFERENCE PROPRIETARY VENDOR'S SUSPENDED CEILING FRAMING ASSEMBLY SYSTEM FOR APPROPRIATE STANDARD SUSPENSION REQUIRED OF HANGERS AND "SEISMIC" DIAGONAL SPLAY WIRES (GAUGE & O/C SPACING) AT FRAMING GRID INTERSECTIONS AND LIGHTING FIXTURE CORNERS (AND IF APPLICABLE) ADDITION ALTERNATING SPLAYS AT SUSPENDED FRAMING SYSTEM (CROSS MEMBERS AND RUNNERS) WHERE LOCATED ABOVE PARTITION WALLS CONTACTING CEILING GRID.

**CEILING LEGEND**

- NOM. 2x4 LAY-IN SUSPENDED (OR) SURFACE MOUNTED CEILING "LED" LIGHTING FIXTURE; FLAT PANEL GASKET DIFFUSING LENS (REFERENCE: ELECTRICAL DWGS FOR ADD'N DETAILED INFO'R'N)
  - RECESS DOWNLIGHT "LAY-IN" SUSPENDED CEILING GRID FIXTURE; (REFERENCE: ELECTRICAL DWGS FOR ADD'N DETAILED INFORMATION)
  - PENDANT LIGHTING FIXTURE (BUILDING OWNER) SHALL SPECIFY AND COORDINATE FINAL LOCATIONS WITH GENERAL CONTRACTOR (REFERENCE: ELECTRICAL DWGS FOR ADD'N DETAILED INFORMATION)
  - PENDANT LIGHTING FIXTURE (BUILDING OWNER) SHALL SPECIFY AND COORDINATE FINAL LOCATIONS WITH GENERAL CONTRACTOR (REFERENCE: ELECTRICAL DWGS FOR ADD'N DETAILED INFORMATION)
  - WALL MOUNTED LIGHT FIXTURE; COORDINATE LOCATION CENTERED ABOVE MIRROR
  - REFLECTED CEILING GRID SYSTEM (RCG), (AND) SOFFIT/BULKHEAD FINISHED HEIGHT ABOVE FINISHED FLOOR (A.F.F.)
  - 2X2 SUPPLY AIR DIFFUSER (REFERENCE MECHANICAL DRAWINGS FOR SIZE AND LOCATIONS)
  - 2X2 RETURN AIR DIFFUSER (REFERENCE MECHANICAL DRAWINGS FOR SIZE AND LOCATIONS)
- (TYP) 2x2 ACOUSTICAL SUSPENDED REFLECTED CEILING GRID SYSTEM ASSEMBLY PLAN (RCP); FINISHED HEIGHT A.F.F. SEE PLAN (UNLESS NOTED OTHERWISE)
- (TYP) CENTER RECESSED LIGHT (OR PENDANT JUNCTION BOX) FIXTURE WITHIN CEILING TILE (OR) WIRE GRILLE/WOOD SLATS SUSPENDED CEILING
- (TYP) LAY-IN LIGHT FIXTURE WITHIN CEILING GRID FRAMING; OVERHEAD WIRE SUSPENSION ALL FOUR CORNERS
- CEILING FINISH**
- 1 = 2x2 SUSPENDED CEILING ACOUSTICAL LAY-IN SYSTEM; COLOR: WHITE TILE/CEILING GRID; (USG "MARS" (HIGH-NRC/HIGH-CAC); REGULAR TILES 7/8"(D) (SL) EDGES; ACOUSTICAL SUSPENSION SYSTEM: DOWN DX/DXL 15/16" GRID)
- 2 = PAINTED GYPSUM SOFFIT/CEILING BOARD (GA214-LEVEL 5 SURFACE TEXTURE FINISH) (OPTIONAL: USG "TUFF-HIDE") SMOOTH SURFACE FINISHED
- HATCH PATTERN AREAS DESIGNATES SUSPENDED GYPSUM BOARD PANEL (HARD) TEXTURE FINISH CEILING OR BUILT-DOWN SOFFIT/BULKHEAD; FINISHED HEIGHT A.F.F. SEE PLAN (UNLESS NOTED OTHERWISE) ASSEMBLY SYSTEM REFERENCE AS FOLLOWS: (SEE SCHEMATIC DETAILS FOR SIMILAR CONSTRUCTION GUIDANCE)
- 1/2" GYPSUM CEILING PANEL SHEATHING (GA-214: LEVEL 4) SURFACE FINISH ALL EXPOSED AREAS
  - SUSPENDED METAL CEILING GRID SYSTEM; HEAVY DUTY TEE/RUNNER (24" O/C EACH-WAY) SUPPORTED W/VERTICAL HANGER GALV WIRES (12 GA.) AT 48" O/C EACH WAY

COPYRIGHT: DESIGN ELEMENTS 2018 THIS DRAWING AND THE DESIGNER'S SHOW ARE THE PROPERTY OF MICHAEL L. SALED, ARCHITECT & DESIGN ELEMENTS INC. THE REPRODUCTION, COPYING OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS.

**Design Elements**  
 M. L. Saleed (MICHAEL), AIA, LEED-AP  
 Architect / President  
 239 Raleigh Street  
 Wilmington, North Carolina 28401  
 P: 910.597.3131

3/20/18

MICHAEL L. SALED, JR. CIVIL ENGINEER  
 13777 WILSON ROAD  
 WILMINGTON, NC 28403  
 P: 910.597.3131

**Proposed Dispatch Office Building for  
 Crete Solutions, LLC**





239 Raleigh Street  
 Wilmington, North Carolina 28401

**REFLECTED CEILING PLAN**

Contract Documents - Issued for Construction

date: 2/15/18  
 job no.: CRETE/BUS  
 drawn by: MSAIEED  
 checked by: MSAIEED  
 drawing no.: A101  
 revision no.: 0

n.o.	date	revision	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL
A	2/19/18	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL	
B	3/7/18	DESIGN DEVELOPMENT PROGRESS REVIEW	
0	3/28/18	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL	



COPYRIGHT: DESIGN ELEMENTS 2018 THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAEED, ARCHITECT & DESIGN ELEMENT, INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS.

**Design Elements**  
M. L. Saheed (Michael), AIA, LEED-AP  
Architect / President  
1213 Colburn Drive, Suite 102  
Wilmington, North Carolina 28405  
910.309.3131

**Proposed Dispatch Office Building for Crete Solutions, LLC**  
239 Raleigh Street  
Wilmington, North Carolina 28401  
EXTERIOR BUILDING ELEVATIONS  
job status  
Contract Documents - Issued for Construction

date: 2/15/18  
job no.: CRETE/BUS  
drawn by: MSAIEED  
checked by: MSAIEED  
drawing no.: **A200**  
revision no.: 0

no.	date	revision	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL
A	2/19/18	1	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18	2	DESIGN DEVELOPMENT PROGRESS REVIEW

MANUFACTURED / ENGINEERED 2x OPEN WEB ROOF TRUSS (MAX. SPACING 24" O/C); WEB CONFIGURATION IS SHOWN SCHEMATICALLY ONLY! REFER TO TRUSS MFG. SHOP DRAWINGS FOR ACTUAL REPRESENTATION.

ROOF SECONDARY MOISTURE BARRIER; MIN. 6" OVER LAP HORZ SEAMS BEFORE INSTALLATION PROVIDE RUBBIZE/ASPHALT SELF-ADHERED MEMBRANE (40mls) STRIP FLASHING (MIN. 12"W) OVER ALL HIP/VALLEY INTERSECTING JOINT TRANSITIONS (CHANGE OF ROOF SLOPE/PLANE) AND VERTICAL HEADWALL TERMINATION (SIM. MRF: GRACE'S ICE & WATER SHIELD)

5-VEE (CORRUGATED VEE PROFILE) METAL ROOFING PANELS; GALVANUM PRE-PAINTED ACRYLIC COATED FINISH (COLOR: (T.B.D.))

CONT. PRE-FORMED "LOW EAVE/RAKE" STAINLESS STL SHINGLE SUPPORT/FLASHING (SS316 - 33Mils); SECURED W/ APPROPRIATE STAINLESS STL FASTENERS 8" O/C PER ROW; (2) ROWS STAGGER 4"

ALUM. PRE-FORMED/FINISHED "OGEE" METAL GUTTER W/ CROSS-BAR BRACKET UNDER EAVE FLASHING; SECURE W/ STAINLESS STL SCREWS

CONT. 1x6 CELLULAR/PVC DRIP BOARD OVER 1x10 CELLULAR/PVC FASCIA TRIM BOARD (0.75" THK'N) WOOD-GRAIN TEXTURE, SECURED TO CONT. PT. 2x8 SUB FASCIA (MITER/SCARF-CUT ALL SECTIONAL JOINTS)

CONT. P.T. 2x SUB-FASCIA (CCA 0.80pcf) CHAMFER TOP EDGE TO SHEATHING (FIELD SIZE AND CUT TO FIT AS REQ'D)

CONT. VENTED VINYL SOFFIT; FRAME FINISH W/ VINYL J-TRIM (TYP) NOM. 2x6 DOUBLE TOP BEARING PLATES

NOM. 1/2" EXTERIOR PLYWOOD PANEL WALL SHEATHING (APA STRUCTURAL GRADE) STAGGER PLYWOOD VERT/HORZ JNTS. OVER WALL STUDS W/ 2x CROSS BLOCKING @ HORZ. JNT. OPTIONAL: PROPRIETARY "ZIP-SYSTEM" WALL PANEL SHEATHING

NOTE: 1  
EXTEND PLYWOOD WALL SHEATHING FULL WALL HEIGHT FROM FND DOUBLE PLATE UP TO ENG/MFR FLOOR TRUSS TOP CHORD FRAME

NOTE: 2  
EXTEND PLYWOOD WALL SHEATHING FULL WALL HEIGHT FROM FND DOUBLE PLATE UP TO ENG/MFR FLOOR TRUSS TOP CHORD FRAME

(TYP) NOM. 6.25" (THK) WALL CAVITY FIBERGLASS INSULATION; UN-FACED; FULL WALL HEIGHT AND CAVITY WIDTH (U<sub>2</sub> R-VALUE = 19)

EXTR HORZ. SHEATHING JOINT (TYP) BETWEEN WALL STUDS, BLOCKING (TYP. EXTERIOR FINISHING) VINYL LAPPED SIDING; MIN. 6" EXPOSURE. (CEDAR WOODGRAIN APPEARANCE (REF MFR. FOR HIGH WIND FASTENER TYPES AND PATTERN) (COLOR SELECTED BY OWNER)

"TYPAR" BUILDING WRAP AIR/WEATHER BARRIER; MIN. 6" OVER LAP HORZ SEAMS; (FULL WALL HT.)

CONT. COPPER FLASHING TRIM (16oz); LAPPED SEAL TAPED TO SHEATHING, FORMED TO CHAMFER EDGE & MIN. 4" VERT. LEG

(TYP) BUILT-UP BANDING ASSEMBLY: CONT. (CCA) NOM. P.T. 2x3 CAP BOARD; TOP EDGE 1/2" CHAMFERED @ 45° OVER P.T. (CCA) 2x12 CONT. BAND BOARD; (SCARF-CUT END SXN JNTS) WRAP WITH VINYL COATED ALUMINUM BREAK METAL

5% GROUND SLOPE WITHIN 10' PERIMETER

NOM. 8" CONCRETE MASONRY UNIT CONT. FOUNDATION WALL; (TOP COURSEING CONT. NOM. 8" HEADER BLOCK) CONC FILLED CELLS SOLID AT VERTICAL REINFORCEMENT; No 4's HOOKED WALL TO FOOTING DOWELS @ 4'-0" O/C AND MAX 1'-4" FROM EACH "INSIDE/OUTSIDE" FOUNDATION CORNER INTERSECTIONS (PEA GRAVEL (3/8"-1/2" MAX AGGREGATE SIZE; CONC. Fc 3000 PSI)

CONT. CONCRETE REINFORCED STRIP FOOTING (REF. ARCH SHEET AS/100 FOR DETAILED REIN. INFORM'N & FOOTING SCHEDULE) MIN. 24" HORZ RE-BAR LAP SPICE AND WIRE TIED; CONCRETE: Fc 3500 PSI; 28 DAY

EXTR PLYWOOD ROOF SHEATHING; (APA STRUCTURAL RATED) TUNG & VEE GROOVED (OR) ALUM. "H" CLIP SHEET CONNECTIONS; NOM. PANEL THICKEN: NOM. 3/4" FOR TRUSSES SPACED @ 19.2"~MAX. 24" O/C; 5/8" FOR TRUSSES OR 2x FRAM'G @ MIN. 16" O/C (OPTIONAL: PROPRIETARY "ZIP-SYSTEM" ROOF PANEL SHEATHING)

(TYP) "INSUL'N STOP" CONT. 2x10 VERT CROSS BLOCKING BETWEEN ROOF TRUSSES

HURRICANE TIE DOWN CLIP @ EACH TRUSS RAFTER BEARING POINT; (H.D. GALV.; ASTM-A535 G90) (SIM. MFG: SIMPSON "H105"-18ga) INSTALL OUTBOARD WALL FRAMING OVER WALL SHEATHING FOR CONT LOAD PATH

(TYP) "GWB NAILER" CONT. 2x HORZ CROSS BLOCKING BETWEEN ROOF TRUSSES

NOM. 12" (THK) UN-FACED FIBERGLASS BATT INSULATION; ATTIC/CEILING THERMAL ENVELOPE (U<sub>5</sub> R-VALUE = 38)

T/WALL BEARING PLATE

(TYP) NOM. 5/8" (MOISTURE RESISTANCE) GYPSUM BOARD CEILING PANELS W/ TAPERED EDGES (GA-214 LEVEL 5 PREP; (USE "TUFF-HI" CEILING SURFACE FINISH ALL EXPOSED AREAS; U.N.O.)

(TYP) GWB HEAD WALL & CORNERS FIBER-REIN/TAPED JOINT SEAL (AIR BARRIER/SEAL)

FINISHED SUSPENDED ACOUSTICAL LAY-IN CEILING FRAME/TILE (ARCH. EL. MIN. 9'-0"~9'-1/2")

(TYP) BETWEEN WALL STUDS, PROVIDE 2x6 VERT BLOCKING AT ABUTTING (HORZ JOINT) SHEATHING PANEL EDGES

(TYP) NOM. 1/2" GYPSUM WALL BOARD (GWB); TAPERED EDGES (GA-214 LEVEL 4 FINISH); PROVIDE MAX. 3/8" ABOVE FLR CLR GAP (U<sub>4</sub> R-VALUE = 0.45)

NOTE: 1  
PROVIDE (MIN.) TRIPLE EXTERIOR WALL (KING) STUDS AT 90° INSIDE/OUTSIDE BLD'G CORNERS; AT WINDOW/DOOR JAMBS PROVIDE DOUBLE (KING) STUDS AND BEARING HEADER (JACK) STUDS

(TYP) 2x6 WOOD WALL STUDS FRAMING & BLOCKING (SPF-No.1 (OR) SYP-No.2 WALL STUDS KD-19% WALL STUDS @ 1'-4" O.C. MAX.

(TYP) "AIR/MOISTURE BARRIER" BUILDING PERIMETER CONCEALED COUNTER FLASHING; THERMOPLASTIC MEMBRANE BARRIER (40 MIL) SELF-ADHERING/FLEXIBLE STRIP SHEET; EXTEND UP VERTICALLY BEHIND BLD'G SHEATHING OVER WALL STUDS, SILL PLATE & OVERLAY SLAB/FOUNDATION EDGE (MIN. 6"); LAP BUILDING CORNERS (MIN. 12") SEAL/ADHERED SEAM LAPS; MIN. 6" OVERLAP JOINTS

CONT. P.T. 2x6 BEARING SILL PLATE (CCA 0.80pcf) STAGGER (MIN. 24" DIST) JOINTS; SECURE W/ 5/8" DIA. H.D. GALV. (ASTM G90) ALL-THREAD ANCHOR RODS W/ 2" SQ. FLAT WASHER & NUT; (CONC. SLAB/FND EMBED'MT (MIN. 14" DEPTH) PROVIDE LOCK NUTS & FENDER WASHER); MAX. SPACING 4'-0" O.C.; AND (TYP) MAX. 1'-4" EACH FOUNDATION INSIDE/OUTSIDE CORNER INTERSECTIONS; TIE TO PERIMETER CONTINUOUS EDGE No. 4 NOSING BAR


CONCRETE (ELEVATED) SLAB-ON-GRADE FLOOR SLAB; REIN. W/ 2.1x2.1-6x6 W.W.F.(SHEET) & MIN. 2" SURFACE COVERAGE (CONC. FINISHED: STEEL TROWEL; Fc 3000 PSI)

PLASTIC SHEETING VAPOR BARRIER (15 MIL) LAP FND SHEET OVER BASE SHT 1'-4" (MIN) VARIES TO SITE CONDITIONS

CLEAN COMPACTED COURSE GRANULAR (DRAINAGE CONTROL) SUB-FILL AND BASE FILL SOILS

(TYPICAL) PREP SOIL UNDER FOOTINGS: REMOVE ORGANIC MATERIALS AND TERMITES TREAT; BEFORE CONSTRUCTING BUILDING FOUNDATIONS; SHALL BE CONTRACTOR RESPONSIBILITY TO PROVIDED FOR REFERENCE PROFESSIONAL SOIL ENGINEER'S SUBSURFACE EGO-TECHNICAL SOIL REPORT FOR RECOMMENDATIONS TO STRUCTURALLY SITE PREP AND CONDITION TO IMPROVE EXISTING GRADES (DENSIFY THE SOIL) TO ACHIEVE PROPER SOIL BEARING CAPACITIES

1 TYPICAL WALL SECTION SCALE: 1" = 1'-0"



3 TYPICAL LOW EAVE ROOF SECTION SCALE: 1-1/2" = 1'-0"

B TYPICAL BANDBOARD PERIMETER TRIM SCALE: 3" = 1'-0"

GENERAL KEYNOTES FOR SHEETS A400 AND A401

- 01 ROOF MEMBRANE UNDERLAYMENT, "ROOF SECONDARY WATER-BARRIER" (MIN. (+40mil) ) SINGLE PLY MYLAR SURFACE FINISHED SELF-ADHERED, RUBBERIZED ASPHALT, FLEXIBLE SHEETING; LAP EDGES MIN. 6"; PROVIDE ADDITIONAL SINGLE STRIPPING AS COUNTER FLASHING AT ALL HEADWALL INTERSECTIONS AND CHANGE OF SLOPE INTERSECTIONS AT HIPS & VALLEYS; EXTEND MIN. 6" VERT/HORZ OVERLAPS (SIMILAR MFG.: WR GRACE "ICE & WATER SHIELD" W/ OPTIONAL "TRIPCOR")
- 02 ARCHITECTURAL METAL ROOF; PRE-FINISHED 5V-CRIMP (RIB NOM. 1/2" HT) PANELS MIN.26 GAUGE; (MAX PANEL: 24" WIDE; 45'-0" RECOMMENDED LENGTHS); ACRYLIC COATED GALVALUME; SECURE W/ APPROPRIATE SIZE AND SPACING EXPOSED STAINLESS STL CAP (METAL TO WOOD) FASTENERS W/ NEOPRENE SEAL WASHERS (SIZE PROPERLY (DIAMETER/LENGTH) TO RESIST PANEL EXPANSION/CONTRACTION (AND) FASTENER "BACK-OUT;" REFERENCE PROPRIETARY MFG. RECOMMENDATIONS FOR COMPLETE ASSEMBLY DETAILS FOR FULL SYSTEM INSTALLATION W/ (20 YR.) WARRANTIES: INSTALLATION, MATERIAL FINISH AND HIGH WIND UP-LIFT RESISTANCE FOR 130mph WIND SPEED; PROVIDE W/ MFR'S AND CONTRACTOR'S "QUALITY OF ASSURANCE"; RECOMMENDED PANEL FASTENER SPACING: (MAX. 6" O/C LINEAR ROOF PERIMETER "END" PANEL EDGES, MAX. 12" O/C EACH WAY WITHIN 48" SQUARE "IN-FILL" AREAS OF ROOF EDGE CORNERS; MAX. 16" O/C ROOF "IN-FILL" PANEL AREAS.) (UL LISTED "CLASS A" ROOF MATERIAL) COLOR FINISH: COLORFAST GALVALUME.
- 03 BUILDING WRAP; "VAPOR PERMEABILITY/MOISTURE BARRIER" SHALL BE INSTALLED EXTERIOR SHEATHING PANELS AND "BACKWRAP" (FLEXI-TAPED FLASHING) THRU ROUGH DOOR AND WINDOW OPENINGS. OVERALL MEMBRANE MATERIAL SHALL NOT HAVE UNSEALED: SEAMS, CUTS, CRACKS PENETRATIONS OR ANY VOIDS IN THE PROPRIETARY PRODUCT; AND VERTICAL AND HORIZONTAL SEAMS SHALL BE OVERLAPPED (MIN. 6") AND CONTINUOUS SEAL TAPED. ALL MECHANICALLY FASTENER SHALL BE SEALED; CONTRACTOR SHALL BE RESPONSIBLE FOR SEAL TAPING ALL JOINT SEAMS W/ PROPRIETARY MEMBRANE TAPE. PROPRIETARY BARRIER MEMBRANE PERFORMANCE: FLEXIBLE AND TEAR RESISTANCE, HIGH BREATHABILITY (VAPOR TRANSMISSION); HIGH AIR PENETRATION PROTECTION; HIGH MOISTURE RESISTANCE (HYDROSTATIC HEAD); (SPECIFIED MFR: "TYPAR" COMMERCIAL BUILDING WRAP)
- 04 "VAPOR BARRIER (VB)" UNDER CONDITIONED SPACES ONLY (MIN. 15mls) UNDER CONCRETE FLOOR SLAB MOISTURE PROTECTION-PUNCTURE RESISTANT PLASTIC SHEETING (METALLOCENE POLYOLEFIN); PROVIDE MIN. 6" SEAL LAPPED JOINTS WITH TAPED SEAMS INSTALLATION; THRU BARRIER/SLAB PIPE PENETRATIONS (ei. PLUMBING AND ELECTRICAL SERVICES) SHALL BE TAPED (OR) MASTIC (MFR. "STEGO INDUSTRIES-15MIL," ASTM E1745 CLASS A; WITH 0.01 PERMANENCE)
- 05 NOM. 5/8" EXTERIOR PLYWOOD PANEL ROOF SHEATHING; (APA STRUCTURAL RATED) OPTIONAL: PROPRIETARY ROOF PANEL SHEATHING W/ BUILT-IN ENERGY EFFICIENT MOISTURE/VAPOR BARRIER SURFACE FINISH; ALL PANEL JOINTS SHALL BE PRESSURED SEAM-SEALED TAPED (ENGINEERED PRODUCT SIM. HUBER ENGR WOODS-"ZIP SYSTEM") PANEL FASTENER TYPES AND SPACING SHALL BE GOVERN BY NRC-12 FOR COASTAL HAZARD HIGH WIND ZONE (AREAS PRONE TO HURRICANE FORCED MIN. 130 mph)
- 06 NOM. 1/2" EXTERIOR PLYWOOD PANEL WALL SHEATHING (APA STRUCTURAL GRADE) STAGGER PLYWOOD VERT/HORZ JNTS. OVER WALL STUDS W/ BLK'G @ HORZ. JNT. OPTIONAL: PROPRIETARY WALL PANEL SHEATHING W/ BUILT-IN ENERGY EFFICIENT MOISTURE/VAPOR BARRIER SURFACE FINISH; ALL PANEL JOINTS SHALL BE PRESSURED SEAM-SEALED TAPED (ENGINEERED PRODUCT SIM. HUBER ENGR WOODS-"ZIP SYSTEM") (U<sub>1</sub> R-VALUE = 0.63)

COPYRIGHT, DESIGN ELEMENTS, 2018 THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SHEED, ARCHITECT & DESIGN ELEMENT, INC. THE REPRODUCTION, COPIING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND APPROVED WILL BE SUBJECT TO LEGAL ACTION.

DESIGN ELEMENTS

1713 Clarendon Drive, Suite 142  
Wilmington, North Carolina 28405  
P.O. BOX 3131

**Design Elements**

M. L. Sheed (Michael, AIA, LEED-AP)

THIS SHEET SHOWS BASIC DRAFTING STANDARDS

PROPOSED DISPATCH OFFICE BUILDING FOR  
**Crete Solutions, LLC**

239 Raleigh Street  
Wilmington, North Carolina 28401

**TYPICAL WALL SECTION AND DETAILS**

Contract Documents - Issued for Construction

DATE: 2/15/18


JOB NO.: CRETE/BUS

DRAWN BY: MSAIEED


CHECKED BY: MSAIEED

DRAWING NO.: **A300**


REVISION NO.: 0




**1 ENLARGED RESTROOM AND DRIVERS LOUNGE PLAN**  
A400 SCALE: 1/2" = 1'-0"




**2 ENLARGED RESTROOM AND BREAK PLAN**  
A400 SCALE: 1/2" = 1'-0"




**3 ENLARGED BREAK ELEVATION**  
A400 SCALE: 1/2" = 1'-0"



**4 ENLARGED LOUNGE ELEVATION**  
A400 SCALE: 1/2" = 1'-0"



**B COUNTER DETAIL**  
A400 SCALE: 1" = 1'-0"



**A ACCESSIBLE VANITY SECTION**  
A400 SCALE: 1" = 1'-0"

**PLAN KEYNOTES THIS SHEET ONLY**

- 01 1 1/2"Ø - STAINLESS STEEL HANDRAIL BACK WALL & SIDE WALL MOUNTED "HORIZONTAL GRAB BARS" WITH "VERTICAL SIDE WALL PULL BAR" (SEE STANDARD HC ACCESSIBILITY DETAILS) SIMILAR MFG: GAMCO PRODUCTS "GRAB BAR"; FINISH: BRUSHED SATIN/TEXTURE GRIP "T". (REFERENCE STANDARD HC ACCESSIBILITY DETAILS 1/N104)
- 02 CUSTOM VANITY UNIT (MIN. 22"(D)); PLASTIC LAMINATE COUNTERTOP AND BACKSPLASH W/ "DROP-IN" LAVATORY; FAUCET FIXTURE SETBACK FROM FRONT RIM (MAX. DIST. 19") PROVIDE ADA COMPLIANT ELECTRONIC SENSOR ACTIVATED FAUCET CONTROLS. (MAX. RIM HT. 34" A.F.F.) SEE GENERAL ACCESSIBILITY REQUIREMENTS (SEE STANDARD HC ACCESSIBILITY DETAILS 1/N100) AND SECTION A/A400 (REF PLUMBING DWG'S FOR ADDITIONAL INFOR'N)
- 03 TOILET TISSUE (MULTI-ROLL) STAINLESS STL. DISPENSERS; TWO UNITS, SURFACE MOUNT (SIM. MFG: BOBRICK: B-4288)
- 04 FLOOR MOUNTED TOILET; TANK TYPE W/ ELONGATED BOWEL AND OPEN-FRONT SEAT WITH INTEGRATED HANDLE; ADA/ANSI ACCESSIBLE; PROVIDE FLUSH VALUE LEVER ON ACCESSIBLE SIDE CLEAR FLOOR AREA (REFERENCE: PLUMBING DWGS)
- 05 WALL MOUNTED VANITY MIRROR - (1/4" TEMP/SAFETY) W/ METAL EDGE CENTERED TO SINK (UNLESS NOTED OTHERWISE FULL LENGTH OF VANITY; VERIFY W/ OWNER); (MIN. 24"(W) x 36"(H)); MOUNT BOTTOM EDGE 40" MAX A.F.F.
- 06 SOAP SANITIZER AND LOTION DISPENSER; SURFACE MOUNTED (SIM. MFG: GEORGIA- PACIFIC; "53253"; COLOR: TRANS-SMOKE)
- 07 COMBINATION; STAINLESS STL. SURFACE-MOUNT FOLDING PAPER TOWEL DISPENSER (ABOVE) AND WALL WASTE RECEPTACLE (BELOW) (SIM. MFG: BOBRICK B-3944-BARRIER FREE)
- 08 (TYP) "BARRIER FREE" ACCESSIBILITY COAT HOOK, MOUNTED (HT. 48" A.F.F.) (SIM. MFG: BOBRICK BRUSHED-NICKEL FINISH)
- 09 WALL MOUNTED URINAL; PROVIDE THRU-WALL VERTICAL CARRIAGE (THIN WALL), ADA/HC ACCESSIBLE WHERE NOTED (HC); (REF PLUMBING DWGS)
- 10 WALL MOUNTED URINAL/PRIVACY (24" WIDTH x 48" HEIGHT; MOUNT BOTTOM EDGE 12" AFF) PARTITIONS (DESIGN WEIGHT SUPPORT 250 lbs); PROVIDE STAINLESS STEEL PANELS; WALL MOUNTED INSTALLATION WITH CONTINUOUS STAINLESS STEEL WALL MOUNTING BRACKETS (FULL PANEL LENGTH)
- 11 WALL-HUNG LAVATORY 19"x 17", VITREOUS CHINA, WITH MATCHING PIPE SHROUD, WHITE; PROVIDE WITH STEEL BRACKET WALL HANGER, INSTALL ADA COMPLIANT ELECTRONIC SENSOR ACTIVATED FAUCET CONTROLS; FAUCET FIXTURE SETBACK FROM FRONT RIM (MAX. DIST. 19") (UNLESS NOTED OTHERWISE;) REFERENCE ACCESSIBILITY DETAILS
- 12 WASTE RECEPTACLE STAINLESS STL. W/ DOME-LIP; FLOOR FREE-STANDING; (SIM. MFG: BOBRICK: B-2300)
- 13 OWNER'S ROUTER/DATA STATION; 19" METAL RACK
- 14 NOM. 24" UNDERCOUNTER REFRIGERATOR (PROVIDED BY OWNER; INSTALLED BY CONTRACTOR)
- 15 NOM. 24"(D)x 36"(H) (UNLESS NOTED OTHERWISE) STANDARD BUILT-IN BASE CABINETS W/ (HP) PLASTIC LAMINATED FINISHES; COUNTER TOP W/ 4"H. BACKSPLASH, FRONT FACE CABINETS W/ DOOR PANELS AND DRAWER; NOM. 12" DEEP WALL CABINETS W/ ADJUSTABLE SHELVING
- 16 STAINLESS STEEL (HEAVY GAUGE 304 TYPE; 33mil) SHALLOW BASIN "DROP-IN" KITCHEN SINK, FULL SEALANT BED SET; PROVIDE LEVER TYPE HOT/COLD WATER SUPPLY HANDLES W/ GOOSE NECK FAUCET; (FAUCET MAX. FRONT RIM DIST. 19") PROVIDE CLEAR FRONT OPEN'G FOR ACCESSIBLE TO PERSONS W/ DISABILITIES SEE DETAILS; (REF. PLUMBING FOR ADD'N INFOR'N)
- 17 PROPOSED LOCATION: (28 GAL CAPACITY; UNLESS DIRECTED OTHERWISE BY OWNER) ELECTRIC "LOWBOY" WATER HEATER (UNDERCOUNTER); PROVIDE DRAINAGE PAN PLUMBING AND PRESSURE RELEASE VALVE "BLOW-OUT". (PLUMBING CONTRACTOR SHALL PROVIDE, ELECTRICAL CONTRACTOR SHALL WIRE FOR FULL POWER SERVICE)
- 18 RESIDENTIAL STYLE FREE-STANDING (SUPPLIED BY OWNER) REFRIGERATOR/FREEZER W/ ICE MAKER; [MAX. CLR FLOOR SPACE 36"(W)] (CONTRACTOR INSTALL), CONTRACTOR SHALL INSTALL ICE/WATER LINES AND LOCAL WATER SHUT-OFF VALVE.
- 19 PROVIDE DEDICATED POWER FOR PROPOSED VENDING MACHINE(S) (PROVIDED BY OWNER) (REFERENCE ARCH SHEET 1/A100)
- 20 ATTIC ACCESS "CEILING RECESS FOLDING PULL-DOWN" LADDER, (REFERENCE ARCH SHEET 1/A100)

**GENERAL ACCESSIBILITY REQUIREMENTS**

THE BUILDING OWNER AND GENERAL CONTRACTOR SHALL INSURE THAT THIS FACILITY SHALL BE "BARRIER FREE" ACCESSIBLE TO AND USABLE BY PERSON(S) WITH DISABILITIES. ACCORDING TO THE LATEST EDITION TO THE ICC-IBC/NBC 2012 CHAPTER 11 & ICC/ANSI A117.1 ACCESSIBILITY CODES REQUIREMENTS OF THE APPLICABLE STANDARDS. THE FOLLOWING IS A PARTIAL LIST (BUT NOT LIMITED TO) OF REQUIREMENTS. (REFERENCE 1/N103 FOR ADDITIONAL DETAILS AND GENERAL NOTES)

1. OPERABLE DOOR HARDWARE SHALL BE MOUNTED BETWEEN 30"(MIN.) AND 42"(MAX.) ABOVE FLOOR OR GROUND LEVEL AND BE LEVER TYPE, DESIGNATED FOR (HC) ACCESSIBLE..
2. TOILETS ROOMS & ACCESSORIES:
  - A. LAVATORY TO HAVE LEVER HANDLES, SPRING FAUCETS OR SELF METERING FAUCETS.
  - B. A COAT HOOK 48" ABOVE THE FLOOR SHALL BE MOUNTED ON THE BACK SIDE OF THE HANDICAPPED STALL DOOR (OR) BACK OF ENTRY DOOR.
  - C. LOCATE THE WATER CLOSET (MIN.)16.6" TO (MAX)17.5" FROM THE CENTER LINE OF THE FIXTURE TO THE FINISHED WALL SURFACE. THE SEAT WILL BE 17" TO 19" ABOVE THE FLOOR TO THE TOP OF SEAT. TANK TYPE FLUSH LEVER SHALL BE POSITION TOWARD (SIDE APPROACH) ACCESSIBLE CLEAR FLOOR AREA FOR SIDE REACH
  - D. PROVIDE ONE 42" AND ONE 36" LONG x 1 1/2" OUTSIDE DIAMETER PEENED GRAB BARS, 1 1/2" FROM THE WALL, WITH (36) BEHIND TOILET AT 6" FROM THE WALL, AND (42) ADJACENT TO AT 12" FROM THE WALL AND CENTERLINE MEASURED 33"-36" PARALLEL TO AND ABOVE THE FLOOR. PROVIDE ADDITIONAL SIMILAR 18" VERTICAL FULL BAR 1-1/2" ABOVE HORIZONTAL SIDE BAR CENTERLINE MEASURED AVE. 39"-41" FROM REAR WALL.
  - E. LAVATORY TO BE MOUNTED 34"(MAX.) ABOVE THE FINISHED FLOOR TO RIM WITH CLEAR FLOOR KNEE SPACE OF 30" IN WIDTH AND 27" IN CLEAR HEIGHT. (29" CLEAR UNDER FRONT EDGE). EXPOSED WATER/WASTE PLUMBING SHALL BE CLEAR OF ACCESSIBLE FLOOR AREA AND PROTECTED WITH PROPRIETARY VENDOR SUPPLIED "VINYL INSULATED PROTECTION COVERS" SHALL BE PROVIDED TO EACH SERVICE LINE (SIM. MFG. "TRUEBRO")
  - F. INSTALL MIRROR 40"(MAX.) ABOVE THE FINISHED FLOOR (BOTTOM FIN. EDGE) AND (72" TOP FIN. EDGE).

no.	date	revision	description
A	2/19/18	1	SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL
B	3/7/18	1	DESIGN DEVELOPMENT PROGRESS REVIEW
0	3/28/18	1	ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL

THIS SHEET SHOWS BASIC DRAFTING STANDARDS

THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFORMATION WILL BE SUBJECT TO LEGAL ACTION

COPYRIGHT: DESIGN ELEMENTS 2018

Proposed Dispatch Office Building for  
**Crete Solutions, LLC**  
239 Raleigh Street  
Wilmington, North Carolina 28401

ENLARGED RESTROOM PLAN & DETAILS  
Contract Documents - Issued for Construction

date 2/15/18  
job no. CRETE/BUS  
drawn by MSAIEED  
checked by MSAIEED  
drawing no.

M.L. SCEED (MICHAEL) AIA, LEED-AP  
Architect / President 818-145  
Wilmington, North Carolina 28405  
910-597-8181

30/2018

DESIGN ELEMENTS

**A400**  
revision no. 0

DOOR AND FRAME SCHEDULE													
DOOR NO.	SPACE	DOOR				FRAME				HDW SET	REMARKS NOTE 1 & 2	DOOR NO.	
		WDTH	HGT.	THK.	MAT'L.	TYPE	GLAZING	MAT'L.	DETAILS				
EXTERIOR DOORS - ALL UNITS													
HOLLOW METAL													
1	ENTRY	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	1	
2	ENTRY	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	2	
3	DRIVER LOUNGE	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	3	
INTERIOR DOORS - ALL UNITS													
4	TOILET	3'-0"	7'-0"	1-3/4"	MDF	B		HM				4	
5	BATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B		HM				5	
6	BATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B		HM				6	
7	DISPATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B		HM				7	
8	ADMIN OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B		HM				8	
9	UTILITY	2'-4"	7'-0"	1-3/4"	MDF	B		HM				9	
10	TOILET	3'-0"	7'-0"	1-3/4"	MDF	B		HM				10	
11	BREAK	4'-0"	7'-0"	---	MDF	---		HM			Cased Opening	11	

**MATERIAL LEGEND:**  
 ALUM - ALUMINUM STOREFRONT  
 SCW - SOLID CORE WOOD  
 HM - HOLLOW METAL  
 I-HM - INSULATED HOLLOW METAL  
 WD - WOOD  
 PLAS - POLYVINYL REINF HOLLOW CORE  
 FRC - FIBERGLASS COMPOSITE OSB CORE  
 MDF - MEDIUM DENSITY FIBERGLASS

GHM - GALVANIZED HOLLOW METAL  
 GIM - GALV INSULATED HOLLOW METAL  
 GMS - GALVANIZED METAL SLATS  
 STL - STEEL RAIL ASSEMBLY  
 GLV - GALVANIZED METAL RAIL ASSEMBLY  
 GIPNL - GALV. INSULATED SECTIONAL PANEL

NOTE 1 SUPPLY WALL MOUNTED DOOR STOPS ON ALL DOORS MOUNTED W/ THE HINGE SIDE 5" OR LESS FROM A PERPENDICULAR WALL  
 NOTE 2 PAINT ALL FRAMES  
 NOTE 3 ALL DOOR HARDWARE TO BE SATIN NICKEL FINISH


**ABBREVIATED DOOR HARDWARE NOTES & SCHEDULE**

OPERABLE DOOR HARDWARE SHALL BE MOUNTED BETWEEN 30"(MIN.) AND 42"(MAX.) ABOVE FLOOR OR GROUND LEVEL AND "ALL" SHALL LEVER STYLE WITH TURN-BACK END RETURN, DESIGNATED FOR ARCHITECTURAL BARRIER FREE ACCESSIBLE. CONTRACTOR SHALL COORDINATE LATCH/LOCKSETS KEYING SCHEDULE WITH BUILDING OWNER BY PROVIDING MASTER AND GRAND MASTER KEYING SYSTEM  
 DOOR HARDWARE MATERIAL FINISH TYPES SHALL BE STAIN NICKEL PLATED (US26D) OR STAIN STAINLESS STEEL (US32D) AND INSTALLED BY CONTRACTOR. IF NOT DIRECTLY SPECIFIED BY OWNER, CONTRACTOR SHALL PROVIDE. ALL EXTERIOR HARDWARE AND MOVING PARTS SHALL HAVE SALT AIR RESISTANCE (STAINLESS STEEL OR BRASS) MECHANISMS SHALL BE HEAVY DUTY GRADE.  
 GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR DOOR ASSEMBLY AND HARDWARE IDENTIFICATIONS AND QUANTITIES AS SHOWN ON PLANS. PRIOR TO ORDERING ANY HARDWARE, CONTRACTOR TO SUPPLY OWNER AND DESIGNER WITH SPECS AND CUT SHEETS FOR APPROVAL AND TO COORDINATE WITH DOOR HARDWARE SPECIALIST AN ASSIGNED MASTER KEYING SYSTEM.


**GENERAL FRAME & GLAZING NOTES**

EXTERIOR METAL STOREFRONT WINDOW / DOOR AND FRAME SYSTEM ASSEMBLIES, U.N.O.  
 (TYP) NOM. 4.5" WIDE ALUM. EXTRUDED FIXED "THERMALLY BROKEN" EXTERIOR STOREFRONT WINDOW FRAME SYSTEMS W/ 1" INSULATED GLAZING (FRAME COLOR: "KYNAR" (CONFIRM WITH OWNER) (70% KYNAR PREMIUM PERFORMANCE COATING) FINISHED FRAMES (AAMA 2605; CLASS 1 611-CURRENT EDITION); GLAZING: PFG/SOLARBAN 60 CLEAR+CLEAR; TINTED, LOW-E GLASS; SHGC MIN. 0.36).  
 WINDOW/DOOR SYSTEM (FRAM'G-GLAZ'G) SHALL BE DESIGN PRESSURE (DP) WIND RATED FOR ITS GEOGRAPHICAL LOCATION; WINDOW INSTALLER SHALL BE RESPONSIBLE FOR ADEQUATELY USING APPROPRIATE FASTENER TYPES, SPACING AND VERTICAL FRAME STEEL STRUTS TO RESIST WIND SPEED (130 MPH) DP RATING. BASIS OF DESIGN:  
 SAFETY (S) - DESIGNATES IMPACT GLAZING.  
 ALL SAFETY GLAZING PRODUCTS SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS UNDER OPCS 16 CFR PART 1201 CATEGORY II FOR TEMPERED/SAFETY-IMPACT GLAZING WHEN SUCH PRODUCTS ARE INSTALLED IN CONDITIONS CONSIDERED HAZARDOUS FOR HUMAN IMPACT AND AS REQUIRED UNDER CHAPTER 24 AND RELATED SECTIONS OF THE INTERNATIONAL BUILDING CODE: ICC/IBC-2012; CHAPTER 24; SECTION 2406  
 WINDOW/DOOR SUPPLIER SHALL PROVIDE ROUGH-OPENING SIZES, BEFORE FRAMING CONSTRUCTION BEGINS!  
 WINDOW INSTALLER SHALL BE RESPONSIBLE FOR ADEQUATELY USING APPROPRIATE MOULDING TRIM STOPS, FASTENER TYPES AND SPACING AND FOR LATERAL STABILITY. PROPRIETARY COMMERCIAL WINDOW MFR SPECIFIED: KAWNEER




(X) SYMBOL INDICATES WINDOW/FRAMING STYLE AND SIZE; REFERENCE FLOOR PLAN A101 FOR WINDOW/FRAMING TYPE SYMBOL LOCATIONS; NOMINAL WINDOW SIZES SHOWN; VERIFY ROUGH OPENING SIZE.






**C EXTERIOR TRIM DETAIL** N.T.S.



**A SCHEMATIC DOOR ELEVATIONS** 1/2" = 1'-0"  
**B SCHEMATIC FRAME ELEVATIONS** 1/2" = 1'-0"



**1 A500 SILL (TYP) EXTERIOR ENTRANCE DOOR DETAIL** 3" = 1'-0"



**2 A500 SILL (TYP) WINDOW DETAIL** 3" = 1'-0"

revision  
 no. date  
 A 2/19/18 SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL  
 B 3/7/18 DESIGN DEVELOPMENT PROGRESS REVIEW  
 0 3/28/18 ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL

COPYRIGHT: DESIGN ELEMENTS 2018 THIS DRAWING AND THE DESIGNS SHOWN ARE THE PROPERTY OF MICHAEL L. SALED, ARCHITECT & DESIGN ELEMENT INC THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.  
 THIS SHEET SHOWS BASIC DRAFTING STANDARDS

**Design Elements**  
 M. L. Saled (Michael) AIA, LEED-AP  
 Architect / President  
 1213 Culbreth Drive, Suite 142  
 Wilmington, North Carolina 28401  
 910.250.3131  
 3/30/2018

**Proposed Dispatch Office Building for Crete Solutions, LLC**  
 WINDOW AND DOOR SCHEDULES & DETAILS  
 Contract Documents - Issued for Construction  
 job status  
 date 2/15/18  
 job no. CRETE/BUS  
 drawn by MSAIEED  
 checked by MSAIEED  
 drawing no.  
 A500  
 revision no. 0

DOOR AND FRAME SCHEDULE													
DOOR NO.	SPACE	DOOR				FRAME				HDW SET	REMARKS NOTE 1 & 2	DOOR NO.	
		WDTH	HGT.	THK.	MAT'L.	TYPE	GLAZING	MAT'L.	DETAILS HEAD JAMB SILL				
<b>EXTERIOR DOORS - ALL UNITS</b>													
HOLLOW METAL													
1	ENTRY	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	1	
2	ENTRY	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	2	
3	DRIVER LOUNGE	3'-0"	7'-0"	1-3/4"	I-HM	A	FULL	CLAD	1/A601 (ACCESSIBLE SILL)	-	Exterior Outswing Door	3	
<b>INTERIOR DOORS - ALL UNITS</b>													
4	TOILET	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	4	
5	BATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	5	
6	BATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	6	
7	DISPATCH OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	7	
8	ADMIN OFFICE	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	8	
9	UTILITY	2'-4"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	9	
10	TOILET	3'-0"	7'-0"	1-3/4"	MDF	B	---	---	---	---	---	10	
11	BREAK	4'-0"	7'-0"	---	MDF	---	---	---	---	---	Cased Opening	11	

**MATERIAL LEGEND:**  
 ALUM - ALUMINUM STOREFRONT  
 SCW - SOLID CORE WOOD  
 HM - HOLLOW METAL  
 I-HM - INSULATED HOLLOW METAL  
 WD - WOOD  
 PLAS - POLYVINYL REINF HOLLOW CORE  
 FRC - FIBERGLASS COMPOSITE OSB CORE  
 MDF - MEDIUM DENSITY FIBERGLASS






GHM - GALVANIZED HOLLOW METAL  
 GIM - GALV INSULATED HOLLOW METAL  
 GMS - GALVANIZED METAL SLATS  
 STL - STEEL RAIL ASSEMBLY  
 GLV - GALVANIZED METAL RAIL ASSEMBLY  
 GIPNL - GALV. INSULATED SECTIONAL PANEL

**GLAZING MATERIAL**  
 FULL - TEMPERED SINGLE PANE (FULL LITE)  
 HALF - TEMPERED SINGLE PANE (HALF LITE)  
 NVP - TEMPERED GLASS NARROW VIEW PANEL  
 DV - DOOR VIEWER (180° FIELD OF VIEW MIN)

**ABBREVIATED DOOR HARDWARE NOTES & SCHEDULE**  
 OPERABLE DOOR HARDWARE SHALL BE MOUNTED BETWEEN 30"(MIN.) AND 42"(MAX.) ABOVE FLOOR OR GROUND LEVEL AND "ALL" SHALL LEVER STYLE WITH TURN-BACK END RETURN, DESIGNATED FOR ARCHITECTURAL BARRIER FREE ACCESSIBLE. CONTRACTOR SHALL COORDINATE LATCH/LOCKSETS KEYING SCHEDULE WITH BUILDING OWNER BY PROVIDING MASTER AND GRAND MASTER KEYING SYSTEM  
 DOOR HARDWARE MATERIAL FINISH TYPES SHALL BE STAIN NICKEL PLATED (US26D) OR STAIN STAINLESS STEEL (US32D) AND INSTALLED BY CONTRACTOR. IF NOT DIRECTLY SPECIFIED BY OWNER, CONTRACTOR SHALL PROVIDE. ALL EXTERIOR HARDWARE AND MOVING PARTS SHALL HAVE SALT AIR RESISTANCE (STAINLESS STEEL OR BRASS) MECHANISMS SHALL BE HEAVY DUTY GRADE.  
 GENERAL CONTRACTOR SHALL BE RESPONSIBLE FOR DOOR ASSEMBLY AND HARDWARE IDENTIFICATIONS AND QUANTITIES AS SHOWN ON PLANS. PRIOR TO ORDERING ANY HARDWARE, CONTRACTOR TO SUPPLY OWNER AND DESIGNER WITH SPECS AND CUT SHEETS FOR APPROVAL AND TO COORDINATE WITH DOOR HARDWARE SPECIALIST AN ASSIGNED MASTER KEYING SYSTEM.

**GENERAL FRAME & GLAZING NOTES**  
 EXTERIOR METAL STOREFRONT WINDOW / DOOR AND FRAME SYSTEM ASSEMBLIES, U.N.O.  
 (TYP) NOM. 4.5" WIDE ALUM. EXTRUDED FIXED "THERMALLY BROKEN" EXTERIOR STOREFRONT WINDOW FRAME SYSTEMS W/ 1" INSULATED GLAZING (FRAME COLOR: "KYNAR" (CONFIRM WITH OWNER) (70% KYNAR PREMIUM PERFORMANCE COATING) FINISHED FRAMES (AAMA 2605; CLASS 1 611-CURRENT EDITION); GLAZING: PFG/SOLARBAN 60 CLEAR+CLEAR; TINTED, LOW-E GLASS; SHGC MIN. 0.36).  
 WINDOW/DOOR SYSTEM (FRAM'G-GLAZ'G) SHALL BE DESIGN PRESSURE (DP) WIND RATED FOR ITS GEOGRAPHICAL LOCATION; WINDOW INSTALLER SHALL BE RESPONSIBLE FOR ADEQUATELY USING APPROPRIATE FASTENER TYPES, SPACING AND VERTICAL FRAME STEEL STRUTS TO RESIST WIND SPEED (130 MPH) DP RATING. BASIS OF DESIGN:  
 SAFETY (S) - DESIGNATES IMPACT GLAZING.  
 ALL SAFETY GLAZING PRODUCTS SHALL COMPLY WITH THE APPLICABLE REQUIREMENTS UNDER OPCS 16 CFR PART 1201 CATEGORY II FOR TEMPERED/SAFETY-IMPACT GLAZING WHEN SUCH PRODUCTS ARE INSTALLED IN CONDITIONS CONSIDERED HAZARDOUS FOR HUMAN IMPACT AND AS REQUIRED UNDER CHAPTER 24 AND RELATED SECTIONS OF THE INTERNATIONAL BUILDING CODE: ICC/IBC-2012; CHAPTER 24; SECTION 2406  
 WINDOW/DOOR SUPPLIER SHALL PROVIDE ROUGH-OPENING SIZES, BEFORE FRAMING CONSTRUCTION BEGINS!  
 WINDOW INSTALLER SHALL BE RESPONSIBLE FOR ADEQUATELY USING APPROPRIATE MOULDING TRIM STOPS, FASTENER TYPES AND SPACING AND FOR LATERAL STABILITY. PROPRIETARY COMMERCIAL WINDOW MFR SPECIFIED: KAWNEER

(X) SYMBOL INDICATES WINDOW/FRAMING STYLE AND SIZE; REFERENCE FLOOR PLAN A101 FOR WINDOW/FRAMING TYPE SYMBOL LOCATIONS; NOMINAL WINDOW SIZES SHOWN; VERIFY ROUGH OPENING SIZE.



revision  
 no. date  
 A 2/19/18 SCHEMATIC DESIGN PROGRESS REVIEW AND APPROVAL  
 B 3/7/18 DESIGN DEVELOPMENT PROGRESS REVIEW  
 0 3/28/18 ISSUE FOR CODE ENFORCEMENT REVIEW AND APPROVAL

COPYRIGHT: DESIGN ELEMENTS 2018 THIS DRAWING AND THE DESIGNS SHOWN ARE THE PROPERTY OF MICHAEL L. SALEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS.

Design Elements  
 M. L. Saleed (Michael) AIA, LEED-AP  
 Architect / President  
 1213 Culbreth Drive, Suite 142  
 Wilmington, North Carolina 28403  
 910.526.3131

Proposed Dispatch Office Building for  
 Crete Solutions, LLC  
 WINDOW AND DOOR SCHEDULES & DETAILS  
 Contract Documents - Issued for Construction

DATE: 3/30/2018  
 PROJECT: DISPATCH OFFICE BUILDING FOR CRETE SOLUTIONS, LLC  
 JOB NO.: CRETE/BUS  
 DRAWN BY: MSAIEED  
 CHECKED BY: MSAIEED  
 DRAWING NO.: A600

date: 2/15/18  
 job no.: CRETE/BUS  
 drawn by: MSAIEED  
 checked by: MSAIEED  
 drawing no.: A600  
 revision no.: 0

# PLUMBING FIXTURE SCHEDULE

P-#	FIXTURES	SPECIFICATIONS	PIPING REQUIRED		
			WASTE	CW	HW
P-1	WATER CLOSET/ADA FLOOR MOUNTED TANK TYPE - 1.6 GPF	AMERICAN STANDARD "CADET RIGHT HEIGHT" MODEL 2298.012 VITREOUS CHINA TOILET WITH ELONGATED BOWL AND TANK WITH SIDE TRIP LEVER, 16 1/2" RIM HEIGHT, 1.6 GPF, 12" ROUGH-IN, BOLT CAPS, COMPLIES WITH ANSI A112.19.2 & A117.1 SEAT: BELMIS/CHURCH DURAGUARD 2100 NSSC ANTI-MICROBIAL HEAVY DUTY WHITE ELONGATED OPEN FRONT SEAT WITH COVER. VALVE: McGUIRE NO. 2166 3/8"x12" FLEX CLOSET SUPPLY WITH STOP.	3"	1/2"	--
P-2	URINAL - HANDICAP 3/4" TOP SPUD - 1.0 GPF MANUAL FLUSH VALVE	AMERICAN STANDARD "ALLBROOK" MODEL 6541.132 1.0 GPF 3/4" TOP SPUD, WHITE VITREOUS CHINA, 2" IPS OUTLET, WALL HANGER. MOUNT RIM 17" AFF TO COMPLY WITH ADA. VALVE: SLOAN REGAL MODEL 1-186-1-ADA, 1GPF, CHROME FLUSH WITH ADA COMPLIANT HANDLE.	2"	1/2"	--
P-3	LAVATORY - WALL MTD. SINGLE LEVER FAUCET ADA	AMERICAN STANDARD "LUCERNE" 0355.012 WALL MTD. WHITE VITREOUS CHINA 20"x18" LAVATORY WITH 4" FAUCET CENTERS. FAUCET: AMERICAN STANDARD "RELIANT +" MODEL NO. 7385 SINGLE LEVER LAVATORY FAUCET WITH CERAMIC DISC CARTRIDGE, INDEXED METAL LEVER, VANDAL RESISTANT 0.5 GPM AERATOR, 3/8" O.D. COPPER INLETS, ADJUSTABLE HOT LIMIT SAFETY STOP. SUPPLIES: McGUIRE NO. 165 3/8"x12" FLEX ANGLE SUPPLY WITH STOP STRAINER; McGUIRE NO. 155-A GRID STRAINER WITH 1 1/2" TAILPIECE. TRAP AND SUPPLY INSULATION: McGUIRE PREWRAPPED PROWRAP INSULATION KIT MODEL NO.2150	1-1/2"	1/2"	1/2"
P-4	LAVATORY - CABINET MTD. SINGLE LEVER FAUCET ADA	AMERICAN STANDARD "AQUALYN" 0476.028 CABINET MTD. WHITE VITREOUS CHINA 20"x17" SELF RIMMING LAVATORY WITH 4" FAUCET CENTERS. FAUCET: AMERICAN STANDARD "RELIANT +" MODEL NO. 7385 SINGLE LEVER LAVATORY FAUCET WITH CERAMIC DISC CARTRIDGE, INDEXED METAL LEVER, VANDAL RESISTANT 0.5 GPM AERATOR, 3/8" O.D. COPPER INLETS, ADJUSTABLE HOT LIMIT SAFETY STOP. TRAP AND SUPPLIES: McGUIRE NO. 155WC OFFSET WHEELCHAIR LAVATORY GRID STRAINER WITH 1 1/2" OUTLET. McGUIRE NO. 8902 17 GA 1 1/2"x1 1/2" P-TRAP & NIPPLE. McGUIRE NO 2165 1/2" IPS X 3/8" FLEX ANGLE SUPPLY WITH STOP.	1-1/2"	1/2"	1/2"
P-5	SINGLE BOWL SINK ADA	JUST MODEL NO. SL-1613-A-GR SINGLE COMPARTMENT SINK. 16"x13", 304 STAINLESS STEEL, 18 GAUGE, 3 1/2" FAUCET LEDGE WITH 4 HOLES @ 4" CENTERS. TRAP AND SUPPLIES: McGUIRE NO 151 CHROME PLATED FORGED BRASS STRAINER WITH 1-1/2" TAILPIECE, McGUIRE NO. 8912 1 1/2" P-TRAP AND NIPPLE. McGUIRE NO. 2165 ANGLE SUPPLIES WITH STOPS. FAUCET: JUST MODEL J1174KS TWO-HANDLE KITCHEN FAUCET. CHROME PLATED BRASS CONSTRUCTION, 6" WRIST BLADE HANDLES, COMPLIES WITH LATEST ADA REQUIREMENTS.	1-1/2"	1/2"	1/2"
P-6	ICE/COFFEE MAKER CONNECTION	PROVIDE RECESSED WALL BOX WITH SHUT-OFF VALVE, ROUTE 3/8" SOFT "K" COPPER TO MACHINE CONNECTION.	--	1/2"	--

## GENERAL PLUMBING SPECIFICATIONS

GENERAL: THE ENTIRE PLUMBING SYSTEM SHALL BE IN ACCORDANCE WITH THE NORTH CAROLINA BUILDING PLUMBING CODE. SUBMIT THREE (3) COPIES OF PLUMBING INSPECTION CERTIFICATES TO OWNER. PLUMBING CONTRACTOR SHALL OBTAIN AND PAY FOR ALL PERMITS REQUIRED BY GOVERNING AUTHORITIES FOR WORK DONE UNDER THIS CONTRACT. PROVIDE AND INSTALL ALL SUPPORTS, BRACKETS, MATERIALS AND LABOR AS REQUIRED FOR A COMPLETE AND ACCEPTABLE PLUMBING SYSTEM. PLUMBING CONTRACTOR SHALL CLEAN ALL PLUMBING FIXTURES AFTER ALL CONSTRUCTION IS COMPLETE.

SOIL, WASTE AND VENT PIPING: WASTE PIPING AND VENT PIPING SHALL BE P.V.C. - D.W.C. SCHEDULE 40 PIPE. HOWEVER, COEXTRUDED PVC "FOAM CORE", ASTM F891, WILL NOT BE ALLOWED.

ALL PENETRATIONS THROUGH NON-COMBUSTIBLE CONSTRUCTION SHALL BE PACKED WITH NON-COMBUSTIBLE FIRE STOPPING MATERIAL.

GRADE WASTE AND VENT PIPING 1/4 INCH PER FOOT WHERE POSSIBLE BUT NOT LESS THAN 1/8 INCH PER FOOT, UNLESS SPECIFICALLY DIRECTED. MAINTAIN INVERTS WHERE INDICATED.

WATER HEATER. ALL FITTINGS SHALL BE SWEAT TYPE WROUGHT COPPER WITH WALL THICKNESS EQUAL TO PIPE WALL THICKNESS. ALL JOINTS SHALL BE MADE WITH 95-5 SOLDER OR SILVABRITE 100. NO SOLDER W/LEAD SHALL BE PERMITTED.

ALL ROUGHING-IN PIPING SHALL BE RUN CONCEALED. ALL EXPOSED WATER LINES, STOPS, TRAP AND WASTE PIPE AT THE FIXTURES SHALL BE CHROME PLATED BRASS, WHICH FOR THE MOST PART WILL BE FINISHED WITH THE FIXTURES. CHROME PLATED ESCUTCHEON RINGS SHALL BE USED AT EACH POINT OF ENTRANCE OF CHROME PIPING INTO WALLS, FLOORS, OR CEILINGS. EXPOSED WORK SHALL BE UNIFORM IN HEIGHT AND LOCATION FOR EACH TYPE FIXTURE.

WATER PIPING UNDER GROUND OUTSIDE OF BUILDING SHALL BE AT LEAST 24 INCHES BELOW THE FINISHED GRADE SURFACE.

THERMAL INSULATION: ALL HOT AND COLD WATER PIPING INSIDE BUILDING AND IN CRAWL SPACE, ALL HOT WATER PIPING BELOW GRADE, AND COLD WATER PIPING BELOW GRADE WITHIN 3'-0" OF OUTSIDE SHALL BE INSULATED WITH 1" THICK "ARMAFLEX" OR IMCOA WITH SEALED JOINTS OR PREMOLED FIBERGLASS WITH VAPOR BARRIER JACKET. IN LIEU OF INSULATING WATER PIPING IN HEATED WALLS PIPING MAY BE ENCASED IN BATT INSULATION WITHIN THE WALL OR FLOOR/CEILING.

WATER HEATERS: WATER HEATERS SHALL BE UL LISTED AND COMPLETE WITH ALL STANDARD FEATURES, FIVE (5) YEAR TANK WARRANTY, GLASS-LINED TANK, FOAM INSULATION ON THE TANK, ANODE ROD, AUTOMATIC TEMPERATURE CONTROL, AND AUTOMATIC HIGH-LIMIT SAFETY CUTOFF.

EACH WATER HEATER SHALL BE PROVIDED WITH AN ASME APPROVED PRESSURE AND TEMPERATURE RELIEF VALVE. UNITS NOT INSTALLED WITH VACUUM BREAKER ON COLD WATER SUPPLY LINE SHALL BE PROVIDED WITH AGA CERTIFIED VACUUM RELIEF VALVE PER ANSI Z21.22. A GATE VALVE SHALL BE INSTALLED ON SAME FLOOR AS UNIT AND NO FURTHER THAN 3 FEET ON THE COLD WATER SUPPLY.

EACH WATER HEATER AND ITS INSTALLATION SHALL COMPLY WITH THE LATEST ISSUE AND ALL ADDENDA THERETO OF THE STATE BOILER INSPECTION LAWS AND REGULATIONS. ALL WIRING AND CONTROLS ASSOCIATED WITH THE HEATERS SHALL BE U.L. APPROVED AND IN ACCORDANCE WITH THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE.

EACH HEATER TANK SHALL BE FITTED WITH APPROVED "DIP" TUBE AND LABELED TO SHOW APPROVAL FOR INSTALLATION.

DISCHARGE RELIEF VALVE FROM EACH WATER HEATER SHALL BE PIPED FULL SIZE TO WITHIN SIX (6) INCHES OF THE FLOOR OVER A FLOOR DRAIN, DRIP PAN OR OTHER SAFE LOCATION. DISCHARGE PIPE SHALL BE SUPPORTED AND ANCHORED SO THAT IT WILL NOT PUT UNDUE STRAIN ON THE RELIEF VALVE BODY OR MOUNTING COUPLING.

SUBMITTAL: THE CONTRACTOR SHALL WITHIN (15) DAYS OF RECEIPT OF PROPERLY SIGNED CONTRACT SUBMIT TO THE ARCHITECT/ENGINEER FOR APPROVAL (5) COPIES OF A LIST OF SUPPLIES AND MANUFACTURER'S MATERIAL AND EQUIPMENT TO BE USED ON THIS PROJECT.

SUBSTITUTION OF MATERIALS AND/OR EQUIPMENT FOR THAT SPECIFIED WILL NOT BE ACCEPTED WITHOUT PRIOR WRITTEN APPROVAL BY THE ARCHITECT/ENGINEER PRIOR TO RECEIPT OF BIDS.

GUARANTEE: THE PLUMBING CONTRACTOR SHALL GUARANTEE ALL MATERIALS AND WORKMANSHIP FOR A PERIOD OF NOT LESS THAN ONE (1) YEAR FROM DATE OF FINAL ACCEPTANCE BY OWNER STATING THE DAY THE GUARANTEE BEGINS AND ENDS.

WATER HEATER (EWH): STATE M/N PCE 20 10MSA, 20 GALLON ELECTRIC WATER HEATER WITH ONE (1) 1500 WATT ELEMENT, 120 VOLT, SINGLE PHASE, WITH 3 YEAR WARRANTY. FURNISH WITH A.S.M.E. APPROVED RELIEF VALVE, WATERGUARD EXPANSION TANK M/N ETC-2X, AND DRAIN PAN. CONNECTION SIZES: C=1 1/4", H=1 1/4"

NOTE: PLANS SHOULD NOT BE SCALED FOR DIMENSIONS. COORDINATE ALL ROUGH IN DIMENSIONS WITH EQUIPMENT TO BE INSTALLED AND DIMENSIONED DRAWINGS INCLUDING KITCHEN EQUIPMENT PLANS IF AVAILABLE. CONTACT ENGINEER BEFORE CONSTRUCTION WITH ANY CONFLICTS.

## PLUMBING GENERAL NOTES:

1. PROVIDE ALL MATERIALS AND LABOR NECESSARY FOR COMPLETE AND PROPERLY FUNCTIONING PLUMBING SYSTEMS. WARRANTY ALL WORK AND ALL MATERIALS, EQUIPMENT AND DEVICES FOR A PERIOD OF ONE YEAR AFTER OWNER'S ACCEPTANCE.

2. WORK SHALL CONFORM TO OR MEET THE REQUIREMENTS OF THE MOST CURRENT EDITION OF:  
A. NORTH CAROLINA PLUMBING CODE  
B. ASPE  
C. UL  
D. ANSI  
E. ALL FEDERAL, STATE AND LOCAL CODES AND ORDINANCES

3. DRAWINGS ARE DIAGRAMMATIC IN NATURE AND ARE NOT INTENDED TO BE SCALED FOR DIMENSIONS, UNLESS DIMENSIONED.

4. ALL MATERIALS, EQUIPMENT AND DEVICES SHALL, AS A MINIMUM, MEET THE REQUIREMENTS OF UL WHERE UL STANDARDS ARE ESTABLISHED FOR THOSE ITEMS. ALL ITEMS SHALL BE CLASSIFIED BY UL AS SUITABLE FOR THE PURPOSE USED.

5. ALL ITEMS SHALL BE NEW, UNLESS NOTED OTHERWISE.

6. ALL MATERIALS AND EQUIPMENT SHALL BE CURRENT PRODUCTS BY MANUFACTURERS REGULARLY ENGAGED IN THE PRODUCTION OF SUCH PRODUCTS.

7. COORDINATE LOCATION OF PLUMBING WORK WITH OTHER TRADES TO AVOID CONFLICTS AND INTERFERENCES.

8. INSTALL ALL EQUIPMENT AND MATERIAL IN ACCORDANCE WITH MANUFACTURER'S WRITTEN PRINTED INSTRUCTIONS AND RECOMMENDATIONS.

9. COORDINATE WITH AND OBTAIN PERMITS AND INSPECTIONS FROM AUTHORITY HAVING JURISDICTION AND INCLUDE ALL FEES IN BID.

10. PROVIDE OWNER WITH CERTIFICATES OF FINAL INSPECTION AND ACCEPTANCE FROM AUTHORITY HAVING JURISDICTION.

11. ALL EQUIPMENT AND PIPE ABOVE CEILING SHALL BE SUPPORTED FROM BUILDING STRUCTURE ABOVE, UNO.

12. WHERE PIPES PENETRATE FIRE RATED BARRIERS (WALLS, FLOORS AND CEILINGS) SEAL OPENING AROUND PIPES AND DUCTWORK WITH U.L. LISTED FIRE STOPPING MATERIAL TO MAINTAIN THE FIRE RATING OF THE BARRIER. PER NC BUILDING CODE VOLUME 1, PENETRATIONS OF NONRATED WALLS, PARTITIONS AND FLOORS OF NONCOMBUSTIBLE CONSTRUCTION SHALL BE FIRE-STOPPED WITH NONCOMBUSTIBLE MATERIAL.

13. PROVIDE EXPANSION-DEFLECTION JOINTS WHERE PIPE CROSSES BUILDING EXPANSION OR SEISMIC JOINTS.

14. PRIOR TO BIDDING, THE CONTRACTOR AND HIS SUBCONTRACTORS SHALL VISIT THE JOBSITE AND SHALL FAMILIARIZE THEMSELVES WITH ALL CONDITIONS UNDER WHICH WORK IS TO BE PERFORMED AND SHALL INCLUDE IN HIS BID ALL LABOR, MATERIAL AND OPERATIONS REQUIRED FOR A COMPLETE JOB. (NOTIFY OWNER AND ENGINEER OF ANY DISCREPANCIES PRIOR TO BID.)



15. CLEANOUTS, LINE SIZE, UNO.

16. FLOOR DRAINS, LINE SIZE, UNO.

17. FLOOR DRAINS WITH SUBSCRIPT CO TO HAVE INTEGRAL CLEANOUT AND SHALL BE SIMILAR TO REGULAR FLOOR DRAIN SPECIFIED, UNO.


18. FLOOR DRAINS AND FLOOR SINKS SHALL BE PROVIDED WITH TRAP PRIMERS OR ALTERNATE METHODS AS APPROVED BY AUTHORITY HAVING JURISDICTION.

## PLUMBING LEGEND



WASTE RISER

SCALE: NONE




(A) ELECTRIC WATER HEATER

SCALE: NONE

no.	date	revision

COPYRIGHT: DESIGN ELEMENTS 2017 THIS SHEET SHOWS BASIC DRAFTING STANDARDS THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.



**Design Elements**  
Michael L. Saheed, Jr., AIA, AIBD  
1913 Calhoun Drive, Suite 142  
Wilmington, North Carolina 28403  
910.509.3131



**Proposed Dispatch Office Building for Crete Solutions, LLC**  
239 Raleigh Street  
Wilmington, North Carolina 28401  
**PLUMBING SCHEDULES, NOTES & DETAILS**  
Issued For Construction

date 28 MAR, 2018  
job no. CRETE/BUS  
drawn by KGLBERT  
checked by SEVERHART  
drawing no.

**P100**  
revision no.

PROJECT NO. 10065  
**McDOWELL CONSULTING ENGINEERS, INC.**  
1000 W. 10th Street, Suite 200  
Wilmington, NC 28403  
TEL (910) 270-3747 FAX (910) 270-3779  
NC LICENSE NO. C-25346

no.	date	revision




1  
P101

PROPOSED FLOOR PLAN — PLUMBING — WASTE

SCALE: 1/4" = 1'-0"

GRAPHIC BAR SCALE (FOOT UNITS)



COPYRIGHT; DESIGN ELEMENTS 2017 THIS DRAWING AND THE DESIGNS SHOWN ARE THE PROPERTY OF MICHAEL L. SAIED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.

**Proposed Dispatch Office Building for  
Crete Solutions, LLC**


239 Raleigh Street  
Wilmington, North Carolina 28401

FLOOR PLAN — PLUMBING — WASTE  
job status


Issued For Construction

date 28 MAR, 2018  
job no. CRETE/BUS  
drawn by KGLBERT  
checked by SEVERHART  
drawing no.

**P101**  
revision no.





Michael L. Saied, Jr., AIA, AIBD  
1213 Calhoun Drive, Suite 142  
Wilmington, North Carolina 28405  
P.O. BOX 3131



PROJECT NO. 10065  
MCDOWELL CONSULTING  
ENGINEERS, INC.  
1000 W. 36th St., Suite 200  
Harrisburg, PA 17104  
TEL (717) 270-3747 FAX (717) 270-3779  
PA LICENSE NO. C-2546



no.	date	revision





1  
P102

PROPOSED FLOOR PLAN — PLUMBING — WATER

SCALE: 1/4" = 1'-0"

GRAPHIC BAR SCALE (FOOT UNITS)



COPYRIGHT; DESIGN ELEMENTS 2017 THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAIED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS


**Proposed Dispatch Office Building for**  
**Crete Solutions, LLC**  
 239 Raleigh Street  
 Wilmington, North Carolina 28401

FLOOR PLAN — PLUMBING — WATER  
 job status  
**Issued For Construction**

date 28 MAR, 2018  
 job no. CRETE/BUS  
 drawn by KGILBERT  
 checked by SEVERHART  
 drawing no.

**P102**  
 revision no.

**Design Elements**  
 Michael L. Saied, Jr., AIA, AIBD  
 1213 Calhoun Drive, Suite 142  
 Wilmington, North Carolina 28405  
 P.O. BOX 3131



PROJECT NO. 10065  
 McDowell Consulting Engineers, Inc.  
 10000 W. Highway 101, Suite 200  
 Huntersville, NC 28043  
 TEL (910) 270-3747 FAX 270-3779  
 NC LICENSE NO. C-2546

GENERAL MECHANICAL SPECIFICATIONS

ALL WORK SHALL COMPLY WITH THE REQUIREMENTS OF THE LATEST EDITION OF THE NC MECHANICAL CODE.

**SHEET METAL WORK:** THIS CONTRACTOR SHALL FURNISH ALL DUCTWORK AND ASSOCIATED SHEET METAL WORK AS CALLED FOR ON THE DRAWINGS AND REQUIRED FOR A COMPLETE DUCTED AIR DISTRIBUTION SYSTEM.

DUCTWORK SHALL BE FABRICATED AND INSTALLED IN ACCORDANCE WITH BEST PRACTICES OF SHEET METAL WORK AND SMACNA STANDARDS.

ALL DUCTWORK SHALL BE GALVANIZED SHEET IRON THROUGHOUT EXCEPT WHERE OTHERWISE SHOWN AND FABRICATED IN ACCORDANCE WITH THE FOLLOWING TABLE (ALL DUCT SIZES ON CONTRACT DRAWINGS ARE SHEET METAL FABRICATION SIZES):

MAXIMUM DIMENSION OF DUCT	GAUGE U.S. STD.	TRANSVERSE JOINT	BRACING
UP TO 12"	26	DRIVE SLIPS 7"-10" CENTERS	NONE
13" TO 30"	24	DRIVE SLIPS 7"-10" CENTERS	1"X1"X1/8" ANGLES 4 FEET FROM JOINT

DUCTS 25 INCHES OR SMALLER IN MAXIMUM DIMENSION SHALL BE SUPPORTED WITH 1 INCH FLAT BAND HANGERS; DUCTS 25 INCHES AND LARGER SHALL BE SUPPORTED BY 3/4 INCH X 1-1/2 INCH ANGLE IRON AND ROUND ROD. SUPPORTS SHALL BE NOT MORE THAN 8 FEET ON CENTERS, PROPERLY FASTENED AND PLACED TO BUILDING STRUCTURES AND SHALL EXTEND AND BE RIVETED TO THE BOTTOM OF DUCTS.

UNLESS OTHERWISE SPECIFIED, FURNISH AND INSTALL ALL NECESSARY LINTELS, PROPERLY SIZED, SHEET METAL SLEEVES AND ESCUTCHEON COLLARS WHERE DUCTWORK RISES THROUGH FLOORS OR PASSES THROUGH WALLS OR CEILINGS.

FURNISH AND INSTALL FLEXIBLE COLLARS IN THE DUCTWORK CONNECTIONS TO AIR HANDLING FANS TO PREVENT NOISE TRANSMISSION BETWEEN SECTIONS.

ALL CHANGES IN DUCT DIRECTION SHALL BE LONG RADIUS ELBOWS OR SHALL BE FITTED WITH TURNING VANES. IT IS ACCEPTABLE TO CHANGE RECTANGULAR DUCTWORK TO THE EQUIVALENT SIZE IN ROUND PROVIDED THE CONTRACTOR COORDINATES ALL CLEARANCE ISSUES.

**DUCT INSULATION:**

ALL CONCEALED DUCTWORK SHALL BE INSULATED ON THE OUTSIDE WITH TWO INCH (2") THICK, 3/4 POUND DENSITY FIBERGLASS BLANKET INSULATION HAVING AN ALUMINUM FOIL-SCRIM VAPOR BARRIER JACKET.

EDGES OF INSULATION SHALL BE CUT STRAIGHT AND TRUE AND SHALL BE TIGHTLY BUTTED. THE VAPOR BARRIER JACKET SHALL OVERLAP THE BLANKET JOINT A MINIMUM OF THREE INCHES (3"). THE JACKET LAP SHALL BE FASTENED WITH MOISTURE RESISTANT ADHESIVE AND ALSO OUTWARD CLINCHING STAPLES SPACED TEN INCHES (10") C/C. THE VAPOR BARRIER EDGE AND STAPLES SHALL THEN BE COVERED WITH A THREE INCH (3") WIDE TAPE OF THE SAME MATERIAL AS THE JACKET AND SHALL BE FASTENED WITH MOISTURE RESISTANT ADHESIVE.

ALL CUTS, TEARS AND PENETRATIONS IN THE VAPOR BARRIER JACKET SHALL BE SEALED WITH JOINT TAPE. ALL EDGES OF INSULATING BLANKET SHALL BE SEALED FROM THE JACKET TO DUCT SURFACE WITH TAPE.

INSULATING BLANKET ON THE BOTTOM OF SURFACES IN EXCESS OF 24 INCHES WIDE SHALL BE SECURED AGAINST THE DUCT WITH ADHESIVE OVER THE ENTIRE AREA, MECHANICAL CLIPS ON 24 INCH CENTER OR BY WIRE TIES AROUND THE DUCT SPACED 24 INCHES C/C.

CONTRACTOR MAY USE FLEXIBLE DUCTWORK (MAXIMUM LENGTHS 15'-0") FOR FINAL CONNECTIONS TO DIFFUSERS/GRILLES. FLEXIBLE DUCTWORK SHALL BE CERTIFLEX 25 AS MANUFACTURED BY THE CERTAINTeed CORPORATION.

**REGISTERS AND GRILLES:** ALL REGISTERS AND GRILLES SHALL BE OF SIZE, STYLE AND CAPACITY CALLED FOR ON PLANS AND IN THE GRILLE SCHEDULE. PROVIDE RUBBER OR EXPANDED FOAM GASKETS COMPLETELY AROUND ALL REGISTER AND GRILLE FRAMES TO PREVENT AIR LEAKAGE BETWEEN GRILLE FRAME AND DUCT OR BETWEEN GRILLE FRAME AND SURROUNDING FINISHED SURFACE. ACCEPTABLE MFGS: PRICE, CARNES, METALAIR, KRUGER. REGISTERS AND GRILLES SHALL BE BALANCED TO CFM SHOWN AND RECORD MADE OF ACTUAL FLOW AND BALANCE METHOD.

**EQUIPMENT:** MECHANICAL AND ELECTRICAL CONTRACTORS SHALL COORDINATE PRIOR TO ORDERING EQUIPMENT TO VERIFY CONSISTANT VOLTAGES. PRIOR TO EQUIPMENT BEING ENERGIZED, VOLTAGE TO EQUIPMENT CIRCUITS SHALL BE VERIFIED AS INSTALLED TO MATCH EQUIPMENT NAMEPLATE.

**OPERATING INSTRUCTIONS, CERTIFICATES AND WARRANTIES:** THE ORIGINAL OF ALL INSPECTION CERTIFICATES SHALL BE DELIVERED TO THE OWNER AND ONE (1) COPY EACH TO THE ENGINEER PRIOR TO REQUEST FOR FINAL PAYMENT.

THREE (3) COPIES OF OPERATING AND MAINTENANCE INSTRUCTIONS AND MANUFACTURER'S WARRANTIES FOR ALL EQUIPMENT PROVIDED UNDER THIS CONTRACT SHALL BE PROVIDED TO THE OWNER PRIOR TO SUBMITTING REQUEST FOR FINAL PAYMENT.

PRIOR TO FINAL PAYMENT TO THE CONTRACT, THE CONTRACTOR SHALL BE RESPONSIBLE TO TRAIN THE AUTHORIZED PERSONNEL ON HOW TO SERVICE, START-UP AND SHUT-DOWN THE VARIOUS SECTIONS OF THE SYSTEM. UPON COMPLETION OF THIS PHASE OF THE CONTRACT, THE CONTRACTOR SHALL SECURE A LETTER OF ACCEPTANCE FROM THE OWNER THAT HE IS SATISFIED WITH THE CONDITIONS STIPULATED HEREIN. UPON ACCEPTANCE OF THIS LETTER AND AT THE DISCRETION OF THE ENGINEER, THE FINAL PAYMENT WILL BE MADE.

THE CONTRACTOR SHALL PROVIDE A WRITTEN GUARANTEE OF ALL MATERIALS AND WORKMANSHIP FOR A PERIOD OF ONE (1) YEAR FROM DATE OF SYSTEM ACCEPTANCE.

THE WORK UNDER THIS CONTRACT WILL BE ACCEPTED ONLY AS AN ENTIRE SYSTEM UPON SATISFACTORY COMPLETION OF THE REQUIRED TESTS. NO PARTIAL ACCEPTANCE OF ANY PART OR PORTION OF APPARATUS WILL BE MADE.

INSTALL AND CONNECT ALL EQUIPMENT IN ACCORDANCE WITH MANUFACTURER'S RECOMMENDATIONS AND DO ALL WORK IN A NEAT AND WORKMANLIKE MANNER AND IN ACCORDANCE WITH ACCEPTED GOOD PRACTICE AS JUDGED BY THE ENGINEER.

ALL EQUIPMENT AND PIPING SHALL BE SO INSTALLED THAT NO OBJECTIONABLE NOISES FROM EQUIPMENT, PIPING OR AIR DISTRIBUTION ARE AUDIBLE IN THE FINISHED AREAS.

**GUARANTEE:** THIS CONTRACTOR SHALL GUARANTEE ALL MATERIALS, EQUIPMENT AND WORKMANSHIP FOR ONE (1) YEAR FOLLOWING FINAL INSPECTION AND ACCEPTANCE OF THE BUILDING BY THE ENGINEER AND OWNER. THIS APPLIES TO ALL MATERIALS AND EQUIPMENT INSTALLED UNDER THIS CONTRACT, REGARDLESS OF SOURCE.

THE ONE (1) YEAR GUARANTEE PERIOD WILL START ON THE DAY OF FINAL INSPECTION AND ACCEPTANCE BY THE OWNER. THE CONTRACTOR SHALL PROVIDE THE ENGINEER A LETTER WITH TWO (2) COPIES STATING THE BEGINNING AND ENDING DATES OF THE GUARANTEE BASED ON THE AFOREMENTIONED STARTING DATES.

**EXTENDED GUARANTEE:** PROVIDE AN ADDITIONAL FOUR (4) YEAR GUARANTEE ON ALL COMPRESSORS BEYOND THE ABOVE MENTIONED ONE (1) YEAR GUARANTEE PERIOD.

**AIR BALANCE:** ALL SYSTEMS SHALL BE BALANCED BY THE CONTRACTOR PER THE REQUIREMENTS OF SECTION 503.2.9 OF THE NORTH CAROLINA STATE BUILDING CODE: ENERGY CONSERVATION CODE.

**ENERGY CODE COMPLIANCE:** HVAC EQUIPMENT SELECTED MEETS PERFORMANCE REQUIREMENTS OF THE NORTH CAROLINA STATE BUILDING CODE: ENERGY CONSERVATION CODE SECTION 506.2.1. ANY SUBSTITUTIONS MUST MEET THIS STANDARD AS WELL. UPON FINAL INSPECTION THE CONTRACTOR SHALL PROVIDE TO OWNER MANUALS AND EVIDENCE OF AIR BALANCE. CONTRACTOR SHALL SCHEDULE DESIGN PROFESSIONAL AND ASSIST TO COMPLETE SYSTEM INSTALLATION STATEMENT IN ACCORDANCE WITH THE NORTH CAROLINA STATE BUILDING CODE: ENERGY CONSERVATION CODE SECTION 503.2.9.

MECHANICAL LEGEND

	NEW DUCTWORK
	NEW SUPPLY GRILLE/DIFFUSER
	NEW RETURN GRILLE/DIFFUSER
	THERMOSTAT
	CFM TAG
	EXHAUST FAN
	CONDENSATE/REFRIGERANT PIPE

MECHANICAL SYSTEMS, SERVICE SYSTEMS AND EQUIPMENT

METHOD OF COMPLIANCE: ENERGY CODE

Prescriptive  Energy Cost Budget

Thermal Zone	_____ ZH
Exterior design conditions	_____
winter dry bulb	_____ 26° F
summer dry bulb	_____ 92° F DB/76° F WB
Interior design conditions	_____
winter dry bulb	_____ 70° F
summer dry bulb	_____ 75° F
relative humidity	_____ 50%
Building heating load	_____ 18.5 MBTU/H
Building cooling load	_____ 3.5 TONS
Mechanical Spacing Conditioning System	_____
Unitary	description of unit _____
heating efficiency	_____ 9.0 HSPF MIN.
cooling efficiency	_____ 15.0 SEER MIN.
heat output of unit	_____ SEE SCHEDULES
cooling output of unit	_____ SEE SCHEDULES
boiler	total boiler output. If oversized, state reason. _____
chiller	total chiller capacity. If oversized, state reason. _____
chiller	total chiller capacity. If oversized, state reason. _____
List equipment efficiencies	_____ N/A

Equipment schedules with motors (mechanical systems)

motor horsepower	_____ SEE SCHEDULES
number of phases	_____ SEE SCHEDULES
minimum efficiency	_____ SEE SCHEDULES
motor type	_____ ODP
# of poles	_____ 4
Additional prescriptive compliance method :	_____ 506.2.1 More Eff. Mech Equip.

DESIGNER STATEMENT:

To the best of my knowledge and belief, the design of this building complies with the mechanical systems, service systems and equipments of the 2012 North Carolina State Energy Code.

SIGNED: \_\_\_\_\_  
 NAME: STEVEN H. EVERHART JR., P.E.  
 TITLE: PROFESSIONAL ENGINEER

SPLIT SYSTEM HEAT PUMP SCHEDULE

UNIT NUMBER	AHU-1	
AREA SERVED		
MANUFACTURER	TRANE	
MODEL NUMBER	TAM7A0C48	
UNIT WEIGHT (LBS)	163	
FAN	TOTAL AIR CFM	1600
	OUTSIDE AIR CFM	160
	FAN H.P.	3/4
	EXT. S.P. (IN. H2O)	0.4
	POWER SUPPLY	208/230/60/1
COOLING CAPACITY	TOTAL CAPACITY COOLING (BTUH)	49,700
	SENSIBLE CAPACITY COOLING (BTUH)	36,700
	ENTERING AIR TEMP.	80/67
HEATING CAPACITY	ENTERING AIR TEMP.	70 °F
	HIGH TEMPERATURE (BTUH) 47°F DB	47,800
	LOW TEMPERATURE (BTUH) 17°F DB	31,000
	AUXILIARY COIL CAPACITY	7.21/9.6 KW @ 208/240
	POWER SUPPLY	208/230/60/1
AIR COOLED HEAT PUMP	UNIT NUMBER	HP-1
	MODEL NUMBER	4TWR5049
	UNIT WEIGHT	294
	ENTERING AIR TEMP.	95°F
	FAN TYPE	PROPELLER
ACCESSORIES	FAN H.P.	1/3
	COMPRESSOR	SCROLL
	POWER SUPPLY	208/230/60/1
	MINIMUM AMPACITY	30
	MAX. OVERCURRENT PROTECTION	50
ACCESSORIES	(1), (2), (3)	

- PROVIDE WALL MOUNTED, PROGRAMMABLE ELECTRONIC THERMOSTAT WITH AUTO CHANGEOVER.
- SYSTEMS SELECTED MEET REQUIREMENTS UNDER SECTION 506 OF THE NORTH CAROLINA STATE BUILDING CODE: ENERGY CONSERVATION CODE.
- PROVIDE STRIP HEAT SHUTOFF PER 503.2.4.1.1

EXHAUST FAN SCHEDULE

TAG	CFM	RPM	S.P. IN.	W.G.	WATTS/HP	SONES	ELECTRIC	MANUFACTURER MODEL NUMBER	DESCRIPTION & ACCESSORIES
EF-1	75	700	.25		50 WATTS	3.0	120-1-60	GREENHECK SP-B90	1, 2, 3

- CABINET CEILING FAN, DIRECT DRIVE, CENTRIFUGAL, SPRING LOADED ALUMINUM BACKDRAFT DAMPER.
- ALUMINUM, WHITE ENAMEL CEILING GRILLE.
- ALUMINUM HOODED WALL CAP WITH BUILT-IN BIRDSCREEN AND DAMPER.

AIR DISTRIBUTION DEVICE SCHEDULE


TAG	SERVICE	NECK SIZE	OVERALL SIZE	MODEL NUMBER	DESCRIPTION & ACCESSORIES
A	SUPPLY	8"	12 X 12	ASCD	1, 2, 4, 7, 8
B	SUPPLY	10"	24 X 24	ASCD	1, 2, 3, 7, 8
C	RETURN	30 X 20	30 X 20	630	1, 2, 4, 5

- PRICE AIR DISTRIBUTION; OR APPROVED EQUAL.
- ALUMINUM CONSTRUCTION, STANDARD WHITE FINISH.
- T-BAR LAY-IN PANEL.
- SURFACE MOUNT BORDER.
- CFM SHOWN IN GRILLE TAG IS MAXIMUM POSSIBLE WITH EXHAUST AND OUTSIDE AIR AT 0.
- DOUBLE DEFLECTION GRILLE.
- SQUARE FACE, ROUND NECK DIFFUSER
- BUTTERFLY STYLE VOLUME CONTROL DAMPER.

NOTE: FLEXIBLE DUCTWORK SHALL MATCH DIFFUSER NECK SIZE UNLESS OTHERWISE NOTED.

THIS SHEET SHOWS BASIC DRAFTING STANDARDS  
 THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SAEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.  
 COPYRIGHT © DESIGN ELEMENTS 2017  
 PROJECT NO. 10065  
 McDowell Consulting Engineers, Inc.  
 1313 Calhoun Drive, Suite 142  
 Wilmington, North Carolina 28405  
 TEL (910) 270-3747 FAX (910) 270-3779  
 NC LICENSE NO. C-2546  
 DESIGN ELEMENTS  
 Michael L. Saheed, Jr., AIA, AIBD  
 1313 Calhoun Drive, Suite 142  
 Wilmington, North Carolina 28405  
 P.O. Box 3131  
 Proposed Dispatch Office Building for  
**Crete Solutions, LLC**  
 239 Raleigh Street  
 Wilmington, North Carolina 28401  
 MECHANICAL SCHEDULES, NOTES & DETAILS  
 job status  
 Issued For Construction  
 date 28 MAR, 2018  
 job no. CRETE/BUS  
 drawn by KGLBERT  
 checked by SEVERHART  
 drawing no.  
**M100**  
 revision no.

no.	date	revision





1  
M101

PROPOSED FLOOR PLAN — MECHANICAL

SCALE: 1/4" = 1'-0"

GRAPHIC BAR SCALE (FOOT UNITS)



GENERAL NOTES:

- ① ROUTE 6" EXHAUST TO WALL OR ROOF CAP AS CORRINATED IN FIELD.
- ② REFRIGERANT PIPING CONCEALED ABOVE CEILING AND IN BUILDING CONSTRUCTION, SIZE AS RECOMMENDED BY UNIT MANUFACTURER. (TYP.)
- ③ 1" CONDENSATE DRAIN PIPING WITH PROPER PITCH. TERMINATE OUTSIDE BUILDING, MIN. 8" ABOVE GRADE WITH ELBOW LOOKING UP. (TYP.)
- ④ MOUNT UNIT ON 4" CONCRETE PAD OR PAVED SURFACE.
- ⑤ ROUTE 8" O.A. TO INTAKE VENT VIA BACKDRAFT DAMPER AND BALANCE DEVICE. MINIMUM 10' BETWEEN O.A. INTAKE AND EXHAUST FAN CAP.
- ⑥ 20 X 12 UP TO CEILING AREA.

COPYRIGHT: DESIGN ELEMENTS 2017 THIS DRAWING AND THE DESIGNS SHOWN ARE THE PROPERTY OF MICHAEL L. SAIED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS

**Proposed Dispatch Office Building for  
Crete Solutions, LLC**


239 Raleigh Street  
Wilmington, North Carolina 28401

FLOOR PLAN — MECHANICAL

job status  
**Issued For Construction**

date 28 MAR, 2018  
job no. CRETE/BUS  
drawn by KGILBERT  
checked by SEVERHART  
drawing no.

**M101**  
revision no.



**Design Elements**  
Michael L. Saied, Jr., AIA, AIBD  
1213 Calhoun Drive, Suite 142  
Wilmington, North Carolina 28405  
P.O. BOX 3131

PROJECT NO. 10065  
MCDOWELL CONSULTING  
ENGINEERS, INC.  
1000 W. 36th St., Suite 200  
Harrisburg, PA 17104  
TEL (717) 270-3747 FAX 270-3779  
PA LICENSE NO. C-2546

**DETAILED ELECTRICAL SPECIFICATIONS**

SCOPE: FURNISH ALL MATERIALS, LABOR, TOOLS, EQUIPMENT AND SUPERVISION NECESSARY TO INSTALL COMPLETE ELECTRICAL POWER AND LIGHTING SYSTEM IN THE BUILDING AS FURTHER DESCRIBED ON THE ELECTRICAL CONTRACT DRAWINGS.

SUPPLY ALL MATERIALS, FITTINGS AND HARDWARE NECESSARY FOR COMPLETE OPERATING SYSTEMS WITHIN THE OBVIOUS INTENT OF THE DRAWINGS. NO ATTEMPT HAS BEEN MADE TO DETAIL OR LIST EACH AND EVERY ITEM OF MATERIAL. THE ELECTRICAL CONTRACTOR IS CAUTIONED TO READ THE ENTIRE PROJECT DRAWINGS AND SPECIFICATIONS TO ASSURE HIMSELF OF A THOROUGH KNOWLEDGE OF BUILDING CONSTRUCTION, STRUCTURAL RESTRICTIONS TO ELECTRICAL CONTRACT WORK AND TO ASSURE THAT NO REFERENCE ANYWHERE IN THE PROJECT DRAWINGS AND SPECIFICATIONS TO WORK BY THE ELECTRICAL CONTRACTOR IS OVERLOOKED.

**CODES, PERMITS AND INSPECTIONS:** THE LATEST EDITION OF THE STATE BUILDING CODE WHICH INCLUDES THE 2014 EDITION OF THE NATIONAL ELECTRICAL CODE IS HEREBY MADE A PART OF THIS SPECIFICATION. CODE REQUIREMENTS SHALL TAKE PRECEDENCE OVER THESE SPECIFICATIONS WHERE THE CODE REQUIREMENTS EXCEED THAT OF THE SPECIFICATIONS. HOWEVER, THE SPECIFICATIONS SHALL BE FOLLOWED WHERE THEY EXCEED CODE REQUIREMENTS. THE ELECTRICAL CONTRACTOR SHALL, AT NO ADDITIONAL COST TO THE OWNER, OBTAIN THE SERVICES OF THE LOCAL ELECTRICAL INSPECTOR TO MAKE ALL REQUIRED DURING CONSTRUCTION AND COMPLETED ELECTRICAL SYSTEM INSPECTIONS.

**MATERIALS AND WORKMANSHIP:** ALL MATERIAL BUILT INTO THIS PROJECT SHALL BE NEW OF EQUIVALENT OR BETTER QUALITY THAN THAT SPECIFIED. SPECIFIC NAMES AND CATALOG NUMBERS USED HEREIN ARE TO ESTABLISH THE ITEM FUNCTION, ARRANGEMENT AND QUALITY REQUIRED AND ARE NOT INTENDED TO RESTRICT COMPETITION. ALL MATERIALS SHALL BE UL LISTED AND LABELED FOR THE PARTICULAR APPLICATION AS USED ON THIS PROJECT.

**CONDUCTORS:** ALL CONDUCTORS SHALL BE COPPER (#10 AWG AND SMALLER SHALL BE SOLID, AND #8 AWG AND LARGER STRANDED) WITH THHN/THWN INSULATION, INSTALLED IN CONDUIT OR APPROVED CABLE ASSEMBLY. NM CABLE SHALL NOT BE USED. CONDUCTORS SHALL BE #12 AWG MINIMUM EXCEPT WITHIN LIGHT FIXTURES, LOW VOLTAGE CONTROLS OR COMMUNICATION/FIRE ALARM EQUIPMENT. CONDUCTOR COLOR CODE SHALL CONFORM TO THE NEC. CONDUCTORS SHALL BE CONTINUOUS FROM TERMINAL TO TERMINAL OR PULL BOX TO PULL BOX. JOINTS SHALL BE MADE WITH IDEAL "WIRENUTS."

**RACEWAYS:** RACEWAYS SHALL BE ELECTRICAL METALLIC TUBING (EMT) WITH THREADED STEEL HEXAGONAL COMPRESSION FITTINGS - NEITHER INDENTOR TYPE OR DIE METAL FITTING WILL BE ACCEPTED. CONDUIT UNDER THE FLOOR SLAB AND UNDER GROUND OUTSIDE THE BUILDING MAY BE PVC. FITTINGS IN EMT SHALL BE WEATHER TIGHT (THOMAS AND BETTS SERIES #5123 WITH NYLON INSULATED THROATS), BENDS SHALL BE FACTORY FABRICATED OR MADE "COLD" WITH BENDING TOOL, FREE OF KINKS OR RESTRICTIONS. NO SINGLE BEND SHALL BE IN EXCESS OF 90 DEGREES. THERE SHALL BE NO MORE THAN THE EQUIVALENT OF THREE (3) 90 DEGREE BENDS IN A GIVEN RACEWAY FROM PULL BOX TO PULL BOX. RIGID RACEWAY THREADS SHALL BE CUT STRAIGHT AND TRUE - PIPE ENDS SHALL BE REAMED AND SMOOTHED INSIDE AND OUT.

SUPPORT 1-1/2 INCH AND LARGER CONDUIT 10 FEET O/C OR LESS, AND 1 INCH AND SMALLER 6 FEET O/C MAXIMUM. RACEWAYS SHALL BE SUPPORTED DIRECTLY FROM BUILDING STRUCTURE WITH BOLTS, SCREWS, STRAPS, HANGER RODS AND BRACKETS. ALL METALLIC HARDWARE SHALL BE GALVANIZED OR CADMIUM PLATED. NAILS, WIRE AND/OR PERFORATED STRAPS WILL NOT BE ACCEPTED.

USE THREADED LOCKNUTS OUTSIDE AND BUSHING INSIDE ALL RACEWAY CONNECTIONS TO BOXES, DEVICES, PANELS AND GUTTERS. USE NON-METALLIC BUSHINGS ON ALL 1-1/4 INCH AND LARGER CONDUIT. EXPOSED CONDUIT SHALL BE RUN STRAIGHT AND TRUE PARALLEL AND PERPENDICULAR TO PRIMARY BUILDING LINES.

**BOXES AND DEVICES:** ALL BOXES, PANELS AND EQUIPMENT SHALL BE SUPPORTED DIRECTLY FROM THE BUILDING STRUCTURE AND SHALL NOT DEPEND ON THE FEEDER RACEWAYS FOR SUPPORT. ALL ITEMS SHALL BE CAREFULLY ALIGNED SO THAT COVERS WILL FINISH FLUSH AND STRAIGHT. ALL UNUSED KNOCKOUTS SHALL BE CLOSED WITH BLANKING DEVICES. BOXES IN CONCRETE OR MASONRY SHALL BE 3-1/2 INCH DEEP (MINIMUM) SQUARE 16 GAUGE GALVANIZED STEEL - STEEL CITY SERIES GW. BOXES INSTALLED IN WOOD PARTITIONS SHALL BE STEEL CITY 3-1/2 INCH DEEP GANGABLE SQUARE CORNER TYPE. RECEPTACLES SHALL BE HUBBELL 5362 OR EQUAL SWITCHES SHALL BE HUBBELL 1120 SERIES OR EQUAL. COVER PLATES SHALL BE IMPACT RESISTANT.

PULL BOXES SHALL BE 14 GAUGE GALVANIZED STEEL WITH BLANK COVER SIZED AS REQUIRED BY NATIONAL ELECTRICAL CODE. LOCATE DEVICES AND EQUIPMENT ABOVE FINISHED FLOOR AS FOLLOWS UNLESS OTHERWISE SPECIFICALLY NOTED ON PLANS:

- WALL SWITCHES - 4"-0" OR TO NEAREST MASONRY COURSE JOINT.
- RECEPTACLES - 1'-6" OR TO NEAREST MASONRY COURSE JOINT.
- LIGHT FIXTURES - AS NOTED ON FIXTURE SCHEDULE.

**GROUNDING:** THE ELECTRICAL SYSTEM AND ALL ELECTRICAL EQUIPMENT SHALL BE GROUNDED IN ACCORDANCE WITH ARTICLE 250 OF THE LATEST EDITION OF THE NATIONAL ELECTRICAL CODE. GREEN EQUIPMENT GROUND WIRE SHALL BE USED WITH ALL FEEDERS AND BRANCH CIRCUITS.

**LIGHTING FIXTURES:** LIGHTING FIXTURES AND LAMPS SHALL BE PROVIDED AND INSTALLED AS PER SCHEDULE. ALL FIXTURES SHALL BE CLEANED ON COMPLETION OF INSTALLATION.

**TESTS:** THE CONTRACTOR SHALL MEGGER ALL BUSWAYS, CABLES AND CONTROL CONNECTIONS TO PROVE INSULATION RESISTANCE IS OF ACCEPTABLE VALUE.

**PANELBOARDS:** PROVIDE PANELBOARDS RATED AND SIZED AS INDICATED IN THE SCHEDULE AND SHOWN ON THE PLANS EQUAL TO SQUARE D COMPANY MODEL QO LOAD CENTER.

ACCEPTABLE MANUFACTURERS: SQUARE D, GENERAL ELECTRIC, SIEMENS, CUTLER-HAMMER

**SAFETY SWITCHES:** SWITCHES SHALL BE EQUAL TO SQUARE D TYPE GD WITH RATINGS AND FUSING PROVISIONS AS INDICATED.

**IDENTIFICATION AND NAMEPLATES:** PROVIDE ENGRAVED, LAMINATED BAKELITE (WHITE LETTERS ON BLACK SURFACE) NAMEPLATES SCREWED TO EACH PIECE OF ELECTRICAL DISTRIBUTION EQUIPMENT AS FOLLOWS:

A. PANELBOARDS, SWITCHBOARDS - DESIGNATION L1, P1, ETC., VOLTAGE, PHASE NUMBER OF WIRES, ETC.; WORDING EXAMPLE: PANEL L1-208V-3 PHASE, 4 WIRE.

B. MOTOR STARTERS, DISCONNECT SWITCHES - UNLESS MOUNTED DIRECTLY ON OR ADJACENT TO IDENTIFY EQUIPMENT; WORDING EXAMPLE: EXHAUST FAN 1, MAKE-UP AIR UNIT.

PROVIDE TYPED DIRECTORIES FOR PANELBOARD BRANCH CIRCUIT IDENTIFICATION. IDENTIFY EACH CIRCUIT BREAKER AS TO THE EXACT ROOM NUMBERS OR AREA SERVED AND THE TYPE OF CIRCUIT, I.E. "ROOMS 101-104 LIGHTS" OR "CAFETERIA EXHAUST FAN".

**EQUIPMENT CONNECTIONS:** THIS CONTRACTOR SHALL BRING ALL REQUIRED ELECTRICAL SERVICE TO ALL EQUIPMENT ITEMS FURNISHED UNDER OTHER SECTIONS OF THESE SPECIFICATIONS OR BY THE OWNER, MAKE FINAL CONNECTIONS, AND LEAVE EQUIPMENT READY FOR OPERATION. THIS CONTRACTOR SHALL COORDINATE WITH ANY AFFECTED TRADE TO ASSURE CORRECT OPERATION OF THE EQUIPMENT ITEM.

**CONTROL AND INTERLOCK WIRING:** EXCEPT AS OTHERWISE INDICATED ON THE DRAWINGS, ALL CONTROL AND INTERLOCK WIRING SHALL BE PERFORMED BY THE RESPECTIVE CONTRACTORS.

THE ELECTRICAL SUBCONTRACTOR SHALL INSTALL ALL STARTERS, PILOT SWITCHES, CONTROL DEVICES AND MISCELLANEOUS ITEMS OF ELECTRICAL EQUIPMENT FURNISHED UNDER OTHER SECTIONS OF THESE SPECIFICATIONS THAT ARE NOT INTEGRALLY MOUNTED WITH THEIR ASSOCIATED EQUIPMENT.

SERVICE: THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR COORDINATING SERVICE WITH THE UTILITY COMPANY. PROVIDE UTILITY REQUIRED METERING PROVISIONS. PROVIDE CT CAN OR CONCRETE PAD FOR TRANSFORMER AS REQUIRED. PROVIDE CONDUIT FOR UTILITY IF REQUIRED. EC SHALL WORK DIRECTLY WITH THE UTILITY AND SHALL COMPLETE AND SUBMIT ALL LOAD DATA SHEETS REQUIRED FOR SERVICE APPLICATION.




**EQUIPMENT CONNECTION SCHEDULE**

CALLOUT	SYMBOL	VOLTS	AMPS	KVA	CIRCUIT	WIRE CALLOUT	MCA	MOCP	DISCONNECT	DISCONNECT DESCRIPTION
AHU		240V 2P 2W	45	10.8	A-1,3	2 #6, #10 GND	55	60	FUSED	240/60/2
HP		240V 2P 2W	24.2	5.8	A-2,4	2 #8, #10 GND	30	50	FUSED	240/60/2/3R
WH		120V 1P 2W	12.5	1.5	A-5	2 #12, #12 GND	16	20	TOGGLE SWITCH	

MOUNTING FLUSH FED FROM UTILITY		VOLTS 240/120V 2P 3W		AIC 22,000				
NOTE		BUS AMPS 200		MAIN BRKR 200				
		NEUTRAL 100%		LUGS STANDARD				
CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA	CKT #	CKT BKR	CIRCUIT DESCRIPTION	LOAD KVA	
			A				B	
1	60/2	AHU	5.4	2	50/2	HP	2.9	
3	-		5.4	4	-		2.9	
5	20/1	WATER HEATER	1.5	6	20/1	LIGHTING	0.621	
7	20/1	SPARE	0	8	20/1	LIGHTING	0.627	
9	20/1	REFRIGERATOR	1.2	10	20/1	EXTERIOR LIGHTING	0.128	
11	20/1	VENDING	1.2	12	20/1	LAN	0.36	
13	20/1	VENDING	1.2	14	20/1	TEL BOARD	0.36	
15	20/1	ADMIN RECEPTACLE	0.9	16	20/1	UC REFRIGERATOR	0.6	
17	20/1	DISPATCH RECEPTACLE	0.54	18	20/1	BREAK RECEPTACLE	0.18	
19	20/1	DISPATCH RECEPTACLE	0.54	20	20/1	BREAK RECEPTACLE	0.18	
21	20/1	TLTS, HALL, OUTSIDE RECEPTACLE	0.9	22	20/1	LOUNGE RECEPTACLE	0.18	
23	20/1	BATCH RECEPTACLE	0.54	24	20/1	LOUNGE RECEPTACLE	0.36	
25	20/1	BATCH RECEPTACLE	0.54	26	20/1	SPARE	0	
27	20/1	LOUNGE RECEPTACLE	0.54	28	20/1	SPARE	0	
29	20/1	SPARE	0	30	20/1	SPARE	0	
31	20/1	SPARE	0	32	20/1	SPARE	0	
33	20/1	SPARE	0	34	20/1	SPARE	0	
35	-/1	SPACE	0	36	-/1	SPACE	0	
37	-/1	SPACE	0	38	-/1	SPACE	0	
39	-/1	SPACE	0	40	-/1	SPACE	0	
			TOTAL CONNECTED KVA BY PHASE				15.6	14.1
			CONN KVA	CALC KVA	CONN KVA	CALC KVA		
LIGHTING			1.38	1.72	1.5	1.88	(125%)	
LARGEST MOTOR			5.8	1.45	10.8	10.8	(100%)	
OTHER MOTORS			0	0	5.8	0	(0%)	
RECEPTACLES			6.12	6.12	0	0	(100%)	
KITCHEN EQUIP			4.2	3.36	0	0	(N/A)	
					29.8	25.3	(125%)	
					TOTAL KVA	29.8	25.3	
					BALANCED AMPS	106		

**ELECTRICAL LEGEND**

SYMBOL	DESCRIPTION
---	CONDUIT
----	CONDUIT UNDERFLOOR OR UNDERGROUND
	ARROW INDICATES HOMERUN, TICKMARKS: NEUTRAL, PHASE, GND.
	POWER PANEL
	DATA/COMM OUTLET
	JUNCTION BOX
	DISCONNECT SWITCH; FUSED; NONFUSED
	FUSE PER NAMEPLATE
	MOTOR TOGGLE SWITCH
	MOTOR
	EXISTING OR BY OTHERS
	LIGHT FIXTURE
	SINGLE POLE SWITCH, 3 WAY, 4 WAY
	DIMMER SWITCH, 3-WAY DIMMER SWITCH
	ABOVE FINISHED FLOOR
	DUPLEX RECEPT, ABOVE COUNTER
	WEATHERPROOF, GROUND FAULT
	QUAD-PLEX RECEPTACLE



no.	date	revision

THIS SHEET SHOWS BASIC DRAFTING STANDARDS

THIS DRAWING AND THE DESIGN SHOWN ARE THE PROPERTY OF MICHAEL L. SKEEDS, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION.


PROJECT NO. 10065  
MCDOWELL CONSULTING ENGINEERS, INC.  
3636 HAWKLEY RD. #204  
HARRISBURG, PA 17111  
TEL (717) 270-3747 FAX (717) 270-3779  
PA LICENSE NO. C-2546

MICHAEL L. SKEEDS, ARCHITECT & DESIGN ELEMENT INC.  
1913 Clarendon Drive, Suite 142  
Wilmington, North Carolina 28405  
910.509.3131

Proposed Dispatch Office Building for  
**Crete Solutions, LLC**  
239 Raleigh Street  
Wilmington, North Carolina 28401  
ELECTRICAL SCHEDULES, NOTES & DETAILS  
Issued For Construction

date 28 MAR, 2018  
job no. CRETE/BUS  
drawn by RGLBERT  
checked by GMCOWELL  
drawing no. E100  
revision no.


no.	date	revision



1 PROPOSED FLOOR PLAN — POWER

SCALE: 1/4" = 1'-0"

GRAPHIC BAR SCALE (FOOT UNITS)




COPYRIGHT; DESIGN ELEMENTS 2017 THIS DRAWING AND THE RESOURCES SHOWN ARE THE PROPERTY OF MICHAEL L. SAIED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND INFRINGEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS

**Proposed Dispatch Office Building for**  
**Crete Solutions, LLC**  
 239 Raleigh Street  
 Wilmington, North Carolina 28401  
**FLOOR PLAN — ELECTRICAL — POWER**  
 job status **Issued For Construction**

date 28 MAR, 2018  
 job no. CRETE/BUS  
 drawn by RGLBERT  
 checked by GMCOWELL  
 drawing no.

**E101**  
 revision no.

**Design Elements**  
 Michael L. Saied, Jr., AIA, AIBD  
 1913 Clarendon Drive, Suite 142  
 Wilmington, North Carolina 28405  
 P.O. 509,3131



PROJECT NO. 10065  
 McDowell Consulting Engineers, Inc.  
 3605 HAWKSTEAD, NC 28443  
 TEL (910) 270-3747 FAX 270-3779  
 NC LICENSE NO. C-2546

LUMINAIRE SCHEDULE								
CALLOUT	LAMP	DESCRIPTION	MOUNTING	MODEL	INPUT WATTS	NOTE 1	QUANTITY	VOLTS
A	LED	2x4 BASKET TROFFER	CEILING	DAY-BRITE 2EVG38L850UNVDIM	37		22	120
B	LED	WRAPAROUND	SURFACE	DAY-BRITE OWL44OL835UNVDIM	37		1	120
C	LED	2' STRIP	WALL	DAY-BRITE FSS220L840UNVDIM	17		1	120
D	LED	DOWNLIGHT	RECESSED	LIGHTOLIER P6RD10NZ10UVB P6RD835VB P6RDCC	10		2	120
E	INCLUDED	EMERGENCY	WALL	CHLORIDE CFX6			3	120
ER	INCLUDED	REMOTE HEAD	WALL	CHLORIDE VLL2R			3	120
EX	LED (EXIT) INCLUDED (EM)	EXIT/EM COMBO	WALL/CEILING	CHLORIDE VCRW			3	120
F	AS REQUIRED	VANITY	WALL	SELECTED BY OWNER	100	100W MAX	2	120
G	LED	KEYLESS FIXTURE	SURFACE	SELECTED BY CONTRACTOR	60		1	120
OA	LED	EXTERIOR SCONCE	WALL	STONCO LPWZ-8BZ	14	UL DAMP LABEL	2	120
OB	LED	EXTERIOR SCONCE	WALL	LIGHTOLIER P6RD15NZ10UVB P6RD840VB P6RDCC	100	UL WET LABEL	1	120

ELECTRICAL SUMMARY

ELECTRICAL SYSTEM AND EQUIPMENT

METHOD OF COMPLIANCE:

Energy Code:  Prescriptive  Performance  
 ASHRAE 90.1:  Prescriptive  Performance

Lighting schedule

lamp type required in fixture See Fixture Schedule  
 number of lamps in fixture See Fixture Schedule  
 ballast type used in the fixture See Fixture Schedule  
 number of ballasts in fixture See Fixture Schedule  
 total wattage per fixture See Fixture Schedule  
 Building Area      Space by Space       
 total interior wattage specified vs allowed 1088/1312  
 total exterior wattage specified vs allowed 48/780

Additional Prescriptive Compliance

- 506.2.1 More Efficient Mechanical Equipment
- 506.2.2 Reduced Lighting Power Density
- 506.2.3 Energy Recovery Ventilation Systems
- 506.2.4 Higher Efficiency Service Water Heating
- 506.2.5 On-Site Supply of Renewable Energy
- 506.2.6 Automatic Daylighting Control System
- N/A EXISTING/RENOVATION


DESIGNER STATEMENT:

To the best of my knowledge and belief, the design of this building complies with the requirements of Chapter 5 of the 2012 North Carolina State Energy Code.

SIGNED: Gregory McDowell  
 NAME: Gregory McDowell  
 TITLE: Professional Engineer


SWITCH SCHEDULE

SYMBOL	NOTE 1
\$ <sub>D</sub>	DIMMER SWITCH
\$	Single Pole Switch
\$ <sub>D</sub>	0-10V LOCAL WALL MOUNT DIMMER / SENSOR WATTSTOPPER PW-311
\$ <sub>3</sub>	WALL BOX OCCUPANCY SENSOR GREENGATE ONW-P-1001-MV-W
\$ <sub>3</sub>	3-WAY SWITCH
\$ <sub>3d</sub>	3-Way Dimmer




NOTE: DIMMERS SHALL BE SLIDE TYPE WITH PRE-SET, COMPATIBLE WITH FIXTURES/LAMPS TO BE CONTROLLED. SIZE FOR MINIMUM 125% OF LOAD CONTROLLED. PROVIDE 0-10V DIMMING CONTROL WIRING WHERE REQUIRED.

REFERENCE NOTES:  
 ① PROVIDE KEYLESS FIXTURE W/LED LAMP IN ATTIC SPACE.



PROPOSED FLOOR PLAN - LIGHTING



no.	date	revision

COPYRIGHT; DESIGN ELEMENTS 2017 THIS DRAWING AND THE RESOURCES SHOWN ARE THE PROPERTY OF MICHAEL L. SAEED, ARCHITECT & DESIGN ELEMENT INC. THE REPRODUCTION, COPYING, OR OTHER USE OF THIS DRAWING WITHOUT THE WRITTEN PERMISSION IS PROHIBITED AND IMPROVEMENT WILL BE SUBJECT TO LEGAL ACTION. THIS SHEET SHOWS BASIC DRAFTING STANDARDS.

Proposed Dispatch Office Building for  
**Crete Solutions, LLC**  
 239 Raleigh Street  
 Wilmington, North Carolina 28401

FLOOR PLAN - ELECTRICAL - LIGHTING  
 Issued For Construction

PROJECT NO. 10065  
 McDowell Consulting Engineers, Inc.  
 1100 W. 36th St., Suite 204  
 Raleigh, NC 27603  
 TEL (919) 270-3747 FAX (919) 270-3779  
 NC LICENSE NO. C-2546

DATE: 28 MAR, 2018  
 JOB NO. CRETE/BUS  
 DRAWN BY: RGLBERT  
 CHECKED BY: GMCOWELL  
 DRAWING NO. E102  
 REVISION NO.

1/2" PLYWOOD. ATTACH TO STUDS W/ 10d NAILS @ 4" O.C. AT PANEL EDGES AND 12" O.C. IN FIELD OF THE PANEL. REF. ARCH. FOR WALL FINISH.


2X6 STUD

SHEETROCK, REF. ARCH.

5/8" Ø X 1'-8" HEADED ANCHOR BOLT WITH 2" SQ. X 3/8" PLATE WASHER & NUT @ 4'-0" O.C.

4" CONCRETE SLAB W/ 6X6-W2.9XW2.9 WWF OVER 15 MIL. MIN. POLYETHYLENE SHEET, 4" GRANULAR FILL AND COMPACTED SUBGRADE.


(2) #5s CONT.



(3) #5s CONT.

#5 @ 24" O.C.

1 ALT. FOOTING SECTION  
 BD1 SCALE: 3/4" = 1'-0"



OFFICE BUILDING  
 CONCRETE BATCHING PLANT  
 239 RALEIGH STREET  
 WILMINGTON, NC 28401

DAVID TERKELTOUB AND ASSOCIATES  
 CONSULTING ENGINEERS

902 PINE GROVE DRIVE  
 WILMINGTON, NC 28409  
 PHONE: (910) 794-3070 FAX: (910) 794-3090  
 DT PROJECT NO.: 18011

CADD FILE:	BD1.0
PROJECT NUMBER:	18011
DRAWN BY:	DT
<b>BD1</b>	
1 OF 1	
DATE: 17 MAY 2018	