



Fire Marshal Division

March 23, 2023

**Re: Providence Creek
196 Providence Creek Dr.
Fuquay-Varina, NC 27526**

Application Number BCOM2303-0015

To Whom It May Concern,

Thank you for submitting the plans for the new Amenity Center. The plans have been carefully reviewed by a qualified code enforcement official to examine for compliance with the North Carolina Fire Prevention Code and all other fire protection regulatory documents. There are some items that were found during the plan review process that need to be addressed before a final inspection of the new facility can be given. These items are outlined and described below.

- **Fire Extinguishers**

- The fire extinguishers provided shall have a minimum rating of 2A10BC and shall not be mounted higher than 5 feet above the finished floor level.
- All fire extinguishers shall be properly mounted and tagged by a fire extinguisher company.

- **Address Numbers**

- The physical address shall be installed on the building so that it is visible from the street. Minimum 6" in height and a contrasting color.

- **Knox Box**

- A Knox Box installation is required for this building
- An order form can be obtained from this office or the box can be order online at www.knoxbox.com.

- **Panic Hardware**

- UL 305 listed panic hardware is required on exit doors serving a room/space with an occupant load >50, also indicated on Building code summary.

- **Occupant Load Posting**

- The occupant load posting shall be provided by the Fire Marshal's Office



at fire final inspection.

- **Means of Egress Illumination**
 - The means of egress illumination shall not be less than 1 foot-candle at the walking surface.
- **Hazard Identification Signs**
 - Ensure that all required Hazard identification signage is installed as it regards to pool chemical storage.
- **503 Fire Apparatus Access Roads**
 - A 20' fire department access road shall extend to within 150' of all portions of the facility and all portions of the exterior walls of the first story of the building.
- **Notes**
 - A final fire inspection is required.
 - Schedule all fire inspections through the Fire Marshal's Office. (919)893-0740.

Thank you again for submitting the plans for the new Amenity Center. Please review the plans and adhere to any notes and alterations that were made in addition to the original drawings. These remarks are for the plans that were submitted and its original intent. These remarks do not apply if the original intent changes or what was submitted on the above date changes. If you have any questions, please do not hesitate to call this office.

Sincerely,



Leslie Jackson
Chief Deputy Fire Marshal
lrjackson@harnett.org