



May 16, 2022

To whom it may concern:

Re: Jersey Mike's Subs
1624 NC 24-87 Highway
Cameron, NC 28326

Dear Sirs:

The 5-ton air handlers to sit on the proposed equipment platform only weight 170 pounds each. The method of framing and attachment of the equipment platforms/toilet ceilings with a ledger and joist hangers is perfectly acceptable. The minimum fastener for the ledger to studs would be two 16d nails. The Simpson SDWS timber screws and short-sapn 2x4 framing are more than adequate to support the wieght.

Respectfully yours,

A handwritten signature in blue ink, appearing to read 'Andrew W. Privette', is written over the typed name.

Andrew W. Privette, AIA

