

DEVELOPMENT DATA

WS-IV-P (CAPE FEAR RIVER - LILLINGTON)

DEVELOPMENT NAME STREET ADDRESS:

LILLINGTON, NC HARNETT COUNTY

DEED BOOK/PAGE: 3996/0923 PLAT BOOK/PAGE:

EXISTING ZONING: (COMM) COMMERCIAL/BUSINESS DISTRICT

REZONING CASE#

WATERSHED DISTRICT OVERLAY DISTRICT:

TOTAL SITE ACRES: 67,173 SF (1.54 AC)

INSIDE TOWN LIMITS

EXISTING USE: AGRICULTURE PROPOSED BUILDING USE: RETAIL SALES

USE GROUP LEVEL:

PROPOSED TOTAL BUILDING AREA: 10,640 SF (8,504 SF SALES FLOOR AREA)

MAX. BUILDING HEIGHT 35 FT MIN LOT AREA: 30,000 SF MIN LOT WIDTH: 100 FT FRONT SETBACK: 35 FT 20 FT SIDE SETBACK (STREET)

SIDE SETBACK (INTERIOR) o FT (20 FT ADJACENT TO RESIDENTIAL) 25 FT

REAR SETBACK:

BUFFER REQUIREMENTS:

15 FT TYPE A, D BUFFER - ADJACENT SINGLE FAMILY PERIMETER BUFFER:

10 FT TYPE C BUFFER - ADJACENT COMMERCIAL 15 FT TYPE D BUFFER - ADJACENT RIGHT-OF-WAY

BUILDING FOUNDATION: 5 FT PLANTING STRIP AT BUILDING

PARKING REQUIREMENTS: TOTAL REQUIRED:

1 SPACE PER 300 SF GFA 10,640 SF/300 = 36 SPACES

110% MAXIMUM SPACES = 40

TOTAL PROVIDED: 36 (9'x18' MIN)

ACCESSIBLE SPACES PROVIDED:

1 PROVIDED (12'x55' MIN) LOADING AREA:

> IMPERVIOUS AREA SUMMARY ON-SITE AREA = 67,173 SF (1.54 AC) BUILDINGS 10,640 SF 0.24 ACRE(S) 15.84 % OF AREA PAVEMENT 26,733 SF 0.62 ACRE(S) 39.80 % OF AREA SIDEWALK 2,748 SF 0.06 ACRE(S) 4.09 % OF AREA

27,052 SF 0.62 ΛCRE(S) 40.27 % OF AREA NCREASE IN IMPERVIOUS AREA: 40,121 SF 0.92 ACRE(S)

PROPOSED

Dollar General Store #23680 US Highway 421 N Lillington, NC Harnett County

TENANT & DEVELOPER

Dollar General Corporation

Rhetson Companies, Inc. Attn. John Parker 2075 Juniper Lake Road West End, NC 27376 (910) 944-0881 john@rhetson.com



CIVIL ENGINEER

Bowman North Carolina, Ltd. 4006 Barrett Drive Suite 104 Raleigh, NC 27609 (919) 553-6570 mlowder@bowman.com FIRM# F-1445


Bowman

CURRENT PROPERTY OWNERS

CEBCO CONSTRUCTION, INC P.O. BOX 591 MAMERS, NC 27552

THOMAS B. PHILLIS 120 DAVIS BROWN LANE LILLINGTON, NC 27546

DONALD L. NORDON & PATRICIA G. MCKEE 852 GRAMETA LANE LILLINGTON, NC 27546







INDEX OF DRAWINGS

- **COVER SHEET** C-1
- **EXISTING CONDITIONS PLAN**
- SITE PLAN C-3
- ROADWAY IMPROVEMENT PLAN C-3A
- ROADWAY IMPROVEMENT PLAN C-3B
- GRADING AND DRAINAGE PLAN
- UTILITY PLAN
- C-6A INITIAL PHASE EROSION CONTROL PLAN
- C-6B FINAL PHASE EROSION CONTROL PLAN
- CONSTRUCTION DETAILS
- CONSTRUCTION DETAILS
- C-8A WATER DETAILS
- NC CONSTRUCTION GENERAL PERMIT (NCGO1) NOTES C-9A
- C-9B EROSION CONTROL DETAILS
- STORMWATER MANAGEMENT DETAILS
- STORMWATER MANAGEMENT DETAILS
- LANDSCAPE PLAN

075 JUNIPER LAKE ROAD WEST END, NC 27376

RHETSON

US Highway 421 N gton, NC Harnett County

concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose nd client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by

Bowman North Carolina, Ltd. shall be


without liability to Bowman North

Drawn Checked

Rhetson Project# Project No. 058004 Initial Date February 28, 2022

COVER SHEET


Sheet No. C-1



OWNER/DEVELOPER: RHETSON COMPANIES, INC ATTN. JOHN PARKER 2075 JUNIPER LAKE ROAD WEST END, NC 27376 (910) 944-0881 ohn@rhetson.com

US Highway 421 N ston, NC Harnett County


his document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be without liability to Bowman North




Rhetson Project# Project No. 058004 Initial Date February 28, 2022

EXISTING

PLAN






OWNER/DEVELOPER: RHETSON COMPANIES, INC ATTN. JOHN PARKER 2075 JUNIPER LAKE ROAD WEST END, NC 27376 (910) 944-0881 ohn@rhetson.com


US Highway 421 N ston, NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be without liability to Bowman North




Rhetson Project# Initial Date February 28, 2022

ROADWAY MPROVEMENT






RHETSON COMPANIES, INC. 2075 JUNIPER LAKE ROAD WEST END, NC 27376



IMPROVEMENT



. ALL CONTOURS AND SPOT ELEVATIONS REFLECT FINISHED GRADES.

3. ALL ELEVATIONS ARE IN REFERENCE TO THE BENCHMARK, AND THIS MUST BE VERIFIED BY THE GENERAL

THE CONTRACTOR SHALL IMMEDIATELY REPORT TO OWNER ANY DISCREPANCIES FOUND BETWEEN ACTUAL FIELD CONDITIONS AND CONSTRUCTION DOCUMENTS AND SHALL WAIT FOR INSTRUCTION

THE CONTRACTOR SHALL BLEND NEW EARTHWORK SMOOTHLY TO TRANSITION BACK TO EXISTING

LIMITS OF CLEARING SHOWN ON GRADING PLAN ARE BASED UPON THE APPROXIMATE CUT AND FILL SLOPE LIMITS, OR OTHER GRADING REQUIREMENTS.

CORRECT SUBBASE OR AGGREGATE BASE COURSE ELEVATIONS TO BE COMPLETED LINDER THIS

THE CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE SO THAT RUNOFF WILL DRAIN BY GRAVITY FLOW ACROSS NEW PAVEMENT AREAS TO NEW OR EXISTING DRAINAGE INLETS OR SHEET OVERLAND.

10. ANY GRADING, BEYOND THE LIMITS OF CONSTRUCTION AS SHOWN ON THE GRADING PLAN, IS SUBJECT

11. GRADING WITHOUT AN APPROVED EROSION CONTROL PLAN IS SUBJECT TO A FINE.

2. STABILIZATION IS THE BEST FORM OF EROSION CONTROL. TEMPORARY SEEDING IS NECESSARY TO ACHIEVE EROSION CONTROL ON DENUDED AREAS AND ESPECIALLY WHEN THE CONSTRUCTION

3. ALL GRADED SLOPES ARE TO BE SEEDED OR LANDSCAPED WITHIN 15 DAYS OF COMPLETION OF GRADING. ALL REMAINING AREAS ARE TO BE SEEDED WITHIN 30 DAYS.

4. EXISTING GRADES, CONTOURS, UTILITIES AND OTHER EXISTING FEATURES FROM FIELD RUN SURVEY

5. THE CONTRACTOR SHALL INCLUDE IN THE CONTRACT PRICE ANY DEWATERING NECESSARY TO

HE CONTRACTOR IS RESPONSIBLE FOR THE DESIGN AND IMPLEMENTATION OF ALL SHEETING, SHORING BRACING AND SPECIAL EXCAVATION MEASURES REQUIRED TO MEET OSHA, FEDERAL, STATE, AND LOCAL REGULATIONS PURSUANT TO THE INSTALLATION OF THE WORK INDICATED ON THESE DRAWINGS. THE DESIGN ENGINEER ACCEPTS NO RESPONSIBILITY FOR THE DESIGN(S) TO INSTALL

THE CONTRACTOR SHALL REFER TO THE ARCHITECTURAL PLANS FOR EXACT LOCATION, ELEVATION, AND DIMENSIONS OF EXIT DOORS, RAMPS, BUILDING DIMENSIONS, AND EXACT BUILDING UTILITY

. ALL FILL MATERIALS, EXISTING BUILDING FOUNDATIONS, PAVEMENT AND UTILITY STRUCTURES, TOPSOIL, AND ANY OTHER DELETERIOUS MATERIALS SHALL BE COMPLETELY REMOVED FROM WITHIN THE BEARING ZONE BELOW THE STRUCTURE.

ALL FOUNDATION EXCAVATION SHALL BE INSPECTED BY A QUALIFIED GEOTECHNICAL REPRESENTATIVE TO DETERMINE WHETHER UNSUITABLE MATERIAL MUST BE REMOVED. ALL UNDESIREABLE MATERIAL SHALL BE REMOVED, BACKFILLED AND COMPACTED AS REQUIRED BY THE GEOTECHNICA

). ALL CUT OR FILL SLOPES SHALL BE 3:1 OR FLATTER UNLESS OTHERWISE NOTED OR DEPICTED

THE CONTRACTOR SHALL ADHERE TO ALL TERMS & CONDITIONS AS OUTLINED IN THE GENERAL N.P.D PERMIT FOR STORMWATER DISCHARGE ASSOCIATED WITH CONSTRUCTION ACTIVITIES.

CONTRACTOR SHALL ADJUST AND/OR CUT EXISTING PAVEMENT AS NECESSARY TO ASSURE A SMOOTH FIT

3. CONTRACTOR SHALL ENSURE POSITIVE DRAINAGE AWAY FROM BUILDINGS FOR ALL NATURAL AND

4. ALL UNSURFACED AREAS DISTRURBED BY GRADING OPERATION SHALL RECEIVE 4 INCHES OF TOPSOIL CONTRACTOR SHALL APPLY STABILIZATION FABRIC TO ALL SLOPES 3H; IV OR STEEPER,

5. CONSTRUCTION SHALL COMPLY WITH ALL APPLICABLE GOVERNING CODES AND BE CONSTRUCTED TO

A MINIMUM GRADE OF 0.50 % SHALL BE MAINTAINED ON ALL PIPES, UNLESS OTHERWISE NOTED.

. PIPE LENGTHS AND SLOPES INDICATED ON THE PLANS ARE APPROXIMATE ONLY.

UNDERGROUND UTILITY LINES SHALL BE INSTALLED IN ACCORDANCE WITH THE FOLLOWING STANDARDS IN ADDITION TO OTHER APPLICABLE CRITERIA:

A. NO MORE THAN 500 LF OF TRENCH MAY BE OPENED AT ONE TIME.

B. EXCAVATED MATERIAL SHALL BE PLACED ON THE UPHILL SIDE OF TRENCHES.

C. EFFLUENT FROM DEWATERING OPERATIONS SHALL BE FILTERED OR PASSED THROUGH AN APPROVED SEDIMENT TRAPPING DEVICE, OR BOTH, AND DISCHARGED IN A MANNER THAT DOES NOT ADVERSELY AFFECT FLOWING STREAMS OR OFF-SITE PROPERTY.

D. MATERIAL USED FOR BACK-FILLING TRENCHES SHALL BE PROPERLY COMPACTED IN ORDER TO MINIMIZE EROSION AND PROMOTE STABILIZATION.

E. RESTABALIZATION SHALL BE ACCOMPLISHED IN ACCORDANCE WITH THE EROSION AND SEDIMENT

CATCH BASINS, MANHOLES, FRAMES, GRATES, ETC. SHALL MEET THE REQUIREMENTS OF THE LATEST EDITION OF THE NORTH CAROLINA DEPARTMENT OF TRANSPORTATION STANDARD DRAWINGS.

REFERENCE THE FOLLOWING STANDARD DETAILS: 840.03 - FRAME, GRATES, AND HOOD FOR CATCH BASINS 840.04 - CONCRETE OPEN THROAT CATCH BASIN

840.16 - DROP INLET FRAME AND GRATES 840.31 - CONCRETE JUNCTION BOX 840.36 - TRAFFIC BEARING GRATED DROP INLET 840.45 - PRECAST DRAINAGE STRUCTURE 838.80 - PRECAST CONCRETE ENDWALL

ALL PIPES SHALL BE LAID ON STRAIGHT ALIGNMENTS AND EVEN GRADES USING A PIPE LASER OR OTHER

TYPE 1: RCP, CLASS III PER ASTM C-76, WITH FLEXIBLE PLASTIC BITUMEN GASKETS AT JOINTS.

TYPE 2: HIGH DENSITY POLYETHYLENE PIPE (HDPE) - AASHTO DESIGNATION M252 TYPE S, M294 TYPE S AND MP7-97 TYPE S, SMOOTH INTERIOR/ANNULAR EXTERIOR. ONLY PERMITTED WHEN SPECIFICALLY INDICATED ON THE CONSTRUCTION DRAWINGS. PIPE SHALL BE INSTALLED IN

ALL STORM DRAINAGE WITHIN THE PUBLIC ROADS SHALL BE CLASS III REINFORCED CONCRETE PIPE

. EXISTING DRAINAGE STRUCTURES TO BE INSPECTED AND REPAIRED AS NEEDED, AND EXISTING PIPES TO

9. IF ANY EXISTING STRUCTURES TO REMAIN ARE DAMAGED DURING CONSTRUCTION IT SHALL BE THE CONTRACTORS RESPONSIBILITY TO REPAIR AND/OR REPLACE THE EXISTING STRUCTURE AS

D. ALL STORM PIPE ENTERING STRUCTURES SHALL BE GROUTED TO ASSURE CONNECTION AT STRUCTURE IS

1. PRECAST STRUCTURES MAYBE USED AT CONTRACTORS OPTION.

2. ALL STORM SEWER MANHOLES IN PAVED AREAS SHALL BE FLUSH WITH PAVEMENT, AND SHALL HAVE TRAFFIC BEARING RING & COVERS. MANHOLES IN UNPAVED AREAS SHALL BE 6" ABOVE FINISH GRADE. LIDS SHALL BE LABELED "STORM SEWER".

STRUCTURE TOP ELEVATIONS SHOWN HERE ARE APPROXIMATE. CONTRACTOR SHALL ADJUST AS

. RIM ELEVATIONS AS NOTED ARE TO THE GUTTER FLOW LINE.

OWNER/DEVELOPER:


RHETSON COMPANIES, INC ATTN. JOHN PARKER 075 JUNIPER LAKE ROAD WEST END, NC 27376 910) 944-0881 ohn@rhetson.com

S Highway 421 N 1, NC Harnett County


This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be

without liability to Bowman North

Carolina, Ltd.




Rhetson Project# Initial Date February 28, 2022





THE PROPOSED BUILDING WILL NOT HAVE A FIRE SPRINKLER SYSTEM


THE ESTIMATED WATER USAGE FOR THIS SITE IS 200GPD BASED ON NCDEO APPROVED FLOW AMOUNT FOR DOLLAR GENERAL DEVELOPMENTS











THE CONTRACTOR IS FULLY RESPONSIBLE FOR CONTACTING APPROPRIATE PARTIES AND ASSURING THAT EXISTING HILL THE ARE LOCATED PRIOR TO THE COMMENCEMENT OF CONSTRUCTION, CONTACT THE LOCAL MUNICIPALITY PUBLIC WORKS DEPARTMENT 48 HOURS PRIOR TO COMMENCEMENT OF WORK FOR UTILITY LOCATING SERVICES. ALL UTILITIES SHOWN ARE APPROXIMATE LOCATIONS ONLY AND HAVE BEEN COMPILED FROM THE LATEST AVAILABLE MAPPING. THE EXACT LOCATION OF

ALL UNDERGROUND UTILITIES SHALL BE VERIFIED BY THE CONTRACTOR PRIOR TO THE START OF CONSTRUCTION.

CONSTRUCTION AND MATERIALS SHALL BE IN ACCORDANCE WITH THE HARNETT COUNTY UTILITY & HEALTH DEPARTMENTS. CONTRACTOR IS RESPONSIBLE FOR COMPLYING TO THE HARNETT COUNTY UTILITY & HEALTH DEPARTMENTS

- CONTRACTOR SHALL COORDINATE WITH ALL UTILITY COMPANIES FOR INSTALLATION REQUIREMENTS AND SPECIFICATIONS. PRE-CONSTRUCTION MEETING WITH THE VARIOUS UTILITY COMPANIES IS REQUIRED PRIOR TO THE START OF ANY CONSTRUCTION ACTIVITY.
- CONTRACTOR SHALL NOTIFY THE CTILITY AUTHORITIES INSPECTOR 72 HOURS BEFORE CONNECTING TO ANY EXISTING LINE.

WITH REGARDS TO MATERIALS AND INSTALLATION OF THE WATER AND SANITARY SEWER LINES.

- THE CONTRACTOR SHALL COORDINATE ANY INTERRUPTION OF UTILITY SERVICE WITH THE OWNER AND THE UTILITY COMPANY, ANY PLANNED INTERRUPTION OF UTILITY SERVICE SHALL BE GIVEN A 48 HOUR NOTICE TO THE UTILITY COMPANY
- SHOULD ANY UNCHARTED OR INCORRECTLY CHARTED UTILITIES BE ENCOUNTERED, THE CONTRACTOR SHALL CONTACT THE OWNER IMMEDIATELY FOR DIRECTIONS
- PRESSURE REDUCING VALVES WILL BE REQUIRED ON THE DOMESTIC WATERLINES FOR EACH BUILDING IF THE STATIC
- PRESSURE IN THE WATER MAIN EXCEEDS 80 PSI. SEE MECHANICAL/PLUMBING PLANS. ROUTES SHOWN FOR WATER SERVICES, ELECTRIC, SANITARY SEWER BUILDING LATERALS AND ROOF DRAIN PIPING ARE
- THE CONTRACTOR SHALL SAW CUT, REMOVE, AND REPLACE ASPHALT PAVEMENT AS NECESSARY TO INSTALL UNDERGROUND ELECTRIC, TELEPHONE, SEWER, AND WATER
- THE CONTRACTOR SHALL VISIT THE SITE AND VERIFY THE ELEVATION AND LOCATION OF ALL UTILITIES BY VARIOUS MEANS PRIOR TO BEGINNING ANY EXCAVATION. TEST PITS SHALL BE DUG AT ALL LOCATIONS WHERE SEWERS CROSS EXISTING UTILITIES, AND THE HORIZONTAL AND VERTICAL LOCATIONS OF THE UTILITIES SHALL BE DETERMINED. THE CONTRACTOR SHALL CONTACT OWNER IN THE EVENT OF ANY UNFORESEEN CONFLICTS BETWEEN EXISTING AND PROPOSED UTILITIES SO THAT AN APPROPRIATE MODIFICATION MAY BE MADE.
- THE CONTRACTOR SHALL INSURE THAT ALL UTILITY COMPANIES AND HARNETT COUNTY UTILITY & HEALTH DEPARTMENTS STANDARDS FOR MATERIALS AND CONSTRUCTION METHODS ARE MET, THE CONTRACTOR SHALL PERFORM PROPER COORDINATION WITH THE RESPECTIVE UTILITY COMPANY. THE CONTRACTOR SHALL COORDINATE WORK TO BE PERFORMED BY THE VARIOUS UTILITY COMPANIES AND SHALL PAY ALL FBES FOR CONNECTIONS, DISCONNECTION, RELOCATIONS, INSPECTIONS, AND DEMOLITION.
- THIS PLAN DETAILS PIPES UP TO 5' FROM THE BUILDING FACE. REFER TO THE BUILDING DRAWINGS FOR BUILDING CONNECTIONS, SUPPLY AND INSTALL PIPE ADAPTERS AS NECESSARY.
- ALL EXISTING PAVEMENT WHERE UTILITY PIPING IS TO BE INSTALLED SHALL BE SAW CUT AND REPLACED IN ACCORDANCE WITH THE PAVEMENT REPAIR REQUIREMENTS OF THE HARNETT COUNTY UTILITY & HEALTH DEPARTMENTS AND NORTH CAROLINA DEPARTMENT OF TRANSPORTATION.
- MAINTAIN MINIMUM 10'-0" HORIZONTAL SEPARATION BETWEEN ON-SITE SANITARY SEWER AND DOMESTIC OR IRRIGATION WATER PIPING WHENEVER POSSIBLE. WHERE WATER PIPING MUST CROSS OVER SANTTARY SEWER PIPING, MAINTAIN A MINIMUM 18" VERTICAL SEPARATION. WHERE SANITARY SEWER PIPING MUST CROSS OVER WATER PIPING, MAINTAIN A MINIMUM 24" VERTICAL SEPARATION AND PROVIDE MIN. 4" THICK CONCRETE ENCASEMENT OR 4" CONTINUOUS CAST IRON PIPI SLEEVE ON WATER PIPING FOR A MINIMUM OF 10'-0" ON EACH SIDE OF THE SAN. SEWER CROSSING. WHERE PERMITTED BY LOCAL CODE, DOMESTIC WATER AND SANITARY SEWER SERVICE PIPING MAY BE INSTALLED IN A COMMON TRENCH. TRENCH AND PIPING PLACEMENT SHALL COMPLY WITH ALL GOVERNING CODES AND REGULATIONS.

HARNETT REGIONAL WATER NOTES

The Fire Marshal's Office shall approve all hydrant types and locations in new subdivisions. However, Harnett Regional Water (HRW) prefers the contractors to install one of the following fire hydrants:

1. Mueller - Super Centurion 250 A-423 model with a 51/4" main valve opening three way (two hose nozzles and one pumper nozzle); 2. American Darling - Mark B-84-B model with a 51/4" main valve opening three way (two hose nozzles andone pumper nozzle) 3. Waterous - Pacer B-67-250 model with a 51/4" main valve opening three way (two hose nozzles and

- Fire hydrants are installed at certain elevations. Any grade change near any fire hydrant, which impedes its operation, shall become the responsibility of the Utility Contractor for correction. Corrections will be monitored by the HRW Utility Construction Inspector and the Harnett County Fire Marshal.
- The Professional Engineer (PE) shall obtain and provide the NCDEQ "Authorization to Construct" permit to the Utility Contractor before the construction of the water line shall begin. The Utility Contractor must post a copy of the NCDEQ "Authorization to Construct" permit issued by the North Carolina Department of Environmental Quality (NCDEQ) on site prior to the start of construction. The permit must be maintained

on site throughout the entire construction process of the proposed water lines that will serve this

- The Utility Contractor shall notify Harnett Regional Water (HRW) and the Professional Engineer (PE) at least two days prior to construction commencing. The Utility Contractor must schedule a pre-construction conference with Mr. Alan Moss, HRW Utility Construction Inspector at least two (2) days before construction will begin and the Utility Contractor must coordinate with HRW for regular inspection visitations and acceptance of the water system(s). Construction work shall be performed only during the normal working hours of HRW which is 8:00 am -5:00 pm Monday through Friday. Holiday and weekend
- work is not permitted by HRW. The Professional Engineer (PE) shall provide HRW and the Utility Contractor with a set of NCDEQ approved plans marked "Released for Construction" at least two days prior to construction commencing. The Registered Land Surveyor (RIS) should stake out all lot corners and the grade stakes for the proposed finish grade for each street before the Utility Contractor begins construction of the water line(s). The

grade stakes should be set with a consistent offset from the street centerline so as not to interfere with

the street grading and utility construction.

The Utility Contractor shall provide the HRW Utility Construction Inspector with material submittals and shop drawings for all project materials prior to the construction of any water line extension(s), and associated water services in Harnett County. The materials to be used on the project must meet the established specifications of HRW and be approved by the Engineer of Record prior to construction. Al substandard materials or materials not approved for use in Harnett County found on the project site

must be removed immediately when notified by the HRW Utility Construction Inspector.

- The water main(s), fire hydrants, service lines, meter setters and all associated appurtenances shall be constructed in strict in accordance with the standard specifications of the Harnett Regional Water (HRW). The Utility Contractor shall be responsible to locate the newly installed water main(s), water service lines and all associated meter setters and meter boxes for other utility companies and their contractors until the new water main(s) have been approved by the North Carolina Department of Environmental Quality,
- Prior to acceptance, all services will be inspected to insure that they are installed at the proper depth All meter boxes must be flush with the ground level at finish grade and the meter setters must be a minimum of 8" below the meter box lid. Meter setters shall be centered in the meter box and supported by brick, block or stone.

Division of Environmental Health, Public Water Supply Section (NCDEQ, DEH, PWS) and accepted by HRW.

- The Utility Contractor shall provide the Professional Engineer (PE) and HRW Utility Construction Inspecto with a set of red line drawings identifying the complete water system installed for each project. The red line drawings should identify the materials, pipe sizes and approximate depths of the water lines as well as the gate valves, fire hydrants, meter setters, blow off assemblies and all associated appurtenances fo all water line(s) constructed in Harnett County. The red line drawings should clearly identify any deviations from the NCDEQ approved plans. All change orders must be approved by HRW and the Professional Engineer (PE) in writing and properly documented in the red line field drawings.
- Potable water mains crossing other utilities and non-potable water lines (sanitary sewer, storm sewer, RCP, etc.) shall be laid to provide a minimum vertical distance of twenty-four (24") inches between the potable water main and all other utilities. NCDOT requires the new water mains to be installed under the storm water lines. The potable water main shall be installed with twenty-four (24") inches of vertical separation and with ductile iron pipe when designed to be placed under a nonpotable water line such as sanitary sewer or storm sewer lines. If these separations cannot be maintained then the water main shall be installed with ductile iron pipe. Both the potable water main and the non-potable water line must be cast iron or ductile iron pipe (DIP) if the state minimum separations cannot be maintained. The ductile iron pipe must be laid so the mechanical joints are at least (10') feet from the point where the potable water main crosses the non-potable water line.
- Potable water mains installed parallel to non-potable water lines (sanitary sewer, storm sewer, RCP, etc.) shall be laid to provide a minimum horizontal distance of ten (10') feet between the potable water main and sanitary sewer mains, sewer laterals and services. The horizontal separation between the potable water main and any other utility or storm sewer shall not be less than five (5') feet. The potable water main must be ductile iron pipe if this horizontal separation of ten (10') feet cannot be maintained. The ductile iron pine shall extend at least ten (10') feet beyond the point where the minimum required horizontal separation of ten (10) feet can be re-established
- Meter setters shall be installed in pairs on every other lot line where possible to leave adequate space for other utilities to be installed at a later time. The meter setters shall be installed at least one (1') foot inside the right-of-way and at least three (3') to five (5') feet from the property line between the lots. M. HRW requires that meter boxes for 1/4" services shall be 12" wide x 17" long ABS plastic boxes at least 18" in height with cast iron lids/covers. Meter boxes for 1" services shall be 17" wide x 21" long ABS plastic boxes at least 18" in height with plastic lids and cast iron flip covers in the center of the lids Meter boxes for 2 services shall be 20 wide x 32 long ABS plastic boxes at least 20 in height with plastic lids and cast iron flip covers in the center of the lids.
- Master meters must be installed in concrete vaults sized for the meter assembly and associated appurtenances so as to provide at least eighteen (18") inches of clearance between the bottom of the concrete vault and the bottom of the meter setter. The master meter must be provided test ports if the meter is not equipped with test ports from the manufacturer in accordance with the HRW established standard specifications and details. Ductile iron pipe must be used for the master meter vault piping and valve vault piping. The Utility Contractor must provide shop drawings for the meter vaults to HRW prior to ordering the concrete vaults.
- The Utility Contractor will install polyethylene SDR-9 water service lines that cross under the pavement inside a schedule 40 PVC conduit to allow for removal and replacement in the future. Two (2)

- independent 34" water service lines may be installed inside one (1) -two (2") inch schedule 40 PVC conduit or two (2) independent 1" water service lines may be installed inside one (1) - three (3") inch schedule 40 PVC conduit, but each water service shall be tapped directly to the water main. Split services are not allowed by HRW. If sidewalks are proposed, the conduit must extend past the sidewalk.
- The water main(s), fire hydrants, gate valves, service lines, meter setters and associated appurtenances must be rated for 200 psi and hydrostatically pressure tested to 200 psi. The hydrostatic pressure test(s) must be witnessed by the HRW Utility Construction Inspector. The Utility Contractor must notify HRW when they are ready to begin filling in lines and coordinate with Harnett Regional Water to witness all pressure
- Q. The Utility Contractor shall conduct a pneumatic pressure test using compressed air or other inert gas on the stainless steel tapping sleeve(s) prior to making the tap on the existing water main. This pneumatic pressure test must be witnessed by the HRW Utility Construction Inspector. The Utility Contractor shall use Romac brand stainless steel tapping sleeve(s) or approved equal for all taps made in Harnett County. All new water line extensions must begin with a resilient wedge type gate valve sized
- equal to the diameter of the new water line extension in order to provide a means of isolation between Harnett Regional Water's existing water mains and the new water line extensions under construction. R. All water mains will be constructed with SDR-21 PVC Pipe or Class 50 Ductile Iron Pipe rated for at least

200 psi or greater. All pipes must be protected during loading, transport, unloading, staging, and

- installation. PVC pipe must be protected from extended exposure to sunlight prior to installation All water mains will be flushed and disinfected in strict accordance with the standard specifications of the Harnett Regional Water. All water samples collected for bacteria testing will be collected by the HRW Utility Construction Inspector and tested in the HRW Laboratory.
- T. All fittings larger than two (2") inches diameter shall be ductile iron. HRW requires that mechanical joints be assembled with grip rings as "Megalug" fittings are not approved by Harnett Regional Water for pipe sizes smaller than twelve inches (12") diameter. PVC pipe used for water mains shall be connected by slip joint or mechanical joint with grip rings. Glued pipe joints are not allowed on PVC pipe used for water
- U. HRW requires that the Utility Contractor install tracer wire in the trench with all water lines. The tracer wire shall be 12 ga. insulated, solid copper conductor and it shall be terminated at the top of the valve boxes or manholes. No spliced wire connections shall be made underground on tracer wire installed in Harnett County. The tracer wire may be secured with duct tape to the top of the pipe before backfilling.
- 7. The Utility Contractor will provide Professional Engineer (PE) and the HRW Utility Construction Inspector with a set of red line field drawings to identify the installed locations of the water line(s) and all associated services. All change orders must be pre-approved by HRW and the Professional Engineer (PE) in writing and properly documented in the red line field drawings.
- W. The Utility Contractor shall spot dig to expose each utility pipe or line which may conflict with construction of proposed water line extensions well in advance to verify locations of the existing utilities. he Utility Contractor shall provide both horizontal and vertical clearances to the Professional Engineer (PE) to allow the PE to adjust the water line design in order to avoid conflicts with existing underground utilities. The Utility Contractor shall coordinate with the utility owner and be responsible for temporary relocation and/or securing existing utility poles, pipes, wires, cables, signs and/or utilities including services in accordance with the utility owner requirements during water line installation, grading and
- X. Prior to the commencement of any work within established utility easements or NCDOT right-of-ways the Utility Contractor is required to have a signed NCDOT encroachment agreement posted on site and notify all concerned utility companies in accordance with G.S. 87-102. The Utility Contractor must call the NC One Call Center at 811 or (800) 632-4949 to verify the location of existing utilities prior to the beginning of construction. Existing utilities shown in these plans are taken from maps furnished by various utility companies and have not been physically located or verified by the P.E. (i.e. TELEPHONE, CABLE, WATER, SEWER, ELECTRICAL POWER, FIBER OPTIC, NATURAL GAS, ETC.). The Utility Contractor will be responsible to repair any and all damages to the satisfaction of the related utility company.
- Y. The Utility Contractor shall provide HRW with at least one (1) fire hydrant wrench and one (1) break-away flange kit for every subdivision with fire hydrants developed in Harnett County. These items must be provided to HRW before the final inspection will be scheduled by the HRW Utility Construction nspector. In addition, the Utility Contractor shall install a 4"x 4" concrete valve marker at the edge of the right-of-way to identify the location of each gate valve installed in the new water system with the exception of the fire hydrant isolation valves. The contractor shall measure the distance from the center of the concrete marker to the center of the valve box. This distance (in linear feet) shall be stamped on the brass plate located on the top of the concrete valve marker. In lieu of installing the concrete valve markers, the Utility Contractor may provide at least two measurements from two independent permanent above ground structures to the Professional Engineer (PE) in the red line drawings to ide ntify the valve locations. The Professional Engineer (PE) must include these measurements in the As-Built Record Drawings submitted to HRW.
- Z. The Utility Contractor will be responsible for any and all repairs due to leakage damage from poor workmanship during the one (1) year warranty period once the water system improvements have been accepted by Harnett Regional Water. Harnett Regional Water will provide maintenance and repairs when requested and bill the Developer and/or Utility Contractor if necessary due to lack of response within 48 ours of notification of warranty work. The Utility Contractor will be responsible for any and all repairs due to damages resulting from failure to locate the new water lines and associated appurtenances for other utilities and their contractors until the water lines have been approved by NCDEQ and accepted by HRW. The final inspection of water system improvements cannot be scheduled with HRW until the streets have been paved; the rights-of-way and utility easements have been seeded and stabilized with an adequate stand of grass in place to prevent erosion issues on site.
- AA The Engineer of Record is responsible to insure that construction is, at all times, in compliance with accepted sanitary engineering practices and approved plans and specifications. No field changes to the approved plans are allowed without prior written approval by HRW. A copy of each engineer's field report is to be submitted to HRW as each such inspection is made on system improvements or testing is performed by the contractor. Water and sewer infrastructure must pass all tests required by HRW pecifications and those of all applicable regulatory agencies. These tests include, but are not limited to: air test, vacuum test, mandrel test, visual test, pressure test, bacteriological test, etc. A HRW Inspector must be present during testing and all test results shall be submitted to HRW. All tests must be satisfied before the final inspection will be scheduled with the HRW Inspector. The Engineer of Record must request n writing to schedule the final inspection once all construction is complete. The Developer's Engineer of Record and the HRW Utility Construction Inspector shall prepare a written punch list of any defects or deficiencies noted during the final inspection, should any exist. Upon completion of the punch list, the Developer's Engineer of Record will schedule another inspection. In the event the number of inspections performed by the HRW exceeds two, additional fees may be accessed to the Developer.



OWNER/DEVELOPER: RHETSON COMPANIES, INC ATTN. JOHN PARKER 075 JUNIPER LAKE ROAD WEST END, NC 27376

910) 944-0881


ohn@rhetson.com

Highway 4, NC Harnett (

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be


without liability to Bowman North

Carolina, Ltd.



Checked Rhetson Project# ^oroject No. -058004 Initial Date February 28, 2022

JTILITY



EROSION CONTROL NOTES

CROSION CONTROL MEASURES TO BE USED IN THE DEVELOPMENT OF THIS SIT REFER TO DETAIL SHEETS FOR TEMPORARY AND PERMANENT SEEDING SCHEDULES FOR PROVIDING GROUND COVER THE FOR THE DEVELOPMENT.

NOTE TO CONTRACTOR:

THE CONTRACTOR SHALL NOTIFY THE PROJECT ENGINEER AND THE PROSION CONTROL INSPECTOR OF THE LOCATION OF ANY OFF-SITE BORROW SOURCE OR OFF-SITE WASTE MATERIAL DISPOSAL SITE. OFF-SITE DISTURBANCES COUNT TOWARDS THE OVERALL PROJECT DISTURBED AREA AND MUST BE COVERED BY THE PERMIT FOR THIS PROJECT AND/OR THE PERMIT FROM ANOTHER ACTIVE NODEQ PERMITTED SITE THAT IS APPROPRIATE FOR THE INTENDED USE (I.E. APPLICABLE MINING REQUIREMENTS). NO OFF-SUTE ACTIVITIES SHALL OCCUR UNTIL THE PERMIT FOR THIS PROJECT HAS BEEN MODIFIED TO INCLUDE THE AFFECTED AREAS OR IT HAS BEEN VERIFIED WITH THE EROSION CONTROL INSPECTOR THAT THE OFF-SITE AREAS ARE COVERED UNDER ACTIVE APPLICABLE NCDEQ PERMITS.

EROSION CONTROL NARRATIVE


CONTRACTOR WILL FIRST INSTALL THE CONSTRUCTION ENTRANCE. THE CONTRACTOR SHALL THEN MOBILIZE ON SITE AND INSTALL THE TEMPORARY EROSION CONTROL DEVICES INCLUDING SILT FENCE. INLET PROTECTION, SKIMMER BASIN, AND OTHER DEVICES IN ACCORDANCE WITH THE PLANS (CLEARING ONLY AS NECESSARY TO INSTALL THESE ITEMS). BEGIN DEMOLITION, CLEARING AND SITE GRADING OPERATIONS. STABILIZATION OF EARTHEN STRUCTURES IS REQUIRED IMMEDIATELY AFTER INSTALLATION. THE ON-SITE STORM SEWER SYSTEM CAN NOW BE NSTALLED. IMMEDIATELY AFTER AN INLET IS INSTALLED, INLET PROTECTION SHALL BE PROPERLY INSTALLED ON THE STRUCTURE. THE ON-SITE NITARY SEWER AND WATER SYSTEMS MAY ALSO BE INSTALLED ONCE THE SITE IS BROUGHT UP TO GRADE. THE SITE PAD WILL BE PREPARED FOR THE PROPOSED BUILDING. THE ROUGH GRADE WILL THEN BE ESTABLISHED FOR THE SITE. INSTALLATION OF CURB AND GUTTER WILL THEN BE PERFORMED. BASE STONE WILL THEN BE PLACED AND FINE GRADED. ALL DISTURBED AREAS WILL BE DRESSED AND SEEDED. REMOVE ALL INLET PROTECTION FROM STORM STRUCTURES WHEN PAVING IS TO BEGIN. PAVING AND STRIPING WILL THEN BE COMPLETED. FINALIZE STORMWATER YOND STRUCTURE ONCE UPSTREAM AREAS HAVE BEEN STABILIZED (REMOVE ACCUMULATED SEDIMENT). ALL LANDSCAPING WILL BE COMPLETED HE ON-SITE STORM SEWER SYSTEM SHALL BE CLEANED OF ANY ACCUMULATED SEDIMENT WHICH SHALL BE DISPOSED OF IN A LAWFUL MANNER. ALL ACCUMULATED SEDIMENT BEHIND SILT FENCE AND OTHER SEDIMENT DEVICES SHALL BE REMOVED AND DISPOSED OF IN A LAWFUL MANNER ACCORDING TO THE GROUND STABILIZATION REQUIREMENTS ON THIS SHEET, REMOVE ALL REMAINING SEDIMENT CONTROL MEASURES FROM TH SITE. CONTRACTOR SHALL MINIMIZE THE LENGTH OF TIME BETWEEN INITIAL LAND DISTURBANCE AND FINAL VEGETATION STABILIZATION OF THE

THE PROPOSED EROSION AND SEDIMENT CONTROL MEASURES ARE INTENDED TO TRAP ANY STORMWATER RUNOFF FROM THE CONSTRUCTION SIT ND DETAIN IT LONG ENOUGH FOR SEDIMENT AND POLLUTANTS TO SETTLE OUT OF THE STORMWATER BEFORE DISCHARGE. VARIOUS EROSION CONTROL MEASURES ARE USED TO PREVENT POLLUTANT-LADEN STORMWATER RUNOFF FROM FLOWING ONTO ADJACENT PROPERTIES.

NOTIFICATION OF COMBINED SELF-MONITORING AND SELF-INSPECTION FORM HE SEDIMENTATION POLLUTION CONTROL ACT WAS AMENDED IN 2006 TO REQUIRE THAT PERSONS RESPONSIBLE FOR LAND-DISTURBING ACTIVI INSPECT A PROJECT AFTER EACH PHASE OF THE PROJECT TO MAKE SURE THAT THE APPROVED EROSION AND SEDIMENTATION CONTROL PLAN IS BEIN FOLLOWED, RULES DETAILING THE DOCUMENTATION OF THESE INSPECTIONS TOOK EFFECT OCTOBER 1, 2010.


O SIMPLIFY DOCUMENTATION OF SELF-INSPECTION REPORTS AND NPDES SELF-MONITORING REPORTS, DWQ AND DEMLR DEVELOPED A COMBINED FORM, THE SELF-INSPECTION PROGRAM IS SEPARATE FROM THE WEEKLY SELF-MONITORING PROGRAM OF THE NPDES STORMWATER PERMIT FOR CONSTRUCTION ACTIVITIES. THE FOCUS OF THE SELF-INSPECTION REPORT IS THE INSTALLATION AND MAINTENANCE OF EROSION AND SEDIMENTATION CONTROL MEASURES ACCORDING TO THE APPROVED PLAN. THE INSPECTIONS SHOULD BE CONDUCTED AFTER EACH PHASE OF THE PROJECT, AND CONTINUED UNTIL PERMANENT GROUND COVER IS ESTABLISHED. THE FORM CAN BE ACCESSED AT: HTTP://PORTAL.NCDENR.ORG/WEB/LR/EROSION

FYOU HAVE QUESTIONS OR CANNOT ACCESS THE FORM, PLEASE CALL THE APPLICABLE NODENR REGIONAL OFFICE; (RALEIGH: 919-791-4200) (FAYETTEVILLE: 910-433-3300) (WILMINGTON: 910-796-7215) (WASHINGTON: 252-946-6481) (WINSTON-SALEM: 336-771-5000) (MOORESVILLE: 704-663-169



(SINGLE-FAMILY)

NOTE TO CONTRACTOR EROSION CONTROL MEASURES TO BE INSTALLED PRIOR TO THE BEGINNING OF DEMOLITION & TREE REMOVAL



NORTH CAROLINA CONSTRUCTION GENERAL PERMIT NOTE

DATA BLOCK

EXTEND LINING TO EXTEND LINING TO

6" MIN. FREEBOARD

TEMPORARY SILT FENCE

TREE PROTECTION PENCE

STRAW WITH NET

LIMITS OF DISTURBANCE

SE/TP SILI TREE PROTECTION FE

B W SS CHANNELLINING

TOP OF DITCH

∕CHANNEL LINING

As of April 1, 2019, all new construction activities are required to complete and submit an electronic Notice of Inten (NOI) form requesting a Certificate of Coverage (COC) under the NCG010000 Construction Stormwater General Permit. This form MUST be submitted prior to the commencement of any land disturbing activity on the above named project. The NOI form may be accessed at deq.nc.gov/NCG01. Please direct questions about the NOI form to Annette Lucas at Annette.lucas@nedenr.gov or Paul Clark at Paul.clark@nedenr.gov.

TEMPORARY DIVERSION DITCH

After you submit a complete and correct NOI Form, a COC will be emailed to you within three business days. Initially, DEMLR will not charge a fee for coverage under the NCG01 permit. However, on or after May 1, 2019, a \$100 fee will be charged annually. This fee is to be sent to the DEMLR Stormwater Central Office staff in Raleigh.

Title 15A NCAC 4B .0118(a) and the NCG01 permit require that the following documentation be kept on file at the

The approved E&SC plan as well as any approved deviation. The NCG01 permit and the COC, once it is received. Records of inspections made during the previous 30 days.

The Certificate of Approval

TEMPORARY DIVERSION

TEMPORARY DIVERSION

DITCH #1

DITCH #2

SEDIMENT & EROSION CONTROL NOTES

FOR STORM WATER DISCHARGES FROM LARGE AND SMALL CONSTRUCTION ACTIVITIES (GENERAL PERMIT) REFER TO THE FROSION AND SEDIMENT CONTROL DETAIL SHEETS FOR EROSION CONTROL DETAILS AND DESIGN TABLES FOR SEDIMENT BASINS,

INSTALLED ACCORDINGLY. CONTRACTOR SHALL PERFORM ALL ACTIVITIES IN STRICT COMPLIANCE WITH THE NORTH CAROLINA NPDES GENERAL PERMIT

DIVERSION DITCHES, AND CULVERTS, SLOPE DRAINS, RIP-RAP APRONS AND OTHER EROSION CONTROL MEASURES.

 $\texttt{EXISTING BOUNDARIES}, \texttt{TOPOGRAPHY}, \texttt{190-YR FLOODPLAIN}, \texttt{UTILITY AND ROAD INFORMATION TAKEN FROM AN EXISTING CONDITIONS SURVEY. ALL \\$ EXISTING INFORMATION IS TO BE FIELD VERIFIED BY THE CONTRACTOR

SEE THE LANDSCAPE PLAN FOR LOCATIONS OF PROPOSED PLANTINGS AND FINAL STABILIZATION.

TEMPORARY DIVERSION DITCHES AND BERMS SHALL BE MAINTAINED AS THE SITE IS BROUGHT TO GRADE. DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL DEVICES AND STRUCTURES TO MINIMIZE EROSION. THE CONTRACTOR SHALL

MAINTAIN CLOSE CONTACT WITH THE EROSION CONTROL INSPECTORS SO THAT PERIODIC INSPECTIONS CAN BE PERFORMED AT APPROPRIATE STAGES O

SEE SITE PLAN, GRADING AND DRAINAGE PLAN, UTILITY PLAN, PLANTING PLAN AND OTHER PLAN SHEETS FOR DETAILED DESIGN INFORMATION OF PERMANENT SITE APPURTENANCES SHOWN ON THIS SHEET.

SEE THE GENERAL NOTES SHEET AND THE GRADING AND DRAINAGE PLAN FOR OTHER NOTES REGARDING GRADING ACTIVITIES.

VHERE THE LIMITS OF DISTURBANCE AND TEMPORARY FENCE (SF, SF-PF, OR PF) LIMITS ARE ADJACENT, THE TEMPORARY FENCE LINE IS THE LIMITS OF DISTURBANCE. THE LINE TYPES ARE SHOWN SEPARATED FOR ILLUSTRATIVE PURPOSES ONLY.

CONTRACTOR SHALL NOT DISTURB ANY EXISTING VEGETATIVE GROUND COVER OR TREES OUTSIDE OF THE LIMITS OF DISTURBANCE OR WITHIN ANY REQUIRED BUFFER LIMITS UNLESS OTHERWISE NOTED OR ILLUSTRATED. PROVIDE CONTROLS OF POLLUTANTS, INCLUDING, BUT NOT LIMITED TO DUST CONTROL, DE-WATERING, SOLID WASTE DISPOSAL, AND HAZARDOUS

CLEAR ONLY AS REQUIRED TO INSTALL EROSION AND SEDIMENTATION CONTROL MEASURES. MASS CLEARING AND GRUBBING CAN BEGIN ONLY AFTER

ALL DOWNSTREAM MEASURES HAVE BEEN INSTALLED. USE ROCK OR WASHED STONE TO BRING CONSTRUCTION EXIT TO GRADE. IMPLEMENT WHEEL WASHES AS NECESSARY THROUGHOUT ALL PHASES OF

CONSTRUCTION. DIVERT STORM WATER RUNOFF OFF THE FACE OF THE SEDIMENT BASIN SLOPES USING DIVERSION DITCHES AND SLOPE DRAINS. CONTRACTOR SHALI

MAINTAIN AND RELOCATE DIVERSION DITCHES AND SLOPES DRAINS TO ENSURE STORM WATER RUNOFF DOES NOT ERODE THE FACE OF FINAL SLOPES MAINTAIN POSITIVE FLOW TO THE SEDIMENT BASINS THROUGHOUT ALL PHASES OF CONSTRUCTION, PLACE EXCAVATED SOILS ALONG DOWNSTREAM

EDGE OF THE DIVERSION DITCHES TO PROVIDE ADDITIONAL CAPACITY. REFER TO THE GRADING AND DRAINAGE PLAN FOR FINAL SITE AND PAVEMENT GRADES AND ELEVATIONS OF THE PROPOSED STORM SEWER SYSTEMS. LAND DISTURBING ACTIVITUES SHALL NOT COMMENCE UNTIL APPROVAL TO DO SO HAS BEEN RECEIVED BY GOVERNING AUTHORITIES. THE GENERAL

GENERAL CONTRACTOR SHALL COMPLY WITH ALL STATE AND LOCAL ORDINANCES THAT APPLY

CONSTRUCTION LIMITS SHALL NOT BE EXCEEDED WITHOUT THE APPROVAL OF NODEO INSPECTOR.

ALL WORK SHALL BE CONFINED TO PERMIT LIMITS SHOWN ON PLANS. UNLESS OTHERWISE NOTED, THE SITE PLAN PROPERTY LIMITS SHALL BE

CONTRACTOR SHALL STRICTLY ADHERE TO THE APPROVED EROSION AND SEDIMENT CONTROL DRAWINGS DURING CONSTRUCTION OPERATIONS.

SUFFICIENT EROSION CONTROL PRACTICES MUST BE INSTALLED AND MAINTAINED TO RETAIN SEDIMENT WITHIN THE BOUNDARIES OF THE SITE. ADDITIONAL EROSION CONTROL MEASURES OR SILT BARRIERS TO BE PLACED AS SHOWN AND/OR DIRECTED BY THE PROJECT ENGINEER AND/OR LOCAL JURISDICTIONAL INSPECTOR.

FOR ALL CONSTRUCTION ALONG AND/OR ACROSS WATERWAYS, BANK PROTECTION AND STABILIZATION SHALL BE REQUIRED AS PER LOCAL JURISDICTIONAL EROSION CONTROL LAWS.

ALL TREE PROTECTION AND EROSION CONTROL MEASURES SHALL BE IN PLACE PRIOR TO COMMENCING CONSTRUCTION AND SHALL BE MAINTAINED D PROPER WORKING ORDER UNTIL ALL DISTURBED AREAS ARE STABILIZED AND GROUND COVER IS ESTABLISHED. CONSTRUCTION ENTRANCE PADS SHAL BE INSTALLED BY THE CONTRACTOR AT CONSTRUCTION ACCESS POINTS PRIOR TO LAND DISTURBANCE. ALL EASEMENTS DISTURBED MUST BE DRESSED AND GRASSED TO CONTROL BROSION IN ACCORDANCE WITH EASEMENT PLATS PRIOR TO ACCEPTANCE.

OCCUR. THE COCICAN BE OBTAINED BY FILLING OUT THE ELECTRONIC NOTICE OF INTENT (E-NOI) FORM AT decline gov/NOG01. PLEASE NOTE, THE E-NOI FORM MAY ONLY BE FILLED OUT ONCE THE PLANS HAVE BEEN APPROVED. A COPY OF THE E&SC PERMIT, THE COC, AND A HARD COPY OF THE PLAN MUS

BE KEPT ON-SITE, PREFERABLY IN A PERMITS BOX, AND ACCESSIBLE DURING INSPECTIONS. 2. CONTACT NODEO FAYETTEVILLE REGIONAL OFFICE BEFORE ANY LAND DISTURBANCE OCCURS

3. CONTRACTOR SHALL ENSURE THAT ALL NECESSARY PERMITS HAVE BEEN RECEIVED AND THAT THOSE REQUIRED TO BE DISPLAYED ON-SITE ARE AVAILABLE. 4. CONTRACTOR SHALL HOLD A PRE-CONSTRUCTION MEETING AT LEAST 48 HOURS BEFORE THE ACTUAL START OF CONSTRUCTION. CONTACT NODEQ INSPECTOR. 5. CONTRACTOR SHALL CONTACT CAROLINA ONE CALL AND ALL ENTITIES HAVING BURIED CTILITIES AT LEAST 72 HOURS PRIOR TO DIGGING OR AS DIRECTED A THE PRE-CONSTRUCTION MEETING.

CONTRACTOR SHALL INSTALL TEMPORARY CONSTRUCTION ENTRANCES AT EACH POINT OF ACCESS TO STORAGE AND CONSTRUCTION AREAS. EROSION CONTROL MEASURES SHALL BE INSTALLED PRIOR TO DEMOLITION AND TREE REMOVAL OPERATIONS.

INITIAL PHASE SEDIMENT AND EROSION CONTROL MEASURES SHALL BE INSTALLED IN ACCORDANCE WITH PLANS BEFORE STARTING WORK INCLUDING SIL FENCE, INLET PROTECTION, SKIMMER BASIN, DIVERSION DITCHES, TREE PROTECTION, ETC., CLEARING ONLY AS NECESSARY FOR THE INSTALLATION OF

CONTRACTOR SHALL INCLUDE A RAIN GAUGE AND LOG BOOK CONTAINING THE INSPECTION RECORDS FOR THE SITE

TEMPORARY DIVERSIONS PRIOR TO BEGINNING MASS GRADING OF THE ST ONCE THE BASIN/DIVERSION ARE INSTALLED SEED/MULCH IMMEDIATELY ALL DEMOLITION DEBRIS IS TO GO TO AN APPROVED LANDFILL OR RELATED FACILITY INITIALLY CONSTRUCT THE GRADE FOR THE BUILDING PAD AND THE PARKING AREAS THAT ARE DRAINING TO THE TEMPORARY SKIMMER BASIN.

INSTALL SKIMMER BASIN AND TEMPORARY DITCHES-STABILIZE EARTH BERMS AS WELL AS BASIN SLOPES & INSTALL EROSION CONTROL MATTING IN

MAINTAINING STORMWATER RUNOFF TOWARD THE BASIN. ADJUST THE LOCATION OF TEMPORARY DITCHES AS NECESSARY TO DIVERT RUNOFF FROI THE DRAINAGE SYSTEMS TO THE TEMPORARY SKIMMER BASIN. ONCE THESE AREAS ARE UP TO GRADE AND STABILIZED WITH CONCRETE, PAVEMENT, OF VEGETATION THEN DIVERT STORMWATER RUNOFF TO THE PROPOSED STORM DRAINAGE DEVICES AND THE TEMPORARY SKIMMER BASIN CAN BE REMOVED AND THE AREA CAN BE BROUGHT UP TO GRADE. ONCE THE AREA IS UP TO GRADE, STABILIZE WITH CONCRETE, PAVEMENT, OR VEGETATION

CONTRACTOR TO USE PARKING AREAS ADJACENT TO THE PROPOSED BUILDING FOR LAY-DOWN/STAGING AREAS - MAINTAIN THESE AREAS SO THAT SEDIMENT LADEN RUNOFF WILL BE DIVERTED TO EROSION CONTROL MEASURES. INSTALL SHIT FENCE AROUND LAY-DOWN/STAGING AREA AS SHOWN CONTRACTOR SHALL DILIGENTLY AND CONTINUOUSLY MAINTAIN ALL EROSION CONTROL DIVICES AND STRUCTURES.

ALL APPLICABLE E&S CONTROL MEASURES MUST BE MAINTAINED UNTIL PERMANENT VEGETATION IS ESTABLISHED WITHIN 24 HOURS OF EVERY RAIN EVENT OF GREATER THAN 1 INCH. ANY NEEDED REPAIRS SHALL BE MADE IMMEDIATELY TO MAINTAIN MEASURES AS

 $DESIGNED. ALL\ ESC\ MEASURES\ SIJALL\ BE\ MAINTAINED\ AS\ SPECIFIED\ IN\ THE\ CONSTRUCTION\ DETAILS\ ON\ THIS\ PLAN.$ STOCKPILE RIP-RAP ON SITE AND INSTALL ALL EROSION CONTROL MEASURES WHERE THE WORK IS OCCURRING. ADDITIONAL EROSION CONTROL MEASURES

MAY BE REQUIRED BY THE ENGINEER OR UPON RECOMMENDATION OF NCDEQ INSPECTION PERSONNEL AS CONDITIONS WARRANT.

. ALL DISTURBED AREAS SHALL HAVE GROUND STABILIZATION BY THE CONTRACTOR ACCORDING TO THE CHART ON THIS SHEET,

2. STABILIZE SITE AS AREAS ARE BROUGHT UP TO FINISHED GRADE.

S. UPON COMPLETION OF THE INSTALLATION AND WITH APPROVAL OF NUDEQ, ALL EROSION CONTROL DEVICES SHALL BE REMOVED AND DISPOSED OF IN AN

DEVICE PRIOR TO DISCHARGE TO RECEIVING OUTLET.

WITH THE EROSION CONTROL INSPECTOR PRIOR TO REMOVAL OF EROSION CONTROL MEASURES. WITH APPROVAL OF NODEO, THE SKIMMER BASIN SHALL BE DECOMMISSIONED. REMOVING AND DISPOSING OF ALL ACCUMULATED SEDIMENT IN A LIAWFIII MANNER USB SILT RAG/FILTER RAG/SEE DETAIL IT ON SHEET C-010 AND PIMP FOR DEWATERING THE RASIN AND DIVERSION DITCHES HER SKIMMER BASIN REMOVAL, PERFORM SEEDBED PREPARATION, SEED, MUÍCH AND ASPHALT TACK ANY RESULTING BARE AREAS IMMEDIATELY.

4. ONCE ADEQUATE PERMANENT GROUND COVER IS ESTABLISHED, ALL TEMPORARY EROSION CONTROL MEASURES SHALL BE REMOVED WITH THE APPROVAL OF

DURING DE-WATERING OPERATIONS, BASINS SHOULD BE CONSTANTLY MONITORED AND WATER SHALL BE PUMPED INTO AN APPROVED FILTERING

; ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE N.C. EROSION & SEDIMENT CONTROL PLANNING AND DESIGN MANUAL, NODOT, U.S. DEPT. OF AGRICULTURE, AND STATE STANDARDS.

6. WHEN THE PROJECT IS COMPLETE, THE PERMITTEES SHALL CONTACT DEMLR TO CLOSE OUT THE EASC PLAN. AFTER DEMLR INFORMS THE PERMITTEE OF THE PROJECT CLOSE OUT, VIA INSPECTION REPORT, THE PERMITTEE SHALL VISIT deq.oc.gov/NCG01 TO SUBMIT AN ELECTRONIC NOTICE OF TERMINATION NOT). A \$100 ANNUAL GENERAL PERMIT FEE WILL BE CHARGED UNTIL THE \leftarrow NOT HAS BEEN FILLED OUT.

OWNER/DEVELOPER: HETSON COMPANIES, INC

ATTN. JOHN PARKER 075 JUNIPER LAKE ROAD WEST END, NC 27376 910) 944-0881 ohn@rhetson.com

Highway 2


This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be

vithout liability to Bowman North

Carolina, Ltd.

Rhetson Project# Initial Date February 28, 2022

INITIAL PHASE



1. The approved E&SC plan as well as any approved deviation.

3. Records of inspections made during the previous 30 days.

2. The NCG01 permit and the COC, once it is received.

The Certificate of Approval

owmar

4006 BARRETT DF Suite 104 RALEIGH, NC 2760 Phone: (919)553-657 bowman.com

PRELIMINARY DOMOTUSE FOR CONSTRUCTION

OWNER/DEVELOPER:
RHETSON COMPANIES, INC.
ATTN. JOHN PARKER
2075 JUNIPER LAKE ROAD
WEST END, NC 27376
(910) 944-0881
john@rhetson.com

RHETSON

21 N ounty

US Highway 421 N ston, NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by

Bowman North Carolina, Ltd. shall be

without liability to Bowman North

35C.

No. Date Desc.

Drawn
Checked
Rhetson Project# 21103
Project No. 058004
Initial Date February 28, 2022

FINAL PHASE
EROSION

Sheet No.

C-6B


#23680-US 421 N. Harnett Coun**t**

; ALL EROSION CONTROL MEASURES SHALL BE CONSTRUCTED IN ACCORDANCE WITH THE N.C. EROSION & SEDIMENT CONTROL PLANNING AND DESIGN

6. WHEN THE PROJECT IS COMPLETE, THE PERMITTEES SHALL CONTACT DEMLE TO CLOSE OUT THE ESSO PLAN. AFTER DEMLE INFORMS THE PERMITTEE OF TE

PROJECT CLOSE OUT, VIA INSPECTION REPORT, THE PERMITTEE SHALL VISIT deque goy/INCGOTTO SUBMIT AN ELECTRONIC NOTICE OF TERMINATION (e-NOT). A STOO ANNUAL GENERAL PERMITTEE WILL BE CHARGED UNTIL THE C-NOT HAS BEEN FILLED OUT.

MANUAL, NCDOT, U.S. DEPT. OF AGRICULTURE, AND STATE STANDARDS.



PAVEMENT GENERAL NOTES:


1, DETAILS ARE DOLLAR GENERAL MINIMUM REQUIREMENTS AND MAY INCREASE WITH VARIOUS SOIL CONDITIONS, A GEOTECHNICAL INVESTIGATION WITH PAVEMENT DESIGN RECOMMENDATIONS SHALL BE COMPLETED FOR EACH DEVELOPMENT. THE FOLLOWING DETAILS ARE MINIMUM DOLLAR GENERAL PAVEMENT REQUIREMENTS. INCREASED RECOMMENDATIONS ARE TO BE USED.

2. THE SUBGRADE MATERIALS SHALL BE PROOF ROLLED AND/OR SCARIFIED AND COMPACTED PRIOR TO PLACEMENT OF BASE MATERIAL. WHERE EXISTING SUBGRADE MATERIALS ARE UNSUITABLE, THEY SHALL BE REMOVED AND


REPLACED WITH COMPACTED SELECT MATERIAL IN ACCORDANCE WITH GEOTECHNICAL RECOMMENDATIONS.


3. HEAVY DUTY CONCRETE PAVEMENT AND STANDARD DUTY CONCRETE PAVEMENT (AS RECOMMENDED BY THE GEOTECHNICAL REPORT OR DOLLAR GENERAL MINIMUMS) SHALL BE STEEL REINFORCED. REINFORCEMENT TYPE SHALL BE PRIOR APPROVED BY DOLLAR GENERAL.


4. CONCRETE PAVEMENT PLAN SHALL BE PROVIDED TO DOLLAR GENERAL FOR PRIOR APPROVAL, ALL JOINTS MUST BE SEALED WITH AN APPROVED SEALANT. STEEL REINFORCING SHALL BE USED AT JOINTS. REFER TO ACI 330R (GUIDE FOR DESIGN AND CONSTRUCTION OF CONCRETE PARKING LOTS) FOR JOINT DESIGN AND LAYOUT.





* REFER TO PROJECT GEOTECHNICAL REPORT FOR ADDITIONAL REQUIREMENTS






















Suite 104 RALEIGH, NC 2760 Phone: (919)553-65




OWNER/DEVELOPER:
RHETSON COMPANIES, INC.
ATTN. JOHN PARKER
2075 JUNIPER LAKE ROAD
WEST END, NC 27376
(910) 944-0881
john@rhetson.com

RHETSO


US Highway 421 N
Lillington, NC Harnett County


This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be without liability to Bowman North Carolina, Ltd.





CONSTRUCTION DETAILS


Sheet No. C-7

















RHETSON COMPANIES, INC. ATTN. JOHN PARKER 2075 JUNIPER LAKE ROAD WEST END, NC 27376 (910) 944-0881 john@rhetson.com




US Highway 421 N gton, NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be without liability to Bowman North Carolina, Ltd.




Checked Rhetson Project# 21103 Project No. 058004 Initial Date February 28, 2022


CONSTRUCTION **DETAILS**



- The Professional Engineer (PE) shall obtain and supply a copy of the sewer permit for the construction and operation of the wastewater collection system to the Utility Contractor before the construction of the sanitary sewer line, sewer line, sewer line, sewer line, sewer line associated force main shall begin. The Utility Contractor must post a copy of the sewer permit issued by the North Carolina Department of Environmental Quality (NCDEQ) on site prior to the start of construction. The permit must be maintained on site during the construction of the sewer system improvements.
- The Utility Contractor shall notify Harnett Regional Water (HRW) and the Professional Engineer (PE) at least two days prior to construction commencing. The Utility Contractor must schedule a pre-construction conference with Mr. Alan Moss, HRW Utility Construction Inspector at least two (2) days before construction will begin and the Utility Contractor must coordinate with HRW for regular inspection visitations and acceptance of the wastewater system(s). Construction work shall be performed only during the normal working hours of HRW which is 8:00 am - 5:00 pm Monday through Friday. Holiday and weekend work is not permitted by HRW.
- The Professional Engineer (PE) shall provide HRW with a set of NCDEQ approved plans marked "Released for Construction" at least two days prior to construction commencing, HRW will stamp the approved plans as "Released for Construction" and provide copies to the utility contractor. The Registered Land Surveyor (RLS) shall stake out all lot corners and establish grade stakes for the proposed finish grade for each street and sewer line before the Utility Contractor begins construction or installation of the manholes, sanitary sewer gravity line(s), sewer lift stations and/or sanitary sewer force main(s). The grade stakes should be set with a consistent offset from the street centerline so as not to interfere with the street grading or utility construction.
- The Utility Contractor shall provide the HRW Utility Construction Inspector with material submittals and shop drawings for all project materials prior to the construction of any gravity sewer line(s), manhole(s), sewer lift station(s) and associated force main(s) in Harnett County. The materials to be used on the project must meet the established specifications of HRW and be approved by the Engineer of Record prior to construction. All substandard materials or materials not approved for use in Harnett County found on the project site must be removed immediately when notified by the HRW Utility Construction Inspector.
- The sanitary sewer lateral connections should be installed 90° (perpendicular) to the sanitary sewer gravity lines with schedule 40 PVC pipe, HRW requires the Utility Contractor to provide the Professional Engineer (PE) with accurate measurements for locating sanitary sewer service lateral and associated each sanitary sewer clean-out. These measurements should be taken from the nearest downstream manhole up along the sanitary sewer main to the in-line way fitting (or tapping saddle) and then another measurement from the in-line way fitting (or tapping saddle) to the 4" x 4" long sweep combination was fitting at the bottom of the sewer clean-out stack. These field measurements must be provided to the Professional Engineer (PE) in the red line drawings from the Utility Contractor for proper documentation in the As-Built Record Drawings submitted to HRW.
- The Utility Contractor shall be responsible to locate the newly installed sanitary sewer gravity line(s), sanitary sewer force main(s), sanitary sewer service lateral(s) and all associated sewer clean-out(s) in the proposed sanitary sewer system for other utility companies and their contractors until the new sanitary sewer line(s) and associated appurtenances have been approved by the North Carolina Department of Environmental Quality (NCDEQ) and accepted by HRW. All new sanitary sewer lines must have at least three (3 ft.) feet of cover and extend under all existing water main and storm water lines with a least 24" of vertical clearance below the bottom of the existing water main and storm water lines. ALL ductile iron sewer piping must be 401 epoxy coated or approved equal. The sanitary sewer gravity line(s), manhole(s), sanitary sewer service lateral(s) and associated clean-out(s) shall be constructed in strict accordance with the standard specifications of the Harnett Regional Water. The sanitary sewer gravity line(s) must pneumatically pressure tested with compressed
- air at 5 psi and the sanitary sewer force main(s) must hydrostatically pressure tested with water or air at 200 psi. Sanitary sewer membeles must be vacuum tested to 10 inches of mercury and cannot drop below 9 inches in 60 seconds for 4 ft. diameter manholes, 75 seconds for 5 ft. diameter manholes. The test must be in accordance with the following standards: For ductile iron pipelines test in accordance with the applicable requirements of ASTM C924. For PVC pipelines test in accordance with ASTM F1417-98 and UBPPA UNI-B-6. Vacuum testing shall be performed in accordance with ASTM C1244. The HRW Utility Construction Inspector and Engineer must witness all tests mentioned above.
- Prior to acceptance, all sewer service laterals will be inspected to insure that they are installed at the proper depth. All sever clean-outs must be installed so the 4" x 4" long sweep combination wye is at least three (3') feet but no more than four (4') feet below the finish grade unless otherwise approved in writing by JRW. The sewer cleanouts shall have a four (4") schedule 40 PVC pipe stubbed up from both ends of the 4" x 4" long sweep combination were to be at least two (2") feet above the finish grade and cover cach end with a four (4") inch temporary cap to keep out dirt, sand, nocks, water and construction debris. The vertical stack on each clean-out must be provided with a concrete donut for protection.
- Once the sanitary sewer gravity line(s) have been installed, pneumatically pressure tested and in place for at least 30 days, the Utility Contractor must contact the HRW Utility Construction Inspector to witness the mandrel test on each PVC sanitary sewer gravity line. The Utility Contractor will notify HRW to schedule the mandrel testing. The mandrel and proving ring must be supplied by the Utility Contractor. Closed circuit video camera inspections (at the Utility Contractor's expense) may be required by the HRW Utility Construction Inspector if the mandrel and mirror tamping testing cannot be completed with satisfactory results. The sanitary sewer lines should be flushed clean using a sewer ball of the proper diameter before any mandrel testing can be performed. The Utility Contractor is responsible to remove all dirt, sand, silt, gravel, mud and debris from the newly constructed sewer lines exercising care to keep the Harnett Regional Water's existing sanitary sewer systems clean. Sanitary sewer force main(s) shall be pressure tested to 200 psi for at least 2 hours like water lines.
- The Utility Contractor shall be responsible to locate the newly installed sanitary sewer system(s) for other utility companies and their contractors until the new sanitary sewer system(s) have been approved by the North Carolina Department of Environmental Quality (NCDEQ) and accepted by
- HRW requires that the Utility Contractor install tracer wire in the trench with all sanitary sewer force mains. The tracer wire shall be 12 ga, insulated, solid copper conductor and it shall be terminated at the top of the valve boxes or manholes. No spliced wire connections shall be made underground on tracer wire installed in Harnett County. The tracer wire may be secured with duet tage to the top of the pine before backfilling. The tracer wire is not required for the gravity sewer line(s) between manholes.
- The Utility Contractor shall provide the Professional Engineer (PE) and HRW Utility Construction Inspector with a set of red line drawings identifying the complete sewer system installed for each project. The red line drawings should identify the materials, pipe sizes and approximate depths of the sewer lines as well as the installed locations of the manhole(s), sanitary sewer gravity line(s), sanitary sewer service laterals, elean-nuts, sewer lift station(s) and associated force main(s). The red line drawings should clearly identify any deviations from the NCDEQ approved plans. All change orders must be approved by HRW and the Professional Engineer (PE) in writing and properly documented in the red line field drawings.
- Prior to the commencement of any work within established utility casements or NCDOT right-of-ways the Utility Contractor is required to notify all concerned utility companies in accordance with G.S. 87-102. The Utility Contractor must call the NC One Call Center at 811 or (800) 632-4949 to verify the location of existing utilities prior to the beginning of construction. Existing utilities shown in these plans are taken from maps furnished by various utility companies and have not been physically located by the P.E. (i.e. TELEPHONE, CABLE, WATER, SEWER, ELECTRICAL POWER,
- The Utility Contractor shall spot dig to expose each existing utility pipe or line which may conflict with construction of proposed sanitary sewer line extensions well in advance to verify locations of the existing utilities. The Utility Contractor shall provide both horizontal and vertical clearances to the Professional Engineer (PE) to allow the PE to adjust the sanitary sewer line design in order to avoid conflicts with existing underground utilities. The Utility Contractor shall coordinate with the utility owner and be responsible for temporary relocation of existing utilities and/or securing existing

- O. When making a tap on an existing sewer force main, the Utility Contractor must have a permit from the North Carolina Department of Environmental Quality (NCDEQ) prior to begin the tap work. The Utility Contractor shall conduct a pneumatic pressure test using compressed air or other incret ga on the stainless steel tapping sleeve and gate valve prior to making the tap on an existing sanitary sewer force main. This pneumatic pressure test must be witnessed by the HRW Utility Construction Inspector. The Utility Contractor shall use Romac brand stainless steel tapping sleeve(s) or approve equal for all taps made on sanitary sewer force mains in Harnett County. The Utility Contractor shall use Romae brand Style "CB" sewer saddles with stainless steel bands or approved equal for all taps made on existing sanitary sever gravity lines in Harnett County.
- P. The Utility Contractor shall provide a grease trap for each sanitary sewer service lateral that will be connected to a restaurant, food processing facility and any other commercial or industrial facility as required by the Harmett County Fat, Oil & Grease Ordinance. The grease trap must be rated for a minimum capacity of at least 1,000 gallons unless otherwise approved in writing by the HRW Pre-Treatment Coordinator, Garbage disposals should not be installed in homes and businesses that discharge wastewater to the Harnett Regional Water's Sanitary Server System as they are not approved
-). Each sewer lift station must be provided with three phase power (at least 480 volts) and constructed to meet the minimum requirements of the latest version of the National Electrical Code (NEC) and Harnett Regional Water standard specifications and details. If three phase power is not available from the power company other arrangements must be approved by HRW Engineering prior to the start of construction
- R. Where a new sanitary sewer force main is connected to an existing manhole in the Harnett Regional Water sewer collections system, the Utility Contractor must provide a protective coating (epoxy) for the interior surfaces of the manhole to protect it against corrosion, erosion and deterioration from
- 5. The sewer lift station design and associated equipment must meet or exceed the MINIMUM REQUIREMENTS FOR HARNETI COUNTY SEWER LIFT STATIONS. Each sanitary sewer lift station must be constructed with an all-weather access road that is at least 20 feet wide. The lift station site must be covered with weed blocking material and at least six (6") inches of ABC stone (crush and run).
- Once a sewer lift station has been installed, the Utility Contractor is responsible to schedule a draw down test with HRW Engineering and Collections staff, the Professional Engineer (PE), the Electrician, the original equipment manufacturers (OEM) representatives [For both the Pumps and the Generator). This draw down test must be completed with power supplied from the electrical utility company and with power supplied by the emergency generator with satisfactory results before final inspections are conducted by the HRW Utility Construction Inspector. Once the Utility Contractor completes the installation of a sewer lift station, the Professional Engineer (PE) must submit the sewer permit certification and As-Built Record Drawings to the North Carolina Department of Environmental Quality (NCDEO) and HRW for final approval. The Utility
- Contractor must supply HRW Engineering staff with three original Operation & Maintenance (O&M) Manuals along with the associated pump curves and electrical schematics for the associated sewer lift station equipment including all warranty information and documentation V. Once the Utility Contractor completes the installed at the new sewer lift station, the Developer must pay HRW the established System Control and Data Acquisition (SCADA) fees before the SCADA system will be installed at the new sewer lift station. The SCADA system must be installed and operational before the utilities may be accepted by HRW and placed into operation.
- W. HRW requires the Utility Contractor to provide all necessary equipment and devices for the testing and inspection of the sanitary sever system. The equipment and devices may include but not limited to lamping with mirrors, mandrels, sewer balls, plugs, air compressors and associated compressor air lines. If the HRW Utility Construction Inspector deems that a closed circuit video camera inspection of the newly constructed sewer system is necessary, then all costs for the closed circuit camera inspection will be the responsibility of the Utility Contractor. All closed circuit video camera inspections must be recorded on VHS tapes that will released to HRW for record keeping, review and approval of the sewer system.
- Any use of sewer plugs to temporarily block Harnett Regional Water's existing sanitary sewer lines must be coordinated with the HRW Collections Supervisor at least two (2) days in advance of installing the plugs. The sewer plugs must be removed as soon as possible once the new sanitary sewer lines have been inspected, pressure tested, mandrel tested, approved by the North Carolina Department of Environmental Quality (NCDEQ) and accepted by HRW to allow the sewer to flow as designed in Harnett Regional Water's existing sanitary sewer lines or when so ordered by the HRW Collections Supervisor to limit interruptions to the normal flow of the sanitary sever collection system(s). The Utility Contractor must provide the pumps hoses and necessary connectors for a temporary pump around setup if required by the HRW Collections Supervisor. Mr. Randolph Clegg, HRW Collections Supervisor may be contacted between 8:00 am and 5:00 pm Monday through Friday at (910) 893-7575 extension 3241.
- Y. The Liftity Contractor will be responsible for any and all repairs due to leakage or damage resulting from poor workmanship during the one (1) year warranty period once the server system improvements have been approved by the North Carolina Department of Environmental Quality (NCDEQ) and accepted by IRRW. The Utility Contractor will be responsible for any and all repairs due to damages resulting from failure to locate the new sanitary sewer lines and associated appurtenances for other utilities and their contractors until the sanitary sewer lines have been approved by NCDEQ and accepted by IIRW. IIRW will provide maintenance and warranty repairs if necessary due to lack of response within 48 hours of notification of warranty work. IIRW will invoice the Developer and/or Utility Contractor for materials and labor in such cases.
- In developments and projects that require utility easements to be established for future URW right-of-way, the Registered Land Surveyor (RLS) must provide the HRW Right-of-Way Agent with an official copy of the recorded plat and legal description of the said easement as recorded with the Harnett Country Register of Deeds. The recorded documents must be provided to the URW Right-of-Way Agent before the utility improvements within the said casement can be placed into operation. Any and all easements that must be obtained from adjoining property owners must be provided to HRW by the Developer at no cost to Harnett County. The final inspection of all sanitary sever system improvements cannot be scheduled with HRW until the streets have been paved; the rights-of-way and utility easements have been each and stabilized with an adequate stand of grass in place to
- VA. The Engineer of Record is responsible to insure that construction is, at all times, in compliance with accepted sanitary engineering practices and approved plans and specifications. No field changes to the approved plans are allowed without prior written approval by HRW. A copy of each engineer's field report is to be submitted to HRW as each such inspection is made on system improvements or testing is performed by the contractor. Water and sewer infrastructure most pass all tests required by HRW specifications and those of all applicable regulatory agencies. These tests include, but are not limited to: air test, vacuum test, mandred test, visual test, pressure test, bacteriological test, etc. A HRW Inspector must be present during testing and all test results shall be submitted to HRW. All tests must be satisfied before the final inspection will be scheduled with the HRW Inspector. Engineer of Record must request in writing to schedule the final inspection once all construction is complete. The Developer's Engineer of Record and the HRW Utility Construction Inspector shall prepare a written punch list of any defects or deficiencies noted during the final inspection, should any exist. Upon completion of the punch list, the Developer's Engineer of Record will schedule another inspection. In the event the number of inspections performed by the HRW exceeds two, additional fees may be accessed to the Developer.





TYPICAL METER BOX DETAIL FOR 3/4" SERVICE/ W

OWNER/DEVELOPER: RHETSON COMPANIES, INC ATTN. JOHN PARKER 2075 JUNIPER LAKE ROAD WEST END, NC 27376 (910) 944-0881 ohn@rhetson.com

(民) | RHETSOI

Highway 421 N , NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written

authorization and adaptation by Bowman North Carolina, Ltd. shall be

without liability to Bowman North

Carolina, Ltd.

Rhetson Project# Initial Date February 28, 2022

CONSTRUCTION

C-8A

23680-US 421 N. Harnett Count

Implementing the details and specifications on this plan sheet will result in the construction activity being considered compliant with the Ground Stabilization and Materials Handling sections of the NCGo1 Construction General Permit ections E and F, respectively). The permittee shall comply with the Erosion and Sediment Control plan approved by the delegated authority having jurisdiction. All details and specifications shown on this sheet may not apply depending on site conditions and the delegated authority having jurisdiction.

	CTION E: GROUND STA	n : 10 10:11	
		Required Ground Stabil	ization Timetrames
Site Area Description		Stabilize within this many calendar days after ceasing land disturbance	Timeframe variations
(a)	Perimeter dikes, swales, ditches, and perimeter slopes	7	None
(b)	High Quality Water (HQW) Zones	7	None
(c)	Slopes steeper than 3:1	7	
(d)	Slopes 3:1 to 4:1	14	-7 days for slopes greater than 50' in length and with slopes steeper than 4:1 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed
(e)	Areas with slopes flatter than 4:1	14	 -7 days for perimeter dikes, swales, ditches, perimeter slopes and HQW Zones -10 days for Falls Lake Watershed unless there is zero slope

Note: After the permanent cessation of construction activities, any areas with temporary ground stabilization shall be converted to permanent ground stabilization as soon as practicable but in no case longer than 90 calendar days after the last land disturbing activity. Temporary ground stabilization shall be maintained in a manner to render the surface stable against accelerated erosion until permanent ground stabilization is achieved.

ROUND STABILIZATION SPECIFICATION

tabilize the ground sufficiently so that rain will not dislodge the soil. Use one of the techniques in the table below: Temporary Stabilization Permanent Stabilization

Temporary grass seed covered with straw or | + Permanent grass seed covered with straw or other mulches and tackifiers Hydroseeding Railed erasion control products with or

- + Geotextile fabrics such as permanent soil reinforcement matting without temporary grass seed Hydroseeding Appropriately applied straw or other mulch • Shrubs or other permanent plantings covered Plastic sheeting with mulch
 - + Uniform and evenly distributed ground cover sufficient to restrain erosion + Structural methods such as concrete, asphalt or retaining walls

• Ralled erasion control products with grass seed

other mulches and tackifiers

- POLYACRYLAMIDES (PAMS) AND FLOCCULANTS
- Select flocculants that are appropriate for the soils being exposed during construction, selecting from the NO DWR List of Approved PAMS/Flocculants. Apply flocculants at or before the inlets to Erosion and Sediment Control Measures.
- Apply flocculants at the concentrations specified in the NC DWR List of Approved PAMS/Flocculants and in accordance with the manufacturer's instructions. Provide ponding area for containment of treated Stormwater before discharging offsite.
- Store floeculants in leak-proof containers that are kept under storm-resistant cover or surrounded by secondary containment structures.

QUIPMENT AND VEHICLE MAINTENANCE

- Maintain vehicles and equipment to prevent discharge of fluids.
- Provide drip pans under any stored equipment. Identify leaks and repair as soon as feasible, or remove leaking equipment from the project. Collect all spent fluids, store in separate containers and properly dispose as hazardous waste (recycle when
- Remove leaking vehicles and construction equipment from service until the problem has been corrected. Bring used fuels, lubricants, coolants, hydraulic fluids and other petroleum products to a recycling or disposal center that handles these materials.

LITTER, BUILDING MATERIAL AND LAND CLEARING WASTE

- Never bury or burn waste. Place litter and debris in approved waste containers.
- Provide a sufficient number and size of waste containers (e.g dumpster, trash receptacle) on site to contain construction and domestic wastes.
- Locate waste containers at least 50 feet away from storm drain inlets and surface waters unless no other alternatives are reasonably available.
- Locate waste containers on areas that do not receive substantial amounts of runoff from upland areas and does not drain directly to a storm drain, stream or wetland.
- Cover waste containers at the end of each workday and before storm events or provide secondary containment. Repair or replace damaged waste containers. Anchor all lightweight items in waste containers during times of high winds.
- Empty waste containers as needed to prevent overflow. Clean up immediately if containers overflow. Dispose waste off-site at an approved disposal facility. On business days, clean up and dispose of waste in designated waste containers.

AINT AND OTHER LIQUID WASTE

- Do not dump paint and other liquid waste into storm drains, streams or wetlands. Locate paint washouts at least 50 feet away from storm drain inlets and surface waters unless no other
- alternatives are reasonably available. Contain liquid wastes in a controlled area.
- Containment must be labeled, sized and placed appropriately for the needs of site.

ARTHEN STOCKPILE MANAGEMENT

alternatives are reasonably available.

Provide stable stone access point when feasible.

NCG01 GROUND STABILIZATION AND MATERIALS HANDLING

- Install portable toilets on level ground, at least 50 feet away from storm drains, streams or wetlands unless ther is no alternative reasonably available. If 50 foot offset is not attainable, provide relocation of portable toilet
- behind silt fence or place on a gravel pad and surround with sand bags. Provide staking or anchoring of portable toilets during periods of high winds or in high foot traffic areas. Monitor portable toilets for leaking and properly dispose of any leaked material. Utilize a licensed sanitary waste

Show stockpile locations on plans. Locate earthen-material stockpile areas at least 50 feet away from storm dra

inlets, sediment basins, perimeter sediment controls and surface waters unless it can be shown no other

Protect stockpile with silt fence installed along toe of slope with a minimum offset of five feet from the toe of

that will restrain accelerated erosion on disturbed soils for temporary or permanent control needs.

hauler to remove leaking portable toilets and replace with properly operating unit.

Do not use concrete washouts for dewatering or storing defective curb or sidewalk sections. Stormwater accumulated within the washout may not be pumped into or discharged to the storm drain system or receiving surface waters. Liquid waste must be pumped out and removed from project.

available, use one of the two types of temporary concrete washouts provided on this detail.

associated materials on impervious barrier and within lot perimeter silt fence.

Locate washouts at least 50 feet from storm drain inlets and surface waters unless it can be shown that no other alternatives are reasonably available. At a minimum, install protection of storm drain inlet(s) closest to the washout which could receive spills or overflow.

ONSITE CONCRETE WASHOUT

LOW PILTRATION SOIL BERM

TRETE WASHOUT STRUCTURES SHALL BE MAINTAINED WHEN 2. THE CONCRETE WASHOUT STRUCTURES SHALL BE MAINTAINED

WITH SIGNAGE NOTING DEVICE.

MINIMUM: 2 INCHES OF FREEBOARD. 3.CONCRETE WASHOUT STRUCTURE NEEDS TO BE CLEARLY MARKED

ABOVE GRADE WASHOUT STRUCTU

QUID AND OR SOLID REACHES 75% OF THE STRUCTURES CAPACITY. WHEN THE LIQUID AND/OR SOLID REACHES 75% OF THE STRUCTURES TE WASHOUT STRUCTURE NEEDS TO BE CLEARLY MARKED WITH — CAPACITY TO PROVIDE ADEQUATE HOLDING CAPACITY WITH A

Dispose of, or recycle settled, hardened concrete residue in accordance with local and state solid waste

Manage washout from mortar mixers in accordance with the above item and in addition place the mixer and

Install temporary concrete washouts per local requirements, where applicable. If an alternate method or

product is to be used, contact your approval authority for review and approval. If local standard details are not

- Locate washouts in an easily accessible area, on level ground and install a stone entrance pad in front of the washout. Additional controls may be required by the approving authority.
- Install at least one sign directing concrete trucks to the washout within the project limits. Post signage on the
- Remove leavings from the washout when at approximately 75% capacity to limit overflow events. Replace the tarp, sand bags or other temporary structural components when no longer functional. When utilizing alternative Stabilize stockpile within the timeframes provided on this sheet and in accordance with the approved plan and or proprietary products, follow manufacturer's instructions. any additional requirements. Soil stabilization is defined as vegetative, physical or chemical coverage technique

BELOW GRADE WASHOUT STRUCTURE

regulations and at an approved facility.

Do not discharge concrete or eement slurry from the site.

ONCRETE WASHOUTS

At the completion of the concrete work, remove remaining leavings and dispose of in an approved disposal facility. Fill pit, if applicable, and stabilize any disturbance caused by removal of washout.

ERBICIDES, PESTICIDES AND RODENTICIDES

- Store and apply herbicides, posticides and rodenticides in accordance with label restrictions. Store herbicides, pesticides and rodenticides in their original containers with the label, which lists directions for
- use, ingredients and first aid steps in case of accidental poisoning. Do not store herbicides, pesticides and rodenticides in areas where flooding is possible or where they may spill
- or leak into wells, stormwater drains, ground water or surface water. If a spill occurs, clean area immediately. Do not stockpile these materials ousite.

IAZARDOUS AND TOXIC WASTE

- Create designated hazardous waste collection areas on-site. Place hazardous waste containers under cover or in secondary containment.
- Do not store hazardous chemicals, drums or bagged materials directly on the ground.

EFFECTIVE: 04/01/19

PART III SELF-INSPECTION, RECORDKEEPING AND REPORTING

SECTION A: SELF-INSPECTION

OR STAPLES

DOMESTVE &

Self-inspections are required during normal business hours in accordance with the table below. When adverse weather or site conditions would cause the safety of the inspection personnel to be in jeopardy, the inspection may be delayed until the next business day on which it is safe to perform the inspection. In addition, when a storm event of equal to or greater than 1.0 inch occurs outside of normal business hours, the self-inspection shall be performed upon the commencement of the next business day. Any time when inspections were delayed shall be noted in the Inspection

Inspect	Frequency (during normal business hours)	inspection records must include:
111 Raingauge maintained in good working order	Daily	Daily rainfall amounts. If no daily rain gauge observations are made during weekend holiday periods, and no individual-day rainfall information available, record the cumulative rain measurement for those u attended days land this will determine if a site inspection needed). Days on which no rainfall occurred shall be recorded "zero." The permittee may use another rain-monitoring device approved by the Division.
[2] &&SC Measures	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the measures inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Indication of whether the measures were operating properly, 5. Description of maintenance needs for the measure, 6. Description, evidence, and date of corrective actions taken.
i3) Stormwater discharge outfalls (SDOs)	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	1. Identification of the discharge outfalls inspected, 2. Date and time of the inspection, 3. Name of the person performing the inspection, 4. Evidence of indicators of stormwater pollution such as oil sheen, floating or suspended solids or discoloration, 5. Indication of visible sediment leaving the site, 6. Description, evidence, and date of corrective actions taken.
4 Perimeter of site	At least once per 7 calendar days and within 24 hours of a rain event > 1.0 inch in 24 hours	If visible sedimentation is found outside site limits, then a record of the following shall be made: 1. Actions taken to clean up or stabilize the sediment that has left the site limits, 2. Description, evidence, and date of corrective actions taken, and 3. An explanation as to the actions taken to control future releases.
5 Streams or wetlands onsite or offsite where accessible	At least once per 7 calendar days and within 24 hours of a rain event ≥ 1.0 inch in 24 hours	If the stream or wetland has increased visible sedimentation or a stream has visible increased turbidity from the construction activity, then a record of the following shall be made: 1. Description, evidence and date of corrective actions taken, an 2. Records of the required reports to the appropriate Division Regional Office per Part III, Section C, Item [2] [a] of this permit of this permit.
[6] Ground stabilization measures	After each phase of grading	1. The phase of gracing juristaliation of perimeter E&SC measures, clearing and grubbing, instaliation of storm drainage facilities, completion of all land-disturbing activity, construction or redevelopment, permanent ground cover). 2. Documentation that the required ground stabilization measures have been provided within the required timeframe or an assurance that they will be provided as soon as possible.

NOTE: The rain inspection resets the required 7 calendar day inspection requirement

E&SC Plan Documentation

SECTION B: RECORDKEEPING

The approved E&SC plan as well as any approved deviation shall be kept on the site. The approved E&SC plan must be kept up-to-date throughout the coverage under this permit. The following items pertaining to the E&SC plan shall be kept on site and available for inspection at all times during normal business hours.

SELF-INSPECTION, RECORDKEEPING AND REPORTING

Item to Document	Documentation Requirements
(a) Each E&SC Measure has been installed and does not significantly deviate from the locations, dimensions and relative elevations shown on the approved E&SC Plan.	Initial and date each E&SC Measure on a copy of the approved E&SC Plan or complete, date and sign an inspection report that lists each E&SC Measure shown on the approved E&SC Plan. This documentation is required upon the initial installation of the E&SC Measures or if the E&SC Measures are modified after initial installation.
(b) A phase of grading has been completed.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate completion of the construction phase.
(c) Ground cover is located and installed in accordance with the approved E&SC Plan.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate compliance with approved ground cover specifications.
(d) The maintenance and repair requirements for all E&SC Measures have been performed.	Complete, date and sign an inspection report.
(e) Corrective actions have been taken to E&SC Measures.	Initial and date a copy of the approved E&SC Plan or complete, date and sign an inspection report to indicate the completion of the corrective action.

. Additional Documentation to be Kept on Site

In addition to the E&SC plan documents above, the following items shall be kept on the site and available for inspectors at all times during normal business hours, unless the Division provides a site-specific exemption based on unique site conditions that make this requirement not practical:

- (a) This General Permit as well as the Certificate of Coverage, after it is received.
- (b) Records of inspections made during the previous twelve months. The permittee shall record the required observations on the Inspection Record Form provided by the Division or a similar inspection form that includes all the required elements. Use of electronically-available records in lieu of the required paper copies will be allowed if shown to provide equal access and utility as the hard-copy records.

3. Documentation to be Retained for Three Years

All data used to complete the e-NOI and all inspection records shall be maintained for ——a period of three years after ject completion and made available upon request. [40 CFR 122.41]

SELF-INSPECTION, RECORD KEEPING AND REPORTING ECTION C: REPORTING

Occurrences that Must be Reported Permittees shall report the following occurrences:

) Visible sediment deposition in a stream or wetland.

- They are 25 gallons or more, They are less than 25 gallons but cannot be cleaned up within 24 hours,
- They cause sheen on surface waters (regardless of volume), or • They are within 100 feet of surface waters (regardless of volume).

c) Releases of hazardous substances in excess of reportable quantities under Section 311 of the Clean Water Act (Ref. 40 CFR 110.3 and 40 CFR 117.3) or Section 102 of CERCLA (Ref. 40 CFR 302.4) or G.S. 143-215.85.

(d) Anticipated bypasses and unanticipated bypasses.

Noncompliance with the conditions of this permit that may endanger health or the environment.

CFR 122.41(I)(7)]

Reporting Timeframes and Other Requirements After a permittee becomes aware of an occurrence that must be reported, he shall contact the appropriate Division regional

rence	Reporting Timeframes (After Discovery) and Other Requirements
ible sed iment	Within 24 hours, an oral or electronic notification.
ition in a	Within 7 calendar days, a report that contains a description of the
n or wetland	sediment and actions taken to address the cause of the deposition.
	Division staff may waive the requirement for a written report on a
	case-by-case basis.
	+ If the stream is named on the <u>NC 303(d) list</u> as impaired for sediment-
	related causes, the permittee may be required to perform additional
	monitoring, inspections or apply more stringent practices if staff
	determine that additional requirements are needed to assure compliance
	with the federal or state impaired-waters conditions.
spills and	Within 24 hours, an oral or electronic notification. The notification
: of	shall include information about the date, time, nature, volume and
DV3	location of the spill or release.
nces per Item	
above	
cipated	A report at least ten days before the date of the bypass, if possible.
es (40 CFR	The report shall include an evaluation of the anticipated quality and
(m)(3)]	effect of the bypass.

(d) Unanticipated Within 24 hours, an oral or electronic notification. bypasses [40 CFR Within 7 calendar days, a report that includes an evaluation of the 122.41(m)(3)] quality and effect of the bypass.

(e) Noncompliance • Within 24 hours, an oral or electronic notification. with the conditions • Within 7 calendar days, a report that contains a description of the of this permit that noncompliance, and its causes; the period of noncompliance, may endanger – including exact dates and times, and if the noncompliance has not health or the been corrected, the anticipated time noncompliance is expected to environment[40]

continue; and steps taken or planned to reduce, eliminate, and prevent reoccurrence of the noncompliance. [40 CFR 122.41(I)(6). Division staff may waive the requirement for a written report on a case-by-case basis.


PART II, SECTION G, ITEM (4) DRAW DOWN OF SEDIMENT BASINS FOR MAINTENANCE OR CLOSE OUT


Sediment basins and traps that receive runoff from drainage areas of one acre or more shall use outlet structures that withdraw water from the surface when these devices need to be drawn down for maintenance or close out unless this is infeasible. The circumstance which it is not feasible to withdraw water from the surface shall be rare (for example, times with extended cold weather). Non-surface withdrawals from sediment basins shall be allowed only when all of the following criteria have been met:

- a) The E&SC plan authority has been provided with documentation of the non-surface withdrawal and the specific time periods or conditions in which it will occur. The non-surface withdrawal
- shall not commence until the E&SC plan authority has approved these items,
- (b) The non-surface withdrawal has been reported as an anticipated bypass in accordance with Part III, Section C, Item (2)(c) and (d) of this permit, (c) Dewatering discharges are treated with controls to minimize discharges of pollutants from stormwater that is removed from the sediment basin. Examples of appropriate controls include properly sited, designed and maintained dewatering tanks, weir tanks, and filtration systems,
- Vegetated, upland areas of the sites or a properly designed stone pad is used to the extent feasible at the outlet of the dewatering treatment devices described in Item (c) above,
- Velocity dissipation devices such as cheek dams, sediment traps, and riprap are provided at the discharge points of all dewatering devices, and Sediment removed from the devatering treatment devices described in Item (c) above is disposed of in a manner that does not cause deposition of sediment into waters of the United States.

NCG01 SELF-INSPECTION, RECORD/CEEPING AND REPORTING

EFFECTIVE: 04/01/19








2075 JUNIPER LAKE ROAD WEST END, NC 27376 910) 944-0881 ohn@rhetson.com

Highway


This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be without liability to Bowman North Carolina, Ltd.



Checked Rhetson Project# ^oroject No. Initial Date February 28, 2022

NC CONSTRUCTION GENERAL PERMIT NCGO₁ NOTES

23680-US 421 N. Harnett Coun



OWNER/DEVELOPER:

HETSON COMPANIES, INC TTN. JOHN PARKER 075 JUNIPER LAKE ROAD WEST END, NC 27376 hn@rhetson.com


Highway 421 N NC Harnett County


This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this locument without written authorization and adaptation by Bowman North Carolina, Ltd. shall be


Initial Date February 28, 2022 **EROSION**


CONTROL


23680-US 421 N. Harnett Cou











at the bottom of the control structure may require a trashrack to mitigate the clogging of the device. Typical details for such racks can be obtained from the stormwater services

Remove the trash/debris

as soon as possible.

Sweep or vacuum the sediment

Regrade soil if necessary to

remove the gully, and then plant

a ground cover and water until it is established. Provide lime and a one-time fertilizer application.

Maintain vegetation at an appropriate height.

Unclog the conveyance and dispose of any sediment offsite.

Make any necessary repairs or replace if damage is too large

Search for the source of the

Provide additional erosion protection such as reinforced I turf matting or riprap if needed to prevent future erosion

Remove the weeds, preferably by hand. If a pesticide is used,

wipe it on the plants rather than

Check to see if the collector

system is clogged and flush if

necessary. If water still ponds,

remove the top few inches of filter bed media and replace. If water still ponds, then consult

Clean out the outlet device.

Repair or replace the outlet

Contact the NC Division of

Water Resources.

Dispose of the sediment offsite.

sediment and remedy the problem if possible. Remove the sediment and stabilize or dispose of it in a location where it will not cause impacts to streams or the BMP

for repair.

problems.

an expert.

Maintain operation and maintenance records in a know set location. Operation and maintenance records

Trash/debris is present.

Sediment is present on the pavement surface.

Areas of bare soil and/or erosive gullies have formed.

Vegetation is too short or too

I'he structure is clogged.

The structure is damaged.

depth of greater than six inches.

Erosion has occurred.

Weeds are present.

Water is ponding on the surface

for more than 24 hours after a

Clogging has occurred.

The outlet device is damaged.

Erosion or other signs of damage have occurred at the outlet.

will be available

upon request.

ljacent pavement (if applicable)

rimeter of sand filte

Flow diversion structure

orebay or pretreatment area

Filter bed and underdrain


llection system

utlet device


ceiving water


	THE DEVELOPER OR HIS AGENT SHALL CONTACT THE CITY OF RALEIGH WHEN THE
	BEST MANAGEMENT PRACTICE(S) ARE CONSTRUCTED AND ABOUT TO BECOME
	OPERATIONAL SO A FINAL INSPECTION CAN BE PERFORMED TO DETERMINE
	COMPLIANCE WITH THE APPROVED PLAN CAN BE PERFORMED.
2.	ANNUAL MAINTENANCE INSPECTION AND REPORT REQUIRED - THE OWNER OF A
	PERMITTED STRUCTURAL STORMWATER BMP/CONTROL SHALL ANNUALLY SUBMIT A
	MAINTENANCE AND INSPECTION REPORT FOR EACH BMP TO THE STORMWATER
	ADMINISTRATOR. ANNUAL INSPECTIONS SHALL BEGIN WITHIN ONE YEAR OF THE
	RECORDATION OF ANY DEED(8) SHOWING STORMWATER BMPs/CONTROL STRUCTURES.
3.	UPON COMPLETION OF THE PROJECT, AND BEFORE A CERTIFICATE OF OCCUPANCY
	SHALL BE GRANTED, THE ENGINEER OF RECORD SHALL CERTIFY THAT THE
	COMPLETED PROJECT IS IN ACCORDANCE WITH THE APPROVED STORMWATER
	MANAGEMENT PLANS AND DESIGNS.
4.	A FINAL INSPECTION OF THE SITE AND STORMWATER MANAGEMENT BMP/CONTROLS
	TO BE SCHEDULED WITH AND COMPLETED BY THE CITY OF RALEIGH INSPECTOR.
5.	THE "AS-BUILT" PLANS SHALL SHOW THE FINAL DESIGN SPECIFICATIONS FOR ALL
	STORNWATER MANAGEMENT FACILITIES AND PRACTICES AND THE FIELD LOCATION,
	SIZE, DEPTH, AND PLANTED VEGETATION OF ALL MEASURES, CONTROLS AND DEVICES,
	AS INSTALLED. THE ENGINEER OF RECORD FOR THE STORMWATER MANAGEMENT
	MEASURES AND PLANS SHALL CERTIFY, UNDER SEAL, THAT THE AS-BUILT
	STORMWATER MEASURES, CONTROLS AND DEVICES ARE IN COMPLIANCE WITH THE
	APPROVED STORMWATER MANAGEMENT PLANS AND DESIGNS AND WITH THE
	REQUIREMENTS OF THIS ORDINANCE.
6.	THE CITY OF RALEIGH AND THEIR ASSIGNS HAVE RIGHT TO ACCESS THE STORMWATER
	CONTROL(s) FOR INSPECTIONS OR MAINTENANCE AS NECESSARY.
<i>7.</i>	THE ENGINEER'S CERTIFICATION OF COMPLETION WILL BE REQUIRED PRIOR TO THE
	FINAL PLAT OR CERTIFICATE OF OCCUPANCY. THE STORMWATER CONTROL IS TO BE
	INSPECTED TO ENSURE IT IS FUNCTIONING AS DESIGNED AND HAS FULL DESIGN
	VOLUME PRIOR TO ISSUANCE OF THE FINAL CERTIFICATE OF OCCUPANCY.
8.	THE PROPERTY OWNER (OR HOMEOWNER'S ASSOCIATION) IS RESPONSIBLE FOR
	MAINTAINING THE STORMWATER CONTROLS(s) ACCORDING TO THE APPROVED
	MAINTENANCE PLAN AND DIRECTION OF THE CITY OF RALEIGH.


RIVER BASIN:	CAPE FEAR				
RECEIVING STREAM:	CAMELS CREEK				
STREAM INDEX:	18-12-(2)				
STREAM CLASS:	WS-IV				
HUC:	0303000401	06 000			
PROJECT COORDINATES:	35.419673°N, -78.935	869°W			
POND DESIGN SUMMAR	Y			_	
DRAINAGE AREA TO POND:					
SITE IMPERVIOUS AREA TO POND					
OFF-SITE DESIGN IMPERVIOUS AF	•				
TOTAL DESIGN IMPERVIOUS ARE:	VIOTONII.	0.92 ACRES			
	PRE-DEVELOPED	POST-DEVELOPED	POST DEVELOPED	POST DEVELOPED	TOTAL
			THROUGH BMP	BYPASS	
	1.54 AC	1.41 AC		0.13 AC	
DRAINAGE AREA:		90.6		77-0	
DRAINAGE AREA: CURVE NUMBER:	78-3	70-0			
CURVE NUMBER:	7 8 -3	30-0			
	78.3	0.392 CFS	0.182 CFS		
CURVE NUMBER: TIME OF CONCENTRATION	78.3 2.573 CFS		0.182 CFS 2.327 CFS	0.200 CFS	2.527 CF8
CURYE NUMBER: TIME OF CONCENTRATION I" STORM EVENT:	, -	0.392 CFS		0.200 CFS 0.288 CFS	2.527 CFS 3.501 CFS
CURVE NUMBER: TIME OF CONCENTRATION 1" STORM EVENT: 1-YEAR STORM EVENT:	2,573 CFS	0.392 CFS 4.746 CFS	2.327 CFS		



STAGE (FT)	ELEVATION (FT)	CONTOUR AREA (SF)	INCREMENTAL STORAGE (CF)	TOTAL STORAGE (CF)
0.0	330.0	N/A	0	0
1.0	331.0	N/A	1413	1413
2.0	332.0	N/ A	2127	3540
3.0	333.0	N /A	1929	5469
3.5	333-5	N/A	525	5994










RHETSON COMPANIES, INC 2075 JUNIPER LAKE ROAD

STORMWATER MANAGEMENT

DETAILS



CUNTECH'
ENGINEERED SOLUTIONS LLC

SFMH60

STORMFILTER


STANDARD DETAIL

SECTION A-A

The Stormwater Management StormFilter*

BMP element:	Potential problem:	How I will remediate the problem	
The entire BMP	Trash/debris is present,	Remove the trash/debris	
Adjacent pavement (if applicable)	Sediment is present on the pavement surface.	Sweep or vacuum the sediment as soon as possible.	
Perimeter of sand filter	Areas of bare soil and/or erosive gullies have formed.	Regrade soil if necessary to remove the gully, and then plant a ground cover and water until it is established. Provide lime and a one-time fertilizer application.	
	Vegetation is too short or too long.	Maintain vegetation at an appropriate height.	
Flow diversion structure	The structure is clogged.	Unclog the conveyance and dispose of any sediment offsite.	
	The structure is damaged.	Make any necessary repairs or replace if damage is too large for repair.	
Forebay or pretreatment area	Sediment has accumulated to a depth of greater than six inches.	Search for the source of the sediment and remedy the problem if possible. Remove the sediment and stabilize or dispose of it in a location where it will not cause impacts to streams or the BMP.	
	Erosion has occurred.	Provide additional erosion protection such as reinforced turf matting or riprap if needed to prevent future erosion problems.	
	Weeds are present.	Remove the weeds, preferably by hand. If a pesticide is used, wipe it on the plants rather than spraying.	
Filter bed and underdrain collection system	Water is ponding on the surface for more than 24 hours after a storm.	Check to see if the collector system is clogged and flush if necessary. If water still ponds, remove the top few inches of filter bed media and replace. If water still ponds, then consult an expert.	
Outlet device	Clogging has occurred.	Clean out the outlet device. Dispose of the sediment offsite.	
	The outlet device is damaged.	Repair or replace the outlet device.	
Receiving water	Erosion or other signs of damage have occurred at the outlet.	Contact the NC Division of Water Resources.	

Bowma



2075 JUNIPER LAKE ROAD WEST END, NC 27376 (910) 944-0881 john@rhetson.com




US Highway 421 N gton, NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be


without liability to Bowman North

Carolina, Ltd.



Checked Rhetson Project# 21103 Project No. 058004 Initial Date February 28, 2022

STORMWATER MANAGEMENT **DETAILS**



OWNER/DEVELOPER: RHETSON COMPANIES, INC ATTN. JOHN PARKER 2075 JUNIPER LAKE ROAD WEST END, NC 27376 ohn@rhetson.com

US Highway 421 N ston, NC Harnett County

This document, together with the concepts and designs presented herein, as an instrument of services, is intended only for the specific purpose and client for which it was prepared. Reuse of and improper reliance on this document without written authorization and adaptation by Bowman North Carolina, Ltd. shall be

Rhetson Project# Initial Date February 28, 2022

LANDSCAPE

#23680-US 421 N. Harnett Coun<mark>t</mark>