ENGINEERING BY
TRENCO
A MiTek Affiliate

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: 22020129
DRB - 106 FARM AT NEILLS CREEK

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Carter Components (Sanford, NC)).

Pages or sheets covered by this seal: I51868717 thru I51868749

My license renewal date for the state of North Carolina is December 31, 2022.

North Carolina COA: C-0844

May 11,2022

Johnson, Andrew

IMPORTANT NOTE: The seal on these truss component designs is a certification that the engineer named is licensed in the jurisdiction(s) identified and that the designs comply with ANSI/TPI 1. These designs are based upon parameters shown (e.g., loads, supports, dimensions, shapes and design codes), which were given to MiTek or TRENCO. Any project specific information included is for MiTek's or TRENCO's customers file reference purpose only, and was not taken into account in the preparation of these designs. MiTek or TRENCO has not independently verified the applicability of the design parameters or the designs for any particular building. Before use, the building designer should verify applicability of design parameters and properly incorporate these designs into the overall building design per ANSI/TPI 1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK I51868717
22020129	A01	Piggyback Base	6	1	Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:40 Page: 1
ID:vmWSYKxMeSKeeaoGnh3QrczhvSE-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:97.2

Plate Offsets (X, Y): [10:0-5-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.68	Vert(LL)	-0.17	22-23	>861	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.62	Vert(CT)	-0.35	22-23	>422	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.62	Horz(CT)	0.04	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 476 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3 *Except* 18-6,18-8,16-8,16-9,20-4,20-5,24-25:2x4 SP No.2
SLIDER Right 2x6 SP No.2 -- 1-6-0

BRACING
TOP CHORD Structural wood sheathing directly applied or 4-8-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-9.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 22-23,20-22.
WEBS 1 Row at midpt 3-22, 6-18, 8-18, 10-16, 4-20, 5-20, 24-25

REACTIONS (lb/size) 13=1060/0-3-8, 18=1697/0-3-8, 22=1647/0-3-8, 23=258/0-3-8
Max Horiz 23=263 (LC 11)
Max Uplift 13=-103 (LC 15), 18=-73 (LC 10), 22=-73 (LC 14), 23=-87 (LC 10)
Max Grav 13=1266 (LC 52), 18=1961 (LC 6), 22=1874 (LC 34), 23=419 (LC 43)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-177/92, 2-3=-42/484, 3-4=-346/158, 4-5=-199/182, 5-6=-302/218, 6-8=-157/176, 8-9=-673/331, 9-11=-1587/350, 11-13=-1745/332, 1-23=-313/130
BOT CHORD 22-23=-264/121, 20-22=-386/203, 19-20=-109/380, 18-19=-109/380, 16-18=-55/487, 14-16=-56/1141, 13-14=-183/1417
WEBS 2-22=-394/225, 3-22=-1369/168, 6-25=-521/143, 18-25=-533/130, 8-18=-1042/321, 8-16=-154/951, 9-16=0/192, 10-16=-825/247, 10-14=-42/531, 11-14=-240/191, 2-23=-37/313, 3-20=0/863, 4-20=-244/60, 20-24=-346/116, 5-24=-334/129, 24-26=-6/8, 25-26=-6/8, 19-26=0/45

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 5-7-0 to 11-2-2, Interior (1) 11-2-2 to 17-5-0, Exterior(2R) 17-5-0 to 28-7-3, Interior (1) 28-7-3 to 38-0-0, Exterior(2R) 38-0-0 to 49-5-6, Interior (1) 49-5-6 to 55-9-2, Exterior(2E) 55-9-2 to 61-4-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) 200.0lb AC unit load placed on the bottom chord, 23-8-8 from left end, supported at two points, 5-0-0 apart.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 22, 18, 23, and 13. This connection is for uplift only and does not consider lateral forces.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
11) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	A02	Piggyback Base	1	1	I51868718 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:42 Page: 1
ID:vmWSYKxMeSKeeaoGnh3QrczhvSE-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:98.5

Plate Offsets (X, Y): [4:0-3-12,0-3-12], [8:0-3-12,0-3-0], [18:0-3-4,0-4-8], [19:0-5-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.55	Vert(LL)	-0.16	15-17	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.55	Vert(CT)	-0.23	15-17	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.91	Horz(CT)	0.02	13	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 467 lb	FT = 20%

LUMBER

TOP CHORD	2x6 SP No.2
BOT CHORD	2x6 SP 2400F 2.0E *Except* 19-18:2x6 SP No.2
WEBS	2x4 SP No.3 *Except* 17-7,17-8,18-7,19-4,18-4,18-5,15-8:2x4 SP No.2
SLIDER	Right 2x6 SP No.2 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-1-1 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 4-8.
BOT CHORD	Rigid ceiling directly applied or 6-0-0 oc bracing.
WEBS	1 Row at midpt 8-17, 3-19, 4-18, 5-18
WEBS	2 Rows at 1/3 pts 7-17

REACTIONS (lb/size) 13=758/0-3-8, 17=2798/0-3-8, 21=1158/0-3-8
Max Horiz 21=259 (LC 13)
Max Uplift 13=-133 (LC 15), 21=-34 (LC 14)
Max Grav 13=943 (LC 53), 17=3220 (LC 3), 21=1331 (LC 60)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-1707/177, 2-3=-1950/320, 3-4=-1374/217, 4-5=-499/196, 5-7=-499/196, 7-8=0/615, 8-10=-884/360, 10-11=-836/197, 11-13=-1125/244, 13-14=0/26, 1-21=-1239/181
BOT CHORD	20-21=-236/202, 17-20=-679/1352, 15-17=-89/199, 13-15=-82/901
WEBS	1-20=-58/1668, 7-17=-1881/285, 8-17=-1252/249, 7-18=-119/1701, 2-20=-694/259, 3-20=-172/568, 3-19=-704/280, 4-19=0/1170, 4-18=-986/83, 5-18=-593/193, 10-15=-654/252, 8-15=-236/1351, 11-15=-343/198

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 5-7-0 to 11-2-2, Interior (1) 11-2-2 to 17-5-0, Exterior(2R) 17-5-0 to 28-7-3, Interior (1) 28-7-3 to 38-2-5, Exterior(2R) 38-2-5 to 49-6-8, Interior (1) 49-6-8 to 56-7-10, Exterior(2E) 56-7-10 to 62-2-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) 200.0lb AC unit load placed on the bottom chord, 18-3-8 from left end, supported at two points, 5-0-0 apart.
7) Provide adequate drainage to prevent water ponding.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 21 and 13. This connection is for uplift only and does not consider lateral forces.
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868719
22020129	A03	Piggyback Base Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:43 Page: 1
ID:ACS0SGCfmETEfJzgbpcWMMzhrbI-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:97.2

Plate Offsets (X, Y): [11:0-3-0,0-3-12], [24:0-3-0,0-3-12], [27:0-2-1,Edge], [43:0-5-0,0-4-8], [47:0-4-0,0-1-4], [56:0-5-0,0-4-8]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.29	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.07	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.22	Horiz(TL)	-0.01	35	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 587 lb	FT = 20%

LUMBER
TOP CHORD 2x6 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3 *Except*
55-12,54-13,53-14,52-15,51-16,50-17,49-19,
47-20,46-21,45-22,44-23:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 11-24.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 9-57, 10-56, 12-55, 13-54, 14-53, 15-52, 16-51, 17-50, 19-49, 20-47, 21-46, 22-45, 23-44, 25-43, 26-42

REACTIONS (lb/size) 35=58/55-11-0, 36=159/55-11-0, 37=155/55-11-0, 38=155/55-11-0, 39=155/55-11-0, 40=155/55-11-0, 41=155/55-11-0, 42=156/55-11-0, 43=154/55-11-0, 44=153/55-11-0, 45=155/55-11-0, 46=155/55-11-0, 47=155/55-11-0, 49=155/55-11-0, 50=155/55-11-0, 51=155/55-11-0, 52=155/55-11-0, 53=155/55-11-0, 54=154/55-11-0, 55=155/55-11-0, 56=154/55-11-0, 57=154/55-11-0, 58=155/55-11-0, 59=155/55-11-0, 60=155/55-11-0, 61=157/55-11-0, 62=154/55-11-0, 63=159/55-11-0, 64=63/55-11-0
Max Horiz 64=266 (LC 11)
Max Uplift 35=-212 (LC 11), 36=-158 (LC 15), 37=-28 (LC 15), 38=-53 (LC 15), 39=-48 (LC 15), 40=-49 (LC 15), 41=-49 (LC 15), 42=-57 (LC 15), 43=-18 (LC 15), 45=-23 (LC 10), 46=-29 (LC 11), 47=-25 (LC 11), 49=-25 (LC 10), 50=-25 (LC 10), 51=-24 (LC 10), 52=-25 (LC 11), 53=-28 (LC 11), 54=-26 (LC 10), 57=-61 (LC 14), 58=-49 (LC 14), 59=-48 (LC 14), 60=-51 (LC 14), 61=-46 (LC 14), 62=-43 (LC 10), 63=-77 (LC 11), 64=-39 (LC 10)
Max Grav 35=182 (LC 12), 36=277 (LC 24), 37=155 (LC 40), 38=166 (LC 24), 39=219 (LC 46), 40=236 (LC 46), 41=234 (LC 46), 42=238 (LC 46), 43=228 (LC 46), 44=189 (LC 53), 45=218 (LC 39), 46=218 (LC 39), 47=211 (LC 39), 49=190 (LC 20), 50=176 (LC 20), 51=189 (LC 21), 52=210 (LC 39), 53=218 (LC 39), 54=218 (LC 39), 55=181 (LC 53), 56=226 (LC 42), 57=237 (LC 42), 58=234 (LC 42), 59=236 (LC 42), 60=219 (LC 42), 61=186 (LC 43), 62=219 (LC 43), 63=222 (LC 43), 64=90 (LC 24)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 1-64=-69/31, 1-2=-52/43, 2-3=-47/60, 3-4=-56/82, 4-5=-69/108, 5-6=-68/119, 6-7=-95/167, 7-8=-113/211, 8-9=-132/273, 9-10=-155/356, 10-11=-162/398, 11-12=-150/384, 12-13=-150/384, 13-14=-150/384, 14-15=-150/384, 15-16=-150/384, 16-17=-150/384, 17-19=-150/384, 19-20=-150/384, 20-21=-150/384, 21-22=-150/384, 22-23=-150/384, 23-24=-150/384, 24-25=-163/400, 25-26=-154/352, 26-28=-132/270, 28-29=-113/224, 29-30=-113/217, 30-31=-127/220, 31-32=-140/224, 32-33=-150/223, 33-34=-194/267, 34-35=-125/158

May 11,2022

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

BOT CHORD 63-64=-223/163, 62-63=-223/163, 61-62=-223/163, 60-61=-223/163, 59-60=-223/163, 58-59=-223/163, 57-58=-223/163, 55-57=-223/163, 54-55=-223/163, 53-54=-223/163, 52-53=-223/163, 51-52=-223/163, 50-51=-223/163, 49-50=-223/163, 47-49=-223/163, 46-47=-223/163, 45-46=-223/163, 44-45=-223/163, 42-44=-223/163, 41-42=-223/163, 40-41=-223/163, 39-40=-223/163, 38-39=-223/163, 37-38=-223/163, 36-37=-223/163, 35-36=-223/163

WEBS 2-63=-182/80, 3-62=-181/60, 4-61=-147/74, 6-60=-180/75, 7-59=-198/71, 8-58=-195/99, 9-57=-199/143, 10-56=-187/63, 12-55=-141/9, 13-54=-179/81, 14-53=-179/90, 15-52=-172/54, 16-51=-151/48, 17-50=-138/48, 19-49=-151/48, 20-47=-172/55, 21-46=-179/92, 22-45=-179/78, 23-44=-150/21, 25-43=-189/72, 26-42=-199/142, 28-41=-195/99, 29-40=-197/72, 30-39=-180/72, 31-38=-123/73, 32-37=-116/65, 33-36=-176/123

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 5-7-0 to 11-5-4, Exterior(2N) 11-5-4 to 17-5-0, Corner(3R) 17-5-0 to 28-7-3, Exterior (2N) 28-7-3 to 38-2-5, Corner(3R) 38-2-5 to 49-5-4, Exterior(2N) 49-5-4 to 55-5-4, Corner(3E) 55-5-4 to 61-2-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) Provide adequate drainage to prevent water ponding.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
10) Gable studs spaced at 2-0-0 oc.
11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
13) N/A
14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
15) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	B01	Piggyback Base	3	1	I51868720 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:44 Page: 1
ID:peT4yLyq7XKivZjUGqMG5_zHvYw-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:89.9

Plate Offsets (X, Y): [7:0-3-12,0-3-0], [16:0-1-2,0-6-7]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.47	Vert(LL)	-0.35	14-16	>826	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.84	Vert(CT)	-0.53	14-16	>541	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.89	Horz(CT)	0.03	12	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 465 lb	FT = 20%

LUMBER

TOP CHORD	2x6 SP No.2
BOT CHORD	2x6 SP No.2
WEBS	2x4 SP No.2 *Except* 21-1,21-2,2-20,14-9,14-10:2x4 SP No.3
OTHERS	2x6 SP No.2
SLIDER	Right 2x6 SP No.2 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-3-2 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 3-7.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing, Except: 8-6-8 oc bracing: 14-16.
WEBS	1 Row at midpt 7-16, 2-21, 3-18, 4-17, 5-22

REACTIONS (lb/size) 12=982/0-3-8, 21=1038/0-3-8, 22=2079/0-3-8
Max Horiz 21=-306 (LC 12)
Max Uplift 12=-243 (LC 15), 21=-180 (LC 14), 22=-94 (LC 11)
Max Grav 12=1248 (LC 49), 21=1379 (LC 35), 22=2471 (LC 44)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-167/147, 2-3=-1193/319, 3-4=-700/294, 4-29=-146/367, 5-29=-136/367, 5-30=-136/367, 7-30=-144/371, 7-9=-1448/518, 9-10=-1345/359, 10-12=-1575/392, 12-13=0/26, 1-21=-217/100
BOT CHORD	20-21=-161/962, 18-20=-120/768, 17-18=-99/622, 14-16=-6/439, 12-14=-229/1258
WEBS	7-16=-951/58, 2-21=-1363/186, 3-20=-54/549, 3-18=-333/73, 4-18=0/758, 4-17=-1176/166, 2-20=-204/287, 9-14=-644/245, 7-14=-191/1386, 10-14=-263/164, 5-22=-1383/18, 17-22=-99/1142, 22-29=-99/1142, 16-22=0/1045, 22-30=0/1045

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 5-1-12 to 10-2-14, Exterior (2R) 10-2-14 to 24-6-7, Interior (1) 24-6-7 to 31-1-12, Exterior(2R) 31-1-12 to 45-6-9, Interior (1) 45-6-9 to 51-8-6, Exterior(2E) 51-8-6 to 56-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) All plates are 4x5 MT20 unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
10) Bearing at joint(s) 22 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 21, 12, and 22. This connection is for uplift only and does not consider lateral forces.
12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	C01	Piggyback Base	3	1	I51868721 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:45

ID:wEsxu2PHLUbbwrpGGIKVTFzhpmq-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:78.4

Plate Offsets (X, Y): [4:0-5-0,0-4-8], [7:0-4-8,0-2-0], [8:0-5-0,0-4-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.62	Vert(LL)	-0.26	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.79	Vert(CT)	-0.40	7-8	>717	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.72	Horz(CT)	-0.05	10	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 199 lb	FT = 20%

LUMBER

TOP CHORD	2x6 SP No.2
BOT CHORD	2x6 SP No.2
WEBS	2x4 SP No.2 *Except* 4-8:2x4 SP No.3
OTHERS	2x4 SP No.3
SLIDER	Left 2x6 SP No.2 -- 1-6-0

BRACING

TOP CHORD	Structural wood sheathing directly applied or 5-8-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 5-6.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS	1 Row at midpt 6-7, 5-7

REACTIONS (lb/size) 2=1004/0-3-8, 10=950/0-3-8
Max Horiz 2=396 (LC 13)
Max Uplift 2=-107 (LC 14), 10=-140 (LC 11)
Max Grav 2=1246 (LC 40), 10=1116 (LC 24)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=0/26, 2-5=-1500/232, 5-6=-159/164, 7-10=-90/1109, 6-10=-263/87
BOT CHORD	2-7=-311/1366
WEBS	5-8=-164/1246, 5-7=-1011/183, 4-8=-597/313

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-6-5, Interior (1) 2-6-5 to 14-2-1, Exterior(2R) 14-2-1 to 20-11-11, Interior (1) 20-11-11 to 23-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
10) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 10. This connection is for uplift only and does not consider lateral forces.
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	D01	Monopitch	7	1	I51868722 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:45 Page: 1
ID:fgJGN1CBxSiq8LzfII_gKzzhpjD-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:54.9

Plate Offsets (X, Y): [2:0-2-14,0-2-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.61	Vert(LL)	-0.03	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.34	Vert(CT)	-0.05	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.51	Horz(CT)	0.01	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 77 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 4-7

REACTIONS (lb/size) 7=481/ Mechanical, 9=525/0-3-8
Max Horiz 9=288 (LC 11)
Max Uplift 7=-126 (LC 14), 9=-43 (LC 14)
Max Grav 7=634 (LC 21), 9=561 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/31, 2-3=-559/107, 3-4=-186/106, 4-5=-13/0, 4-7=-264/64, 2-9=-508/151
BOT CHORD 8-9=-277/261, 7-8=-101/419, 6-7=0/0
WEBS 3-8=0/233, 3-7=-510/172, 2-8=0/318

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 8-11-8, Exterior(2E) 8-11-8 to 11-11-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) Refer to girder(s) for truss to truss connections.
8) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 126 lb uplift at joint 7.
9) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 9. This connection is for uplift only and does not consider lateral forces.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	D02	Monopitch Supported Gable	1	1	I51868723 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:46 Page: 1
ID:YRYnCOFh?hCFcyHRX82cVpzhpj9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:54.9

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.69	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.20	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.17	Horz(CT)	-0.04	9	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 84 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.
WEBS 1 Row at midpt 8-10

REACTIONS (lb/size) 9=12/11-11-8, 10=57/11-11-8, 11=156/11-11-8, 12=156/11-11-8, 13=154/11-11-8, 14=158/11-11-8, 15=141/11-11-8, 16=135/11-11-8
Max Horiz 16=280 (LC 11)
Max Uplift 9=-82 (LC 14), 10=-146 (LC 13), 11=-53 (LC 14), 12=-46 (LC 14), 13=-58 (LC 14), 14=-14 (LC 14), 15=-199 (LC 14), 16=-96 (LC 10)
Max Grav 9=93 (LC 13), 10=144 (LC 10), 11=232 (LC 21), 12=223 (LC 21), 13=165 (LC 24), 14=158 (LC 1), 15=237 (LC 24), 16=256 (LC 29)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-16=-199/75, 1-2=0/30, 2-3=-259/166, 3-4=-184/120, 4-5=-170/109, 5-6=-154/98, 6-7=-145/99, 7-8=-109/117, 8-9=-87/66, 8-10=-145/105
BOT CHORD 15-16=-115/144, 14-15=-115/144, 13-14=-115/144, 12-13=-115/144, 11-12=-115/144, 10-11=-115/144
WEBS 5-13=-124/105, 4-14=-119/83, 3-15=-157/205, 6-12=-185/118, 7-11=-193/57

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 1-11-12, Exterior (2N) 1-11-12 to 11-11-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) All plates are 2x4 MT20 unless otherwise indicated.
7) Gable requires continuous bottom chord bearing.
8) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
9) Gable studs spaced at 2-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 96 lb uplift at joint 16, 82 lb uplift at joint 9, 146 lb uplift at joint 10, 58 lb uplift at joint 13, 14 lb uplift at joint 14, 199 lb uplift at joint 15, 46 lb uplift at joint 12 and 53 lb uplift at joint 11.
13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	E01	Roof Special	7	1	I51868724 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:46 Page: 1
ID:0AA0YMgemRcHJKS94?AqQBzhpic-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:66.9

Plate Offsets (X, Y): [1:0-3-0,0-1-8], [9:0-6-0,0-2-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.80	Vert(LL)	-0.35	8-9	>746	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	1.00	Vert(CT)	-0.67	8-9	>388	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.92	Horz(CT)	0.37	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 129 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2 *Except* 1-3:2x4 SP 2400F 2.0E
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 9-1,9-3:2x4 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-2-2 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 1-4-12 oc bracing.
WEBS 1 Row at midpt 4-6

REACTIONS (lb/size) 6=870/0-3-8, 10=870/0-3-8
Max Horiz 10=276 (LC 11)
Max Uplift 6=-102 (LC 14), 10=-81 (LC 14)
Max Grav 6=1023 (LC 23), 10=990 (LC 23)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-10=-1134/253, 1-2=-4869/845, 2-4=-4834/982, 4-5=-194/148, 5-6=-287/117
BOT CHORD 9-10=-326/550, 8-9=-287/1632, 6-8=-36/682
WEBS 1-9=-648/4077, 2-9=-209/179, 3-9=-759/3387, 3-8=-906/313, 4-8=-122/1087, 4-6=-986/107

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 13-0-0, Exterior(2R) 13-0-0 to 18-10-12, Exterior(2E) 18-10-12 to 21-10-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
7) Bearing at joint(s) 10 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 10 and 6. This connection is for uplift only and does not consider lateral forces.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	E02	Roof Special Supported Gable	1	1	I51868725 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:46 Page: 1
ID:rgAQfUnjKO4NkJvevcJ9cNzhphB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:66.7

Plate Offsets (X, Y): [6:0-1-12,0-2-4]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.30	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.19	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.14	Horiz(TL)	0.00	14	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 132 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing, Except:
6-0-0 oc bracing: 24-25.

REACTIONS (lb/size) 14=64/22-0-8, 15=161/22-0-8, 16=160/22-0-8, 18=142/22-0-8, 19=161/22-0-8, 20=154/22-0-8, 21=155/22-0-8, 22=156/22-0-8, 23=149/22-0-8, 24=8/22-0-8, 25=151/22-0-8, 26=166/22-0-8, 27=57/22-0-8
Max Horiz 27=267 (LC 11)
Max Uplift 14=-50 (LC 14), 15=-41 (LC 15), 16=-52 (LC 15), 18=-10 (LC 13), 19=-49 (LC 14), 20=-50 (LC 14), 21=-49 (LC 14), 22=-47 (LC 14), 23=-53 (LC 14), 24=-32 (LC 13), 25=-4 (LC 14), 26=-230 (LC 14), 27=-183 (LC 12)
Max Grav 14=68 (LC 21), 15=227 (LC 21), 16=243 (LC 21), 18=161 (LC 27), 19=245 (LC 20), 20=219 (LC 20), 21=162 (LC 23), 22=161 (LC 23), 23=155 (LC 23), 24=34 (LC 10), 25=151 (LC 1), 26=282 (LC 23), 27=292 (LC 11)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-27=-185/123, 1-2=-276/217, 2-3=-203/162, 3-4=-186/153, 4-5=-164/134, 5-6=-151/130, 6-8=-137/126, 8-9=-124/131, 9-10=-137/174, 10-11=-137/174, 11-12=-110/130, 12-13=-87/98, 13-14=-80/70
BOT CHORD 26-27=-100/77, 25-26=-67/70, 24-25=-73/60, 23-24=-53/51, 22-23=-53/51, 21-22=-53/51, 20-21=-53/51, 19-20=-53/51, 18-19=-53/51, 16-18=-53/51, 15-16=-53/51, 14-15=-53/51
WEBS 10-18=-123/52, 9-19=-206/72, 8-20=-180/73, 6-21=-123/72, 5-22=-121/71, 4-23=-126/78, 3-25=-115/51, 2-26=-183/163, 11-16=-205/72, 12-15=-187/78

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Interior (1) 3-1-12 to 13-0-0, Exterior(2R) 13-0-0 to 18-10-12, Exterior(2E) 18-10-12 to 21-10-12 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) All plates are 2x4 MT20 unless otherwise indicated.
7) Gable requires continuous bottom chord bearing.
8) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
9) Gable studs spaced at 2-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 24, 4 lb uplift at joint 25 and 230 lb uplift at joint 26.
13) N/A
14) Beveled plate or shim required to provide full bearing surface with truss chord at joint(s) 24, 14, 18, 19, 20, 21, 22, 23, 25, 26, 16, 15.

May 11,2022

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

15) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868726
22020129	F01	Common	3	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:46
ID:83UDOfsHl8rKoauzUUuAOszHwvY-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:52.5

Plate Offsets (X, Y): [1:Edge,0-1-12]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.04	5-6	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.28	Vert(CT)	-0.08	5-6	>951	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.32	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 73 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=143/0-3-8, 5=395/0-3-8, 6=246/0-3-8
Max Horiz 6=221 (LC 11)
Max Uplift 4=-47 (LC 15), 5=-19 (LC 14), 6=-32 (LC 14)
Max Grav 4=207 (LC 21), 5=410 (LC 20), 6=312 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-164/100, 2-3=-104/116, 1-6=-254/85, 3-4=-186/54
BOT CHORD	5-6=-196/188, 4-5=-74/82
WEBS	2-5=-328/61, 1-5=-115/114, 3-5=-108/108

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Exterior (2R) 3-1-12 to 6-11-4, Exterior(2E) 6-11-4 to 9-11-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6, 4, and 5. This connection is for uplift only and does not consider lateral forces.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	G01	Attic	3	1	I51868727 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:47

ID:wN9MV2a7ngO0fSyKmTVeHIzhpg9-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:84.4

Plate Offsets (X, Y): [3:0-3-8,0-2-4], [5:0-3-12,0-2-12], [6:0-3-12,0-2-12], [14:0-3-4,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.23	18-19	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.38	18-19	>624	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.06	10	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.20	12-26	>795	360		
BCDL	10.0										Weight: 239 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2 *Except* 27-14:2x4 SP No.1
WEBS 2x4 SP No.3 *Except* 3-25,8-11,4-7:2x4 SP No.2, 3-4,7-8:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-10-14 max.): 5-6.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except:
2-10-0 oc bracing: 16-21
3-9-0 oc bracing: 21-24
3-11-0 oc bracing: 13-16
10-0-0 oc bracing: 24-26, 12-13
WEBS 1 Row at midpt 8-10, 3-27
JOINTS 1 Brace at Jt(s): 13, 24, 16, 21, 28

REACTIONS (lb/size) 10=1138/0-3-8, 27=1189/0-3-8
Max Horiz 27=358 (LC 13)
Max Grav 10=1500 (LC 46), 27=1572 (LC 46)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/52, 2-3=-314/273, 3-4=-660/148, 4-5=-1003/346, 5-6=-983/117, 6-7=-973/339, 7-8=-661/162, 8-9=-291/232, 2-27=-467/254, 9-10=-358/238
BOT CHORD 25-27=-91/548, 22-25=-5/1654, 20-22=0/3362, 17-20=0/3867, 11-17=0/3346, 10-11=-71/532, 24-26=-95/227, 23-24=-2165/0, 21-23=-2165/0, 19-21=-3446/0, 18-19=-3446/0, 16-18=-3446/0, 15-16=-2115/0, 13-15=-2086/0, 12-13=-105/245
WEBS 25-26=0/858, 3-26=0/1025, 11-12=0/854, 8-12=0/1031, 8-10=-1624/81, 4-28=-502/547, 7-28=-539/493, 3-27=-1608/59, 11-13=-1440/0, 24-25=-1459/0, 13-14=0/1093, 22-24=0/1125, 14-15=-192/0, 22-23=-160/0, 14-16=-893/0, 21-22=-867/0, 16-17=-15/617, 20-21=0/590, 17-18=-204/0, 19-20=-197/0, 6-28=-212/410, 5-28=-188/407

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-8-5 to 2-3-11, Exterior(2R) 2-3-11 to 16-7-4, Exterior(2E) 16-7-4 to 19-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Provide adequate drainage to prevent water ponding.
7) All plates are 3x5 MT20 unless otherwise indicated.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Ceiling dead load (5.0 psf) on member(s). 3-4, 7-8, 4-28, 7-28; Wall dead load (5.0psf) on member(s).3-26, 8-12
11) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 24-26, 23-24, 21-23, 19-21, 18-19, 16-18, 15-16, 13-15, 12-13
12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
13) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
14) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	G02	Attic	6	1	I51868728 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:48 Page: 1

ID:PwMtYSc3X5EpzgXspX1pmRzhpep-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:82.3

Plate Offsets (X, Y): [4:0-3-12,0-2-12], [5:0-3-12,0-2-12], [13:0-3-4,0-3-0]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.73	Vert(LL)	-0.23	17-18	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.96	Vert(CT)	-0.38	17-18	>623	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.79	Horz(CT)	0.06	9	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH		Attic	-0.20	11-25	>795	360		
BCDL	10.0										Weight: 237 lb	FT = 20%

LUMBER

TOP CHORD 2x6 SP No.2
BOT CHORD 2x4 SP No.2 *Except* 26-13:2x4 SP No.1
WEBS 2x4 SP No.3 *Except* 2-24,7-10,3-6:2x4 SP No.2, 2-3,6-7:2x6 SP No.2

BRACING

TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (4-10-14 max.): 4-5.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing. Except:
2-10-0 oc bracing: 15-20
3-9-0 oc bracing: 20-23
3-11-0 oc bracing: 12-15
10-0-0 oc bracing: 23-25, 11-12
WEBS 1 Row at midpt 7-9, 2-26
JOINTS 1 Brace at Jt(s): 12, 23, 15, 20, 27

REACTIONS (lb/size) 9=1139/0-3-8, 26=1138/0-3-8
Max Horiz 26=347 (LC 11)
Max Grav 9=1501 (LC 45), 26=1506 (LC 45)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-301/227, 2-3=-660/144, 3-4=-1003/343, 4-5=-982/118, 5-6=-972/342, 6-7=-662/147, 7-8=-288/234, 1-26=-382/233, 8-9=-352/241
BOT CHORD 24-26=-88/547, 21-24=0/1655, 19-21=0/3363, 16-19=0/3868, 10-16=0/3346, 9-10=-68/531, 23-25=-98/223, 22-23=-2166/0, 20-22=-2166/0, 18-20=-3446/0, 17-18=-3446/0, 15-17=-3446/0, 14-15=-2114/0, 12-14=-2085/0, 11-12=-101/246
WEBS 24-25=0/857, 2-25=0/1024, 10-11=0/854, 7-11=0/1031, 7-9=-1622/71, 3-27=-501/546, 6-27=-542/490, 2-26=-1592/70, 10-12=-1440/0, 23-24=-1459/0, 12-13=0/1093, 21-23=0/1125, 13-14=-192/0, 21-22=-160/0, 13-15=-894/0, 20-21=-867/0, 15-16=-10/618, 19-20=0/586, 16-17=-204/0, 18-19=-197/0, 4-27=-193/399, 5-27=-203/406

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-3-12, Exterior (2R) 3-3-12 to 16-7-4, Exterior(2E) 16-7-4 to 19-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Provide adequate drainage to prevent water ponding.
6) All plates are 3x5 MT20 unless otherwise indicated.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Ceiling dead load (5.0 psf) on member(s). 2-3, 6-7, 3-27, 6-27; Wall dead load (5.0psf) on member(s).2-25, 7-11
10) Bottom chord live load (40.0 psf) and additional bottom chord dead load (5.0 psf) applied only to room. 23-25, 22-23, 20-22, 18-20, 17-18, 15-17, 14-15, 12-14, 11-12
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
12) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
13) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	G03	Attic Supported Gable	1	1	I51868729 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:49 Page: 1

ID:mTC1KUi0mrxofallau1_zozhpVg-RfC?PsB7QHc3NSpqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:79.7

Plate Offsets (X, Y): [2:0-2-14,0-2-0], [6:0-3-4,0-2-12], [10:0-3-4,0-2-12], [14:0-2-0,0-1-12], [22:0-3-0,0-3-0]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.14	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.14	Horz(CT)	-0.01	15	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 237 lb	FT = 20%

LUMBER

TOP CHORD	2x6 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 5-11:2x4 SP No.2, 4-5,11-12:2x6 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals, and 2-0-0 oc purlins (6-0-0 max.): 6-10.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing. Except: 6-0-0 oc bracing: 18-33
WEBS	1 Row at midpt 4-34, 12-17
JOINTS	1 Brace at Jt(s): 37, 38, 39, 40, 41

REACTIONS (lb/size) 15=280/19-11-0, 16=84/19-11-0, 17=206/19-11-0, 20=73/19-11-0, 22=77/19-11-0, 24=77/19-11-0, 26=78/19-11-0, 28=77/19-11-0, 30=77/19-11-0, 32=71/19-11-0, 34=206/19-11-0, 35=103/19-11-0, 36=307/19-11-0

Max Horiz 36=329 (LC 13)

Max Uplift 15=-280 (LC 11), 16=-39 (LC 14), 17=-225 (LC 10), 34=-366 (LC 11), 35=-29 (LC 14), 36=-287 (LC 10)

Max Grav 15=407 (LC 47), 16=218 (LC 50), 17=321 (LC 50), 20=202 (LC 21), 22=238 (LC 21), 24=229 (LC 21), 26=234 (LC 21), 28=230 (LC 21), 30=239 (LC 21), 32=194 (LC 21), 34=425 (LC 48), 35=194 (LC 50), 36=430 (LC 49)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD 2-36=-393/274, 1-2=0/50, 2-3=-177/211, 3-4=-169/237, 4-5=-366/249, 5-6=-995/267, 6-7=-903/244, 7-8=-903/244, 8-9=-903/244, 9-10=-903/244, 10-11=-1002/267, 11-12=-370/249, 12-13=-176/230, 13-14=-179/193, 14-15=-370/264

BOT CHORD 35-36=-300/262, 34-35=-300/262, 32-34=-188/143, 30-32=-188/143, 28-30=-188/143, 26-28=-188/143, 24-26=-188/143, 20-24=-188/148, 17-20=-184/148, 16-17=-95/115, 15-16=-95/115, 31-33=-4/11, 29-31=-4/11, 27-29=-4/11, 25-27=-4/11, 23-25=-4/11, 21-23=-4/11, 19-21=-8/5, 18-19=-8/5

WEBS 3-37=-97/79, 31-32=-98/0, 29-30=-119/0, 27-28=-115/0, 25-26=-116/0, 23-24=-116/0, 21-22=-119/0, 19-20=-100/0, 16-38=-112/81, 5-42=-169/773, 40-42=-173/792, 39-40=-173/792, 39-41=-173/792, 41-43=-173/792, 11-43=-167/772, 33-34=-454/145, 4-33=-462/147, 17-18=-409/116, 12-18=-417/116, 8-39=-9/1, 7-40=-94/29, 9-41=-98/29, 2-37=-290/331, 34-37=-340/389, 17-38=-238/277, 14-38=-286/331, 35-37=-142/78, 13-38=-136/88, 6-42=-53/158, 10-43=-53/169

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-8-5 to 2-3-11, Exterior(2N) 2-3-11 to 2-10-8, Corner(3R) 2-10-8 to 8-10-8, Exterior (2N) 8-10-8 to 11-4-0, Corner(3R) 11-4-0 to 16-7-4, Corner(3E) 16-7-4 to 19-9-4 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.

May 11,2022

Continued on page 2

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Provide adequate drainage to prevent water ponding.
8) All plates are 2x4 MT20 unless otherwise indicated.
9) Gable requires continuous bottom chord bearing.
10) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
11) Gable studs spaced at 2-0-0 oc.
12) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
13) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
14) Ceiling dead load (5.0 psf) on member(s). 4-5, 11-12, 5-42, 40-42, 39-40, 39-41, 41-43, 11-43; Wall dead load (5.0psf) on member(s).33-34, 4-33, 17-18, 12-18
15) N/A

16) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
17) Graphical purlin representation does not depict the size or the orientation of the purlin along the top and/or bottom chord.
18) Attic room checked for L/360 deflection.

LOAD CASE(S) Standard

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868730
22020129	H01	Common	1	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:49
ID:odQRt_LKkd3VzU9QYSTuUUzhpTY-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:40.5

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.24	Vert(LL)	0.01	8-9	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	-0.01	8-9	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.28	Horz(CT)	0.00	8	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 58 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3 *Except* 10-2,8-6:2x6 SP No.2
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 8=347/0-3-8, 10=347/0-3-8
Max Horiz 10=-135 (LC 12)
Max Uplift 8=-36 (LC 15), 10=-36 (LC 14)
Max Grav 8=462 (LC 22), 10=462 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=0/53, 2-3=-289/266, 3-4=-204/303, 4-5=-204/303, 5-6=-289/266, 6-7=0/53, 2-10=-428/319, 6-8=-428/319
BOT CHORD	9-10=-120/133, 8-9=-19/61
WEBS	4-9=-252/105, 2-11=-44/126, 9-11=-49/126, 9-12=-52/126, 6-12=-46/126, 3-11=-55/34, 5-12=-55/34

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 1-10-8, Exterior (2R) 1-10-8 to 5-10-8, Exterior(2E) 5-10-8 to 8-7-8 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 10 and 8. This connection is for uplift only and does not consider lateral forces.
12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868731
22020129	H02	Common	3	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:50
ID:1RaY1JHdbHmaiJXEZ7Mx6jzhpSL-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:40.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.41	Vert(LL)	0.01	5-6	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.15	Vert(CT)	-0.01	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 49 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 5-3:2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=356/0-3-8, 7=279/0-3-8
Max Horiz 7=-134 (LC 10)
Max Uplift 5=-36 (LC 15), 7=-25 (LC 10)
Max Grav 5=436 (LC 22), 7=373 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-262/274, 2-3=-285/276, 3-4=0/42, 1-7=-347/280, 3-5=-408/324
BOT CHORD 6-7=-118/123, 5-6=-23/25
WEBS 2-6=-203/97, 1-6=-112/142, 3-6=-37/139

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-1-12 to 3-1-12, Exterior (2R) 3-1-12 to 5-4-4, Exterior(2E) 5-4-4 to 8-4-4 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 5. This connection is for uplift only and does not consider lateral forces.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	H03	Common	1	1	Job Reference (optional)	I51868732

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:50 Page: 1
ID:DqG8vucB?uIc3cgcC?sVEdzhpRv-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:40.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	0.01	5-6	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.15	Vert(CT)	-0.01	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 48 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 5-3:2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=345/0-3-8, 7=268/0-3-8
Max Horiz 7=-137 (LC 12)
Max Uplift 5=-35 (LC 15), 7=-29 (LC 10)
Max Grav 5=411 (LC 22), 7=353 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-239/267, 2-3=-264/259, 3-4=0/42, 1-7=-330/280, 3-5=-382/311
BOT CHORD 6-7=-117/124, 5-6=-23/25
WEBS 2-6=-193/87, 1-6=-112/134, 3-6=-37/129

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-5-0 to 3-7-4, Exterior(2R) 3-7-4 to 5-4-4, Exterior(2E) 5-4-4 to 8-4-4 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 7 and 5. This connection is for uplift only and does not consider lateral forces.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868733
22020129	H04	Common	2	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:50 Page: 1
ID:pX6RsgnziB3dlmII0x6npazhpRh-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:36.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	0.01	5-6	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(CT)	-0.01	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 44 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 4=255/0-3-8, 6=255/0-3-8
Max Horiz 6=-122 (LC 10)
Max Uplift 4=-28 (LC 11), 6=-28 (LC 10)
Max Grav 4=321 (LC 21), 6=321 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-213/235, 2-3=-213/235, 1-6=-296/248, 3-4=-296/248
BOT CHORD 5-6=-114/109, 4-5=-29/32
WEBS 2-5=-157/70, 1-5=-80/117, 3-5=-80/117

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6 and 4. This connection is for uplift only and does not consider lateral forces.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	J01	Monopitch	6	1	I51868734
					Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:50 Page: 1
ID:H_CEdq?GTjK3vX7m4jR0XNzhpRP-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.7

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.75	Vert(LL)	0.09	6-7	>714	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.35	Vert(CT)	0.08	6-7	>879	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 25 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3 *Except* 7-2:2x6 SP No.2

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 6=236/0-3-8, 7=292/0-3-8
Max Horiz 7=109 (LC 13)
Max Uplift 6=-92 (LC 10), 7=-116 (LC 10)
Max Grav 6=322 (LC 21), 7=395 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/28, 2-3=-177/130, 3-4=-8/0, 3-6=-239/164, 2-7=-362/276
BOT CHORD 6-7=-96/95, 5-6=0/0

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 3-0-0, Exterior(2E) 3-0-0 to 6-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
3) Unbalanced snow loads have been considered for this design.
4) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
7) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 6 and 7. This connection is for uplift only and does not consider lateral forces.
8) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	J02	Monopitch Girder	1	**2**	I51868735 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:51 ID:pKhjZ7PzisUOMc86V9WlNKzhpQu-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:33.1

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.48	Vert(LL)	-0.03	5-6	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.36	Vert(CT)	-0.04	5-6	>999	180		
TCDL	10.0	Rep Stress Incr	NO	WB	0.00	Horz(CT)	0.00	5	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 53 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x6 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 5-8-12 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 5=607/0-3-8, 6=533/0-3-8
Max Horiz 6=96 (LC 32)
Max Uplift 5=-109 (LC 8), 6=-87 (LC 8)
Max Grav 5=690 (LC 18), 6=607 (LC 18)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-231/32, 2-3=-7/0, 2-5=-225/73, 1-6=-256/64
BOT CHORD 5-6=-47/159, 4-5=0/0

NOTES
1) 2-ply truss to be connected together as follows:
Top chords connected with 10d (0.131"x3") nails as follows: 2x4 - 1 row at 0-9-0 oc.
Bottom chords connected with 10d (0.131"x3") nails as follows: 2x6 - 2 rows staggered at 0-9-0 oc.
2) All loads are considered equally applied to all plies, except if noted as front (F) or back (B) face in the LOAD CASE(S) section. Ply to ply connections have been provided to distribute only loads noted as (F) or (B), unless otherwise indicated.
3) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed; Lumber DOL=1.60 plate grip DOL=1.60
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 5 and 6. This connection is for uplift only and does not consider lateral forces.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
10) Use Simpson Strong-Tie LUS26 (4-10d Girder, 3-10d Truss, Single Ply Girder) or equivalent spaced at 2-0-0 oc max. starting at 2-0-0 from the left end to 4-0-0 to connect truss(es) to front face of bottom chord.
11) Fill all nail holes where hanger is in contact with lumber.

LOAD CASE(S) Standard
1) Dead + Snow (balanced): Lumber Increase=1.15, Plate Increase=1.15
Uniform Loads (lb/ft)
Vert: 1-2=-58, 2-3=-58, 4-6=-19
Concentrated Loads (lb)
Vert: 7=-354 (F), 8=-354 (F)

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	J03	Monopitch Supported Gable	1	1	Job Reference (optional)	I51868736

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:51
ID:TeQF4DYUtY?hoS3PCgkZsszhpQi-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:33.6

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.09	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.06	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 28 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 6=3/5-8-12, 7=69/5-8-12, 8=157/5-8-12, 9=142/5-8-12, 10=138/5-8-12
Max Horiz 10=106 (LC 11)
Max Uplift 6=-28 (LC 10), 7=-22 (LC 11), 8=-24 (LC 10), 9=-56 (LC 14), 10=-23 (LC 10)
Max Grav 6=14 (LC 19), 7=96 (LC 21), 8=212 (LC 21), 9=197 (LC 21), 10=182 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-10=-164/127, 1-2=0/25, 2-3=-84/20, 3-4=-51/24, 4-5=-48/44, 5-6=-24/13, 5-7=-81/20
BOT CHORD	9-10=-36/43, 8-9=-36/43, 7-8=-36/43
WEBS	4-8=-174/149, 3-9=-160/194

NOTES

1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 2-0-0, Exterior(2N) 2-0-0 to 6-0-0 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) All plates are 2x4 MT20 unless otherwise indicated.
7) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 6.



May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868737
22020129	L01	Common Supported Gable	5	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:51
ID:U5CzCuUcXWbZOtE48eu3mpzhpis-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:42.4

Plate Offsets (X, Y): [2:0-3-8,Edge], [4:0-3-8,Edge]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.91	Vert(LL)	0.05	7-8	>999	240	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.30	Vert(CT)	-0.05	7-8	>999	180		
TCDL	10.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 69 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 6=526/0-3-8, 8=526/0-3-8
Max Horiz 8=145 (LC 13)
Max Uplift 6=-56 (LC 15), 8=-56 (LC 14)
Max Grav 6=619 (LC 22), 8=619 (LC 21)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	2-8=-566/356, 1-2=0/34, 2-3=-539/408, 3-4=-539/408, 4-5=0/34, 4-6=-566/356
BOT CHORD	7-8=-173/252, 6-7=-115/252
WEBS	3-7=-284/208, 4-7=-92/249, 2-7=-88/249

NOTES

1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) -0-10-8 to 2-1-8, Interior (1) 2-1-8 to 2-11-8, Exterior(2R) 2-11-8 to 8-11-8, Interior (1) 8-11-8 to 9-9-8, Exterior(2E) 9-9-8 to 12-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed; porch left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
7) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 8 and 6. This connection is for uplift only and does not consider lateral forces.
9) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY
TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868738
22020129	L02	Common Supported Gable	1	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:52 Page: 1
ID:MsRT1GX6al6_tUXrNTz?wfzhpio-RfC?PsB70Hq3NSgPqnL8w3ulTXbGKWrCDoi7J4zJC?f



Scale = 1:37.3

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.11	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.06	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.09	Horz(CT)	0.00	10	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MR								
BCDL	10.0										Weight: 69 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 6-0-0 oc bracing.

REACTIONS (lb/size) 10=131/11-11-0, 11=141/11-11-0, 12=165/11-11-0, 13=146/11-11-0, 14=165/11-11-0, 15=141/11-11-0, 16=131/11-11-0
Max Horiz 16=-141 (LC 12)
Max Uplift 10=-46 (LC 14), 11=-80 (LC 15), 12=-53 (LC 15), 14=-52 (LC 14), 15=-82 (LC 14), 16=-53 (LC 10)
Max Grav 10=143 (LC 24), 11=200 (LC 22), 12=256 (LC 22), 13=161 (LC 27), 14=256 (LC 21), 15=200 (LC 21), 16=149 (LC 25)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 2-16=-118/157, 1-2=0/33, 2-3=-77/96, 3-4=-75/173, 4-5=-113/248, 5-6=-113/248, 6-7=-75/173, 7-8=-68/96, 8-9=0/33, 8-10=-117/157
BOT CHORD 15-16=-71/68, 14-15=-71/68, 13-14=-71/68, 12-13=-71/68, 11-12=-71/68, 10-11=-71/68
WEBS 5-13=-197/32, 4-14=-217/112, 3-15=-162/117, 6-12=-217/112, 7-11=-162/117

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) -0-10-8 to 1-11-8, Exterior(2N) 1-11-8 to 2-11-8, Corner(3R) 2-11-8 to 8-11-8, Exterior (2N) 8-11-8 to 9-9-8, Corner(3E) 9-9-8 to 12-9-8 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Truss to be fully sheathed from one face or securely braced against lateral movement (i.e. diagonal web).
10) Gable studs spaced at 2-0-0 oc.
11) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
12) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
13) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 53 lb uplift at joint 16, 46 lb uplift at joint 10, 52 lb uplift at joint 14, 82 lb uplift at joint 15, 53 lb uplift at joint 12 and 80 lb uplift at joint 11.
14) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	PB1	Piggyback	10	1	I51868739 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:52 Page: 1
ID:wqE9XHIrfY1kw2gm2JUHo?zHvhW-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:44.6

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.30	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.17	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.13	Horz(CT)	0.00	20	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 83 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=67/19-0-15, 8=67/19-0-15, 10=253/19-0-15, 11=346/19-0-15, 13=260/19-0-15, 14=346/19-0-15, 15=253/19-0-15, 16=67/19-0-15, 20=67/19-0-15
Max Horiz 2=-138 (LC 12), 16=-138 (LC 12)
Max Uplift 2=-36 (LC 10), 8=-9 (LC 11), 10=-79 (LC 15), 11=-115 (LC 15), 14=-116 (LC 14), 15=-80 (LC 14), 16=-36 (LC 10), 20=-9 (LC 11)
Max Grav 2=89 (LC 25), 8=75 (LC 22), 10=310 (LC 25), 11=479 (LC 6), 13=374 (LC 24), 14=479 (LC 5), 15=311 (LC 24), 16=89 (LC 25), 20=75 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-127/108, 3-4=-130/87, 4-5=-147/128, 5-6=-147/111, 6-7=-90/52, 7-8=-91/55, 8-9=0/16
BOT CHORD 2-15=-39/90, 14-15=-39/90, 13-14=-39/90, 11-13=-39/90, 10-11=-39/90, 8-10=-39/90
WEBS 5-13=-203/0, 4-14=-395/165, 3-15=-206/129, 6-11=-395/164, 7-10=-206/128

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-3-11 to 3-3-11, Interior (1) 3-3-11 to 7-4-10, Exterior(2R) 7-4-10 to 13-4-10, Interior (1) 13-4-10 to 17-5-10, Exterior(2E) 17-5-10 to 20-5-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Gable studs spaced at 4-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
12) N/A
13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
14) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK I51868740
22020129	PB2	Piggyback	1	1	Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:52 Page: 1
ID:OvaXnpHesqpQkCbmd7MgygzHvb5-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:44.6

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.07	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horz(CT)	0.00	12	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 101 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=90/19-0-15, 12=90/19-0-15, 14=144/19-0-15, 15=158/19-0-15, 16=153/19-0-15, 18=161/19-0-15, 19=128/19-0-15, 20=161/19-0-15, 21=153/19-0-15, 22=158/19-0-15, 23=144/19-0-15, 24=90/19-0-15, 27=90/19-0-15
Max Horiz 2=-134 (LC 12), 24=-134 (LC 12)
Max Uplift 2=-24 (LC 10), 14=-47 (LC 15), 15=-49 (LC 15), 16=-50 (LC 15), 18=-50 (LC 15), 20=-51 (LC 14), 21=-49 (LC 14), 22=-49 (LC 14), 23=-49 (LC 14), 24=-24 (LC 10)
Max Grav 2=102 (LC 25), 12=91 (LC 22), 14=151 (LC 25), 15=164 (LC 25), 16=219 (LC 22), 18=245 (LC 22), 19=149 (LC 27), 20=245 (LC 21), 21=219 (LC 21), 22=164 (LC 24), 23=153 (LC 24), 24=102 (LC 25), 27=91 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-114/100, 3-4=-96/86, 4-5=-87/74, 5-6=-76/99, 6-7=-82/148, 7-8=-82/148, 8-9=-64/97, 9-10=-49/45, 10-11=-57/34, 11-12=-79/48, 12-13=0/16
BOT CHORD 2-23=-42/97, 22-23=-42/97, 21-22=-42/97, 20-21=-42/97, 19-20=-42/97, 18-19=-42/97, 16-18=-42/97, 15-16=-42/97, 14-15=-42/97, 12-14=-42/97
WEBS 7-19=-110/5, 6-20=-206/79, 5-21=-180/80, 4-22=-126/83, 3-23=-110/81, 8-18=-206/79, 9-16=-180/80, 10-15=-126/83, 11-14=-110/81

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-3-11 to 3-3-11, Exterior(2N) 3-3-11 to 7-4-10, Corner(3R) 7-4-10 to 13-4-10, Exterior (2N) 13-4-10 to 17-5-10, Corner(3E) 17-5-10 to 20-5-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) All plates are 2x4 MT20 unless otherwise indicated.
8) Gable requires continuous bottom chord bearing.
9) Gable studs spaced at 2-0-0 oc.
10) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
11) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
12) N/A
13) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
14) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard



May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	PB3	Piggyback	3	1	Job Reference (optional)	I51868741

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:52 Page: 1
ID:gKt_2hRK?ORI5CjExemzTUzHww5-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:30.9

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.10	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.07	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 25 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=57/5-9-8, 5=116/5-9-8, 6=288/5-9-8, 7=57/5-9-8
Max Horiz 2=124 (LC 14), 7=124 (LC 14)
Max Uplift 5=-37 (LC 14), 6=-93 (LC 14)
Max Grav 2=64 (LC 30), 5=172 (LC 21), 6=425 (LC 21), 7=64 (LC 30)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/16, 2-3=-164/102, 3-4=-105/54
BOT CHORD 2-6=-12/12, 5-6=0/0
WEBS 3-6=-369/193, 4-5=-142/73

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 4-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) N/A
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
12) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

NORTH CAROLINA PROFESSIONAL SEAL 45844 ENGINEER ANDREW JOHNSON

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	PB5	Piggyback	9	1	I51868742 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:53 Page: 1
ID:__1c4MYtF38IP9oyf2SACtzhpgB-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:30.6

Plate Offsets (X, Y): [2:0-3-1,0-1-8], [4:0-3-1,0-1-8]

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.27	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.02	Horz(CT)	0.00	2	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 31 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=205/7-2-1, 4=205/7-2-1, 6=212/7-2-1, 7=205/7-2-1, 11=205/7-2-1
Max Horiz 2=-78 (LC 12), 7=-78 (LC 12)
Max Uplift 2=-37 (LC 14), 4=-46 (LC 15), 7=-37 (LC 14), 11=-46 (LC 15)
Max Grav 2=300 (LC 21), 4=300 (LC 22), 6=228 (LC 21), 7=300 (LC 21), 11=300 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/26, 2-3=-206/113, 3-4=-206/113, 4-5=0/26
BOT CHORD 2-6=-34/82, 4-6=-24/82
WEBS 3-6=-80/0

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-14 to 3-2-14, Exterior (2R) 3-2-14 to 5-2-10, Exterior(2E) 5-2-10 to 8-2-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 4-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) N/A
12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
13) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	I51868743
22020129	PB6	Piggyback	1	1	Job Reference (optional)	

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:53 Page: 1
ID:yJrm4RdFA?AfxfI8EdwakXzhpVm-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:30.6

Plate Offsets (X, Y): [2:0-2-1,0-1-0], [6:0-2-1,0-1-0]

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.08	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.03	Vert(CT)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.05	Horz(CT)	0.00	6	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 35 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 2=85/7-2-1, 6=85/7-2-1, 8=165/7-2-1, 9=104/7-2-1, 10=165/7-2-1, 11=85/7-2-1, 15=85/7-2-1
Max Horiz 2=-76 (LC 12), 11=-76 (LC 12)
Max Uplift 2=-9 (LC 10), 8=-87 (LC 15), 10=-87 (LC 14), 11=-9 (LC 10)
Max Grav 2=127 (LC 21), 6=127 (LC 22), 8=252 (LC 22), 9=111 (LC 21), 10=252 (LC 21), 11=127 (LC 21), 15=127 (LC 22)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/25, 2-3=-59/53, 3-4=-100/84, 4-5=-100/84, 5-6=-46/34, 6-7=0/25
BOT CHORD 2-10=-24/77, 9-10=-24/77, 8-9=-24/77, 6-8=-24/77
WEBS 4-9=-73/0, 3-10=-209/155, 5-8=-209/155

NOTES
1) Unbalanced roof live loads have been considered for this design.
2) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-2-14 to 3-2-14, Exterior (2R) 3-2-14 to 5-2-10, Exterior(2E) 5-2-10 to 8-2-10 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
4) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
5) Unbalanced snow loads have been considered for this design.
6) This truss has been designed for greater of min roof live load of 12.0 psf or 1.00 times flat roof load of 20.0 psf on overhangs non-concurrent with other live loads.
7) Gable requires continuous bottom chord bearing.
8) Gable studs spaced at 2-0-0 oc.
9) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
10) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
11) N/A
12) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.
13) See Standard Industry Piggyback Truss Connection Detail for Connection to base truss as applicable, or consult qualified building designer.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	V1	Valley	1	1	I51868744
					Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:53 Page: 1
ID:obI8CR79AVIhJxhIYr2zsHzhpM4-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:44.9

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.49	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.15	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.12	Horiz(TL)	0.00	7	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 67 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=121/11-9-11, 7=59/11-9-11, 8=160/11-9-11, 9=169/11-9-11, 10=96/11-9-11, 11=299/11-9-11
Max Horiz 1=229 (LC 11)
Max Uplift 1=-3 (LC 10), 7=-32 (LC 11), 8=-52 (LC 14), 9=-50 (LC 14), 10=-40 (LC 14), 11=-74 (LC 14)
Max Grav 1=152 (LC 24), 7=87 (LC 20), 8=239 (LC 20), 9=238 (LC 20), 10=104 (LC 20), 11=306 (LC 23)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-241/135, 2-3=-153/93, 3-4=-132/85, 4-5=-125/83, 5-6=-93/94, 6-7=-72/26
BOT CHORD 1-11=-98/177, 10-11=-98/124, 9-10=-98/124, 8-9=-98/124, 7-8=-98/124
WEBS 5-8=-200/74, 4-9=-192/123, 3-10=-95/82, 2-11=-199/157

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Corner(3E) 0-0-7 to 3-0-7, Exterior(2N) 3-0-7 to 8-8-6, Corner(3E) 8-8-6 to 11-8-6 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) All plates are 2x4 MT20 unless otherwise indicated.
6) Gable requires continuous bottom chord bearing.
7) Gable studs spaced at 2-0-0 oc.
8) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
9) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
10) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 7, 3 lb uplift at joint 1, 52 lb uplift at joint 8, 50 lb uplift at joint 9, 40 lb uplift at joint 10 and 74 lb uplift at joint 11.
11) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	V2	Valley	1	1	Job Reference (optional)	I51868745

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:53 ID:gMYf1oAgDjo6oY?3nh7v07zhpM0-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f Page: 1



Scale = 1:36.2

Loading	(psf)	Spacing	1-11-4	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.39	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.27	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.10	Horiz(TL)	0.01	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 40 lb	FT = 20%

LUMBER

TOP CHORD	2x4 SP No.2
BOT CHORD	2x4 SP No.2
WEBS	2x4 SP No.3
OTHERS	2x4 SP No.3

BRACING

TOP CHORD	Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD	Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=168/9-4-7, 4=94/9-4-7, 5=453/9-4-7
Max Horiz 1=179 (LC 11)
Max Uplift 4=-28 (LC 11), 5=-112 (LC 14)
Max Grav 1=192 (LC 24), 4=170 (LC 5), 5=579 (LC 5)

FORCES (lb) - Maximum Compression/Maximum Tension

TOP CHORD	1-2=-312/130, 2-3=-123/65, 3-4=-141/41
BOT CHORD	1-5=-78/272, 4-5=-78/86
WEBS	2-5=-433/169

NOTES

1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-7 to 3-0-7, Interior (1) 3-0-7 to 5-0-3, Exterior(2R) 5-0-3 to 9-3-2 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 4-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 4 and 112 lb uplift at joint 5.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	V3	Valley	1	1	Job Reference (optional)	I51868746

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:54 Page: 1
ID:dlfQSUCwlL2q1s9Sv59O5YzhpM_-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:35.4

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.37	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.25	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.10	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MSH								
BCDL	10.0										Weight: 39 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=162/9-0-8, 4=103/9-0-8, 5=446/9-0-8
Max Horiz 1=178 (LC 11)
Max Uplift 4=-28 (LC 11), 5=-113 (LC 14)
Max Grav 1=170 (LC 28), 4=169 (LC 20), 5=570 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-270/126, 2-3=-123/63, 3-4=-148/42
BOT CHORD 1-5=-77/235, 4-5=-77/85
WEBS 2-5=-435/173

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) 0-0-7 to 3-0-7, Interior (1) 3-0-7 to 4-8-4, Exterior(2R) 4-8-4 to 8-11-3 zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 4-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 28 lb uplift at joint 4 and 113 lb uplift at joint 5.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	V4	Valley	1	1	I51868747 Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:54 Page: 1
ID:Z7nAtADAHyIYGAIq0WBsBzzhpLy-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:29.3

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 26 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=55/6-6-2, 4=125/6-6-2, 5=329/6-6-2
Max Horiz 1=125 (LC 11)
Max Uplift 1=-5 (LC 10), 4=-22 (LC 11), 5=-93 (LC 14)
Max Grav 1=75 (LC 24), 4=186 (LC 20), 5=468 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-108/97, 2-3=-114/59, 3-4=-154/40
BOT CHORD 1-5=-58/63, 4-5=-58/63
WEBS 2-5=-401/195

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 4-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 5 lb uplift at joint 1, 22 lb uplift at joint 4 and 93 lb uplift at joint 5.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK
22020129	V5	Valley	1	1	I51868748
					Job Reference (optional)

Carter Components (Sanford), Sanford, NC - 27332, Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:54 Page: 1
ID:VWvwIsFRpZYGWTSD8xEKGOzhpLw-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f



Scale = 1:28.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.31	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.12	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.08	Horiz(TL)	0.00	4	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 25 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 6-0-0 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=36/6-2-3, 4=125/6-2-3, 5=321/6-2-3
Max Horiz 1=119 (LC 11)
Max Uplift 1=-10 (LC 10), 4=-27 (LC 14), 5=-90 (LC 14)
Max Grav 1=59 (LC 28), 4=186 (LC 20), 5=464 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-113/98, 2-3=-114/58, 3-4=-153/45
BOT CHORD 1-5=-55/60, 4-5=-55/60
WEBS 2-5=-412/207

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 4-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 27 lb uplift at joint 4, 10 lb uplift at joint 1 and 90 lb uplift at joint 5.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	DRB - 106 FARM AT NEILLS CREEK	
22020129	V6	Valley	1	1	Job Reference (optional)	I51868749

Carter Components (Sanford), Sanford, NC - 27332,

Run: 8.53 S Apr 27 2022 Print: 8.530 S Apr 27 2022 MiTek Industries, Inc. Tue May 10 15:10:54
ID:OH8R8DIxto2i?5m_NnIGQEzhpLs-RfC?PsB70Hq3NSgPqnL8w3uITXbGKWrCDoi7J4zJC?f

Page: 1



Scale = 1:22.5

Loading	(psf)	Spacing	2-0-0	CSI		DEFL	in	(loc)	l/defl	L/d	PLATES	GRIP
TCLL (roof)	20.0	Plate Grip DOL	1.15	TC	0.21	Vert(LL)	n/a	-	n/a	999	MT20	244/190
Snow (Pf)	20.0	Lumber DOL	1.15	BC	0.25	Vert(TL)	n/a	-	n/a	999		
TCDL	10.0	Rep Stress Incr	YES	WB	0.00	Horiz(TL)	0.00	3	n/a	n/a		
BCLL	0.0*	Code	IRC2018/TPI2014	Matrix-MP								
BCDL	10.0										Weight: 13 lb	FT = 20%

LUMBER
TOP CHORD 2x4 SP No.2
BOT CHORD 2x4 SP No.2
WEBS 2x4 SP No.3

BRACING
TOP CHORD Structural wood sheathing directly applied or 3-7-14 oc purlins, except end verticals.
BOT CHORD Rigid ceiling directly applied or 10-0-0 oc bracing.

REACTIONS (lb/size) 1=140/3-7-14, 3=140/3-7-14
Max Horiz 1=66 (LC 11)
Max Uplift 1=-13 (LC 14), 3=-32 (LC 14)
Max Grav 1=197 (LC 20), 3=197 (LC 20)

FORCES (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=-289/54, 2-3=-130/46
BOT CHORD 1-3=-61/240

NOTES
1) Wind: ASCE 7-16; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=25ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) exterior zone and C-C Exterior(2E) zone; cantilever left and right exposed ; end vertical left and right exposed;C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
2) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
3) TCLL: ASCE 7-16; Pr=20.0 psf (roof LL: Lum DOL=1.15 Plate DOL=1.15); Pf=20.0 psf (Lum DOL=1.15 Plate DOL=1.15); Is=1.0; Rough Cat B; Fully Exp.; Ce=0.9; Cs=1.00; Ct=1.10
4) Unbalanced snow loads have been considered for this design.
5) Gable requires continuous bottom chord bearing.
6) Gable studs spaced at 4-0-0 oc.
7) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
8) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-06-00 tall by 2-00-00 wide will fit between the bottom chord and any other members.
9) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 32 lb uplift at joint 3 and 13 lb uplift at joint 1.
10) This truss is designed in accordance with the 2018 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S) Standard

May 11,2022

ENGINEERING BY TRENCO
A MiTek Affiliate
818 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION



Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.

*** Plate location details available in MiTek 20/20 software or upon request.**

PLATE SIZE

4 x 4

The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.

LATERAL BRACING LOCATION



Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.

BEARING



Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.

Industry Standards:

ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
DSB-89: Design Standard for Bracing.
BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

ESR-1311, ESR-1352, ESR1988
ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

MiTek Engineering Reference Sheet: MII-7473 rev. 5/19/2020

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

1. Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
2. Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor I bracing should be considered.
3. Never exceed the design loading shown and never stack materials on inadequately braced trusses.
4. Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
5. Cut members to bear tightly against each other.
6. Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
7. Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
8. Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
9. Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
10. Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
11. Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
12. Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
13. Top chords must be sheathed or purlins provided at spacing indicated on design.
14. Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
15. Connections not shown are the responsibility of others.
16. Do not cut or alter truss member or plate without prior approval of an engineer.
17. Install and load vertically unless indicated otherwise.
18. Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
19. Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
20. Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.
21. The design does not take into account any dynamic or other loads other than those expressly stated.