

214 Fountainhead Road Portland, TN 37148 (615)-252-2880www.ascentbuildings.com

## BUILDING LOADS / DESCRIPTION: BUILDING: LENGTH: 16'-0"/ 17'-6" 69'-2" 99'–2" (BUILDING DIMENSIONS ARE NOMINAL, REFER TO PLANS). THIS STRUCTURE IS DESIGNED UTILIZING THE LOADS INDICATED IBC 15 / NCBC 18 AND APPLIED AS REQUIRED BY : THE CONTRACTOR IS TO CONFIRM THAT THESE LOADS COMPLY WITH THE REQUIREMENTS OF THE LOCAL BUILDING DEPARTMENT. OCCUPANCY CATEGORY: II — Normal ROOF DEAD LOAD: PSF (ROOF PANELS & PURLINS) COLLATERAL LOAD: PSF 20.00 PSF (REDUCIBLE) ROOF LIVE LOAD: GROUND SNOW LOAD: 15 1.0000 PSF SNOW LOAD IMPORTANCE: 10.5 **ROOF SNOW LOAD:** SNOW EXPOSURE: 1.0000 1.00 THERMAL FACTOR: BASE: BASIC WIND SPEED: 118 mph MPH DOWNSPOUTS: WIND EXPOSURE: LINER: WIND LOAD IMPORTANCE: 1.00 0.18 / -0.18 INTERNAL PRESSURE COEFF.: SEISMIC IMPORTANCE FACTOR: 1.00 SEISMIC DESIGN CATEGORY: SEISMIC ZONE: SITE CLASS: MAPPED SPECTRAL RESPONSE ACC. Ss 0.17 SI 0.08 SPECTRAL RESPONSE COEFF. Sds 0.18 Sd1 0.13 DESIGN BASE SHEAR, V: LONGITUDINAL 12.48 TRANSVERSE 11.92 **GENERAL NOTES:** 1) MATERIALS MINIMUM YIELD:

50.0000

50.0000

50.0000

57.0000

60.0000

FY = 60.0000 ksi MIN.

A307 & A325

THE METAL BUILDING MANUFACTURER RESERVES THE RIGHT TO SUBSTITUTE THE ABOVE MATERIALS WITH EQUAL OR BETTER MATERIAL.

ALL HIGH STRENGTH BOLTS ARE A325 UNLESS NOTED OTHERWISE. HIGH STRENGTH BOLTS SHALL BE TIGHTENED BY THE TURN OF THE NUT METHOD IN ACCORDANCE WITH THE LATEST EDITION AISC "SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS". A325 BOLTS SHALL BE INSTALLED WITH OUT WASHERS WHEN TIGHTENED BY THE "TURN OF THE NUT" METHOD. ALL BOLTED CONNECTIONS, FOR SHEAR/BEARING CONNECTION TYPE WITH BOLT THREADS EXCLUDED FROM THE SHEAR PLANE SHALL BE

3) ALL STRUCTUAL STEEL TO RECEIVE A RUST INHIBITIVE PRIMER. THIS PAINT IS NOT INTENDED FOR LONG TERM EXPOSURE TO THE ELEMENTS.

ksi MIN.

ksi MIN.

ksi MIN.

ksi MIN.

HOT ROLLED BAR

WALL SHEETING

ROOF SHEETING

SNUG TIGHT ONLY.

BOLTS

STRUCTURAL STEEL SHEET

STRUCTURAL STEEL PLATE

2) <u>BOLT TIGHTENING REQUIREMENTS:</u>

COLD FORMED SHAPES

ROOF PANELS:	-					
TYPE: RL	GAGE: _	26	COLOR:	Galvalume	Plus	_25-y
WALL PANELS:	<u>:</u>					
TYPE: RLR	GAGE: _	26	COLOR:	Galvalume	Plus	_25-y
PARAPET BACK F	PANEL	_				
TYPE: ML	GAGE: _	26	COLOR:	Brown		_
SOFFIT PANELS:						
TYPE: N/A	GAGE: _	N/A	COLOR:	N/A		_
TRIM COLORS:	:					
RAKE:	Galvalum	ne Plus	25-yr			
EAVE:	Galvalum	ne Plus	25-yr			
CORNER:	Galvalum	ne Plus	25-yr			
FRAMED OPENINGS:	Galvalum	ne Plus	25-yr			

Galvalume Plus 25-yr

Brown

DEFLECTION	LIMTS:
EW COL:	600
EW RAF LIVE:	180
EW RAF WIND:	180
WALL GIRT:	600
PURL LIVE:	180
PURL WIND:	150
WALL PANEL:	600
ROOF PANEL LIVE:	60
ROOF PANEL WIND:	60
RF HORIZONTAL:	120
RF VERTICAL:	180
WIND BENT:	120
RF CRANE:	100
RF SEIS:	50
WIND BENT SEIS:	50

## BUILDER / CONTRACTOR RESPONSIBILITIES

IT IS THE RESPONSIBILITY OF THE BUILDER/CONTRACTOR TO INSURE THAT ALL PROJECT PLANS AND SPECIFICATIONS COMPLY WITH THE APPLICABLE REQUIREMENTS OF ANY GOVERNING BUILDING AUTHORITIES. THE SUPPLYING OF SEALED ENGINEERING DATA AND DRAWINGS FOR THE METAL BUILDING SYSTEM DOES NOT IMPLY OR CONSTITUTE AN AGREEMENT THAT THE METAL BUILDING SYSTEM MANUFACTURER OR ITS DESIGN ENGINEER IS ACTING AS THE ENGINEER OF RECORD OR DESIGN PROFESSIONAL FOR A CONSTRUCTION PROJECT. THE CONTRACTOR MUST SECURE ALL REQUIRED APPROVALS AND PERMITS FROM THE APPROPRIATE AGENCY AS THE CONTRACTOR MUST SECURE ALL REQUIRED APPROVALS AND PERMITS FROM THE APPROPRIATE AGENCY AS THAT THE METAL BUILDING SYSTEM MANUFACTURER CORRECTLY INTERPRETED AND APPLIED THE REQUIREMENTS OF THE CONTRACT DRAWINGS AND SPECIFICATIONS. (SECT. 4.2.1 AISC CODE OF STANDARD PRACTICES, 9TH ED.) WHERE DISCREPANCIES EXIST BETWEEN THE METAL BUILDING SYSTEM MANUFACTURER'S STRUCTURAL STEEL PLANS AND THE PLANS FOR OTHER TRADES, THE STRUCTURAL STEEL PLANS SHALL GOVERN. (SECT. 3.3 AISC CODE OF STANDARD PRACTICE 9TH ED.) DESIGN CONSIDERATIONS OF ANY MATERIALS IN THE STRUCTURE WHICH ARE NOT FURNISHED BY THE METAL BUILDING SYSTEM MANUFACTURER ARE THE RESPONSIBILITY OF THE CONTRACTORS AND ENGINEERS OTHER THAN THE METAL BUILDING SYSTEM MANUFACTURER'S ENGINEER UNLESS SPECIFICALLY INDICATED.

THE CONTRACTOR IS RESPONSIBLE FOR ALL ERECTION OF STEEL AND ASSOCIATED WORK IN COMPLIANCE WITH THE METAL BUILDING SYSTEM MANUFACTURER "FOR CONSTRUCTION" DRAWINGS.

ALL BRACING AS SHOWN AND PROVIDED BY THE METAL BUILDING SYSTEM MANUFACTURER FOR THIS BUILDING IS REQUIRED AND SHALL BE INSTALLED BY THE ERECTOR AS A PERMANENT PART OF THE STRUCTURE.

TEMPORARY SUPPORTS, SUCH AS TEMPORARY GUYS, BRACES, FALSE WORK, CRIBBING OR OTHER ELEMENTS REQUIRED FOR THE ERECTION OPERATION WILL BE DETERMINED AND FURNISHED AND INSTALLED BY THE ERECTOR. THESE TEMPORARY SUPPORTS WILL SECURE THE STEEL FRAMING, OR ANY PARTLY ASSEMBLED STEEL FRAMING, AGAINST LOADS COMPARABLE

IN INTENSITY TO THOSE FOR WHICH THE STRUCTURE WAS DESIGNED, RESULTING FROM WIND, SEISMIC FORCES AND ERECTION OPERATIONS, BUT NOT THE LOADS RESULTING FROM THE PERFORMANCE OF WORK BY OR THE ACTS OF OTHERS, NOR SUCH UNPREDICTABLE LOADS AS THOSE DUE TO TORNADO, EXPLOSION, OR COLLISION. (SECT. 7.9.1AISC CODE OF STANDARD PRACTICE, 9TH ED.)

WARNING: IN NO CASE SHOULD GALVALUME STEEL PANELS BE USED IN CONJUNCTION WITH LEAD OR COPPER. BOTH LEAD AND COPPER HAVE HARMFUL CORROSION EFFECTS ON THE ALUMINUM ZINC ALLOY COATING WHEN THEY ARE USED IN CONTACT WITH GALVALUME STEEL PANELS. EVEN RUN-OFF FROM COPPER FLASHING, WIRING, ORTUBING ONTO GALVALUME SHOULD BE AVOIDED.

ERECTOR NOTE: PANEL BUNDLES MUST BE HANDLED WITH CARE!!! USE A SPREADER BAR FOR HANDLING. THE METAL BUILDING SYSTEM MANUFACTURER IS NOT RESPONSIBLE FOR MATERIALS DAMAGED ONSITE. STORE PANELS WHERE MOISTURE CAN PROPERLY DRAIN. THE METAL BUILDING SYSTEM MANUFACTURER WILL NOT WARRANT PANELS THAT HAVE BEEN STORED WHERE MOISTURE CAN BE CAPTURED BETWEEN PANELS THAT ARE BUNDLED.

CORRECTION OF MINOR MISFITS IN THE FIELD IS CONSIDERED NORMAL AND IS NOT SUBJECT TO BACK CHARGE. MAJOR CORRECTIVE WORK MUST BE AUTHORIZED IN ADVANCED BY THE ENGINEERING DEPARTMENT OF THE METAL BUILDING SYSTEM MANUFACTURER. REQUEST TO PERFORM CORRECTIVE WORK MUST BE SUBMITTED IN WRITING ALONG WITH PHOTOS AND A DESCRIPTION OF THE MODIFICATION THAT IS BEING REQUESTED. NO BACK CHARGE WILL BE PAID THAT IS NOT AUTHORIZED IN ADVANCED BY THE METAL BUILDING SYSTEM MANUFACTURER.

INDEX OF SHEETS							
PAGE	DESCRIPTION	REV					
C1	COVER SHEET	0					
AB1	ANCHOR BOLT PLAN	2					
AB2	ANCHOR BOLT DETAILS	2					
AB2	ANCHOR BOLT REACTIONS	2					
E1	ROOF FRAMING PLAN	0					
E2	ROOF SHEETING PLAN	0					
E3	SIDEWALL FRAMING & SHEETING	0					
E4	SIDEWALL FRAMING & SHEETING	0					
E5	ENDWALL FRAMING & SHEETING	0					
E6	ENDWALL FRAMING & SHEETING	0					
E7 & E8	RIGID FRAME ELEVATION	0					
E9	WIND BENT ELEVATION	0					
D1 - D4	ERECTION DETAILS	0					

INDEX OF SHEETS

ORTH CAROLINA
75
NO. 034784


$\triangle$					DESCRIPTION:	CHEET				
$\triangle$	08/29/22	ISSUED FOR CONSTRUCTION	PSK	KDR	COVER	R SHEET				
Ĉ	08/16/22	REVISED FOR PERMIT/CONST.	MAR	PNR	CUSTOMER: Barefoot Build	lina Company	PROJECT:	T&L Coats Buildina	2	
B	07/13/22	REVISED FOR PERMIT/CONST.	PSK	PNR	LOCATION: Coats, NC 27521					
À	06/17/22	ISSUED FOR PERMIT/CONST.	MAR	PNR	SCALE JOB NO. SHEET NO.					
REV.	DATE	REVISION	DRN. BY	CK'D BY		22-104		C1 OF C	1	


LORTH CAROLINATION OF THE PROPERTY OF THE PROP
NO.034784

					DESCRIPTION:	OLLEET.		
Ô	08/29/22	ISSUED FOR CONSTRUCTION	PSK	KDR	COVER	SHEET		
$\Diamond$	08/16/22	REVISED FOR PERMIT/CONST.	MAR	PNR	CUSTOMER: Barefoot Build	ing Company	PROJECT:	— Т&
B	07/13/22	REVISED FOR PERMIT/CONST.	PSK	PNR	LOCATION: Coats, NC	, ,		
Â	06/17/22	ISSUED FOR PERMIT/CONST.	MAR	PNR	SCALE	JOB N	١٥.	
	7	DEVICION		21/22 22/	\ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \ \			

	ASCENT BUILDINGS	
4	Fountainhead Road Portland, TN 37148	

(615)-252-2880 www.ascentbuildings.com





DETAIL G



(615)-252-2880 www.ascentbuildings.com Job Number

22-10407

Customer

Barefoot Building Company

DRAWING STATUS

Project Name & Location T&L Coats Building 2

Coats, NC 27521

Preliminary
(Not For Construction)

For Approval
(Not For Construction)

For Construction Permit

For Erector Installation

MAR

Sheet Number AB2 OF AB3

Project Engineer

Drawn By: Checked By:

Scale:


NTS

Description
ISSUED FOR CONSTRUCTION
REVISED FOR CONSTRUCTION
REVISED FOR CONSTRUCTION

The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned

engineer is not the overall engineer of record for the project





intended use of the building. i.e. Ascent Buildings, LLC. does not serve

Ascent Buildings, LLC. IS NOT RESPONSIBLE FOR FIT OF

IN THE EXACT LOCATIONS SHOWN ON THESE DRAWINGS.

FRAMING STEEL IN INSTANCES WHERE ANCHOR BOLTS ARE NOT SET

as the Engineer of Record.

FRAME LINES: 1 5

B

C

D

H

V

FRAME LINES: 2 3 4

RIGID F	RAME:		MAXIMUM F	REACTIONS, AN	CHOR BOL	TS, & BAS	E PLATES						
Frm Line	Col Line	Load Id	Hmax H	umn_Reaction V Vmax	s(k ) Load Id	Hmin H	V Vmin	– Bolt Qty	(in) Dia	Base Width	_Plate(in) Length	Thick	Grout (in)
1*	A	5 7	4.3 3.4	2.3 4.2	13 10	-2.9 -2.9	-1.9 -4.4	4	0.750	8.000	10.75	0.500	0.0
1*	D	11 6	3.3 -3.6	-9.4 8.6	4 11	-4.5 3.3	8.4 -9.4	4	0.750	8.000	10.75	0.500	0.0
1*	В	12 3	0.0 0.0	-6.2 10.3	12	0.0	-6.2	4	0.750	6.000	8.000	0.500	0.0
1*	С	10 7	0.0 0.0	-10.5 10.6	10	0.0	-10.5	4	0.750	6.000	8.000	0.500	0.0
1*	Frame li	nes:	1 5										
RIGID F	RAME:		MAXIMUM F	REACTIONS, AN	ICHOR BOL	TS, & BAS	E PLATES						
F	Cal		Col	umn_Reaction		Heate		- Dall	/: <sub></sub> \	Desa	Diata/:m\		Carrid
Frm Line ———	Col Line	Load Id — —	Hmax H	V Vmax —	Load Id — —	Hmin H	Vmin 	Bolt Qty	(in) Dia 	Width — ————	_Plate(in) Length 	Thick	Grout (in)
2*	A	2	15.5	20.6	8 10	-9.1 -8.3	-8.6 -9.0	4	0.750	8.000	11.00	0.500	0.0
2*	D	9 2	6.0 -15.5	-5.6 20.7	2 10	-15.5 0.9	20.7 -9.3	4	0.750	8.000	11.00	0.500	0.0

IG BR	ACING F	REACTION	NS					ANCHO	OR BOLT SUM	MARY		
Line  1 D 5 A	- Col Line - 1,2 4,5 Torsional		E Reactio Wind — Vert  5.9 5.9	smic - Vert - - 4.0 4.0	Panel_S — (lb, Wind —	Shear /ft) Seis 	Note (h) (b) (b) (h)	Qty ○ 48 ※ 16 ※ 40	Locate Jamb Endwall Frame	Dia (in)  5/8" 3/4" 3/4"	A307 A307	
		_										

Frame lines:

(b)Wind bent in bay, base above finish floor

(h)Rigid frame at endwall

— Wall

B\_SW

2 3 4

NOTES FOR REACTIONS

\_\_COLUMN LINE

\_\_COLUMN LINE

2.50

2.50

- All loading conditions are examined and only maximum/minimum H or V and the corresponding H or V are reported.
- Positive reactions are as shown in the sketch. Foundation loads are in opposite directions.
- 3. Bracing reactions are in the plane of the brace with the H pointing away
- from the braced bay. The vertical reaction is downward.
- 4. Building reactions are based on the following building data:
- Width (ft) = 69.2 Length (ft) = 99.2 Eave Height (ft) = 16.0/ 17.5
- Roof Slope (rise/12 )
   = 0.3

   Dead Load (psf )
   = 2.5

   Collateral Load (psf )
   = 5.0

   Roof Live Load(psf )
   = 20.0
- Frame Live Load(psf ) = 12.0

  Snow Load (psf ) = 10.5

  Wind Speed (mph ) = 118.0

  Wind Code = NCBC 18 (IBC 15)

  Exposure = B

  Closed/Open = C
- Importance Wind = 1.00
  Importance Seismic = 1.00
  Seismic Zone = B
  Seismic Coeff (Fa\*Ss) = 0.27
- 5. Loading conditions are:
- 1 Dead+Collateral+Live 2 Dead+Collateral+Rain 3 Dead+Collateral+Snow+Snow\_Drift 4 Dead+0.6Wind\_Long1R
- 5 Dead+0.6Wind\_Long2R
  6 Dead+Collateral+0.75Snow+0.45Wind\_Long1R+0.75Snow\_Drift
  7 Dead+Collateral+0.75Snow+0.45Wind\_Long2R+0.75Snow\_Drift
- 7 Dead+Collateral+0.75Snow+0.45Wind 8 0.6Dead+0.6Wind\_Left1 9 0.6Dead+0.6Wind\_Right1
- 13 0.57Dead+0.7Seismic\_LongL
  14 0.6Dead+0.6Wind\_Right2+0.6Wind\_Suction
  15 0.6Dead+0.6Wind\_Pressure+0.6Wind\_Long2L
- 16 Dead+0.6Wind\_Right2+0.6Wind\_Suction
  17 0.6Dead+0.6Wind\_Left1+0.6Wind\_Suction
  18 0.6Dead+0.6Wind Pressure+0.6Wind Long
- 17 0.6Dead+0.6Wind\_Lett1+0.6Wind\_Suction
  18 0.6Dead+0.6Wind\_Pressure+0.6Wind\_Long1L
  19 0.6Dead+0.6Wind\_Right1+0.6Wind\_Suction
  20 0.6Dead+0.6Wind\_Suction+0.6Wind\_Long1L

BUILDINGS
214 Fountainhead Road

Portland, TN 37148 (615)-252-2880 www.ascentbuildings.com

Job Number 22-10407

Customer

Barefoot Building Company

Project Name & Location

T&L Coats Building 2

Coats, NC 27521

DRAWING STATUS

- Preliminary
  (Not For Construction)
- For Approval
  (Not For Construction)
- For Construction Permit

For Erector Installation

NTS

Sheet Number AB3 OF AB3
Project Engineer JRC


Drawn By: MAR
Checked By: PNR


Scale:


Date

06/17/22 ISSUED FOR CONSTRUCTION
07/13/22 REVISED FOR CONSTRUCTION
08/16/22 REVISED FOR CONSTRUCTION

The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project







BUILDINGS

214 Fountainhead Road
Portland, TN 37148

(615)-252-2880 www.ascentbuildings.com

Job Number 22-10407

ustomer

Barefoot Building Company

Project Name & Location
T&L Coats Building 2
Coats, NC 27521

Coats, NC 2/52

Preliminary
(Not For Construction)

DRAWING STATUS

For Approval
(Not For Construction)

(Not For Construction)

For Construction Permit

For Erector Installation

Sheet Number E2 OF E9

Project Engineer JRC

Drawn By: MAR

Checked By: PNR
Scale: NTS

ion By C
MIT MAR I
RMIT PSK I
STRUCTION PSK I


Jescr 722 ISSUED FOR PE 722 REVISED FOR P 7/22 ISSUED FOR CO


The Engineer whose seal of


The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project


ord for the project


PANELS: 26 Ga. RL — Galvalume Plus 25—yr














BUILDINGS

214 Fountainhead Road
Portland, TN 37148

(615)-252-2880
www.ascentbuildings.com

Job Number 22-10407

Customer

Barefoot Building Company

Project Name & Location
T&L Coats Building 2
Coats, NC 27521

DRAWING STATUS

Preliminary
(Not For Construction)

For Approval
(Not For Construction)

For Construction Permit

For Erector Installation

Sheet Number E8 OF E9

Project Engineer JRC

Drawn By: MAR

Checked By: PNR

Scale: NTS

ISSUED FOR PERMIT


REVISED FOR PERMIT

ISSUED FOR CONSTRUCTION


PSK KDR


KDR

The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project



CDLIOE DO	TO.						MEMBER SIZE	TADIF		
SPLICE BOI Splice Mark	QuanBolt						MARK	MEMBER	LENGTH	
Mark SP- 1	Top/         Bot         Type         Dia         Length           4         4         A325         3/4"         2 3/4"						WF-2 WF-1	B16a6c B14a5c	21'-8 7/8" 15'-10"	
										BUILDINGS
										BUILDINGS  214 Fountainhead Road  Portland, TN 37148
										(615)-252-2880 www.ascentbuildings.com
										Job Number 22-10407
										Customer
			_							Barefoot Building Company
										Project Name & Location T&L Coats Building 2
										Coats, NC 27521
										DRAWING STATUS
					WF-2					Preliminary (Not For Construction)
										For Approval (Not For Construction)
										For Construction Permit
										For Erector Installation
										Sheet Number E9 OF E9
										Project Engineer JRC  Drawn By: MAR
										Checked By: PNR
										Chk'd PNR KDR KDR NLS
										MAR PI
										A 2 2 3
										CTION
										PERMIT CONSTRU
										Descripti OR PE FOR P OR CO
										Descriț ISSUED FOR F REVISED FOR (
										ISS   SS   SS   SS   SS   SS   SS   SS
										/22 /22 /22
										Date 06/17 06/13 08/29
										A B B O
										8
										hereon is an employee for the manufacturer for the material described herein. Said seal or
										The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project
		— — — — — — — — — — — — — — — — — — —				1	1 C 33 1			engineer is not the overall engineer of record for the project
		/   0		25	9—1"	1/	16 1			ORTH CAROLING
				<u> </u>	ı		2			NO. 034784
		4					5			W SPEECH
				WIND BENT ELEVAT	ION: FRAME LINE					







Job Number 22-10407

Customer Barefoot Building Company

Project Name & Location T&L Coats Building 2 Coats, NC 27521


DRAWING STATUS


Preliminary (Not For Construction)


For Approval (Not For Construction)

For Construction Permit For Erector Installation Sheet Number D2 OF D4 Project Engineer JRC Drawn By: MAR Checked By: PNR Scale: NTS 

The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project







ASCENT BUILDINGS 214 Fountainhead Road Portland, TN 37148 (615)-252-2880 www.ascentbuildings.com

22-10407

Barefoot Building Company

Project Name & Location T&L Coats Building 2 Coats, NC 27521

Preliminary
(Not For Construction)

For Approval (Not For Construction)

For Erector Installation

The Engineer whose seal appears hereon is an employee for the manufacturer for the material described herein. Said seal or certification is limited to the products designed and manufactured by manufacturer only. The undersigned engineer is not the overall engineer of record for the project

