


3540 Privacy Set Lever

Grade 2 Cylindrical Lever



Applications:

- Standard duty commercial
- No exposed mounting screws
- Non-handed

Function:

- 40 - Privacy (ANSI F76A)



PRODUCT SPECIFICATIONS

CERTIFICATIONS:

- BHMA Certified ANSI A156.2, Series 4000, Grade 2
- ADA Compliant ANSI A117.1 Accessibility Code
- UL/cUL Listed for all functions up to 3 hours "A" label single doors (for double doors application, UL/cUL Listed when used with 3/4" latchbolt)
- ANSI A250.13 Severe Windstorm Component
- UL10C Positive Pressure Rated
- UL10B Neutral Pressure Rated
- Lifetime warranty

EXPOSED TRIM:

- Levers: cast zinc
- Rose: wrought brass or stainless steel

LOCK CHASSIS:

- Heavy gauge steel, zinc dichromated for corrosion resistance
- Free wheeling (levers only)
- Removable thru-bolts
- Failure to install thru-bolts and removable screw posts voids BHMA certification, UL Rating, and Warranty.

ROSE DIAMETER:

- 3-11/32" (85 mm) levers

DOOR THICKNESS:

- Levers: 1-3/8" - 2" (35 mm - 51 mm)

BACKSET:

- 2-3/4" (70 mm) - Standard
- 2-3/8" (60 mm) - Optional
- 3-3/4" (94 mm) - Optional
- 5" (128 mm) - Optional

LATCHBOLT:

- 1/2" (13 mm) Throw
- Stainless steel
- 1-1/8" x 2-1/4" (25 mm x 57 mm) Faceplate for 2-3/4" (70 mm) backset
- 1" x 2-1/4" (25 mm x 57 mm) Faceplate for 2-3/8" (60 mm) backset

STRIKES:

- 3935 ASA 1-1/4" x 4-7/8" (32 mm x 124 mm) strike
- Standard

FINISHES:

- US3, US4, US10, US10B, US26, US26D
- Anti-Microbial Coating (US26D finish only)

FUNCTIONS:

- 40 - Privacy

OPTIONS:

- Lead Lined (Levers Only)
- Tactile Knurling (Levers Only)
- Split Finish
- Additional latchbolts and strikes available

STANDARD DOOR PREP:

- 2-1/8" diameter (cross bore)
- Latch hole: 1" diameter (edge bore)

LEVER OPTIONS:

- Archer, August, Withnell levers

EPD:

- [3500 Cylindrical Lock Environmental Product Declaration](#)