

Construction Services / CMT - Project Closeout / Summary Report

To:

Name: Jim Moore
Company: Piney Grove Storage
Address: 78 Piney Grove Rawls Rd.
Fuquay Varina, NC 27526
Email: jim@pineygrovestorage.com
Phone: 910-922-7010

Re:

Project Name: Baucom Business Park
Project No.: CMT2400166
Project Location: 11132 401 N
Fuquay Varina, NC 27526
Work Type(s): Self Storage Facility - **Building S3**
Date: 12/12/2024

Observations

Foundation excavation observation (sub-surface testing with respect to bearing capacity).

Recommendations

The exposed soils have been observed and tested for adequate bearing capacity (Probe and DCP). Based on our testing and review, the soil and conditions for the foundation are suitable for the minimum required bearing pressure of 2000 psf.

Project Notes

This report is an assessment of vertical bearing capacity only. Minimum testing requirements include probe rod testing across the entire excavation and augers (minimum three locations) at multiple depths with Dynamic Cone Penetrometer (DCP) testing. Bearing capacity test results are voided if significant precipitation or water intrusion has occurred before concrete placement. JDS Consulting is not responsible for site conditions that divert water towards the foundation or that prevents drainage away from the foundation, which can lead to soft soils and future settlement problems. It is the contractor's responsibility to ensure that all foundation areas are free of organics, loose material, standing water, and any other deleterious materials prior to placement of stone or concrete. Retaining wall stability nor slope stability analysis has been evaluated. JDS Consulting shall not be held responsible for current or future retaining-wall or slope-related issues.

If you have any questions or if I can be of further assistance to you on this project, please contact me at your earliest convenience. Thank you!

Respectfully Submitted,
Jarrett Hollingsworth
(919) 690-9255

JDS Firm License Number: P-0961



Reviewing Engineer:
Maxwell C. Danskin, PE