

SOUTHEASTERN SOIL & ENVIRONMENTAL ASSOC., INC.

PROPOSED SUBSURFACE WASTE DISPOSAL SYSTEM DETAIL SHEET

SUBDIVISION: BLAKE ROAD

LOT 101

INITIAL SYSTEM: APPROVED 25% REDUCTION

REPAIR: APPROVED 25% REDUCTION

DISTRIBUTION: D-Box

DISTRIBUTION SERIAL

BENCHMARK: 100.0

LOCATION CONTROL PT

NO. BEDROOMS: 3

LTAR 0.3 GPD/FT<sup>2</sup>

SEPTIC TANK SIZE: 1000

PUMP TANK SIZE: NA

LINE	FLAG COLOR	ELEVATION	LENGTH
------	------------	-----------	--------

*Installed  
septa*

1	B	97.75	100'
2	Y	97.25	100'
3	B	96.75	100'
			<u>300'</u>

4	Y	96.25	75'
5	B	95.50	75'
6	Y	94.75	75'
7	B	94.34	75'
			<u>300'</u>

BY: M EAKER

DATE 12/2022

TYPICAL PROFILE

0-10 US/VEF, w/1  
10-40+ SCL (F; MIL)  
CS ≥ 34"  
INSTALL AT 18"

THERE SHALL BE NO GRADING,  
 CUTTING, LOGGING OR OTHER SOIL

DISTURBANCE IN SEPTIC AREA

HEALTH DEPARTMENT USE ONLY.  
 DESIGNS DO NOT GURANTEE FUNCTIONALITY

# Southeastern Soil & Environmental Associates, Inc.

P.O. Box 9321  
Fayetteville, NC 28311  
Phone/Fax (910) 822-4540  
Email mike@southeasternsoil.com

