

NO.	ROOM NAME	FLOOR	BASE	WALL MATERIAL - FINISH	TRIM	CEILING	CEILING HEIGHT	REMARKS
100	EXISTING SALES AREA	EXIST VCT/ NEW VCT-2	EXIST VB	EXIST WP W/ P-7(A) UP TO CEILING AT FRONT WALL, EXIST WP W/ P-13(A) STRIPE AND P-7(A) UP TO CEILING AT OTHER SALES WALLS	P-3 (B)	EXPOSED STRUCTURE, EXIST GWB & ACT, NEW ACT-1 AT FRONT CORRIDOR	EXIST EXPOSE STRUCTURE, 12'-0" & 9'-6"	FINISH SCHEDULE NOTE #1,3,7,8,17,19 & RE: SHEET A2.02
101	EXISTING VESTIBULE	NEW CPT-1	EXIST MQBR/ NEW MQBR & VB-1	EXIST SPLIT-FACE CMU, DO NOT PAINT/ EXIST GWB P-3(B) & EXIST WP	P-3 (B)	EXIST/NEW GWB P-4(D)	12'-0"	----
102	EXISTING WORKROOM	EXIST VCT	EXIST VB	EXIST WP & GWB	P-3 (B)	EXIST PLYWD	12'-0"	FINISH SCHEDULE NOTE #1,7,16. PAINT ALL EXPOSED WOOD P-3 (B)
103	NEW CUSTOMER SERVICE	NEW VCT-2	NEW VB-1	NEW WP-2	----	EXIST ACT	12'-0"	
104	EXISTING BROOM CLOSET	EXIST CS	EXIST VB	EXIST CS	----	EXIST GWB	8'-0"	
105	EXISTING D/B CLOSET	EXIST QT	EXIST QTB	EXIST FRP & QT	----	EXIST PLYWOOD	8'-0"	
106	EXISTING D/B PREP	EXIST QT	EXIST QTB	EXIST CWT	----	EXIST ACT	9'-6"	SEE FINISH SCHEDULE NOTE #6, RE: SHEET A2.02
107	EXISTING DELI/BAKERY FREEZER	EXIST MTP	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
108	EXISTING D/B COOLER	EXIST QT	EXIST QTB	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
109A	EXISTING CORRIDOR #1	EXIST VCT	EXIST VB	EXIST WP	----	EXIST GWB	9'-0"	FINISH SCHEDULE NOTE #1,3,7. RE: SHEET A2.02
109B	EXISTING CORRIDOR #2	EXIST VCT	EXIST VB/NEW VB-1	EXIST WP/NEW WP-2	P-3 (B)	EXIST / NEW ACT-1	12'-0"	FINISH SCHEDULE NOTE #1,3,7. NEW STAINLESS STEEL TRIM AS NECESSARY AT EXPOSED CORNERS.
109C	EXISTING CORRIDOR #3	EXIST VCT	EXIST VB	EXIST WP	----	EXIST GWB	9'-0"	FINISH SCHEDULE NOTE #1,3,7.
109D	EXISTING CORRIDOR #4	EXIST VCT	EXIST VB	EXIST WP	----	EXIST ACT	9'-6"	FINISH SCHEDULE NOTE #1,3,7. REPLACE AND/OR ADD NEW STAINLESS STEEL TRIM AS NECESSARY AT EXPOSED CORNERS
110	EXISTING MEN'S RESTROOM	EXIST PT	EXIST PTB	EXIST PWT	----	EXIST GWB	8'-0"	FINISH SCHEDULE NOTE #6,7.
111	EXISTING WOMEN'S RESTROOM	EXIST PT	EXIST PTB	EXIST PWT	----	EXIST GWB	8'-0"	FINISH SCHEDULE NOTE #6,7.
112	EXISTING DEPT. MANAGER'S OFFICE	EXIST VCT	EXIST VB	EXIST WP	----	EXIST GWB	8'-0"	FINISH SCHEDULE NOTE #1,5,7,9. PAINT ALL EXPOSED WOOD P3 (B)
113	EXISTING MECHANICAL ROOM	EXIST CS	----	EXISTING	----	EXIST EXPOSED STRUCTURE	EXISTING	
114	EXISTING ICE CREAM FREEZER	EXIST MTP	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
115	EXISTING DAIRY COOLER	EXIST CS	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
116	EXISTING UNISEX RESTROOM	EXIST PT	EXIST PTB	EXIST PWT	----	EXIST GWB	8'-1"	FINISH SCHEDULE NOTE #6,7.
117	EXISTING FAMILY RESTROOM	EXIST PT	EXIST PTB	EXIST PWT	----	EXIST GWB	8'-1"	FINISH SCHEDULE NOTE #6,7.
118	EXISTING LOUNGE	EXIST VCT	EXIST VB	EXIST WP	----	EXIST ACT	8'-1"	FINISH SCHEDULE NOTE #1,7.
119	EXIST. GROCERY STAGING/RECEIVING	EXIST CS	----	EXIST UNPAINTED CMU, PLYWOOD & PRE-FAB PNL,	----	EXIST EXPOSED STRUCTURE	EXISTING	
120	EXISTING STORAGE CLOSET	EXIST VCT	EXIST VB	EXIST WP & GWB	----	EXIST GWB	12'-0"	
122	EXISTING ELECTRICAL AREA	EXIST CS	----	EXIST UNPAINTED CMU	----	EXIST EXPOSED STRUCTURE	EXISTING	
123	EXISTING JANITORS CLOSET	EXIST CS & QT	----	EXIST CMU & GWB P-4(B), EXIST QT	----	EXIST PLYWOOD P-4 (B)	8'-0"	FINISH SCHEDULE NOTE #3,13
124	EXISTING PC TRAINING ROOM	EXIST VCT	EXIST VB	EXIST WP	----	EXIST GWB	8'-0"	FINISH SCHEDULE NOTE #1,7,16. PAINT ALL EXPOSED WOOD P-3 (B)
125	EXISTING MEAT OFFICE	EXIST QT	EXIST QTB	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	8'-0"	
126	EXISTING MEAT FREEZER	EXIST MTP	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
127	EXISTING MEAT PREP	EXIST QT	EXIST QTB	EXIST PRE-FAB PNL & FRP	----	EXIST PRE-FAB PNL	10'-0"	
128	EXISTING MEAT COOLER	EXIST QT	EXIST QTB	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
129	EXISTING PRODUCE PREP	EXIST CS	----	EXIST FRP & PRE-FAB PNL	----	EXIST ACT	9'-10"	FINISH SCHEDULE NOTE #2
130	EXISTING PRODUCE COOLER	EXIST CS	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
131	EXISTING STORAGE FREEZER	EXIST MTP	----	EXIST PRE-FAB PNL	----	EXIST PRE-FAB PNL	EXISTING	
132	EXISTING OFFICE	EXIST VCT	EXIST VB	EXIST WP	P-3(B)	EXIST GWB	7'-10"	FINISH SCHEDULE NOTE #1,7. PAINT ALL EXPOSED WOOD P-3 (B)
133	EXISTING DELI/BAKERY STORAGE ROOM	EXIST QT	EXIST QTB	EXIST FRP	----	EXIST PLYWOOD	8'-0"	
134	NEW E-COMMERCE ROOM	NEW VCT-2	NEW VB-1	EXIST/NEW GWB P-3 (B), EXIST WP & NEW WP-2	EXIST/ NEW WOOD TRIM TO MATCH EXIST P-3	EXIST GWB / NEW GWB P-4(C)	12'-0"	----

GENERAL NOTES:

- ALL CONSTRUCTION TO BE TYPE IIB OR BETTER (NCBC)
- REFER TO SHEET A1.04 FOR ADDITIONAL CEILING INFORMATION.
- REFER TO SHEET A2.02 FOR SALES FINISH & A4.03 FOR RESTROOM FINISH LOCATIONS
- REFER TO G1.01 FOR NATIONAL ACCOUNT INFORMATION
- REPLACE ANY BROKEN/ DAMAGED MATERIALS (ACT, FLOOR/WALL TILE, ETC.) TO MATCH EXISTING UNLESS NEW SPECIFICATION IS LISTED.
- DO NOT PAINT POLISHED ALUMINUM TRIM.
- REFER TO A1.05 FOR FLOOR FINISHES.

FINISH SCHEDULE NOTES


- MARLITE BRAND PANELS (MBP): USE TRADITIONAL PROFILE ALUMINUM TRIM PIECES WITH A FACTORY FINISH TO MATCH MARLITE. INSTALL REPLACEMENT MARLITE BRAND PANELS PER MANUFACTURER'S SPECIFICATIONS. USE ONLY ACCEPTABLE MARLITE ACCESSORIES.
 - EXISTING MARLITE PANELING (WP-2) TO REMAIN AND REPAIR AS NEEDED WITH MATCHING PANELS.
 - EXISTING MARLITE PANELING TO BE REPAIRED AS NEEDED, THEN PAINTED P-2(G) - REFER TO SPECIFICATIONS ON PROPER PRIMER, REPAIR & COATING INSTRUCTIONS.
 - SEE FINISH MATERIAL/COLOR LEGEND FOR NEW MARLITE BRAND PANELS (WP-2)
- CAULK 2x6 P.T. WOOD BASEBOARD AT COOLER/FREEZER PANELS & METAL STUD WALLS IN REAR AREA, TOP AND BOTTOM. PAINTED WITH P-4(B).
- ALL GYPSUM WALLBOARD TO BE TAPED, MUDDED AND SANDED (PAINT READY).
- GENERAL CONTRACTOR SHALL PAINT FIRE LANES IN REAR AREAS, IF REQUIRED.
- NEW MILLWORK LAMINATE TO BE WILSONART #4842-60 "CANYON ZEPHYR" MATTE FINISH, REFER TO A4.06, PAINT SUPPORTS P-3(B). NEW LAMINATE IN NON-CUSTOMER FACING OFFICES TO BE WILSONART #899-58 "DESERT BEIGE" MATTE FINISH, REFER TO A4.06, PAINT SUPPORTS P-3(B).
- REFER TO A4.03 & A2.02 FOR RESTROOM TILE & DELI-BAKERY TILE. DOORS AND FRAMES TO BE PAINTED- P-3(B), UNLESS OTHERWISE NOTED. (EXCEPT ALLUM. STOREFRONT DOORS & WINDOWS)
- ALL WOOD TRIM ADJACENT TO OR CASINGS AROUND DOORS, WINDOWS, TOP OF MARLITE, OPENINGS TO BE REMOVED.
- ALL WOOD TRIM AT CEILINGS, TO BE PAINTED P-7(B).
- RESINOUS DECORATIVE FLOORING SHALL BE PURCHASED FROM DUR-A-FLEX INC. (CONTACT: KEVIN STEPHENS 919-208-8662), OR PROTECTIVE INDUSTRIAL POLYMERS (CONTACT: STEVE MCCAMEY AT 804-937-5000).
- PROVIDE 1/2" GYP. BD. OVERLAY ON EXISTING CEILING FINISH, TAPE, MUD, SAND AND PREP FOR NEW PAINT AS INDICATED. TEMPORARILY UN-INSTALL EXISTING LIGHT FIXTURE AS REQUIRED TO INSTALL OVERLAY.
- PRE-FAB COOLER/FREEZER PANELS AND DOORS TO BE PAINTED P-18(C). COORDINATE PAINT METHOD W/FOOD LION CONSTRUCTION MANAGER.
- COORDINATE WITH FOOD LION CONSTRUCTION MANAGER FOR PAINTING OF WALLS, DOORS & FRAMES.
- PROVIDE 4" HIGH FIRE RETARDANT (FRT) PLYWOOD WITH FRT 2X6 WOOD BASE @ EXPOSED COOLER FREEZER WALLS - PAINT BASE PER NOTE #2 AND LEAVE PLYWOOD UNFINISHED.
- ALL WALLS BELOW 8' WITHOUT WALL PANELING SHALL BE PAINTED WITH P-7(A), EXCEPT THE SALES FLOOR WILL RECEIVE NEW WALL COVERING (SEE A2.02).
- SAFE AND SAFE TRIM TO BE PAINTED P-3(B) ON SALES AREA SIDE AND P-3(B) ON WORK ROOM SIDE. (HAND MACHINE ROLLED NOT BRUSHED).
- ALL SALES FLOOR GWB WALLS TO RECEIVE SHERWIN WILLIAMS PROBLOCK OIL BASED PRIMER PRIOR TO PAINTING - SALES FLOOR ONLY.
- REMOVE 2X6 WOOD BASE. APPLY RESINOUS FLOORING DIRECTLY TO CMU, FRP, AND COOLER WALLS. RESINOUS COVE BASE TO MATCH HEIGHT OF REMOVED WOOD BASE.
- SALES AREA COLUMNS TO BE SANDED, PRIMED & PAINTED P-7(B) EPOXY. DO NOT PAINT STAINLESS STEEL WRAPS.
- CONFERENCE ROOM CARPET TO VCT TRANSITION STRIP TO BE ARMSTRONG VT 060 (BLACK).



2600 Maitland Center Parkway
Suite #200
Maitland, FL 32751
P (407) 661-9100
F (407) 661-9101
c-p.com
Florida Corporate Certificate #AA C000526

COPYRIGHT © 2021 - ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES & OTHER DOCUMENTS ARE INSTRUMENTS OF SERVICE PREPARED BY CUHACI PETERSON. (CP) AS INSTRUMENTS OF SERVICE REMAIN THE PROPERTY OF CP. CP SHALL RETAIN ALL COMMON LAW, STATUTORY AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THEREIN. ANY USE OR REPRODUCTION OF THIS DOCUMENT WITHOUT WRITTEN PERMISSION FROM CP IS A VIOLATION OF FEDERAL COPYRIGHT LAWS.

ARCHITECT/ENGINEER SEAL
04/14/2023



MARCUS JAMES BOYLE
NC 16078

CONSULTANT

FOOD LION

2110 EXECUTIVE DRIVE
SALISBURY, NC 28145
PH: 704-633-8250 FX: 704-636-4940

REVISION / ISSUE HISTORY

REV	DATE	REVISION / ISSUE NAME
-	04/14/2023	PERMIT

PROJECT NO 2220380 DRAWN BY JB

PERMIT SUB DATE 04/14/2023 CHECKED BY RD

PROJECT FOOD LION STORE #2594
3260 RAY ROAD
SPRING LAKE, NC 28390
2594FLMK23

CLIENT FOOD LION
2110 EXECUTIVE DRIVE
SALISBURY, NC 28145
PH: 704-633-8250 F: 704-636-5940

SHEET TITLE ROOM FINISH SCHEDULE

SHEET NO 2594A6.01_00 REV A6.01

FINISH MATERIAL/COLOR LEGEND:

FLOORS: (SEE SHEETS A1.05 & FOR SPECIFIC MATERIALS)

RESINOUS
R-1 RESINOUS TOPPING - COLOR FOOD LION #FL105. SEE FINISH SCHEDULE NOTE #10.
R-2 RESINOUS TOPPING - COLOR FOOD LION #FL106. SEE FINISH SCHEDULE NOTE #10.

CARPET
CPT-1 CARPET-PORTRICO DIPLOMAT "MINK"
CPT-2 CARPET- MOHAWK RESTORE "EMERGE" #358
CPT-3 CARPET- OAK CHARCOAL #4307

CONCRETE
CS CONCRETE SEALER
QT QUARRY TILE

PORCELAIN TILE
PT-1 DAL TILE - REMINISCENT SERIES, "DECLAINED GRAY" #RM23 UNPOLISHED 12"x12" FLOOR TILE (SEE G9 FOR GROUT DETAILS)
PT-2 DAL TILE - REMINISCENT SERIES, "MOMENTO WHITE" #RM20 12"x12" FLOOR TILE (SEE G9 FOR GROUT DETAILS)

CERAMIC TILE
CT-1 DAL TILE - HEATHLAND SERIES, "AMBER HLO3" 12"x12" GLAZED CERAMIC FLOOR TILE (SEE G10 FOR GROUT DETAILS)

VINYL TILE
VCT-1 VINYL COMPOSITION TILE ARMSTRONG RAFIA-COCCA 5805 12"x24"
VCT-2 VINYL COMPOSITION TILE- EXCELON IMPERIAL TEXTURE "EARTHSTONE GREIGE" 12"x12"
VCT-3 VINYL COMPOSITION TILE- EXCELON IMPERIAL TEXTURE "ANTIQUE WHITE" 12"x12"

OTHER
WM WALK-OFF MAT-PORTRICO SYSTEMS "DIPLOMAT"
MTP METAL TREAD PLATE

BASE:

RESINOUS
RB-1 RESINOUS TOPPING, FL105, TURNED UP WALL. SEE SHEET A3.02.
RB-2 RESINOUS TOPPING, FL106, TURNED UP WALL. SEE SHEET A3.02.

PORCELAIN
PTB-1 DAL TILE - REMINISCENT SERIES, "MOMENTO WHITE" #RM20 6"x12" (SEE G8 FOR GROUT DETAILS). 12"x12" TILE CUT IN FIELD TO CREATE 6"x12" TILE TO BE USED WITH SCHLÜTER DILEX-EHK STAINLESS COVE BASE.

CERAMIC
CTB-1 DAL TILE - AFFINITY SERIES, "BEIGE AF02" P-4309 3"x12" (SEE G7 FOR GROUT DETAILS).

VINYL
VB-1 4" VINYL COVE BASE BY JOHNSONITE- MATTE BLACK 40

QUARRY TILE BASE
QTB QUARRY TILE BASE

OTHER
MTPB METAL TREAD PLATE BASE
MQBR MCQUE BOY RAIL
WD 2x6 P.T. WOOD

CEILING FINISHES: (SEE SHEET A1.04)

ACT-1 2X4 ARMSTRONG HUMAGUARD PLUS IN PRELUDE XL GRID
ACT-2 2X4 2" FOAM DOUBLE SIDED FIBERLITE FRP PANEL BY NUDO PRODUCTS
ACT-3 2X4 ARMSTRONG VINYL CLAD TILE IN PRELUDE XL GRID

FRP FIBER REINFORCED PANEL
GWB PAINTED GYPSUM BOARD

TRIM:
STAINLESS
ST-1 SCHLUTER- DILEX-EHK EBHKU11-011 STAINLESS STEEL COVE BASE
ST-2 SCHLUTER- RONDEC R0100E STAINLESS STEEL TRIM

ACROVYN
CR-1 ACROVYN 4000 FR-225N ACCENT RAIL (BLACK)

WALLS SURFACES: (REFER TO A2.02 & A4.03)

CERAMIC WALL TILE
CWT-1 DAL TILE-"DESERT GRAY" X114 6"x6" SEE (G2) FOR GROUT DETAILS
CWT-2 DAL TILE-"ARCTIC WHITE" 0190 6"x6" SEE (G3) FOR GROUT DETAILS
CWT-3 DAL TILE-"AFFINITY SERIES" "BEIGE AF02" 10x14" SEE (G7) FOR GROUT DETAILS
CWT-4 DAL TILE-BRIXTON SERIES "MUSHROOM" BX03 9"x12" (MATCH EXISTING GROUT)
CWT-5 DAL TILE-"URBAN PUTTY" 0161 SEMI-GLOSS 4"x12" SEE G7 FOR GROUT DETAILS
CWT-6 DAL TILE-"URBAN PUTTY" 0161 MATTE 4"x12" SEE G7 FOR GROUT DETAILS
CWT-7 DAL TILE-"ARCHITECTURAL GRAY" 0109 SEMI-GLOSS 6"x6" SEE G7 FOR GROUT DETAILS
CWT-8 DAL TILE-"ARTISAN BROWN" 0144 SEMI-GLOSS 1"x6" SEE G7 FOR GROUT DETAILS

PORCELAIN WALL TILE
PWT-1 DAL TILE REMINISCENT SERIES, "MOMENTO WHITE" #RM20 UNPOLISHED 12"x12" WALL TILE (SEE G8 FOR GROUT DETAILS)

WALL PANELS/COVERING
WP-1 WHEAT #5347-S4 MARLITE PANEL
WP-2 CODY #194 MARLITE PANEL
WP-3 LAREDO OAK #324-S2 MARLITE PANEL
WP-4 PLANTATION OAK #323-S2 MARLITE PANEL
WP-5 PAINTABLE WHITE #1001-BG2 MARLITE PANEL
WP-6 MORNING HAZE #5446-S2 MARLITE PANEL
WP-7 PEARL GRAY ACROVYN WALL COVERING
WP-8 (NOT USED)
WP-9 WHITE P-100 MARLITE FRP
WP-10 ALMOND P-118 MARLITE FRP

PLASTIC LAMINATE:
PL-1 WILSONART "CANYON ZEPHYR" (MATTE FINISH)
PL-2 WILSONART "DESERT BEIGE" (MATTE FINISH)

INTERIOR WALL FINISH PAINTING LEGEND:

(A) EG-SHEL LATEX
(B) SEMI-GLOSS EPOXY
(C) LOW GLOSS EPOXY
(D) FLAT
(E) ELECTROSTATIC SEMI GLOSS
(F) EG-SHEL EPOXY
(G) SEMI-GLOSS LATEX

INTERIOR GROUT FINISH LEGEND:

(G1) TO USE GROUT: CUSTOM BUILDING PRODUCTS "TRUFFLE" #540
(G2) TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER GRAY" #386
(G3) TO USE GROUT: CUSTOM BUILDING PRODUCTS "NEW TAUPE" #185
(G4) TO USE GROUT: CUSTOM BUILDING PRODUCTS "STONE" #362
(G5) TO USE GROUT: CUSTOM BUILDING PRODUCTS "OYSTER" #381
(G6) TO USE GROUT: CUSTOM BUILDING PRODUCTS "NATURAL" #09
(G7) TO USE GROUT: CUSTOM BUILDING PRODUCTS "LINEN" #122
(G8) TO USE GROUT: CUSTOM BUILDING PRODUCTS "CAPE GRAY" #546
(G9) TO USE GROUT: CUSTOM BUILDING PRODUCTS "WINTER GRAY" #355
(G10) TO USE GROUT: CUSTOM BUILDING PRODUCTS "SAHARA TAN" #22

NOTE: USE A 1/16" JOINT FOR CERAMIC TILE. USE A 3/16" JOINT FOR PORCELAIN TILE. ALL FLOOR TILE GROUT SHALL BE CEG-IG 100K SOLIDS INDUSTRIAL GRADE EPOXY GROUT BY CUSTOM BUILDING PRODUCTS (COLOR AS INDICATED IN DRAWINGS).

PAIN: (REFER TO A2.02)

P-1 PAINT "SOFTER TAN" SW6141
P-2 PAINT "ELLIE GRAY" SW7650
P-3 PAINT "MACADAMIA" SW6142
P-4 PAINT "PURE WHITE" SW7005
P-5 PAINT "ORGANIC GREEN" SW6732
P-6 PAINT "CRIZLE GRAY" SW7058
P-7 PAINT "MARSHMALLOW" SW7001
P-8 PAINT "HIGHWAY TRAFFIC WHITE"
P-9 PAINT "POPULAR GRAY" SW6071
P-10 PAINT "TONY TAUPE" SW7038
P-11 PAINT "ENDURING BRONZE" SW7055
P-12 PAINT "TRAFFIC YELLOW"
P-13 PAINT "MEDITATIVE" SW6227
P-14 PAINT "INKWELL" SW6992
P-15 PAINT "MEGA GREIGE" SW7031
P-16 PAINT "PANEW GRAY" SW7030
P-17 PAINT "TROMAN COLUMN" SW7562
P-18 PAINT "SMOKY BEIGE" SW9087