



2600 Maitland Center Parkway Suite #200 Maitland, FL 32751

P (407) 661-9100 F (407) 661-9101 C-p.com Florida Corporate Certificate #AA C000526

COPYRIGHT © 2021 - ALL REPORTS, PLANS, SPECIFICATIONS, COMPUTER FILES, FIELD DATA, NOTES & OTHER DOCUMENTS ARE INSTRUMENTS OF SERVICE PREPARED BY: CUHACI PETERSON, (CP) AS INSTRUMENTS OF SERVICE REMAIN THE PROPERTY OF CP. CP SHALL RETAIN ALL COMMON LAW, STATUTORY, AND OTHER RESERVED RIGHTS, INCLUDING THE COPYRIGHT THERETO. ANY USE OR REPRODUCTION OF THIS DOCUMEN' WITHOUT WRITTEN PERMISSION FROM CP IS A VIOLATION OF FEDERAL

ARCHITECT/ENGINEER SEAL



CONSULTANT

HAAS & KENNEDY ENGINEERS, P.A.

ELECTRICAL ENGINEERS

212 N. McDOWELL — SUITE 100
P.O. BOX 37291
CHARLOTTE, NORTH CAROLINA 28237
(704) 333-6590 FAX (704) 343-0075

DRAWN BY: KAK
CHECKED BY: HK
PROJECT NO: 23043

FOOD 鴉 LION

2110 EXECUTIVE DRIVE SALISBURY, NC 28145 PH: 704-633-8250 FX: 704-636-4940

REVISION / ISSUE HISTORY			
REV	DATE	RE	EVISION / ISSUE NAME
	04/14/2023	PERMI	Т
	<u> </u>		
PROJECT NO			DRAWN BY
2220380			KAK
PERMIT SUB DATE			CHECKED BY

PROJECT FOOD LION STORE #2594

HCK

3260 RAY ROAD SPRING LAKE, NC 28390 2594FLMK23

CLIENT

04/14/2023

FOOD LION

2110 EXECUTIVE DRIVE SALISBURY, NC 28145 PH: 704-633-8250 F: 704-636-5940

SHEET TITLE

ELECTRICAL DEMOLITION

E0.01

SHEET NO 2594E0.01_00



ELECTRICAL DEMOLITION GENERAL NOTES

- 1. ALL ACCESSIBLE ITEMS OF ELECTRICAL EQUIPMENT CONDUITS, WIRING, LIGHTS, RECEPTACLES, ETC. AFFECTED BY THE RENOVATION WORK AND NOT REQUIRED IN THE COMPLETED WORK SHALL BE CAREFULLY REMOVED. DAMAGED WALLS, FLOORS, CEILINGS, ETC. SHALL BE PATCHED AND FINISHED TO MATCH THE EXISTING ADJACENT SURFACES. REMOVED ITEMS SHALL BE PROPERLY DISPOSED OF OFF SITE AND NOT RE-USED EXCEPT AS NOTED. TURN OVER ALL EXISTING EQUIPMENT DESIRED BY BUILDING OWNER. ITEMS TO BE RE-USED SHALL BE CAREFULLY REMOVED AND STORED IN A PROTECTED AREA.
- REMOVE EXISTING CIRCUITS IN PANELS NOT REQUIRED FOR COMPLETED WORK. UTILIZE EXISTING BREAKERS FOR NEW WORK SHOWN. PROVIDE NEW BREAKERS AS REQUIRED TO SERVE NEW CIRCUITS. LABEL ALL BREAKERS. LABEL ALL BREAKERS NOT USED AS SPARE.
- 3. RECONNECT CIRCUITS AS REQUIRED TO MAINTAIN CONTINUITY TO EXISTING DEVICES AND EQUIPMENT NOTED TO REMAIN AS WELL AS ADJACENT AREAS WHICH ARE NOT IN CONTRACT.
- 4. REMOVE UNUSED CONDUIT AND WIRE BACK TO SOURCE.
- 5. ALL WIRING SHALL BE DONE IN STRICT ACCORDANCE WITH N.E.C. STANDARDS AND WITH FOOD LION STANDARDS. ALL WORK SHALL BE OF FIRST QUALITY. NO HAZARDOUS WORK WILL BE ACCEPTED. ELECTRICAL CONTRACTOR IS TO MAKE SURE THAT NO MC OR FLEX CABLES ARE USED UNLESS OTHERWISE NOTED. MC OR FLEX CABLES CAN ONLY BE USED IN SHORT RUNS FOR LIGHTING FEEDS. EMT MUST BE USED TO CONNECT PANEL TO JUNCTION BOX AND HAVE COMPRESSION TYPE FITTINGS. SEE SPECIFICATIONS FOR STANDARD PRACTICES.
- 6. DO NOT DISRUPT THE PULL STATIONS, SAFE, OR ANY COMPONENT OF THE FIRE OR SECURITY SYSTEM WITHOUT FIRST CONTACTING FOOD LION PHYSICAL SECURITY AT (704) 633-8250 ext.
- 7. THE ELECTRICAL CONTRACTOR SHALL REVIEW THE HAZARDOUS MATERIAL REPORT, IF APPLICABLE, AND COORDINATE ALL HAZARDOUS MATERIAL REMOVAL WITH THE FOOD LION CONSTRUCTION
- 8. THE ELECTRICAL CONTRACTOR SHALL PHOTOGRAPH OR VIDEOTAPE EXISTING CONDITIONS IN AND AROUND THE STORE PRIOR TO BEGINNING CONSTRUCTION. PARTICULAR ATTENTION SHOULD BE DIRECTED TO THE CEILING, ALL LIGHTING AND PANELS.
- THE ELECTRICAL CONTRACTOR SHALL COORDINATE REMOVAL/RELOCATION OF LOTTERY EQUIPMENT WITH THE GENERAL CONTRACTOR AND THE FOOD LION CONSTRUCTION MANAGER.
- O. ANY WORK IN REST ROOMS TO BE SCHEDULED TO ALLOW FOR AT LEAST ONE TO REMAIN OPEN AT ALL TIMES. COORDINATE WITH FOOD LION CONSTRUCTION MANAGER. PROPER SIGNAGE MUST BE INSTALLED WITH UNISEX RESTROOMS, USE SLIDE LOCK. PROVIDED BY FOOD LION.
- 11. THE GENERAL CONTRACTOR SHALL COORDINATE THE REMOVAL, RELOCATION AND RETENTION OF THE EXISTING SALES AREA LIGHTING WITH THE ELECTRICAL CONTRACTOR. THE ELECTRICAL CONTRACTOR SHALL REMOVE ANY SPOTLIGHTS FROM THE SALES AREA UNLESS NOTED TO REMAIN.

ELECTRICAL DEMOLITION KEYED NOTES

- 1 REFRIGERATED CASE TO BE REMOVED/RELOCATED. COORDINATE REQUIREMENTS WITH THE REFRIGERATION CONTRACTOR. SEE E1.03 FOR NEW LOCATION OF RELOCATED CASES.
- 2 ELECTRICAL CONTRACTOR SHALL DISCONNECT CHECKSTAND AND ASSOCIATED EQUIPMENT, MACRO SHALL PULL ALL POINT OF SALE EQUIPMENT, FOOD LION VENDOR SHALL REMOVE AND DISPOSE OF CHECKSTANDS. CIRCUITRY TO REMAIN FOR REUSE. EXISTING CIRCUITRY TO REMAIN FOR CONNECTION TO NEW EQUIPMENT.
- 3 EXISTING CUSTOMER SERVICE KIOSK TO BE REMOVED. EXTEND EXISTING CIRCUITS TO NEW CUSTOMER SERVICE KIOSK AS REQUIRED.
- 4 EQUIPMENT TO BE REMOVED/RELOCATED. DISCONNECT AS REQUIRED. REMOVE DEVICES, WIRE, CONDUITS, ETC. AND LABEL BREAKERS AS SPARE FOR NON-REUSED CIRCUITS. SEE E1.02 AND E1.03 FOR LOCATION OF NEW AND RELOCATED EQUIPMENT.
- 5 REMOVE OR CAP ANY UNUSED ELECTRICAL DEVICES, WIRING AND CONDUIT LOCATED ON FRONT EXTERIOR. FIELD VERIFY EXTENT OF WORK.
- 6 TRELLIS/TRACK, LIGHTING FIXTURES AND ASSOCIATED EQUIPMENT TO BE REMOVED. SEE SHEET
- E1.01 FOR EXENDED AND RE-USED LIGHTING CIRCUITS.

 7 LIGHTING FIXTURE TO BE REMOVED/RELOCATED. SEE SHEET E1.01 FOR NEW FIXTURE LOCATIONS AND INFORMATION ON REUSED CIRCUITS.
- (8) REMOVE ALL WIRING, CAP OFF RECESSED BOXES, REMOVE SURFACE MOUNTED BOXES AND/OR
- CONDUITS WITHIN PROPANE EXCHANGE CLEARANCE AREA. FIELD VERIFY EXTENT OF WORK.

 9 WALL SECTION TO BE DEMOLISHED. REMOVE ALL AFFECTED DEVICES, CONDUIT, WIRE, ETC. MAKE
- PROVISIONS AS NECESSARY TO MAINTAIN DOWNSTREAM LOADS.
- ① EXISTING OFFICE AREA TO BE RENOVATED. REMOVE ALL WALL MOUNTED ELECTRICAL ASSOCIATED WITH MILLWORK/CASEWORK TO BE REMOVED THIS AREA. MAKE PROVISIONS AS REQUIRED TO MAINTAIN DOWNSTREAM LOADS.

NOTE:
REMOVE ANY JUNCTION BOXES THAT DO NOT FALL UNDER THE GONDOLAS. PATCH AND/OR REPAIR THE FLOOR WHERE EXISTING JUNCTION BOXES ARE REMOVED. COORDINATE WITH THE FOOD LION CONSTRUCTION MANAGER.

ATM NOTE:

ELECTRICAL CONTRACTOR SHALL NOT UNPLUG ATM FOR ANY REASON. NO ONE IS ALLOWED TO USE THE ELECTRICAL OUTLET OR PHONE LINE JACK FOR ANY REASON. IT IS ILLEGAL TO ATTACH ANY DEVICE TO THE ATM LINE FOR ANY REASON. THE ONLY PEOPLE ALLOWED TO UNPLUG THE ATM ARE NATIONWIDE SERVICE AND THE COMPANY THAT REPLENISHES CASH IN THE ATM. COORDINATE ANY AND ALL WORK ASSOCIATED WITH THE ATM WITH FOOD LION CONSTRUCTION SUPERVISOR AND NATIONWIDE SERVICE AND/OR THE COMPANY THAT REPLENISHES CASH.

SPECIAL REPAIR NOTES

(D-XXX) INDICATES CRESCENT CONSTRUCTION SERVICES REPORT DEFICIENCY. SEE SHEET E6.03 FOR LIST OF CRESCENT REPAIR NOTES.