

PLUMBING GENERAL NOTES

GENERAL REQUIREMENTS:

- GENERAL AND SPECIAL CONDITIONS: GENERAL AND SPECIAL CONDITIONS ARE HEREBY MADE AN INTEGRAL PART OF THIS DIVISION OF THE SPECIFICATIONS INsofar AS SAME ARE APPLICABLE TO THE WORK UNDER THIS DIVISION AND UNLESS OTHERWISE SPECIFIED.
- SCOPE PROVIDE ALL LABOR, MATERIAL AND EQUIPMENT REQUIRED FOR THE COMPLETION AND OPERATION OF ALL SYSTEMS IN THIS SECTION OF WORK IN ACCORDANCE WITH ALL APPLICABLE CODES.
- PERMITS: APPLY FOR AND PAY FOR ALL NECESSARY PERMITS, FEES, AND INSPECTIONS REQUIRED BY ANY PUBLIC AUTHORITY HAVING JURISDICTION.
- WARRANTY: PROVIDE ALL MATERIALS AND EQUIPMENT UNDER THIS SECTION OF THE SPECIFICATIONS WITH A ONE YEAR WARRANTY FROM THE DATE OF ACCEPTANCE OF WORK BY THE OWNER.
- COORDINATION: VERIFY ALL ROUGH-IN LOCATIONS AND COORDINATE PIPING AND EQUIPMENT LOCATIONS WITH WORK UNDER OTHER DIVISIONS OF THE SPECIFICATIONS TO AVOID CONFLICTS. CONTRACTOR MUST COORDINATE WITH OTHER TRADES FOR ALL STRUCTURES, PIPING, CONDUIT, DUCTWORK, LIGHTING, ETC. TO PROPERLY BE INSTALLED. ANY CONFLICTS SHALL BE RESOLVED AT NO CHARGE TO THE OWNER. COORDINATE INSTALLATION OF ALL PLUMBING LINES AT CMU WALLS SO THAT PLUMBING LINES ARE PLACED IN WALL DURING CMU WALL CONSTRUCTION. CUTTING AND PATCHING OF CMU WALLS IN PLACE WILL NOT BE PERMITTED.
- FIELD VERIFICATION: FIELD VERIFY EXISTING CONDITIONS BEFORE STARTING CONSTRUCTION AND NOTIFY THE ARCHITECT/ENGINEER OF RECORD OF ANY DISCREPANCIES BETWEEN THE CONSTRUCTION DOCUMENTS AND EXISTING CONDITIONS AND/OR ANY POTENTIAL PROBLEMS OBSERVED BEFORE CONTINUING WORK IN THE EFFECTED AREAS.
- PLUMBING SYSTEMS INCLUDE, BUT ARE NOT LIMITED TO:
 - PLUMBING FIXTURES AND EQUIPMENT
 - FIRE STOPPING
 - DOMESTIC WATER SYSTEM
 - SANITARY WASTE AND VENT SYSTEM
 - GAS SYSTEM
 - STORM DRAIN/SEWER SYSTEM

FIXTURES:

- PROVIDE COMPLETE FIXTURES AND INCLUDE SUPPLIES, STOPS, VALVES, FAUCETS, DRAINS, TRAPS, TAIL PIECES, ESCUTCHEONS, ETC.

FIRE STOPPING:

- FIRE STOP ALL PENETRATIONS, BY PIPING OR CONDUITS, OF FIRE RATED WALLS, FLOORS AND PARTITIONS, PROVIDE A DEVICE(S) OR SYSTEM(S) WHICH HAS BEEN TESTED AND LISTED AS COMPLYING WITH ASTM E-814 AND INSTALL IN ACCORDANCE WITH THE CONDITIONS OF THEIR LISTING. PROVIDE A DEVICE(S) OR SYSTEM(S) WITH AN "F" RATING EQUAL TO THE RATING OF THE ASSEMBLY BEING PENETRATED.

DOMESTIC WATER:

- FURNISH AND INSTALL A COMPLETE SYSTEM OF HOT AND COLD WATER, AND WASTE PIPING FROM EXISTING SUPPLIES TO ALL FIXTURES AND/OR EQUIPMENT REQUIRING THIS SERVICE. VERIFY LOCATION OF BEGINNING POINTS.
- DOMESTIC WATER PIPING BELOW GRADE: SOFT ANNEALED SEAMLESS COPPER TUBING, TYPE "K" WITH NO JOINTS BELOW GRADE (ASTM B 88).
- DOMESTIC WATER PIPING AND JOINTS ABOVE GRADE: HARD DRAWN SEAMLESS COPPER TUBING, TYPE "L" WITH 95-5 SILVER SOLDERED JOINTS (ASTM B 88), CPVC AND OR CROSS-LINKED POLYETHYLENE (PEX TYPE A) (ASTM F877). PLASTIC HOT AND COLD WATER DISTRIBUTION IS ALLOWED WHERE PERMISSIBLE AND PRE-APPROVED.
- STERILIZE DOMESTIC WATER PIPING IN ACCORDANCE WITH THE AMERICAN WATER WORKS ASSOCIATION'S SPECIFICATIONS AND LOCAL HEALTH DEPARTMENT REGULATIONS.
- INSULATE DOMESTIC WATER PIPING ABOVE GRADE (EXCEPT EXPOSED CONNECTIONS TO PLUMBING FIXTURES) WITH ENGINEERED POLYMER FOAM INSULATION OR FIBERGLASS WITH FITTING INSERTS AND PVC COVERS. FOLLOW THIS SCHEDULE:

SERVICE	PIPE SIZE	INS. THICKNESS
DOMESTIC HOT WATER (105-140 DEG F)	1/2" - 1-1/2"	1/2"
DOMESTIC HOT WATER (105-140 DEG F)	2" AND UP	3/4"
DOMESTIC HOT WATER (140-160 DEG F)	ALL	1"
DOMESTIC HOT WATER CIRCULATION	ALL	1/2"
DOMESTIC COLD WATER	ALL	1/2"
- DOMESTIC WATER PIPING INSULATION, JACKETS, COVERINGS, SEALERS, MASTICS AND ADHESIVES ARE REQUIRED TO MEET A FLAME-SPREAD RATING OF 25 OR LESS AND A SMOKE-DEVELOPED RATING OF 50 OR LESS, AS TESTED BY ASTM E84 (NFPA 255) METHOD.
- DO NOT INSTALL DOMESTIC WATER PIPING IN AREAS SUBJECT TO FREEZING TEMPERATURES. INSTALL WATER PIPING IN EXTERIOR WALLS ON THE CONDITIONED SIDE OF THE WALL INSULATION.
- SHUT OFF VALVES: PROVIDE FULL PORT, BALL TYPE, AND INSTALL IN A LOCATION THAT PERMITS ACCESS FOR SERVICE WITHOUT DAMAGE TO THE BUILDING OR FINISHED MATERIALS. PROVIDE ACCESS DOORS IF REQUIRED.
- PROTECT COPPER PIPING AGAINST CONTACT WITH DISSIMILAR METALS. ALL HANGERS, SUPPORTS, ANCHORS, AND CLIPS SHALL BE COPPER OR COPPER PLATED. WHERE COPPER PIPING IS CARRIED ON IRON TRAPEZE HANGERS WITH OTHER PIPING, PROVIDE A PERMANENT ELECTROLYTIC ISOLATION MATERIAL TO PREVENT CONTACT WITH OTHER METALS.
- PROTECT COPPER PIPING AGAINST CONTACT WITH ALL MASONRY. WHERE COPPER IS SLEEVED THROUGH MASONRY, PROVIDE COPPER OR RED BRASS SLEEVES. WHERE COPPER MUST BE CONCEALED IN OR AGAINST MASONRY PARTITIONS, PROVIDE A HEAVY COATING OF ASPHALTIC ENAMEL ON THE COPPER PIPING AND 1# ASPHALT SATURATED FELT BETWEEN THE PIPING AND THE MASONRY PARTITION.
- HOSE BIBS SHALL BE PROVIDED WITH A NON-REMOVABLE VACUUM BREAKER.
- FURNISH BURST PROOF BRAIDED FLEXIBLE CONNECTORS FOR SINK CONNECTIONS AND CONNECTIONS TO EQUIPMENT.

- PROVIDE ZURN WILKINS MODEL 740 (OR EQUAL) BACKFLOW PREVENTION TYPE VACUUM BREAKER FOR ICE MACHINE, CARBONATOR AND OTHER EQUIPMENT AS REQUIRED BY CODE.
- P.C. SHALL VERIFY THE INCOMING WATER PRESSURE AND PROVIDE A PRESSURE REDUCING VALVE IF PRESSURE IS 80 PSI OR GREATER.
- P.C. SHALL INSTALL HAMMER ARRESTORS ON PROJECTS THAT USE QUICK CLOSING DEVICES SUCH AS FLUSH VALVES, ICE MAKER, WASHER MACHINES, ETC., SIZED PER MANUFACTURER RECOMMENDATIONS.
- P.C. SHALL PROVIDE ALL WATER HEATERS (WATTAGE/INPUT AND CAPACITY AS NOTED IN SCHEDULE), ALL WATER HEATERS SHALL BE THIRD PARTY CERTIFIED; PROVIDE PANS FOR WATER HEATERS IN ACCORDANCE WITH 504.7 OF THE NC PLUMBING CODE. ELECTRICAL CONNECTIONS SHALL BE BY ELECTRICAL CONTRACTOR, P.C. SHALL COORDINATE WITH EC ON ELECTRICAL CHARACTERISTICS OF THE EQUIPMENT PROVIDED.
- ALL PUMPS SHALL BE RATED FOR TRANSPORT OF POTABLE WATER. PUMPS IN AN INDIVIDUAL WATER SUPPLY SYSTEM SHALL BE CONSTRUCTED AND INSTALLED SO AS TO PREVENT CONTAMINATION FROM ENTERING THE WATER SUPPLY SYSTEM.

SANITARY WASTE AND VENT PIPING:

- FURNISH AND INSTALL COMPLETE SYSTEMS OF SOIL, WASTE, AND VENT PIPING FROM ALL PLUMBING FIXTURES, AND/OR OTHER EQUIPMENT. ALL SOIL, WASTE AND VENT LINES SHALL BE CONCEALED IN THE BUILDING CONSTRUCTION WHERE POSSIBLE.
- INVERT ELEVATIONS SHALL BE ESTABLISHED AND VERIFIED BEFORE WASTE PIPING IS INSTALLED IN ORDER THAT PROPER SLOPES WILL BE MAINTAINED.
- SANITARY WASTE AND VENT PIPING AND FITTINGS: SERVICE WEIGHT CAST IRON, HUB AND SPIGOT TYPE WITH COMPRESSION JOINTS (ASTM A 74) OR NO-HUB PIPING WITH COUPLINGS (CISPI 301).
 - IF PERMITTED BY LOCAL CODES, SCHEDULE 40 PVC (ASTM D 2665) WITH SCHEDULE 40 SOCKET-TYPE PIPE FITTINGS (ASTM D 3311) MAY BE USED. DO NOT INSTALL PVC PIPING IN RETURN AIR PLENUMS. PVC FOAM CORE DWV PIPING NOT PERMITTED.
- SLOPE SANITARY WASTE PIPING 2-1/2" AND SMALLER AT 1/4" PER FOOT MIN. SLOPE SANITARY WASTE PIPING 3" AND LARGER AT 1/8" PER FOOT MINIMUM.
- WHERE WASTE PIPING IS EXPOSED IN REST ROOM AREAS, PROVIDE CHROME PLATED BRASS PIPING, WITH MATCHING STOPS AND ESCUTCHEONS. PROVIDE REMOVABLE TRAPS WITH INTEGRAL CLEAN-OUT PLUG FOR ALL LAVATORIES.
- INSTALL CLEAN-OUTS IN A LOCATION THAT PERMITS ACCESS FOR SERVICE WITHOUT DAMAGE TO THE BUILDING OR FINISHED MATERIALS. PROVIDE CLEANOUTS AT THE BASE OF ALL WASTE STACKS, AT ALL CHANGE IN DIRECTION OF PIPING IN EXCESS OF 45 DEGREES AND EVERY 100 FEET.
- ALL INDIRECT WASTE CONNECTIONS TO BE INSTALLED WITH AN AIR GAP BETWEEN INDIRECT WASTE PIPE AND THE FLOOD RIM OF THE WASTE RECEPTOR SHALL BE MINIMUM OF TWICE THE EFFECTIVE OPENING OF THE INDIRECT WASTE PIPE.
- ROOF PENETRATIONS SHALL MAINTAIN A MINIMUM CLEARANCE OF 16" BETWEEN PENETRATIONS.
- PLUMBING VENTS SHALL BE INSTALLED WITH MINIMUM HEIGHTS AS REQUIRED BY LOCAL JURISDICTION HAVING AUTHORITY.

BACKFLOW PREVENTION:

- VERIFY BACKFLOW PREVENTOR REQUIREMENTS OF LOCAL AUTHORITY AND PROVIDE BACKFLOW PREVENTION DEVICES AS REQUIRED. COORDINATE LOCATION WITH OTHER TRADES.

WATER METER:

- VERIFY DOMESTIC WATER METER REQUIREMENTS OF LOCAL AUTHORITY AND PROVIDE DOMESTIC WATER METER AS REQUIRED. COORDINATE LOCATION WITH OTHER TRADES.

SEISMIC REQUIREMENTS:

- PROPERLY SUPPORT AND BRACE VERTICALLY AND HORIZONTALLY ALL PIPING, APPARATUS, EQUIPMENT, ETC. IN ACCORDANCE WITH APPLICABLE CODES TO PREVENT EXCESSIVE MOVEMENT DURING SEISMIC CONDITIONS.

GAS PIPING:

- WORK TO INCLUDE PIPING FROM GAS METER TO GAS FIRED EQUIPMENT. PLUMBING CONTRACTOR TO PROVIDE SHUT-OFF VALVE, DIRT TRAP AND PRESSURE REGULATOR AT THE GAS FIRED EQUIPMENT.
- ALL WORK SHALL BE IN ACCORDANCE WITH ALL APPLICABLE LOCAL CODE REQUIREMENTS AND THE PROVISIONS OF NFPA-54 AND NFPA-98.
- THE CONTRACTOR SHALL SUPPLY ALL PERMITS, FEES AND LICENSES REQUIRED FOR THE WORK AND FOR ALL INSPECTIONS REQUIRED.
- PIPE 3" AND SMALLER SHALL BE SCHEDULE 40 STEEL WITH THREADED MALLEABLE FITTINGS.
- VALVES SHALL BE GAS COCKS MANUFACTURED BY NIBCO.
- ALL PIPING EXPOSED TO THE OUTDOORS OR RUN IN UNCONDITIONED SPACES SHALL BE PAINTED WITH TWO COATS OF RUST RESISTANT ENAMEL.
- ALL GAS PIPING WITH A SERVICE PRESSURE GREATER THAN 0.5PSI MUST BE IDENTIFIED PER NCFGC 410.2.
- PRESSURE TEST PORTS MUST BE PROVIDED AT ALL MP REGULATORS IN ACCORDANCE TO NCFGC 410.2.
- ALL GAS PIPING MUST COMPLY WITH NCFGC T.415.1.

PLUMBING FIXTURE SCHEDULE

MARK	DESCRIPTION	REMARKS	FIXTURE CONNECTIONS			
			CW	HW	WASTE	VENT
FCO	FLOOR CLEANOUT	ZURN MODEL ZN-1400 "LEVEL-TROL" ADJUSTABLE FLOOR CLEANOUT WITH NICKEL BRONZE TOP. CLEANOUT SIZE SHALL MATCH LINE SIZE. PROVIDE ANY NECESSARY MODIFICATIONS OR ACCESSORIES SUCH AS CARPET MARKER, TILE OR SQUARE TOP AS REQUIRED TO BE FLUSH WITH AND MATCH FLOOR FINISH. PROVIDED AND INSTALLED BY PLUMBING CONTRACTOR.	-	-	4"	-
WC-1	WATER CLOSET - TANK TYPE (ADA)	AMERICAN STANDARD - CHAMPION PRO (1.28 GPF) # 211AA004.020. TWO PIECE FLOOR MOUNTED WATER CLOSET. ADA HEIGHT. COLOR: WHITE. PRO LOW PFTSC02000WH ELONGATED BOWL SEAT. COLOR: WHITE. PROVIDED AND INSTALLED BY PLUMBING CONTRACTOR.	1/2"	-	3"	2"
LV-1	LAVATORY (ADA) - WALL HUNG	WALL HUNG LAVATORY (AMERICAN STANDARD "LUCERNE," 0355012020) WITH CONCEALED ARM CARRIER MOUNTING. PROVIDE PROFLO PFW52840CP FAUCET. HANDICAP DRAIN OFFSET W/GRID DRAIN (ZURN Z8748-PC) AND CHROME PLATED P-TRAP (ZURN Z8701-PC). MCGUIRE MODEL LF2165, CHROME PLATED BRASS ANGLE SUPPLY STOPS WITH BRASS STEMS, WHEEL HANDLES, 1/2" IPS INLETS, 3/8" COMPRESSION OUTLETS, 12" CHROME PLATED FLEXIBLE SUPPLY RISERS. INSULATE TRAP AND SUPPLY LINES (TRUEBRO "LAVGUARD" #103 E-Z). PLUMBING CONTRACTOR SHALL FURNISH AND INSTALL AN ASSE 1070 COMPLIANT THERMOSTATIC MIXING VALVE SET AT 105 DEGREES.	1/2"	1/2"	2"	2"

NOTE: CONTRACTOR SHALL COORDINATE FINAL FIXTURE SELECTIONS WITH OWNER AND ARCHITECT PRIOR TO PURCHASE AND INSTALLATION

PLUMBING DRAWING INDEX	
P0.1	PLUMBING LEGENDS AND NOTES
P1.1	WASTE PIPING PLAN - TOP FLOOR
P1.2	WATER PIPING PLAN - TOP FLOOR

PLUMBING LEGEND


	DOMESTIC COLD WATER PIPING (CW)
	DOMESTIC HOT WATER PIPING (HW)
	SANITARY PIPING
	GREASE PIPING
	VENT PIPING
	FLOOR CLEANOUT
	PIPE CONTINUES
	PIPE DOWN
	PIPE UP
	BALL VALVE
	PRESSURE REDUCING VALVE
	METER
	PLUMBING CONTRACTOR
	DOMESTIC COLD WATER PIPING
	DOMESTIC HOT WATER PIPING
	DOMESTIC HOT WATER RECIRCULATING
	SANITARY WASTE PIPING
	VENT THROUGH ROOF

SEE ARCHITECTURAL PLANS FOR MINIMUM FACILITIES CALCULATIONS


CONNECTED LOADS	DFU
SOIL AND WASTE	DFU
COLD WATER	WFSU
DEMAND	GPM

PLUMBING EQUIPMENT SCHEDULE

MARK	DESCRIPTION	LOCATION	MANUFACTURER	MODEL	SPECIFICATIONS
POU-1	POINT-OF-USE WATER HEATER	BATHROOMS	EEMAX	SPEX2412	TANKLESS POINT-OF-USE WATER HEATER. UNIT SHALL HAVE ABS UL 94 5VA RATED COVER. UNIT SHALL ALLOW MOUNTING IN ANY ORIENTATION. ELEMENT SHALL BE REPLACEABLE CARTRIDGE INSERT. ELEMENT SHALL BE IRON-FREE, NICKEL-CHROME MATERIAL. UNIT SHALL HAVE REPLACEABLE FILTER IN THE INLET CONNECTOR. UNIT SHALL INCLUDE AN INTEGRATED FLOW METER TO ENSURE ACCURATE TURN-ON / TURN-OFF FLOW RATE. HEATER SHALL BE FITTED WITH 3/8" COMPRESSION FITTINGS TO ELIMINATE THE NEED FOR SOLDERING. MAXIMUM OPERATING PRESSURE OF 150 PSI. DIAGNOSTIC FEATURES TO INCLUDE LED ERROR/FAULT INDICATOR. HEATER SHALL EMPLOY TECHNOLOGY THAT ENGAGES UPON START-UP TO AVOID DRY-FIRE OCCURRENCE. HOT WATER STORAGE TANKS PROHIBITED. UNIT SHALL BE EEMAX OR APPROVED EQUAL.



1 WASTE PIPING RISER DIAGRAM
NOT TO SCALE




2 WATER PIPING RISER DIAGRAM
NOT TO SCALE



DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FLUJAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

PLUMBING LEGENDS AND NOTES

P0.1


WASTE KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	CONTINUES TO SANITARY SEWER TIE IN ON SITE. SEE SITE PLANS BY OTHERS FOR EXACT TIE-IN LOCATION.



1 WASTE PLAN - TOP FLOOR
SCALE - 3/32" = 1'0"



DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526


REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: OMS
CHECKED BY: OMS
WASTE PIPING PLAN - TOP FLOOR

P1.1

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: OMS
CHECKED BY: OMS
WATER PIPING PLAN - TOP FLOOR

P1.2

WATER KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	CONTINUES TO CW TIE IN ON SITE. SEE SITE PLANS BY OTHERS FOR EXACT TIE-IN LOCATION AND LOCATION OF MAIN SHUT-OFF VALVE.

ALL REQUIRED VALVES NOT SHOWN.
INSTALL FULL OPEN VALVES PER 2018 PC CODE 606.1.5 AND 606.1.8
INSTALL SHUT OFF VALVES PER 2018 NC PLUMBING CODE 606.2 AND 606.2.1



1 WATER PLAN - TOP FLOOR
SCALE - 3/32" = 10"

HVAC GENERAL NOTES

- MECHANICAL CONTRACTOR SHALL FURNISH ALL LABOR, MATERIAL AND EQUIPMENT REQUIRED FOR THE COMPLETE INSTALLATION AND OPERATION OF ALL SYSTEMS IN THIS SECTION OF WORK IN ACCORDANCE WITH RECOMMENDED PRACTICE, 2018 NORTH CAROLINA MECHANICAL CODE AND ALL APPLICABLE CODES ADOPTED BY THE AUTHORITY HAVING JURISDICTION.
- DO NOT SCALE DRAWINGS. SEE ARCHITECTURAL DRAWINGS FOR EXACT LOCATION OF WALLS, DOORS, WINDOWS, FURNITURE, LIGHTS, CEILING DIFFUSERS, ETC.
- ALL MECHANICAL PERMITS AND INSPECTION FEES SHALL BE OBTAINED AND PAID FOR BY THE MECHANICAL CONTRACTOR.
- MECHANICAL CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS FOR ONE YEAR. REFRIGERANT COMPRESSORS SHALL BE GUARANTEED FOR FIVE YEARS. WARRANTY PERIOD SHALL BE EFFECTIVE THE DAY THE PROJECT IS ACCEPTED BY THE OWNER.
- DRAWINGS ARE DIAGRAMMATIC AND MAY NOT SHOW ALL REQUIRED FITTINGS. MECHANICAL CONTRACTOR IS RESPONSIBLE FOR COORDINATING THE TYPE, SIZE AND LOCATION OF ALL AIR DEVICES, DUCTWORK, PIPING AND EQUIPMENT WITH THE CEILING PLAN, LIGHTS, STRUCTURAL ELEMENTS AND OTHER TRADES. MECHANICAL CONTRACTOR TO FURNISH AND INSTALL ALL BENDS, OFFSETS, ELBOWS, ETC. AS REQUIRED. VERIFY ALL CLEARANCES PRIOR TO FABRICATING DUCTWORK, OR ORDERING ANY EQUIPMENT, PIPING, ETC.
- MECHANICAL CONTRACTOR IS RESPONSIBLE FOR PROVIDING MATERIALS AND INSTALLING THE WORK IN ACCORDANCE WITH ALL APPLICABLE LOCAL, STATE AND NATIONAL CODES ADOPTED BY THE AUTHORITY HAVING JURISDICTION.
- THE MC SHALL VISIT THE SITE PRIOR TO BIDDING TO BECOME FAMILIAR WITH EXISTING CONDITIONS. THE MC SHALL CONTACT THE ENGINEER TO RESOLVE ANY DISCREPANCIES BETWEEN EXISTING CONDITIONS AND THESE PLANS. THE MC SHALL COORDINATE WITH OTHER TRADES PRIOR TO THE START OF CONSTRUCTION.
- THE MC SHALL VERIFY THE FUNCTIONALITY AND OPERATION OF ALL EXISTING MECHANICAL EQUIPMENT IN THE AREA OF WORK. REPLACE FILTERS, LEAK TEST AND RECHARGE REFRIGERANT LINES, REPLACE OR LUBRICATE BEARINGS, CHECK LINKAGES AND ACTUATORS, AND PERFORM OTHER MAINTENANCE SERVICE AS NECESSARY TO GET THE EQUIPMENT IN PROPER WORKING ORDER.
- DUCTWORK
 - NON-RESIDENTIAL AREAS: ALL DUCTWORK SHALL BE GALVANIZED SHEET METAL CONSTRUCTED IN ACCORDANCE WITH SMACNA STANDARDS WITH A MINIMUM PRESSURE CLASSIFICATION OF 2", SEAL CLASS C, WITH A MAXIMUM LEAKAGE RATE OF 5%. RESIDENTIAL/DWELLING AREAS: ALL DUCTWORK SHALL BE FIBROUS GLASS DUCT BOARD FACED ON THE OUTSIDE WITH A FIRE RETARDANT, REINFORCED FOIL-SCRIM-KRAFT FACING, CONSTRUCTED IN ACCORDANCE WITH SMACNA STANDARDS. DUCT INSULATION IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES.
 - ALL SQUARE ELBOWS SHALL HAVE TURNING VANES.
 - ALL DUCT DIMENSIONS SHOWN ARE INTERNAL CLEAR DIMENSIONS.
 - PROVIDE A MANUAL BALANCING DAMPER AT ALL SUPPLY AND RETURN BRANCH TAKEOFFS, AS WELL AS ALL OUTSIDE AIR MAIN & BRANCH DUCTS.
 - FLEXIBLE DUCT, IF SHOWN ON DRAWINGS, SHALL BE INSULATED ROUND DUCT WITH AN OUTER GLASS REINFORCED SILVER MYLAR JACKET ENCLOSING MIN. 1-1/2" THICK GLASS FIBER INSULATION AROUND A CONTINUOUS INNER LINER, AND SHALL CONFORM TO THE REQUIREMENTS OF U.L. 181 FOR CLASS 1 FLEXIBLE AIR DUCTS. MAXIMUM LENGTH OF FLEXIBLE DUCT SHALL BE 6 FEET FOR COMMON AREA SYSTEMS. MAXIMUM LENGTH OF FLEXIBLE DUCT SHALL NOT BE LIMITED FOR DWELLING UNIT SYSTEMS. "R" VALUE TO MEET EXCEED ENERGY CODE (NCECC SECTION C 403.2.9). DUCT INSULATION IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES.
 - ALL SHEET METAL DUCTWORK WITHIN 10' OF THE AIR HANDLING UNIT SHALL BE PROVIDED WITH ACOUSTICAL DUCT LINER. THIS IS IN ADDITION TO THERMAL INSULATION REQUIREMENTS.
 - ALL DUCT SYSTEMS ARE TO BE PER U.L. STANDARDS. DUCTS ARE TO BE INSTALLED WITH NO RESTRICTIONS AND AN ABSOLUTE MINIMUM AMOUNT OF AIR LEAKAGE.
 - ALL DUCT INSULATION SHALL BE RUN CONTINUOUSLY THROUGH FLOORS AND PARTITIONS.
- PIPING
 - CONDENSATE DRAINS SHALL BE SCHEDULE 40 PVC OR TYPE L COPPER WITH SOLDERED JOINTS WHEN INSTALLED BELOW CEILING LEVEL. DRAINS INSTALLED IN A RETURN AIR PLENUM SHALL BE TYPE L COPPER WITH SOLDERED JOINTS OR SCHEDULE 40 CPVC.
 - REFRIGERANT PIPING SHALL BE TYPE ACR WROUGHT COPPER WITH WROUGHT COPPER FITTINGS AND BRAZED JOINTS.
 - REFRIGERANT COMPONENTS SHALL BE PRESSURE TESTED IN ACCORDANCE WITH ASHRAE 15.
 - MECHANICAL CONTRACTOR SHALL PROVIDE REFRIGERANT PIPING FOR ALL MECHANICAL SYSTEMS WITHIN THIS SCOPE OF WORK. COORDINATE ROUTING AND INSTALLATION WITH THE GENERAL CONTRACTOR. SIZE REFRIGERANT LINES PER MANUFACTURER'S REQUIREMENTS.
- INSULATION
 - DUCT LINER - FIBROUS GLASS DUCT LINER, WITH COATED SURFACE EXPOSED TO AIR STREAM. APPLY WITH MECHANICAL FASTENERS AND 100% COVERAGE OF ADHESIVE. LINER TO BE COATED WITH AN EPA REGISTERED ANTI-MICROBIAL AGENT. DUCT INSULATION VALUE IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES. DUCT LINER USED FOR ACOUSTICAL PURPOSES ONLY SHALL BE 1" THICK.
 - DUCT WRAP - MINERAL FIBER BLANKET, WITH REINFORCED FOIL AND PAPER VAPOR RETARDANT JACKET. APPLY WITH MECHANICAL FASTENERS AND ADHESIVE. DUCT INSULATION IS TO BE MIN. R-6 WHEN LOCATED WITHIN THE CONDITIONED BUILDING ENVELOPE; MIN. R-8 WHEN LOCATED IN THE ATTIC, OUTSIDE THE BUILDING ENVELOPE OR UNCONDITIONED SPACES.
 - INTERIOR CONDENSATE DRAINS - INSULATE CONDENSATE DRAINS LOCATED IN THE ATTIC, EXTERIOR WALLS OR UNCONDITIONED SPACES WITH 1/2" THICK FLEXIBLE ELASTOMERIC PIPE INSULATION.
 - REFRIGERANT SUCTION LINES - INSULATE WITH 1" THICK FLEXIBLE ELASTOMERIC PIPE INSULATION. PROVIDE ALUMINUM JACKET OVER INSULATION FOR ALL EXTERIOR REFRIGERANT PIPING.
 - AIR DISTRIBUTION - INSULATE THE TOP-SIDE OF ALL AIR DISTRIBUTION DEVICES.
- ALL PIPING, DUCTS, VENTS, ETC., EXTENDING THROUGH WALLS & ROOF SHALL BE FLASHED & COUNTER-FLASHED IN A WATERPROOF MANNER.
- EXTEND ALL CONDENSATE DRAINS TO JANITORS SINK, FLOOR DRAIN, SPLASH BLOCK OR AS REQUIRED PER CODE. DRAINS FROM MECHANICAL EQUIPMENT SHALL BE PROVIDED W/ A DEEP SEAL TRAP. SLOPE CONDENSATE DRAIN PIPING AT MIN. 1/8" PER FOOT.
- NON-RESIDENTIAL AREAS: LOCATE ALL THERMOSTATS, SWITCHES AND OTHER CONTROL DEVICES AT 4'-0" ABOVE FINISHED FLOOR. FURNISH A THERMOSTATIC CONTROL DEVICE FOR EVERY DEVICE REQUIRING ONE WHETHER SHOWN ON DRAWINGS OR NOT RESIDENTIAL/DWELLING AREAS: LOCATE ALL THERMOSTATS, SWITCHES AND OTHER CONTROL DEVICES AT 4'-0" TO ABOVE FINISHED FLOOR FOR STANDARD DWELLING UNITS; 4'-0" TO TOP OF DEVICE FOR ACCESSIBLE UNIT TYPES. FURNISH THERMOSTATIC CONTROL DEVICE FOR EVERY DEVICE REQUIRING ONE WHETHER SHOWN ON DRAWINGS OR NOT.
- ALL EQUIPMENT SHALL BE INSTALLED PER CODE & MANUFACTURER'S REQUIREMENTS FOR PROPER OPERATION AND SERVICE/ACCESS CLEARANCES.
- ALL EQUIPMENT SHALL BE U.L. LISTED.
- MECHANICAL CONTRACTOR SHALL BALANCE ALL MECHANICAL SYSTEMS TO AIR QUANTITIES INDICATED ON PLANS. CONTRACTOR SHALL PROVIDE A COMPLETE BALANCING REPORT FOR AT LEAST ONE SYSTEM IN EACH DWELLING UNIT TYPE, AND ALL COMMON AREA SYSTEMS IN ACCORDANCE WITH NEBB OR ABC STANDARDS.
- CONTROL WIRING FOR ALL MECHANICAL SYSTEMS WITHIN THIS SCOPE OF WORK SHALL BE BY THE MECHANICAL CONTRACTOR.
- DUCT SMOKE DETECTORS SHALL BE INSTALLED IN THE RETURN AIR DUCT OR PLENUM UPSTREAM OF ANY FILTERS OR DECONTAMINATION EQUIPMENT UPON ACTIVATION THE SMOKE DETECTOR SHALL SHUT DOWN THE AIR HANDLING UNIT AS REQUIRED BY 2018 NORTH CAROLINA MECHANICAL CODE 806. * IF THERE IS A FIRE ALARM SYSTEM, DETECTORS SHALL BE FURNISHED AND WIRED BY THE ELECTRICAL CONTRACTOR. INSTALLED BY THE MECHANICAL CONTRACTOR. ACTIVATION OF THE DUCT SMOKE DETECTOR SHALL INITIATE A VISIBLE AND AUDIBLE SUPERVISORY SIGNAL AT A CONSTANTLY ATTENDED LOCATION. * IF THERE IS NOT A FIRE ALARM SYSTEM, DETECTORS SHALL BE FURNISHED, WIRED AND INSTALLED BY THE MECHANICAL CONTRACTOR. ACTIVATION OF THE DUCT SMOKE DETECTOR SHALL INITIATE A VISIBLE AND AUDIBLE SUPERVISORY SIGNAL AT A CONSTANTLY ATTENDED LOCATION.

- PROVIDE A CLEAN SET OF FILTERS FOR ALL AIR HANDLING EQUIPMENT AT SUBSTANTIAL COMPLETION.
- MAINTAIN A MINIMUM 10'-0" BETWEEN OUTDOOR AIR INTAKES AND EXHAUST FAN DISCHARGE AND PLUMBING VENTS, ETC. FIELD COORDINATE FINAL LOCATIONS.
- PROVIDE 4" THICK CONCRETE PAD FOR ALL GROUND MOUNTED OUTDOOR MECHANICAL UNITS. PADS SHALL BE MINIMUM 6" LARGER THAN UNIT ON ALL SIDES.
- RUN DUCT UP WITHIN STRUCTURE OR THROUGH JOIST WEBS WHERE POSSIBLE & WHERE REQUIRED TO MAINTAIN CEILING HEIGHTS. PROVIDE OFFSETS AND/OR TRANSITIONS IN DUCT WHERE REQUIRED WITH MAX. 45° DEG. ELBOWS. MAKE BRANCH TAPS OFF TOP, SIDES OR BOTTOM AS REQUIRED. NO BACK TO BACK 90° DEG. ELBOWS ALLOWED.
- REFRIGERANT PIPING SHALL BE SIZED & INSTALLED IN ACCORDANCE WITH THE MANUFACTURER'S RECOMMENDATIONS AND INSTALLATION INSTRUCTIONS.
- ALL EQUIPMENT SHALL BE LABELED ACCORDING TO NUMBERING / IDENTIFICATION SYSTEM PER PLANS.
- ALL EQUIPMENT SUPPORTS ARE REQUIRED TO MEET ASCE 9.6.
- MECHANICAL CONTRACTOR SHALL PROVIDE U.L. LISTED FIRE DAMPERS, RADIATION DAMPERS AND/OR FIRE/SMOKE DAMPERS WHERE REQUIRED FOR FIRE PROTECTION AS REQUIRED BY LOCAL CODES. M.C. SHALL PROVIDE A MEANS OF ACCESS TO TEST & RESET ALL SUCH DAMPERS AND/OR ACTUATORS.
- ON MAKING PIPE CONNECTIONS TO EQUIPMENT, CARE SHOULD BE TAKEN TO ARRANGE PIPES SO AS NOT TO INTERFERE WITH OPENING OF ACCESS DOORS.
- ELECTRICAL CONTRACTOR TO PROVIDE ALL HIGH VOLTAGE (120V AND GREATER) ELECTRICAL WIRING, CONDUIT, DISCONNECT SWITCHES, FUSES, ETC. TO ALL MECHANICAL EQUIPMENT WITHIN THIS SCOPE OF WORK. ALL FINAL ELECTRICAL CONNECTIONS ARE BY ELECTRICAL CONTRACTOR. MECHANICAL CONTRACTOR SHALL COORDINATE ELECTRICAL REQUIREMENTS FOR ALL APPROVED MECHANICAL EQUIPMENT WITH THE ELECTRICAL CONTRACTOR.
- PRIOR TO BEGINNING ANY WORK, MECHANICAL CONTRACTOR IS RESPONSIBLE TO NOTIFY THE OWNER'S REPRESENTATIVE, ARCHITECT OR ENGINEER IF THE MECHANICAL DESIGN CONFLICTS WITH EXISTING OR UNFORESEEN FIELD CONDITIONS.
- MECHANICAL CONTRACTOR SHALL PROVIDE A MIN. OF FOUR COPIES OF SHOP DRAWINGS TO THE ARCHITECT/ENGINEER FOR ALL INSTALLED EQUIPMENT AND MATERIALS NEEDING APPROVAL PRIOR TO PURCHASING. IN ADDITION, M.C. SHALL PROVIDE THE OWNER WITH TWO COPIES OF OPERATION & MAINTENANCE MANUALS FOR ALL INSTALLED EQUIPMENT, MANUFACTURER'S & INSTALLER'S WARRANTIES AND TRAINING FOR CONTROLS OF ALL SUCH EQUIPMENT.

Mechanical Design Summary

MECHANICAL SYSTEMS, SERVICE SYSTEMS AND EQUIPMENT

Thermal Zone: 3A

winter dry bulb: 23.1 °F
summer dry bulb: 91.7 °F
summer wet bulb: 75.6 °F

Interior design conditions

winter dry bulb: 70 °F
summer dry bulb: 75 °F
relative humidity: 50%

Building heating load: 354,500 btu

Building cooling load: 291,700 btu

Mechanical Spacing Conditioning System

Unitary
description of unit: Split System DX
heating efficiency: See Schedules
cooling efficiency: See Schedules
size category of unit: See Schedules

Boiler
Size category: If oversized, state reason: N/A
Chiller
Size category: If oversized, state reason: N/A

List equipment efficiencies: N/A

To the best of my knowledge, the mechanical design for this building complies with mechanical and equipment requirements of the 2018 North Carolina state building code and 2018 North Carolina energy conservation code.

MECHANICAL LEGEND

SYMBOL	DESCRIPTION
	THERMOSTAT (HONEYWELL VISION PRO 8000 OR EQUAL) WITH KEY LOCKING GUARD COVER
	CEILING SUPPLY DIFFUSER
	CEILING RETURN DIFFUSER
	SPIRAL DUCT SUPPLY DIFFUSER
	RECTANGULAR METAL DUCT
	ROUND METAL/SPIRAL DUCT
	MAIN TRUNK AND BRANCH DUCT TAKEOFF WITH VOLUME DAMPER
	FLEX DUCT
	1" DOOR UNDER CUT
	TURNING VANES
SA	SUPPLY AIR
RA	RETURN AIR
EA	EXHAUST AIR
OA	OUTSIDE AIR
CFM	CUBIC FEET PER MINUTE
AH	AIR HANDLER
HP	HEAT PUMP
AC	AIR CONDITIONING UNIT
RTU	ROOFTOP UNIT
BDD	BACK DRAFT DAMPER
REL	RELOCATE
VD	VOLUME DAMPER
AFF	ABOVE FINISHED FLOOR
GC	GENERAL CONTRACTOR
MC	MECHANICAL CONTRACTOR

AIR DISTRIBUTION SCHEDULE

TAG	DESCRIPTION	MANUFACTURER	MODEL	FRAME/MOUNTING	FACE SIZE/LENGTH	MAX NC	REMARKS
A	DOUBLE DEFLECTION SUPPLY	TITUS	300FS	SURFACE	18"x6"	20	1,2,3,4
R	ALUMINUM RETURN GRILLE	TITUS	3FS	SURFACE	36"x12"	30	1,2,3

- PROVIDE WITH STANDARD WHITE FINISH
- PROVIDE ALUMINUM CONSTRUCTION
- PROVIDE TRANSITION TO OFFSET GRILLE 45 DEG. TOWARDS FLOOR. SEE DETAIL 3 ON SHEET M2.1.
- OR EQUAL BY HART AND COOLEY, PRICE, OR NAILED

SPLIT-SYSTEM HEAT PUMP SCHEDULE

TAG	MANUFACTURER / MODEL	NOMINAL CAPACITY (TONS)	COMPRESSOR #	COND. FAN #	SEER	HSPF	VOLT / PHASE / HZ	MCA (AMPS)	MOCP	WEIGHT(LBS)	REMARKS
HP-1 THROUGH HP-8	YORK / YH2E48T21S	4	1	1	14.3	7.5	208/1/60	26.1	45	215	1,2,4,5,6,7,8

SPLIT-SYSTEM AIR HANDLING UNIT SCHEDULE

TAG	MANUFACTURER / MODEL	NOMINAL CAPACITY (TONS)	ELEC. HEAT (KW)	AIRFLOW (CFM)	OUTDOOR AIR (CFM)	E.S.P. IN W.G	SENSIBLE CAPACITY (MBH)	LATENT CAPACITY (MBH)	VOLT / PHASE / HZ	MCA (AMPS)	MOCP	WEIGHT(LBS)	REMARKS
AHU-1 THROUGH AHU-8	YORK / JHETC48GBCS2N1	4	10	1600	320*	0.50	34.7	13.4	208/1/60	50	60	129	2,3,4,6,7,8

- PROVIDE CONCRETE PAD FOR UNIT TO SIT ON
- 7-DAY PROGRAMMABLE THERMOSTAT AND TEMPERATURE SENSOR SHALL MEET REQUIREMENTS OF LATEST ENERGY CODE
- REPLACE ALL FILTERS AT PROJECT COMPLETION
- PROVIDE HEAT STRIP OUTDOOR TEMPERATURE LOCKOUT TO PREVENT SUPPLEMENTAL HEAT OPERATION IN RESPONSE TO THE THERMOSTAT BEING CHANGED TO A WARMER SETTING. SET NO LOWER THAN 35°F AND NO HIGHER THAN 40 DEG. F
- PROVIDE HARD START KIT
- CONSULT MANUFACTURER ON REFRIGERANT LINE SETS EXCEEDING 60'-0" IN DEVELOPED LENGTH
- BASIS OF DESIGN YORK. ACCEPTABLE ALTERNATIVE MANUFACTURERS: TRANE, CARRIER, DAIKIN, LENNOX, BRYANT, HEIL, GOODMAN
- MAINTAIN MANUFACTURER'S RECOMMENDED CLEARANCES
- *SET OUTSIDE AIR VOLUME TO 320CFM FOR AHU-3,4,5,7

FAN SCHEDULE

TAG	MANUFACTURER	MODEL	AIRFLOW (CFM)	E.S.P. IN W.G	SONES	FAN TYPE	MOUNT	VOLT/PHASE/HZ	MCA (AMPS)	CONTROL	REMARKS
EF-1	GREENHECK	SP-A90	75	0.125	1.4	EXHAUST	CEILING MOUNT	115 / 1 / 60	0.3	WALL SWITCH / OCC. SENSOR	1,2,3
EF-2	GREENHECK	SP-A90	75	0.125	1.4	EXHAUST	CEILING MOUNT	115 / 1 / 60	0.3	WALL SWITCH / OCC. SENSOR	1,2,3

- PROVIDE INTEGRAL BACKDRAFT DAMPER
- PROVIDE FAN SPEED CONTROL IF REQUIRED TO MEET SPECIFIED CFM RATING.
- COORDINATE LINE VOLTAGE AND CONTROL WIRING TERMINATIONS WITH ELECTRICAL CONTRACTOR PRIOR TO ROUGH-IN INSTALLATION

OUTSIDE AIR VENTILATION CALCULATIONS

HVAC Unit	Location	Zone Occupancy	Occupant Density (People/1000 sf)	Outdoor Air CFM/Person (Rp)	Zone Population (Pz)	Outdoor Air CFM' sf (Ra)	Floor Area (Az)	Initial Zone Outdoor Airflow (Vbz)	Zone Area Distribution Effectiveness (Ez)	People Quantity (Ps)	Design Zone Supply Air (CFM)
See Schedule	Corridors	Corridors	0	0	0	0.06	21184	1271.04	0.8	10	12800
										10	12800
										Required OA Intake (CFM)	1271


Calculations are based on the 2018 NCMC Table 403.3.1.1

MECHANICAL DRAWING INDEX	
M0.1	MECHANICAL LEGENDS AND NOTES
M1.1	MECHANICAL PLAN - BOTTOM FLOOR
M1.2	MECHANICAL PLAN - TOP FLOOR
M2.1	ALTERNATE MECHANICAL PLAN - BOTTOM FLOOR
M2.2	ALTERNATE MECHANICAL PLAN - TOP FLOOR
M3.1	MECHANICAL DETAILS



DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: GMS
CHECKED BY: GMS

MECHANICAL LEGENDS AND NOTES


M0.1

MECHANICAL KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	SUSPEND UNIT FROM STRUCTURE ABOVE. COORDINATE EXACT MOUNTING LOCATION WITH OWNER.
2	ROUTE CONDENSATE LINES TO DAYLIGHT. PROVIDE CONDENSATE PUMP FOR UNITS ON BOTTOM FLOOR NOT IN CLOSE PROXIMITY TO DAYLIGHT.
3	COORDINATE EXACT MOUNTING LOCATION OF THERMOSTAT WITH OWNER PRIOR TO ROUGH-IN.
4	MC TO ROUTE OUTSIDE AIR DUCT THROUGH SIDEWALL. PROVIDE WITH WALL CAP. MAINTAIN MINIMUM 10" FROM ALL FORMS OF EXHAUST.
5	MC TO STUB OUT SUPPLY DUCT MINIMUM 36" FROM AIR HANDLER. MC TO LEAVE SUPPLY OPEN ENDED TO CONDITION SPACE. INTERNALLY LINE SUPPLY DUCT.
6	MC TO STUB OUT RETURN DUCT MINIMUM 36" FROM AIR HANDLER. PROVIDE FILTER SECTION IN UNIT. INTERNALLY LINE RETURN DUCT AND PROVIDE WITH SCREEN.



1 MECHANICAL PLAN - BOTTOM FLOOR
SCALE - 3/32" = 1'0"

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

MECHANICAL PLAN - BOTTOM FLOOR

M2.1

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

MECHANICAL PLAN - TOP FLOOR


M2.2

MECHANICAL KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	SUSPEND UNIT FROM STRUCTURE ABOVE. COORDINATE EXACT MOUNTING LOCATION WITH OWNER.
2	ROUTE CONDENSATE LINES TO DAYLIGHT.
3	COORDINATE EXACT MOUNTING LOCATION OF THERMOSTAT WITH OWNER PRIOR TO ROUGH-IN.
4	COMBINE EACH 6" Ø EXHAUST DUCT TO SINGLE 8" Ø EXHAUST DUCT THROUGH ROOF WITH ROOF CAP. PROVIDE BACKDRAFT DAMPER FOR EACH EXHAUST FAN UPSTREAM OF COMBINING EXHAUST DUCTS IF NOT INTEGRAL TO FAN FROM MANUFACTURER. MAINTAIN MINIMUM 10'0" FROM ALL OUTSIDE AIR INTAKES.
5	MC TO ROUTE OUTSIDE AIR DUCT THROUGH SIDEWALL. PROVIDE WITH WALL CAP. MAINTAIN MINIMUM 10'0" FROM ALL FORMS OF EXHAUST.
6	MC TO STUB OUT SUPPLY DUCT MINIMUM 36" FROM AIR HANDLER. MC TO LEAVE SUPPLY OPEN ENDED TO CONDITION SPACE. INTERNALLY LINE SUPPLY DUCT.
7	MC TO STUB OUT RETURN DUCT MINIMUM 36" FROM AIR HANDLER. PROVIDE FILTER SECTION IN UNIT. INTERNALLY LINE RETURN DUCT AND PROVIDE WITH SCREEN.



1 MECHANICAL PLAN - TOP FLOOR
SCALE - 3/32" = 1'0"


MECHANICAL KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	SUSPEND UNIT FROM STRUCTURE ABOVE. COORDINATE EXACT MOUNTING LOCATION WITH OWNER.
2	ROUTE CONDENSATE LINES TO DAYLIGHT. PROVIDE CONDENSATE PUMP FOR UNITS ON BOTTOM FLOOR NOT IN CLOSE PROXIMITY TO DAYLIGHT.
3	COORDINATE EXACT MOUNTING LOCATION OF THERMOSTAT WITH OWNER PRIOR TO ROUGH-IN.
4	MC TO ROUTE OUTSIDE AIR DUCT THROUGH SIDEWALL. PROVIDE WITH WALL CAP. MAINTAIN MINIMUM 10" FROM ALL FORMS OF EXHAUST.



1 ALTERNATE MECHANICAL PLAN - BOTTOM FLOOR
SCALE - 3/32" = 1'0"

SHARPE
ENGINEERING & CONSULTING, PLLC
P.O. Box G
Wilson's Mills, NC 27593
NC License # P-2821
P: 336.425.5815
sharpengineers.com

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526


REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS
ALTERNATE MECHANICAL PLAN - BOTTOM FLOOR


M2.1

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

MECHANICAL KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	SUSPEND UNIT FROM STRUCTURE ABOVE. COORDINATE EXACT MOUNTING LOCATION WITH OWNER.
2	ROUTE CONDENSATE LINES TO DAYLIGHT.
3	COORDINATE EXACT MOUNTING LOCATION OF THERMOSTAT WITH OWNER PRIOR TO ROUGH-IN.
4	COMBINE EACH 6" Ø EXHAUST DUCT TO SINGLE 8" Ø EXHAUST DUCT THROUGH ROOF WITH ROOF CAP. PROVIDE BACKDRAFT DAMPER FOR EACH EXHAUST FAN UPSTREAM OF COMBINING EXHAUST DUCTS IF NOT INTEGRAL TO FAN FROM MANUFACTURER. MAINTAIN MINIMUM 10'0" FROM ALL OUTSIDE AIR INTAKES.
5	MC TO ROUTE OUTSIDE AIR DUCT THROUGH SIDEWALL. PROVIDE WITH WALL CAP. MAINTAIN MINIMUM 10'0" FROM ALL FORMS OF EXHAUST.




1 ALTERNATE MECHANICAL PLAN - TOP FLOOR
SCALE - 3/32" = 1'0"

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS
ALTERNATE MECHANICAL PLAN - TOP FLOOR


M2.2




1 CEILING EXHAUST FAN DETAIL
NOT TO SCALE



2 ROOF CAP DETAIL
NOT TO SCALE




3 SUPPLY GRILLE TAKEOFF DETAIL
NOT TO SCALE



HANGER SIZES FOR RECTANGULAR DUCTS			
MAX. SIDE	HANGER	SUPPORT ANGLE HORIZONTAL	SPACING MAXIMUM
30"	1" x 1/8" GAUGE STRAP	NONE REQUIRED	10'-0"
36"	1/4" ROUND ROD	1-1/2' x 1-1/2' x 1/8"	8'-0"
48"	1/4" ROUND ROD	2' x 2' x 1/8"	8'-0"
60"	5/16" ROUND ROD	2' x 2' x 1/8"	8'-0"
84"	3/8" ROUND ROD	2' x 2' x 1/8"	8'-0"

4 RECTANGULAR DUCT HANGER DETAIL
NOT TO SCALE

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

MECHANICAL DETAILS

M3.1



















GENERAL ELECTRICAL NOTES

- G1. ALL ELECTRICAL WORK SHALL BE IN ACCORDANCE WITH 2020 NATIONAL ELECTRICAL CODE WITH N.C. AMENDMENTS AND ALL APPLICABLE LOCAL AND STATE CODES.
- G2. ALL MATERIAL, EQUIPMENT AND APPLIANCES SHALL BE NEW, LABELED AND LISTED FOR ITS INTENDED USE BY A QUALIFIED THIRD-PARTY ELECTRICAL TESTING LABORATORY (I.E. UL, ETL, ETC.) AND THE NATIONAL ELECTRICAL MANUFACTURERS ASSOCIATION PER NEC ARTICLES 90.7, 110.2 AND 110.3. WHERE UNDERWRITERS LABORATORIES LABELING IS AVAILABLE FOR THE CLASS OF MATERIAL INVOLVED, MATERIALS SHALL BE FURNISHED WITH A UL LABEL OR LISTING, OR THE ELECTRICAL CONTRACTOR SHALL PROVE IT IS NOT REQUIRED.
- G3. ALL ELECTRICAL PERMITS AND INSPECTION FEES SHALL BE OBTAINED AND PAID FOR BY THE ELECTRICAL CONTRACTOR.
- G4. ELECTRICAL CONTRACT DRAWINGS ARE DIAGRAMMATIC AND INDICATE THE GENERAL ARRANGEMENT OF ELECTRICAL EQUIPMENT. DO NOT SCALE ELECTRICAL PLANS. OBTAIN ALL DIMENSIONS FROM THE ARCHITECT'S DIMENSIONED DRAWINGS AND FIELD MEASUREMENTS. THE CONTRACTOR SHALL REVIEW ARCHITECTURAL PLANS FOR DOOR SWINGS AND BUILT-IN EQUIPMENT, CONDITIONS INDICATED ON THOSE PLANS SHALL GOVERN FOR THIS WORK.
- G5. VERIFY ALL UTILITY REQUIREMENTS FOR ELECTRICAL SERVICE (PRIOR TO STARTING ANY WORK) SUCH AS VOLTAGE, PHASES, FAULT CURRENT, ETC., AND COORDINATE EXACT LOCATION OF INCOMING ELECTRICAL SERVICE WITH LOCAL POWER COMPANY PRIOR TO PROJECT START. NOTIFY ENGINEER OF ANY DIFFERENCES FROM WHAT IS SHOWN ON PLANS.
- G6. ELECTRICAL CONTRACTOR SHALL GUARANTEE ALL WORK AND MATERIALS FOR ONE YEAR EFFECTIVE FROM THE DATE OF SUBSTANTIAL COMPLETION.
- G7. A COMPLETE GROUNDING SYSTEM SHALL BE PROVIDED AND INSTALLED IN ACCORDANCE WITH ARTICLE 250 OF THE NEC, AND AS SHOWN ON THE DRAWINGS.
- G8. ALL CUTTING AND PATCHING REQUIRED FOR INSTALLATION OF ELECTRICAL EQUIPMENT SHALL BE THE RESPONSIBILITY OF THE ELECTRICAL CONTRACTOR. DO NOT CUT ANY MATERIAL THAT WILL WEAKEN THE STRUCTURE WITHOUT WRITTEN PERMISSION OF THE ARCHITECT. PATCHING SHALL BE ACCOMPLISHED TO MATCH ADJACENT SURFACES IN EVERY RESPECT. ENGAGE ORIGINAL INSTALLER FOR CUTTING/PATCHING OF ROOFS.
- G9. PROVIDE A TYPED DIRECTORY IN ALL PANELBOARDS CLEARLY DESCRIBING THE LOCATION AND TYPE OF LOAD SERVED FOR ALL CIRCUITS.
- G10. THE ELECTRICAL CONTRACTOR SHALL REQUEST A SELECTIVE BREAKER COORDINATION STUDY FROM THE ELECTRICAL GEAR MANUFACTURER PER NEC 700 REQUIREMENTS.
- G11. PROVIDE ENGRAVED PHENOLIC NAMEPLATES FOR ALL PANELBOARDS AND DISCONNECT SWITCHES, WHITE LETTERS ON BLACK BACKGROUND. NAMEPLATE SHALL CONTAIN EQUIPMENT DESIGNATION, VOLTAGE, FEEDER SOURCE, AIC RATING & DATE INSTALLED.
- G12. PROVIDE "FLASH HAZARD" LABELS FOR ALL PANELBOARDS IN ACCORDANCE WITH NEC REQUIREMENTS.
- G13. ALL TERMINALS/SLUGS SHALL BE 60 DEGREE/75 DEGREE RATED.
- G14. FUSES 0-600 AMPS SHALL BE UL CLASS "RK-5" LOW PEAK DUAL ELEMENT TIME DELAY WITH 200,000 AMPERE INTERRUPTING RATING AS MANUFACTURED BY BUSSMAN UNLESS NOTED OTHERWISE.
- G15. ALL WATER HEATERS SHALL HAVE DISCONNECT SIZED PER 422.11(E)3).
- G16. ELECTRICAL CONTRACTOR SHALL MAKE ALL FINAL ELECTRICAL CONNECTIONS TO EQUIPMENT REGARDLESS OF WHO SUPPLIES THE EQUIPMENT. THIS INCLUDES ALL HVAC, PLUMBING AND OWNER FURNISHED EQUIPMENT CONNECTIONS OF 120V OR HIGHER.
- G17. RACEWAYS SHALL BE INSTALLED CONCEALED IN NEW WALL CONSTRUCTION, ABOVE CEILINGS, BELOW FLOOR, AND IN OTHER CAVITIES TO THE GREATEST EXTENT POSSIBLE. WHERE EXPOSED RACEWAYS MUST BE USED, LAYOUT RACEWAYS TO MINIMIZE THE NUMBER OF VERTICAL RUNS.
- G18. ALL EXPOSED RACEWAY SHALL BE RUN PARALLEL OR PERPENDICULAR TO THE BUILDING SURFACES AND SHALL BE PAINTED AS DIRECTED BY THE ARCHITECT. NO EXPOSED CONDUIT SHALL BE ALLOWED IN FINISHED SPACES EXCEPT AS PERMITTED BY OWNER OR ARCHITECT. EXPOSED RACEWAY IN FINISHED SPACES SHALL BE WIREMOLD TYPE.
- G19. BEFORE COMMENCING WITH ANY ROUGH-IN, COORDINATE THE EXACT LOCATION AND MOUNTING HEIGHT OF ALL WALL MOUNTED DEVICES WITH THE ARCHITECTURAL INTERIOR ELEVATIONS, CASEWORK SHOP DRAWINGS, AND EXISTING CONDITIONS. IF ANY DISCREPANCIES ARE DISCOVERED, NOTIFY THE ARCHITECT FOR FURTHER DIRECTION. MINOR ADJUSTMENTS IN DEVICE LOCATION, I.E. 5/8" IN ANY DIRECTION SHALL BE DONE AT NO ADDITIONAL COST TO THE CONTRACTOR.
- G20. ALL WIRING SHALL BE INSTALLED IN IMC, RMC, EMT OR TYPES AC AND MC FLEXIBLE CABLES. RNC CONDUIT (PVC), SHALL ONLY BE USED UNDERGROUND AND OUTDOORS, WHERE NOT SUBJECT TO PHYSICAL DAMAGE. MINIMUM SIZE CONDUIT SHALL BE 3/4". AC AND MC FLEXIBLE CABLES SHALL BE USED ONLY IN AREAS PERMITTED BY CODE. INDOOR BRANCH CIRCUIT WIRING MAY BE TYPE NM, NMC, OR NMS FOR DWELLING UNITS OR OTHER BUILDINGS PERMITTED TO BE OF TYPES III, IV OR V CONSTRUCTION. DWELLING UNIT SERVICE FEEDERS MAY BE TYPE SE OR USE CABLES IN AREAS PERMITTED BY CODE. AMPACITY FOR SE AND USE CABLES SHOWN ON THE SER FEEDER SCHEDULE INCLUDED IN THESE DRAWINGS IS BASED ON THE 60 C AMPACITY OF TABLE 310.15(B)(16) FOR INSTALLATION IN INSULATION. SHOULD SER CABLE NOT BE IN CONTACT WITH INSULATION CONTACT ENGINEER FOR REVISED FEEDER SIZES (IN INSULATION SHALL BE AS DEFINED IN ARTICLE 310.15(A)(2) AND AS DETERMINED BY THE LOCAL AHJ). ALL SER FEEDERS LOCATED WITHIN TYPE I AND/OR II BUILDING AREAS (NONCOMBUSTIBLE CONSTRUCTION) SHALL BE RUN IN EMT CONDUIT PER NEC. ONCE THE CONDUIT PENETRATES THE TRANSITION SLAB AND ENTER INTO THE TYPE III, IV OR V CONSTRUCTION THE SER CABLE MAY BE RUN FREELY AS ALLOWED PER NEC. ALL OTHER WIRING IN DWELLING UNITS EXCEEDING 50 AMPERES SHALL BE INSTALLED IN EMT INDOORS OR PVC OUTDOORS, WHERE NOT SUBJECT TO PHYSICAL DAMAGE.
- G21. ALL FLEX SHALL BE LIQUID TIGHT FLEXIBLE METAL.
- G22. PROVIDE A PULL WIRE OR FISH TAPE IN ALL EMPTY CONDUITS. PROVIDE A BLANK COVER PLATE OVER ALL UNUSED BOXES INCLUDING DATA/COMM BOXES.
- G23. WHERE A SINGLE HOMERUN IS SHOWN THE CIRCUIT SHALL BE INSTALLED IN A DEDICATED CONDUIT, DO NOT COMBINE WITH OTHER CIRCUITS. WHERE A CIRCUIT HOMERUN IS NOT SHOWN THE CONTRACTOR SHALL COMBINE CIRCUITS AS FOLLOWS AND IN ACCORDANCE WITH THE NEC.
1. A MAXIMUM OF THREE 20A, 1 POLE BRANCH CIRCUITS MAY BE COMBINED IN COMMON HOMERUN SHARING A COMMON NEUTRAL OR WITH SEPARATE NEUTRALS, FOR A TOTAL OF SIX CURRENT CARRYING CONDUCTORS. ALL BRANCH CIRCUITS LARGER THAN 20A SHALL BE SEPARATELY HOMERUN TO PANEL.
 2. EACH MULTIWIRE BRANCH CIRCUIT SHARING A COMMON NEUTRAL SHALL BE PROVIDED WITH A MEANS THAT WILL SIMULTANEOUSLY DISCONNECT ALL UNGROUNDED CONDUCTORS AT THE POINT WHERE THE BRANCH CIRCUIT ORIGINATES.
- G24. CONDUCTORS SHALL BE COPPER, RATED AT NOT LESS THAN 600 VOLTS. MINIMUM SIZE SHALL BE NO. 12 AWG UNLESS OTHERWISE NOTED ON THE DRAWINGS. ALL WIRE #8 AWG AND LARGER SHALL BE STRANDED, #10 THRU #12 AWG CONDUCTORS SHALL BE SOLID. ALL INSULATION TYPES SHALL BE THW/THWN. FEEDER CIRCUIT CONDUCTORS MAY BE COPPER OR ALUMINUM.
- G25. 20A/120V BRANCH CIRCUITS EXTENDING UP TO 56" IN LENGTH, FROM PANEL TO FARTHEST DEVICE, SHALL USE AT MINIMUM NO. 12 (CU) CONDUCTORS AND 3/4". FOR 20A/120V BRANCH CIRCUITS EXTENDING UP TO 93" IN LENGTH, FROM PANEL TO FARTHEST DEVICE, SHALL USE NO. 10 (CU) CONDUCTORS AND 3/4". ANY BRANCH CIRCUIT LENGTHS THAT EXCEED 93", THE ELECTRICAL CONTRACTOR SHALL CONTACT THE ENGINEER IMMEDIATELY FOR UPDATED CONDUCTOR AND CONDUIT SIZES.
- G26. TO PREVENT UNDER-VOLTAGE, THE FEEDERS SHOWN ON THE VOLTAGE DROP TABLE(S) HAVE BEEN SIZED TO COMPENSATE FOR WHEREVER A MAXIMUM TOTAL VOLTAGE DROP ON BOTH FEEDERS AND BRANCH CIRCUITS TO THE FARTHEST DEVICE DOES NOT EXCEED 5%. FOR FEEDER LENGTHS EXCEEDING THE ONE-WAY DISTANCES PROVIDED ON THE VOLTAGE DROP TABLE(S) THE ELECTRICAL CONTRACTOR SHALL IMMEDIATELY CONTACT THE ENGINEER PRIOR TO BIDDING, PURCHASING AND ROUGHING-IN FOR UPDATED CONDUCTOR AND CONDUIT SIZES BASED ON UPDATED VOLTAGE DROP CALCULATIONS.
- G27. FOR EVERY WIRING DEVICE MARK THE BRANCH CIRCUIT TO WHICH IT IS CONNECTED ON THE BACK OF EACH DEVICE PLATE, USING AN INDELEBIL MARKER PEN.
- G28. COORDINATE ALL DEVICE AND DEVICE PLATE COLORS WITH OWNER/ARCHITECT. DEVICES AND DEVICE PLATES LOCATED IN CABINERY SHALL BE A DARK COLOR TO MATCH CABINERY FINISH.
- G29. EXACT LOCATION OF ALL FLOOR-MOUNTED OUTLETS SHALL BE COORDINATED WITH THE OWNER/ARCHITECT BEFORE ROUGH-IN.
- G30. TWO OR MORE ADJACENT POWER OR COMMUNICATION RECEPTACLES SHALL BE GANGED WITH A COMMON FACEPLATE - IF THEY CANNOT BE GANGED THEY SHALL BE INSTALLED WITH A MINIMUM DISTANCE BETWEEN UNITS.
- G31. WALL RECEPTACLES SHOWN BACK TO BACK MAY BE OFFSET BUT SHALL BE INSTALLED DIRECTLY ADJACENT TO ONE ANOTHER.
- G32. LIGHT SWITCHES SHALL BE NO MORE THAN 6" FROM EDGE OF DOOR FRAME.
- G33. WHERE PENETRATIONS ARE MADE THROUGH A REQUIRED FIRE-RESISTIVE WALL, FLOOR, OR PARTITION FOR THE PURPOSE OF RUNNING RACEWAY CARRYING ELECTRICAL, TELEPHONE, TELEVISION, OR LOCAL COMMUNICATION AND/OR SIGNALING CIRCUITS, THE OPENING AROUND THE RACEWAY SHALL BE FIRE STOPPED PER THE STATE BUILDING CODE. COORDINATION WITH THE GENERAL CONTRACTOR SHALL BE MAINTAINED TO ENSURE THAT THIS FIRE STOPPING IS ACCOMPLISHED. USE APPROVED ASSEMBLIES SUCH AS THE FOLLOWING:
- * CONDUIT PENETRATIONS OF 1, 2, 3 & 4 HOUR GYP BOARD WALLS - U.L.#WL1001
 - * CONDUIT PENETRATIONS OF 2, 3 & 4 HOUR CONCRETE OR BLOCK WALLS - U.L.#CAJ1001
 - * CONDUIT PENETRATIONS OF 2, 3 & 4 HOUR CONCRETE FLOORS - U.L.#CAJ1001
 - * CONDUIT PENETRATIONS OF 1 HOUR GYPBOARD CEILING ASSEMBLY - L526
 - * MULT. CONDUIT PENETRATIONS OF 2, 3 & 4 HOUR CONCRETE OR BLOCK WALL OR FLOOR - CAJ1042
- G34. IN REQUIRED FIRE RATED WALLS AND PARTITIONS, OPENINGS FOR INSTALLATION OF BOXES SHALL BE IN ACCORDANCE WITH THE APPLICABLE BUILDING CODE AND THE MANUFACTURER'S INSTALLATION INSTRUCTIONS INCLUDED WITH THE BOX LISTING. COORDINATE CLOSELY WITH THE GENERAL CONTRACTOR TO ENSURE THAT THE INTEGRITY OF THE U.L. RATING IS MAINTAINED.
- G35. OUTLET BOXES FOR DEVICES MOUNTED ON OPPOSITE SIDES OF FIRE RATED PARTITIONS SHALL NOT BE MOUNTED IN THE SAME WALL CAVITY. SEPARATE WALL PENETRATIONS BY MOUNTING ON OPPOSITE SIDES OF WALL STUDS OR OTHER VERTICAL STRUCTURAL MEMBER IN THE WALL.
- G36. PRIOR TO ORDERING ANY EQUIPMENT THE ELECTRICAL CONTRACTOR SHALL PROVIDE SHOP DRAWING SUBMITTALS TO THE OWNER, ARCHITECT AND ELECTRICAL ENGINEER FOR THE LIGHTING FIXTURES, ELECTRICAL GEAR, FIRE ALARM SYSTEM AND OTHER SIMILAR SYSTEMS. SHOP DRAWING SUBMITTALS SHALL BE PROVIDED REGARDLESS IF THE EQUIPMENT BEING SUPPLIED IS THE SAME AS WHAT IS SPECIFIED ON THE PLANS.




- G37. THE ELECTRICAL CONTRACTOR SHALL BE RESPONSIBLE FOR PROVIDING RESTRAINTS TO RESIST THE EARTHQUAKE EFFECTS ON THE ELECTRICAL SYSTEM. THE REQUIREMENTS FOR THOSE RESTRAINTS ARE FOUND IN THE IBC, THE ANCHORING OF THE EQUIPMENT SHALL COMPLY WITH IBC SECTION 1613.
- G38. IF DURING THE COURSE OF WORK THE ELECTRICAL CONTRACTOR DISCOVERS A PROBLEM WITH THE PERFORMANCE OF THE INSTALLATION RELATIVE TO THE PLANS AND SPECIFICATIONS OR NEC OR OTHER CODES, THE ELECTRICAL CONTRACTOR SHALL IMMEDIATELY BRING THE PROBLEM TO THE ATTENTION OF THE ARCHITECT AND ENGINEER FOR RESOLUTION PRIOR TO THE EXECUTION OF THE WORK.
- G39. SEE PANEL SCHEDULES FOR BRANCH CIRCUIT CONDUCTOR SIZES. THE "WIRE SIZE" COLUMN INDICATES THE SIZE OF THE PHASE (IE HOT) AND NEUTRAL CONDUCTORS. THE EC SHALL SIZE THE EQUIPMENT GROUNDING CONDUCTORS PER NEC TABLE 250.122, THE EC SHALL SIZE THE CONDUIT (IF REQUIRED) PER NEC ANNEX C. THE QUANTITY OF CONDUCTORS IS BASED ON THE "POLE" COLUMN AND FOLLOWS THE PROCESS BELOW, PARALLEL SET QUANTITIES ARE MULTIPLIED BY THE NUMBER OF SETS:
- 120V/277V - 1 POLE
1- PHASE (IE HOT) - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- NEUTRAL - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- GROUND - PER NEC TABLE 250.122
CONDUIT SIZED PER NEC ANNEX C (IF REQUIRED)
- 208V/240V/480V - 2 POLE
2- PHASE (IE HOT) - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- NEUTRAL (EC VERIFY IF REQUIRED FOR INSTALLED EQUIPMENT) - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- GROUND - PER NEC TABLE 250.122
CONDUIT SIZED PER NEC ANNEX C (IF REQUIRED)
- 208V/240V/480V - 3 POLE
3- PHASE (IE HOT) - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- NEUTRAL (EC VERIFY IF REQUIRED FOR INSTALLED EQUIPMENT) - CONDUCTOR SIZE PER "WIRE SIZE" COLUMN IN PANEL SCHEDULE
1- GROUND - PER NEC TABLE 250.122
CONDUIT SIZED PER NEC ANNEX C (IF REQUIRED)
- G40. ELECTRICAL CONTRACTOR SHALL COORDINATE WITH GEAR MANUFACTURER WHERE THE HIGHEST CONTINUOUS TRIP SETTING FOR WHICH THE ACTUAL DEVICE INSTALLED IN A CIRCUIT BREAKER IS RATED OR CAN BE ADJUSTED IS 1200A OR HIGHER SHALL HAVE ARC ENERGY REDUCTION IN ACCORDANCE WITH NEC 240.87.
- G41. COLOR CODE CONDUCTORS PER NEC. FEEDERS SHALL BE IDENTIFIED IN ACCORDANCE WITH NEC 215.12. USE BLACK, RED, AND BLUE FOR PHASES A, B, AND C RESPECTIVELY ON 208Y/120 VOLT THREE-PHASE Y SYSTEMS AND WHITE FOR THE NEUTRAL. ISOLATED GROUND WIRES SHALL BE GREEN WITH YELLOW BANDS OR STRIPES. THIS IDENTIFICATION SHALL BE MADE AT EACH POINT WHERE A CONNECTION IS MADE. COLORS SHALL BE FACTORY APPLIED FOR CONDUCTORS #6 AWG AND SMALLER. ALL EQUIPMENT GROUNDING CONDUCTORS SHALL BE GREEN IN COLOR AND MINIMUM #12 AWG. THE EC SHALL PROVIDE PLENUM RATED CABLE FOR ANY ELECTRICAL, TELEPHONE, COMMUNICATION, OR OTHER CABLE THAT ENTERS CEILING RETURN PLENUMS.
- G42. WHERE CONDUCTORS ARE RUN IN PARALLEL, THE EC SHALL COMPLY WITH NEC 310.4.
- G43. ISOLATED-GROUND TYPE RECEPTACLES SHALL BE INSTALLED IN ACCORDANCE WITH 250.146(D). ISOLATED GROUND RECEPTACLES SHALL BE ORANGE IN COLOR.
- G44. IN ASSEMBLY AREAS EXCEEDING 100 PERSONS OCCUPANCY, WIRING METHODS SHALL COMPLY WITH NEC 518.

ELECTRICAL SYSTEM AND EQUIPMENT METHOD OF COMPLIANCE SUMMARY	
ELECTRICAL SYSTEM AND EQUIPMENT	
Method of Compliance: <u>Energy Code - Prescriptive</u>	
Lighting schedule:	
lamp type required in fixture number of lamps in fixture ballast type used in the fixture number of ballasts in fixture total wattage per fixture total interior wattage specified vs. allowed: total exterior wattage specified vs. allowed:	See Light Fixture Schedule on sheet
Additional Efficiency Package Options (When using the 2018 NCECC; not required for ASHRAE 90.1)	
<input type="checkbox"/> C406.2 More Efficient HVAC Equipment Performance <input checked="" type="checkbox"/> C406.3 Reduced Lighting Power Density <input type="checkbox"/> C406.4 Enhanced Digital Lighting Controls <input type="checkbox"/> C406.5 On-Site Renewable Energy <input type="checkbox"/> C406.6 Dedicated Outdoor Air System <input type="checkbox"/> C406.7 Reduced Energy Use in Service Water Heating	
DESIGNER STATEMENT:	
To the best of my knowledge and belief, the design of this building/space complies with the electrical system and equipment requirements of the 2018 North Carolina Energy Conservation Code.	

ELECTRICAL SYMBOL LEGEND

	DIUPLEX RECEPTACLE, 20A, 120 VOLT, +18" A.F.F. (U.N.O.) *GFCI INDICATES GROUND FAULT PROTECTION *WP INDICATES WEATHERPROOF
	QUADPLEX RECEPTACLE, 20A, 120 VOLT, +18" A.F.F. (U.N.O.)
	SIMPLEX RECEPTACLE, 20A, 120 VOLT, +18" A.F.F. (U.N.O.) 208/230 VOLT 1Ø RECEPTACLE
	208/230 VOLT 3Ø RECEPTACLE DIUPLEX RECEPTACLE RECESSED IN FLOOR WITH BRASS COVER
	QUADPLEX RECEPTACLE RECESSED IN FLOOR WITH BRASS COVER DIUPLEX RECEPTACLE MOUNTED IN CEILING
	QUADPLEX RECEPTACLE MOUNTED IN CEILING
	JUNCTION BOX
	DISCONNECT SWITCH, FUSED, HEAVY DUTY, NEMA 1 FOR INTERIOR, NEMA 3R FOR EXTERIOR, FUSE ACCORDING TO NAMEPLATE DATA
	NON-FUSED PULL DISCONNECT SWITCH, NEMA 1 FOR INTERIOR, NEMA 3R FOR EXTERIOR.
	TELEPHONE/DATA JACK (JUNCTION BOX WITH 1" CONDUIT STUBBED TO ABOVE CEILING) CONDUCTORS AND TERMINATIONS PROVIDED AND INSTALLED BY COMMUNICATIONS CONTRACTOR
	PASSIVE INFRARED CEILING MOUNTING LINEAR OCCUPANCY SENSOR (WATTSTOPPER CX-100-3 OR EQUAL), TWO-SIDED AISLEWAY OCCUPANCY SENSOR, PROVIDE POWER PACK AS NEEDED FOR OPERATION, WIRE TO LOW VOLTAGE SWITCH FOR MANUAL OVERRIDE. SET OCCUPANCY TIMER TO 15 MINUTES.
	SINGLE POLE SWITCH
	3 WAY SWITCH
	WALL MOUNT INFRARED OCCUPANCY SENSOR WITH UP TO 30 MINUTE TIME-ON SETTING AND MANUAL OVERRIDE, MIN. COVERAGE 500- SQFT. WATTSTOPPER MODEL WS-250 OR EQUAL, 120/277V RATED
	MOTOR RATED SWITCH RATED AT 20 AMPS, VOLTAGE TO MATCH EQUIPMENT
	20 AMP SWITCH IN WEATHERPROOF BOX WITH WEATHERPROOF COVER
	ELECTRICAL PANEL
	DUSK/DAWN PHOTOCCELL
GC	GENERAL CONTRACTOR
EC	ELECTRICAL CONTRACTOR
AFF	ABOVE FINISHED FLOOR
AFG	ABOVE FINISHED GRADE
RECEPT	RECEPTACLE
LTS	LIGHTS
IG	ISOLATED GROUND
WP	WEATHER PROOF (DEVICE TO HAVE WEATHERPROOF IN-USE COVER)
GFCI	GROUND FAULT CIRCUIT INTERRUPTER
AFCI	ARC FAULT CIRCUIT INTERRUPTER

LUMINAIRE SCHEDULE


MARK	DESCRIPTION	MANUFACTURER	MODEL	CCT	MOUNTING	MAX WATTS	BALLAST/DRIVER	REMARKS
A	8' LINEAR LED	LITHONIA	CSS-L96-8000LM-UVOLT-35K-80CRI	3500K	SURFACE	75	LED	1
B	4' LINEAR LED	LITHONIA	CSS-L48-4000LM-UVOLT-35K-80CRI	3500K	SURFACE	35	LED	1
C	FLOOD LIGHT	NUVO	65-715	3000K	SURFACE	20	LED	1
D	EXTERIOR GOOSE NECK	NUVO	65-661	VARIES	SURFACE	50	LED	1
	EXIT UNIT COMBO LIGHT	EXITRONIX	VLED-1WH-EL90-R	-	VARIES	2	LED	1
	EMERGENCY WALL LIGHT	EXITRONIX	LED-90-G2	-	VARIES	2	LED	1
	REMOTE LED LAMP HEAD / WP	EXITRONIX	2CLED-WP	-	SURFACE	2	LED	1

1. PROVIDE INTEGRAL MOTION SENSOR.

GENERAL NOTES:


- A. THE CONTRACTOR SHALL VERIFY THE LEAD TIME OF ALL PRODUCTS SPECIFIED IN THIS SCHEDULE AT THE TIME OF PACKAGE QUOTE.
- B. DURING THE BID PROCESS, THE CONTRACTOR SHALL NOTIFY THE ARCHITECT/ENGINEER OF ANY DELIVERY/SCHEDULING ISSUES.
- C. NO SUBSTITUTIONS WILL BE ALLOWED DUE TO THE LACK OF COORDINATION OF DELIVERY DATES AND CONSTRUCTION SCHEDULE AFTER BID.
- D. ALL EXPEDITED EXPENSES SHALL BE THE RESPONSIBILITY OF THE CONTRACTORS.
- E. FIXTURES TO BE INSTALLED IN CEILINGS, INDICATE ON THE ARCHITECTURAL PLANS AS HAVING INSULATION IN CONTACT WITH THE CEILING SURFACE. SHALL BE IC RATED BY MANUFACTURER.
- F. LIGHTING FIXTURES SHALL MEET THE AESTHETICS, DESCRIPTION AND SPECIFICATIONS, SUBSTITUTIONS SHALL INCLUDE PT. BY PT. CALCULATIONS.
- G. LIGHTING FIXTURES, AS SPECIFIED, HAVE BEEN SO SELECTED TO ACHIEVE REQUIRED/DESIRED FOOTCANDLE LEVELS IN THEIR RESPECTIVE AREA. HENCE SPECIFIC FIXTURE CHARACTERISTICS WHICH MAY CREATE PARTICULAR ILLUMINATION RESULTS ARE ESSENTIAL. ANY DEVIATIONS FROM SPECIFIED FIXTURES SHALL DEEM THE SUBMITTING AGENT AND CONTRACTORS RESPONSIBLE IN PROVIDINGSUCH DEVIATION FOR THE ARCHITECT/ENGINEER AND OWNER TO MAKE AN INFORMED DECISION.
- H. SUBSTITUTIONS APPROVED BY THE ENGINEER PREVIOUS TO BID ARE ACCEPTABLE AS LONG AS THEY ARE EQUAL TO THE FIXTURE SPECIFIED, UNLESS OTHERWISE NOTED. THIS INCLUDES LENS, COLORS, REFLECTORS, PHOTOMETRICS, HOUSING MATERIAL, FINISHES, ETC. ALL SUBSTITUTIONS SHALL BE SUBMITTED TO THE ENGINEER WITH CUT SHEETS FOR APPROVAL. SUBSTITUTE FIXTURES SHALL BE PRICED WITH THE SPECIFIED FIXTURE AND LISTED SEPARATELY SO THE ARCHITECT, ENGINEER AND OWNER CAN MAKE AN INFORMED DECISION.
- I. ANY FIXTURE WITH THE TEXT "N.L." ADJACENT TO IT SHALL INDICATE THAT THAT FIXTURE IS A NIGHT LIGHT (24HR LIGHT), THE FIXTURE SHALL BE CONNECTED TO THE UNSWITCHED HOT LEG OF THE INDICATED CIRCUIT.
- J. ACRYLIC PRISMATIC LENSES SHALL BE 0.156" NOMINAL MINIMUM THICKNESS.
- K. ALL EXIT AND EMERGENCY FIXTURES SHALL COMPLY WITH NCSB STANDARDS AND HAVE AUTOMATIC TESTING DEVICES.
- L. LED EMERGENCY BATTERY SHALL PROVIDE 1400 MINIMUM LUMENS OUTPUT FROM 1 LAMP FOR 90 MINUTES MINIMUM.
- M. ELECTRICAL CONTRACTOR SHALL CONNECT ALL LED EMERGENCY FIXTURES TO CLOSEST AVAILABLE LIGHTING CIRCUIT UNLESS NOTED OTHERWISE.
- N. LED MODULES SHALL BE REPLACEABLE.
- O. ELECTRICAL CONTRACTOR SHALL RECEIVE APPROVAL FOR ALL LIGHTING FIXTURES FROM ARCHITECT/OWNER PRIOR TO PURCHASE AND ROUGH-IN. THE ABOVE FIXTURE TYPES ARE LISTED AS THE DESIGN BASIS.

ELECTRICAL DRAWING INDEX	
E0.1	ELECTRICAL LEGENDS AND NOTES
E1.1	LIGHTING PLAN - BOTTOM FLOOR
E1.2	LIGHTING PLAN - TOP FLOOR
E1.3	POWER PLAN - BOTTOM FLOOR
E1.4	POWER PLAN - TOP FLOOR
E2.1	PANEL SCHEDULES AND ONE-LINE DIAGRAM
E3.1	ELECTRICAL DETAILS



DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1

11132 U.S. 401 N
FUQUAY-VARINA, NC 27526


REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.:	DRAWN BY:
24-029	GMS
ELECTRICAL LEGENDS AND NOTES	

E0.1


LIGHTING KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	LIGHTING TO BE CONTROLLED BY INTEGRAL MOTION SENSORS TO FIXTURES.
2	PROVIDE LOW VOLTAGE SWITCH FOR MANUAL CONTROL OF LIGHTING FIXTURES.
3	VERIFY ANGLE AND MOUNTING LOCATION OF 2-WAY LINEAR MOTION SENSOR TO ENSURE OPERATION IN SPACE.



1 LIGHTING PLAN - BOTTOM FLOOR
SCALE - 3/32" = 1'0"

DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		


ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

LIGHTING PLAN - BOTTOM FLOOR


E1.1

LIGHTING KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	LIGHTING TO BE CONTROLLED BY INTEGRAL MOTION SENSORS TO FIXTURES.
2	PROVIDE LOW VOLTAGE SWITCH FOR MANUAL CONTROL OF LIGHTING FIXTURES.
3	VERIFY ANGLE AND MOUNTING LOCATION OF 2-WAY LINEAR MOTION SENSOR TO ENSURE OPERATION IN SPACE.



1 LIGHTING PLAN - TOP FLOOR
SCALE - 3/32" = 10"

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526


REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS


LIGHTING PLAN - TOP FLOOR
E1.2

POWER KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	PROVIDE EQUIPMENT DISCONNECT. REFER TO MECHANICAL EQUIPMENT SCHEDULE FOR ADDITIONAL INFORMATION.
2	VERIFY EXACT MOUNTING LOCATION OF PANEL PRIOR TO BEGINNING WORK.



1 POWER PLAN - BOTTOM FLOOR
SCALE - 3/32" = 10"

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526


REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS


POWER PLAN - BOTTOM FLOOR
E1.3

POWER KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	PROVIDE EQUIPMENT DISCONNECT. REFER TO MECHANICAL EQUIPMENT SCHEDULE FOR ADDITIONAL INFORMATION.
2	VERIFY EXACT MOUNTING LOCATION OF PANEL PRIOR TO BEGINNING WORK.
3	PROVIDE RECESSED JUNCTION BOX FOR UNIT HEATER.
4	PROVIDE JUNCTION BOX FOR POINT OF USE WATER HEATER. PROVIDE MEANS OF DISCONNECT FOR MAINTENANCE.
5	PROVIDE JUNCTION BOX FOR FIRE ALARM CONTROL PANEL.



1 POWER PLAN - TOP FLOOR
SCALE - 3/32" = 10"

DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: **24-029**
DRAWN BY: **DBAS**
CHECKED BY: **DBAS**


E1.4

600 AMP MAIN LUG ONLY										PANELBOARD A										LOCATION: S1			
600 AMP BUS RATING										42 POLES										22 KA SHORT CIRCUIT RATING		ENCLOSURE RATING: NEMA 1	
208Y/120 VOLTS										3 PHASE 4 WIRE 60 HZ										MOUNTING: SURFACE			
CIRCUIT NO.	DESCRIPTION	BREAKER AMPS/POLES	LOAD KVA			BREAKER AMPS/POLES	DESCRIPTION	CIRCUIT NO.	LOAD KVA			BREAKER AMPS/POLES	DESCRIPTION	CIRCUIT NO.									
			PHASE A	PHASE B	PHASE C				PHASE A	PHASE B	PHASE C												
1	TOP FLOOR LIGHTING	20/1	1.31	1.69		20/1	TOP FLOOR LIGHTING	2				20/1	TOP FLOOR LIGHTING	2									
3	GENERAL RECEPTS.	20/1			0.72	0.72	20/1	GENERAL RECEPTS.	4			20/1	GENERAL RECEPTS.	4									
5	EXTERIOR RECEPTS.	20/1					20/1	EXTERIOR RECEPTS.	6			20/1	EXTERIOR RECEPTS.	6									
7	AHU-5	60/2	5.20	5.20			60/2	AHU-6	8			60/2	AHU-6	8									
9					5.20	5.20			10					10									
11	AHU-7	60/2					60/2	AHU-8	12			60/2	AHU-8	12									
13			5.20	5.20					14					14									
15	HP-1	45/2			2.71	2.71	45/2	HP-2	16			45/2	HP-2	16									
17									18					18									
19	HP-3	45/2	2.71	2.71			45/2	HP-4	20			45/2	HP-4	20									
21					2.71	2.71			22					22									
23	HP-5	45/2					45/2	HP-6	24			45/2	HP-6	24									
25			2.71	2.71					26					26									
27	HP-7	45/2			2.71	2.71	45/2	HP-8	28			45/2	HP-8	28									
29									30					30									
31	BATHROOM/SPRINKLER LIGHTING	20/1	0.35	1.50			20/2	EUH-1	32			20/2	EUH-1	32									
33	POINT OF USE WATER HEATER	20/1			2.40	1.50			34					34									
35	POINT OF USE WATER HEATER	20/1					20/2	EUH-2	36			20/2	EUH-2	36									
37			13.76	1.50					38					38									
39	PANEL A2	200/3			16.32	1.50	20/2	EUH-3	40			20/2	EUH-3	40									
41									42					42									
TOTAL PHASE KVA PER PHASE			51.75	49.82		49.82	DEMAND KVA:			180.40													
TOTALCONNECTED KVA			151.39			DEMAND AMPS:			501														
AMPS PER PHASE			431	415		415																	

NOTES:
1
2
3
4

200 AMP MAIN LUG ONLY										PANELBOARD A2										LOCATION: BOTTOM FLOOR			
225 AMP BUS RATING										30 POLES										10 KA SHORT CIRCUIT RATING		ENCLOSURE RATING: NEMA 1	
208Y/120 VOLTS										3 PHASE 4 WIRE 60 HZ										MOUNTING: SURFACE			
CIRCUIT NO.	DESCRIPTION	BREAKER AMPS/POLES	LOAD KVA			BREAKER AMPS/POLES	DESCRIPTION	CIRCUIT NO.	LOAD KVA			BREAKER AMPS/POLES	DESCRIPTION	CIRCUIT NO.									
			PHASE A	PHASE B	PHASE C				PHASE A	PHASE B	PHASE C												
1	BOTTOM FLOOR LIGHTING	20/1	1.50	1.50		20/1	BOTTOM FLOOR LIGHTING	2				20/1	BOTTOM FLOOR LIGHTING	2									
3	GENERAL RECEPTS.	20/1			5.20	0.72	20/1	GENERAL RECEPTS.	4			20/1	GENERAL RECEPTS.	4									
5	AHU-1	60/2					60/2	AHU-2	6			60/2	AHU-2	6									
7			5.20	0.36					8					8									
9	AHU-2	60/2			5.20	0.72	60/2	AHU-3	10			60/2	AHU-3	10									
11									12					12									
13	AHU-3	60/2	5.20	0.35			60/2	AHU-4	14			60/2	AHU-4	14									
15					5.20	0.18			16					16									
17	AHU-4	60/2					60/2	SPACE	18			60/2	SPACE	18									
19	SPACE							SPACE	20					20									
21	SPACE							SPACE	22					22									
23	SPACE							SPACE	24					24									
25	SPACE							SPACE	26					26									
27	SPACE							SPACE	28					28									
29	SPACE							SPACE	30					30									
TOTAL PHASE KVA PER PHASE			14.11	17.22		16.395	DEMAND KVA:			63.59													
TOTALCONNECTED KVA			47.725			DEMAND AMPS:			177														
AMPS PER PHASE			118	144		137																	

NOTES:
1
2
3
4




1 ONE-LINE DIAGRAM
NOT TO SCALE

FEEDER SCHEDULE - 3 PHASE				
STANDARD OVERCURRENT PROTECTION SIZE	FEEDER WIRE - # SETS (CONDUCTOR SIZE, EQUIP. GND., CONDUIT SIZE)		CONDUCTOR TYPE: THHN - DRY, THWN - WET	
	COPPER WIRE	GEC	ALUMINUM WIRE	GEC
30	1 [4 #10, #10G, 3/4"C]		1 [4 #8, #8G, 3/4"C]	
35	1 [4 #8, #10G, 3/4"C]		1 [4 #6, #8G, 1"C]	
40	1 [4 #8, #10G, 3/4"C]		1 [4 #6, #8G, 1"C]	
45	1 [4 #6, #10G, 1"C]		1 [4 #4, #8G, 1-1/4"C]	
50	1 [4 #6, #10G, 1"C]		1 [4 #4, #8G, 1-1/4"C]	
60	1 [4 #4, #10G, 1-1/4"C]		1 [4 #3, #8G, 1-1/4"C]	
70	1 [4 #4, #8G, 1-1/4"C]		1 [4 #2, #6G, 1-1/4"C]	
80	1 [4 #3, #8G, 1-1/4"C]		1 [4 #1, #6G, 1-1/2"C]	
90	1 [4 #2, #8G, 1-1/4"C]		1 [4 #1/0, #6G, 2"C]	
100	1 [4 #1, #6G, 1-1/2"C]	#8	1 [4 #1/0, #6G, 2"C]	#6
110	1 [4 #1, #6G, 1-1/2"C]	#8	1 [4 #1/0, #4G, 2"C]	#6
125	1 [4 #1, #6G, 1-1/2"C]	#6	1 [4 #2/0, #4G, 2"C]	#4
150	1 [4 #1/0, #6G, 2"C]	#6	1 [4 #3/0, #4G, 2"C]	#4
175	1 [4 #2/0, #6G, 2"C]	#4	1 [4 #4/0, #4G, 2-1/2"C]	#2
200	1 [4 #3/0, #6G, 2"C]	#4	1 [4 #250KCMIL, #4G, 2-1/2"C]	#2
225	1 [4 #4/0, #4G, 2-1/2"C]	#2	1 [4 #300KCMIL, #2G, 3"C]	#1/0
250	1 [4 #250KCMIL, #4G, 2-1/2"C]	#2	1 [4 #350KCMIL, #2G, 3"C]	#1/0
300	1 [4 #300KCMIL, #4G, 3"C]	#2	1 [4 #500KCMIL, #2G, 3"C]	#1/0
350	2 [4 #2/0, #3G, 2"C]	#2	2 [4 #4/0, #1G, 2-1/2"C]	#1/0
400	2 [4 #3/0, #3G, 2"C]	#2	2 [4 #250KCMIL, #1G, 2-1/2"C]	#1/0
450	2 [4 #4/0, #2G, 2-1/2"C]	#1/0	2 [4 #300KCMIL, #1/0G, 3"C]	#3/0
500	2 [4 #250KCMIL, #2G, 2-1/2"C]	#1/0	2 [4 #350KCMIL, #1/0G, 3"C]	#3/0
600	2 [4 #350KCMIL, #1G, 3"C]	#2/0	2 [4 #500KCMIL, #2/0G, 3"C]	#4/0
700	2 [4 #500KCMIL, #1/0G, 3"C]	#2/0	3 [4 #350KCMIL, #3/0G, 3"C]	#4/0
800	3 [4 #300KCMIL, #1/0G, 3"C]	#3/0	3 [4 #400KCMIL, #3/0G, 3"C]	#4/0
1000	3 [4 #400KCMIL, #2/0G, 3"C]	#3/0	4 [4 #350KCMIL, #4/0G, 3"C]	#4/0
1200	4 [4 #350KCMIL, #3/0G, 3"C]	#3/0	4 [4 #500KCMIL, #250KCMIL G, 3"C]	#250 KCMIL
1600	5 [4 #400KCMIL, #4/0G, 3"C]	#3/0	6 [4 #400KCMIL, #350KCMIL G, 3"C]	#250 KCMIL
2000	6 [4 #400KCMIL, #250KCMIL G, 3"C]	#3/0	7 [4 #500KCMIL, #400KCMIL G, 3"C]	#250 KCMIL
2500	7 [4 #500KCMIL, #350KCMIL G, 3"C]	#3/0	9 [4 #500KCMIL, #600KCMIL G, 3"C]	#250 KCMIL
3000	8 [4 #500KCMIL, #400KCMIL G, 3"C]	#3/0	10 [4 #500KCMIL, #600KCMIL G, 3"C]	#250 KCMIL
4000	11 [4 #500KCMIL, #500KCMIL G, 3"C]	#3/0	13 [4 #500KCMIL, #750KCMIL G, 3"C]	#250 KCMIL

FEEDER SCHEDULE NOTES:
1. ALL FEEDER SIZES MAY NOT BE LISTED IN ONE-LINE DIAGRAM
2. ELECTRICAL CONTRACTOR TO VERIFY CONDUIT SIZE REQUIRED IF WIRE TYPES OTHER THAN THOSE LISTED ABOVE ARE USED. REFER TO APPLICABLE TABLE IN ANNEX C OF NEC.
3. IF CONDUIT OTHER THAN EMT IS REQUIRED, BASE BID ON NEXT TRADE SIZE ABOVE THAT INDICATED.
4. 'GEC' DENOTES GROUNDING ELECTRODE CONDUCTOR PER NEC TABLE 250.66.
* EC SHALL VERIFY WITH AUTHORITY HAVING JURISDICTION AND UTILITY COMPANY THAT ALUMINUM CONDUCTORS ARE ACCEPTABLE FOR USE AS UTILITY TRANSFORMER SECONDARIES AND FEEDER CIRCUITS.



DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.




DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: GMS
CHECKED BY: GMS
PANEL SCHEDULES AND ONE-LINE DIAGRAM


E2.1




1 SERVICE GROUNDING DETAIL
NOT TO SCALE

- GROUNDING DETAIL NOTES:**
- GROUNDING ELECTRODES SHALL BE PROVIDED IN ACCORDANCE WITH NEC 250.52(A).
 - GROUNDING ELECTRODES SHALL BE INSTALLED IN ACCORDANCE WITH NEC 250.53.

NOT ALL ELECTRODES MAY BE PRESENT ON-SITE, THEREFORE NOT ALL ELECTRODES ON THIS DETAIL MAY APPLY. DETAIL IS DIAGRAMMATIC ONLY




2 WORKING CLEARANCE FOR ELECTRICAL EQUIPMENT
NEC ARTICLE 110.26



PANELBOARD NAMEPLATES

- NOTES:**
- SEE SPECIFICATIONS FOR ADDITIONAL REQUIREMENTS, COLORS, ETC.
 - PROVIDE SHORT-CIRCUIT CURRENT RATINGS AND AVAILABLE FAULT CURRENT ON EACH NON-DWELLING SERVICE EQUIPMENT NAMEPLATE.

3 TYPICAL NAMEPLATE DIAGRAM
NOT TO SCALE




- NOTES:**
- ALL DIMENSIONS ARE TO CENTER LINE OF DEVICE, UNLESS OTHERWISE NOTED.

4 TYPICAL DEVICE MOUNTING ELEVATION
NOT TO SCALE

DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		


PROJECT NO.: 24-029
DRAWN BY: OMS
CHECKED BY: OMS

ELECTRICAL DETAILS

E3.1

FIRE ALARM GENERAL NOTES

- FACP SHALL HAVE A MINIMUM 24HR. BATTERY BACKUP.
- FACP SHALL BE FULLY ANALOG ADDRESSABLE.
- FACP SHALL BE CONNECTED TO A UL APPROVED CENTRAL STATION.
- ZONE PER NFPA 72, 2013 AND MANUFACTURER'S RECOMMENDATIONS WITH NO ONE ZONE EXCEEDING 15,000 S.F. PER FLOOR.
- COORDINATE QUANTITY AND LOCATIONS OF DEVICES WITH CONTRACT DRAWINGS.
- LOCATE SMOKE DETECTOR WITHIN 5' OF THE MAGNETIC HOLD OPEN DOORS. (TYPICAL)
- LOCATE FIRE ALARM PULL STATION WITHIN 5' OF THE EXIT DOOR.
- LOCATE SMOKE/HEAT DETECTOR WITHIN 5' OF THE FA EQUIPMENT (FACP, FATC, NAC).
- LOCATION OF CEILING MOUNTED SMOKE/HEAT DETECTOR SHALL BE FIELD COORDINATED PRIOR TO ROUGH IN. THE DETECTOR SHALL BE A MINIMUM OF 2' AWAY FROM LIGHT FIXTURE AND A MINIMUM OF 3' AWAY FROM AIR DISTRIBUTION DEVICES.
- AUTOMATIC DOOR CLOSING SHALL BE ACCOMPLISHED BY THE ACTIVATION OF THE BUILDING FIRE ALARM SYSTEM. SMOKE DETECTOR ACTIVATION SHALL ALERT THE BUILDING FIRE ALARM SYSTEM. THE FIRE ALARM SYSTEM SHALL CAUSE ALL HOLD OPEN DOORS TO CLOSE UPON ALARM ACTIVATION IN THE BUILDING.
- ACTIVATION OF AN ALARM ZONE SHALL CAUSE ALL AIR HANDLING EQUIPMENT TO SHUT DOWN (ALL DAMPERS, AIR HANDLERS AND EXHAUST FANS MUST STOP).
- ACTIVATION OF KITCHEN HOOD SUPPRESSION SYSTEM PROVIDES SIGNAL TO FACP WHICH IN TURN ACTIVATES ALL ANNUNCIATING ZONES & SHUTS DOWN HOOD SUPPLY AIR. HOOD EXHAUST SHALL CONTINUE TO OPERATE.
- ELECTRICAL CONTRACTOR SHALL COORDINATE EXACT LOCATIONS OF ALL FLOW, PRESSURE, & TAMPER SWITCHES WITH FIRE PROTECTION CONTRACTOR PRIOR TO INSTALLATION.
- ALL VISUAL DEVICES WITHIN THE SAME AREA SHALL BE SYNCHRONIZED.
- ALL FIRE ALARM WIRING SHALL BE IN RED COLORED CONDUIT. FIRE ALARM CABLING SHALL BE PLENUM RATED.
- PROVIDE MULTI-TEMPORAL SOUNDING CAPABILITY AT ALL AUDIO DEVICES FOR EMERGENCY NOTIFICATION FOR NON VOICE SYSTEMS COMPONENTS.
- THE FIRE ALARM SYSTEM MANUFACTURER SHALL PROVIDE NOTIFICATION APPLIANCE CIRCUIT (NAC) POWER EXTENDERS AS REQUIRED.
- THE DUCT SMOKE DETECTORS SHALL COMPLY WITH IFC 907.2.12.1.2 AND 907.3.1.
- PROVIDE DITEK #DTK-DF120S1 SERIES OR EQUAL TVSS FOR 120V SUPPLY TO FIRE ALARM CONTROL PANELS, WITH TVSS DRY CONTACT TO BE MONITORED BY FACP. PROVIDE DITEK, DTK-2MHLP24F-WB OR EQUAL FOR ALL FIRE ALARM CABLES THAT EXIT THE PHYSICAL BUILDING. TAMPER SWITCHES DTK-2MHLP24B-WB AND EACH LUB/EXTENDER FIRE ALARM PANEL, NAC, PIV, IDC SURGE, DTK-2MHLP24B-WB OR EQUAL, DIALER SURGE, DTK-2MHTPW WB FIBER MEDIA CONVERTER PROTECTOR DTK-PVPIP OR EQUAL.
- THE CIRCUIT FEEDING THE FIRE ALARM PANEL IS DEDICATED FOR THE FIRE ALARM ONLY. BREAKER SHALL BE PROVIDED WITH A LABEL "FIRE ALARM CIRCUIT" AND SHALL BE RED. PROVIDE BREAKER LOCK ON DEVICE.
- PROVIDE REMOTE LIGHT WITH TEST SWITCH FOR DUCT SMOKE DETECTOR ON CEILING WHERE UNIT IS ABOVE CEILING.
- CONTRACTOR SHALL INCLUDE IN BID LABOR AND MATERIAL FOR UP TO (2) DUCT DETECTORS, (5) ANNUNCIATION DEVICES, (2) SMOKE DETECTORS AND (2) PULL STATIONS 100' FROM LOCAL PANEL (IN WALL) AS REQUIRED BY LOCAL AHJ/ENGINEER. INCLUDE ALL PROGRAMMING COSTS.
- CONTRACTOR RESPONSIBLE FOR SHOP DRAWINGS AS REQUIRED BY LOCAL AHJ.
- DUCT DETECTORS SHALL BE VERIFIED WITH THE MECHANICAL DRAWINGS FOR QUANTITY AND LOCATION. TOTAL QUANTITY MINIMUM SHALL BE BASED ON BOTH MECHANICAL SCHEDULES AND MECHANICAL PLAN LOCATIONS AND ELECTRICAL PLANS. WHEN DEVICE QUANTITIES (ELECTRICAL VS. MECHANICAL) ARE IN CONFLICT, PROVIDE THE GREATER QUANTITY OF DETECTORS.
- DIGITAL ALARM COMMUNICATOR TRANSMITTER SHALL BE ACCEPTABLE TO THE REMOTE CENTRAL STATION AND SHALL COMPLY WITH UL 632. CELLULAR LINE - SINGLE MAIN SOURCE. PROVIDE NAPCO STARLINK (SLD-CMDA-FIRE) FIRE ALARM COMMUNICATOR AND SLE-ANTEX50 EXTERNAL ANTENNA TO OR EQUAL AND COORDINATED WITH THE CELLULAR DIAL OUT SERVICE. CELLULAR DIAL OUT SHALL BE BACKED UP AS PART OF BATTERY BACKUP AS WELL AS GENERATOR BACKUP WHERE AVAILABLE. FUNCTIONAL PERFORMANCE UNIT SHALL RECEIVE AN ALARM, SUPERVISORY OR TROUBLE SIGNAL FROM FIRE ALARM CONTROL UNIT AND AUTOMATICALLY CAPTURE A PRESET NUMBER FOR A REMOTE CENTRAL STATION. WHEN CONTACT IS MADE WITH CENTRAL STATION(S), SIGNALS SHALL BE TRANSMITTED. IF SERVICE ON THE CELLULAR LINE IS INTERRUPTED FOR LONGER THAN 45 SECONDS, TRANSMITTER SHALL INITIATE A LOCAL TROUBLE SIGNAL. TRANSMITTER SHALL AUTOMATICALLY REPORT CELLULAR SERVICE RESTORATION TO THE CENTRAL STATION. IF SERVICE IS LOST, TRANSMITTER SHALL INITIATE THE LOCAL TROUBLE SIGNAL.
- SLEEPING AREAS SHALL COMPLY WITH NFPA 72 2013 SECTION 18.4.5.3. WHERE AUDIBLE APPLIANCES ARE PROVIDED TO PRODUCE SIGNALS FOR SLEEPING AREAS, AUDIBLE DEVICE SHALL PRODUCE A LOW FREQUENCY ALARM SIGNAL OF 520HZ SQUAREWAVE ALARM SIGNAL.



- NOTES:
- LOCATIONS WHERE TV MOUNT IS BACK TO BACK ON SAME WALL, AN OFFSET OF 8-12" WILL BE NEEDED FOR INSTALLATION OF JACK/RECEPTACLE.
 - DEVICES ABOVE COUNTER TOPS SHALL BE A MAXIMUM OF 48" TO TOP OF DEVICE.
 - DEVICES NEXT TO DOOR EXIT SHALL BE WITHIN 8" (MAXIMUM) TYPICAL OF DOOR UNLESS OBSTACLES SUCH AS SIDELITES, ETC.
 - ALL DEVICES ARE TO CENTER LINE OF DEVICE, UNLESS OTHERWISE NOTED.

1 MOUNTING HEIGHTS OF DEVICES-ELEVATION


NOT TO SCALE

FIRE ALARM SYSTEM INPUT/OUTPUT MATRIX	SYSTEM OUTPUTS																								
	FACP ANNUNCIATION												NOTIFICATION						REQUIRED FIRE SAFETY CONTROL						
SYSTEM INPUTS	A	B	C	D	E	F	G	H	I	J	K	L	M	N	O	P	Q	R	S	T	U	V	W	X	Y
1 FIRE ALARM SYSTEM AC POWER FAILURE																									
2 FIRE ALARM SYSTEM LOW BATTERY																									
3 OPEN CIRCUIT																									
4 GROUND FAULT																									
5 NOTIFICATION APPLIANCE CIRCUIT SHORT																									
6 BUILDING MANUAL PULL STATIONS																									
7 CORRIDOR SMOKE DETECTORS																									
8 AREA SMOKE DETECTORS																									
9 HVAC AIR DUCT SMOKE DETECTORS																									
10 AREA HEAT DETECTORS																									
11 HOOD OR ROOF FIRE SUPPRESSION SYSTEM ALARM																									
12 SPRINKLER TAMPER SWITCH																									
13 SPRINKLER WATER FLOW IN BUILDING																									
14 SPRINKLER WATER FLOW IN ELEV EQUIP RM OR SHAFT																									
15 ELEV EQUIP RM AREA SMOKE DETECTOR																									
16 ELEV SHAFT AND ELEV EQUIP RM HEAT DETECTORS																									
17 ELEV LOBBY SMOKE DETECTORS - UPPER FLOORS																									
18 ELEV LOBBY SMOKE DETECTOR - RECALL FLOOR																									
19 ELEV CONTROLLER POWER SHUNT TRIP STATUS																									
20 FIRE PUMP POWER FAILURE/PHASE REVERSAL																									
21 FIRE PUMP RUNNING																									
22 FIRE PUMP SYSTEM NOT IN AUTOMATIC																									
23 LEGALLY REQUIRED GENERATOR SYSTEM LOW FUEL																									
24 LEGALLY REQUIRED GENERATOR NOT IN AUTOMATIC																									
25 AREA OF REFUGE TWO-WAY COMMUNICATIONS STATUS																									
26																									
27																									

NFPA FIRE ALARM LEGEND	
SYMBOL	DESCRIPTION
[FACP]	FIRE ALARM CONTROL PANEL
[TPRN]	FIRE ALARM TERMINAL CABINET (N = TRANSPONDER NUMBER)
[FSCP]	FIRE SUPPRESSION CONTROL PANEL (N DENOTES SUPPRESSION TYPE)
[GAP]	GRAPHIC ANNUNCIATOR PANEL
[DACT]	DIGITAL ALARM COMMUNICATOR TRANSMITTER
[FAA]	FIRE ALARM ANNUNCIATOR
[PRN]	PRINTER
[MIC]	REMOTE VOICE / EVACUATION VOICE / EVACUATION MICROPHONE
[E]	FIRE SERVICE OR EMERGENCY PHONE STATION
[WFS]	WATER FLOW SWITCH
[LTS]	LOW TEMPERATURE SWITCH
[HPS]	HIGH PRESSURE SWITCH
[MR]	MAIN / RESERVE
[PS]	PRESSURE DETECTOR / SWITCH
[VSS]	VALVE SUPERVISORY SWITCH
[AS]	ABORT SWITCH
[MRS]	MANUAL RELEASING STATION
[AIM]	ADDRESSABLE INPUT MONITOR
[AOM]	ADDRESSABLE OUTPUT (RELAY)
[AION]	ADDRESSABLE INPUT/OUTPUT MODULE (N DENOTES NUMBER OF INPUTS AND OUTPUTS)
[ACM]	ADDRESSABLE CONTROL MODULE
[GX]	GAS DETECTOR (X = GAS TYPE, EX. CO FOR CARBON MONOXIDE)
[HX]	HEAT DETECTOR/SENSOR (X = TYPE)
[GXHX]	PROVIDE BOX, AS SHOWN, TO DENOTE COMBINATION DETECTORS
[LH]	HEAT DETECTOR LINE TYPE
[E]	PULL STATION / FIRE ALARM
[GX]	SMOKE DETECTOR/SENSOR (DEFAULT PHOTOELECTRIC TYPE)
[GXION]	SMOKE DETECTOR - IONIZATION TYPE
[SS]	SMOKE ALARM (SINGLE STATION)
[MS]	SMOKE ALARM (MULT. STATION)
[SB]	DETECTOR WITH SOUNDER BASE
[MC]	DETECTOR - MULTI CRITERIA TYPE
[GXGX]	DUCT SMOKE DETECTOR (NFPA 72, SECTION 17.7.5.5)
[CD]	AUDIBLE ONLY APPLIANCE (WALL MOUNTED)
[VCD]	VISUAL ONLY APPLIANCE (WALL MOUNTED)
[CD]	AUDIBLE/VISUAL APPLIANCE (WALL MOUNTED)
[CD]	VISUAL ONLY APPLIANCE (CEILING MOUNTED)
[CD]	AUDIBLE ONLY APPLIANCE (CEILING MOUNTED)
[VCD]	AUDIBLE/VISUAL APPLIANCE (CEILING MOUNTED)
[R]	END OF LINE RESISTOR

DISCLAIMER

THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		


PROJECT NO.: 24-029
DRAWN BY: OMS
CHECKED BY: OMS

FIRE ALARM LEGENDS AND NOTES

FA0.1

FIRE ALARM KEYNOTE LEGEND	
KEY VALUE	KEYNOTE TEXT
1	FIRE ALARM CONTROL PANEL LOCATED IN SPRINKLER ROOM. SMOKE ALARM TO BE PLACED ABOVE PANEL.
2	FLOW AND TAMPER SWITCHES TO BE INSTALLED WITH SPRINKLER SYSTEM AT RISER AND EACH ZONE CONTROL VALVE. COORDINATE ALL NECESSARY LOCATIONS WITH SPRINKLER CONTRACTOR.


NOTE:
BUILDING IS SPRINKLER MONITORED ONLY



1 FIRE ALARM PLAN - TOP FLOOR
SCALE - 3/32" = 1'0"



DISCLAIMER
THESE DRAWINGS, THE PROJECT SPECIFICATIONS MANUAL, AND THE DESIGN ARE INSTRUMENTS OF SERVICE ONLY AND REMAIN THE PROPERTY OF SHARPE ENGINEERING & CONSULTING, PLLC. THE REPRODUCTION AND/OR UNAUTHORIZED USE OF THESE DOCUMENTS WITHOUT THE EXPRESS WRITTEN PERMISSION OF SHARPE ENGINEERING & CONSULTING, PLLC IS PROHIBITED.



DESIGN FOR:
BAUCOM BUSINESS PLAZA - S1
11132 U.S. 401 N
FUQUAY-VARINA, NC 27526

REV. NO.	DATE	DESCRIPTION
1		
2		
3		
4		
5		
6		
7		

ISS. NO.	DATE	DESCRIPTION
1	8-22-24	FOR PERMITTING
2		
3		
4		
5		
6		
7		

PROJECT NO.: 24-029
DRAWN BY: DBAS
CHECKED BY: DBAS

FIRE ALARM PLAN
FA1.1