

SEGMENTAL RETAINING WALLS

INDEX OF DRAWINGS:

Sheet 1 of 5: Sheet 2 of 5: Cover Sheet Plan View Elevation Views (Wall 1) Details


Sheet 3 of 5: Sheet 4 of 5: Sheet 5 of 5:


50 Harnett




COMMICATE NS - 2446 (704) 483-5225 Fax: (704) 483-5466 4090 N, NC HWY 16 P.O. Box 2189 DENVER, NC 28037 www.WWEgeo.com MLKiser@bellsouth.net











704) 483-5225 ax: (704) 483-5466 4090 N. NC HWY 16 P.O. Box 2189 DENVER, NC 28037 www.WWEgeo.com MLKiser@bellsouth.net



NOT TO SCALE


NOTES:

THIS SHEET IS NOT A CERTIFIED DOCUMENT OF WORLDWIDE ENGINEERING GEO. DIV. INC.. GRADING PLAN IS THE PROPERTY OF THE CIVIL ENGINEER OF RECORD AND IS SHOWN FOR REFERENCE TO VIEW WALLS. LOCATE WALLS USING CIVIL ENGINEER'S DOCUMENTS ONLY.

2021 IBC CODE REQUIRES SEGMENTAL RETAINING WALLS TO BE CERTIFIED AT THE END OF CONSTRUCTION. THE CERTIFYING FIRM SHALL BE UNDER CONTRACT AND ONSITE AT THE BEGINNING OF CONSTRUCTION.

					PLAN VIEW
					Fairway Pointe at Anderson Creek RETAINING WALLS Harnett County, NC
DECICNED MICHAEL HISER PR					MLK 5/22/24 - PIR 5/22/24
REVISIONS	DRN	DATE	CHK	DATE	SEGMENTAL RETAINING WALL
	designer: michael kiser pe REVISIONS				

WALL PROFILE #1



- NOTES:

 1. THE REINFORCED BACKFILL SHALL BE A CLEAN SAND AND IS RESTRICTED TO HAVING A MAXIMUM FINE CONTENT OF 50% PASSING THE #200 SIEVE, A MAXIMUM LIQUID LIMIT OF 30 AND A MAXIMUM PI OF 10.


 2. THE CLEAN SAND IN THE REINFORCED BACKFILL SHALL BE SEPARATED FROM THE WASHED STONE FILL WITH A 4 OUNCE GEOTEXTILE FABRIC.


 3. THE CONTRACTOR WRAP THE LEVELING PAD WITH A 4 OUNCE GEOTEXTILE FABRIC.

ENGINEERING CONSULTING ENGINEERS & PLANNERS


солисате №—2446 (704) 483-5225 ax: (704) 483-5466 www.WWEgeo.com MLKiser**©**bellsouth.net









PLACE GEOGRAP IN NEXT LATER OF BLOCK WITH THE NUM REPOYED, BUT IN THE PROPERTY BEAUTY PARTY BY PROPERTY BEAUTY PARTY BY PROPERTY BEAUTY BY PROPERTY B




TYPICAL ROADWAY GUARD RAIL LOCATION DETAIL N.I.S.




DRAINAGE STRUCTURE DETAIL, (SCALE: NTS)






TYPICAL HANDRAIL LOCATION DETAIL N.T.S.







LEVELING PAD DETAL. (SCALE HTS)

П		T				DETAILS
						Fairway Pointe at Anderson Creek RETAINING WALLS Harnett County, NC
Ħ	DESIGNER: MICHAEL KISER PE					MLK = 5/22/24 = = = = = = = = = = = = = = = = = = =
NO.	REVISIONS	DRN	DATE	CHK	DATE	SEGMENTAL RETAINING WALL

EXCIPELING CONSULTING ENGINEERS & PLANNE	
EXIGINEERING CONSULTING ENGINEERS & PLANNE	Edwariow
	\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\\
CONSULTING ENGINEERS & PLANNE	
	CONSULTING ENGINEERS & PLANNE





Diamond Pro Retaining Walls

Segmental Retaining Wall Systems are designed as a gravity retaining wall utilizing a high tenacity polyester geogrid to reinforce the soil zone behind the wall. The geogrid is positively connected to the modular concrete block creating a reinforced soil mass capable of resisting lateral earth pressures and surcharged loads. All references to the Engineer refer to Worldwide Engineering.

The soil material associated with the retaining wall in the reinforced zone, the retained zone, or the foundation bedding shall have the following properties:

- A) Foundation Soils: Ø=30°, cohesion=0 psf, unit weight=120 lbs./cu.ft (moist weight) B) Retained Soils: Ø=30°, cohesion=0 psf, unit weight=120 lbs./cu.ft (moist weight)
- C) Reinforced Soils: Ø=30°, cohesion=0 psf, unit weight=120 lbs./cu.ft (moist weight)

The soil characteristics above were assumed based on information supplied to the Engineer. If this information does not represent the actual soil to be used, the Engineer shall be notified immediately, the new soil parameters shall be submitted to the Engineer, and the wall will be required to be redesigned. Payment for all designs is the responsibility of the Owner and/or General Contractor.

1.3 Foundation Loads

The maximum applied foundation load for this wall is 2 KIPS/sq.ft.

1,4 Concrete Mesonry Wall Units

Cancrete Wall Units shall be segmental units manufactured in accordance with ASTM—C90 and ASTM C140 and shall have a minimum 28 day compressive strength of 3000 psi.

The geogrid reinforcing material shall be a polyethylene or polyester meeting a minimum Long—Term Deelgn Strength (LTDS) published by the manufacturer of:

MIRAFI 3XT

1.6 Wall Batter

Botter for the entire wall shall be maintained at 8 degrees (1" setback per course).

The foundation bearing capacity that was assumed for design shall be verified in the the field, and copies of the test data filed with the Engineer. The faating shall be cleared of loose soil. A minimum of 12° of washed stone shall be placed at the back of each block as indicated on the details.

Moterial shall consist of compacted sand, gravel, crushed rock, or unreinforced concrete. The pad shall be 6" thick when pad is concrete and 8" thick otherwise. Sand or gravel material shall be compacted to 95% Standard Proctor. Aggregate material shall receive a minimum of one pass of the compaction equipment. The top of the leveling pad shall be maintained at a depth of 1.5 feet when the exposed height of the woll acceeds 7 feet.

2.2 Unit FIII

The vold within each unit shall be filled with a washed stane having 100% of the aggregate possing the 1.5" sleve. A minimum of 3/8" washed stone size is required (no more than 5% passing the #200 sleve). Place this material behind the block as wail. All excess material shall be swept clean from the top of the block prior to installing the next course. Each course of block shall be completely filled before proceeding to the next course.

The first course of block shall be placed on top of and in full contact with the Isvelling pad. The units shall mointain a distance of a minimum 6° from the front and back of the Isvelling pad. Proper alignment may be achieved with the did of a string line. Place stone below the first block and the Isvelling pad and Isvelling below the first block in the proceed to the next course of block. Each unit shall contact the units on both sides as well as above and below. Some adjustments may be required for walls with curves and a batter.

2.4 Caps

Apply a construction adhesive to the cap units to prevent their removal

The geogrid reinforcement shall be loid horizontally on compacted backfill and installed to the face of the block. Geogrid shall be pulled tout removing all slock from the material and anchored before adding fill. Geogrid shall be installed at the elevations and lengths required as shown on the plans (refer to details for the appropriate orientation). Soil surface shall be smooth and level and have been compacted to 95% Standard Proctor before installing the grid.

Backfill material shall be placed on a maximum 8" compacted to 95% Standard Practor. Only hand operated equipment shall be allowed within 3 feet of the Segmental Block units. Backfill shall be placed from the well rearward to insure tautness of the geogrid. Construction equipment shall not be operated directly on the geogrid.

Soils containing roots, brush, sad or other organic material shall not be allowed. Frozen soils, snow, ice, heavy clays, or wet soils shall not be allowed. Material passing the #40 sieve shall not have a liquid limit of greater than 30 and a PI of greater than 10, unless written consent is obtained from the Engineer prior to placement.

3.3 Soil Properties

Minimum internol ongle of friction shall equal or be greater than 30' with 0 psf cohesion. Verification shall be filed with the Engineer that the soil will meet this criteria. If soils are greater than 35% fines, then the top twa (2) geogrid layers shall be increased by 25% for the entire length of the will.

Compaction testing shall be performed for every lift elevation requiring geogrid or every 3rd lift as a minimum Tests shall be performed for every 100 linear feet of wall face. Compaction tests as well as a verified friction angle shall be filed with the Engineer's office.

5.0 Hydrostatic Pressure Potential

The Engineer shall be notified if any of the following should become evident:

-water or wetness from or in a cut bank

-local springs, local starm drains, sewers, water lines under ar behind the wall

Segmental Block units shall be used and kept free of defects that would interfere with the placing or positioning of the unit or impair its strength. Minor crocks incidental to the usual method of manufacturing or minor chipping resulting from shipment and delivery are not grounds for rejection.

Cacgrid shall be rejected if 20% or more of a structural rib has been cut or ripped. The Contractor shall inspect all geogrid delivered to the site and reject materials that meets this criteria. If the geogrid is damaged on the construction site, it shall be replaced at the Contractors expense.

8.0 Drainage Composite- (Applies to cut wall applications only)

Drainage Composite shall be installed to cover 30% of the aut behind the geogrid layers. It (6 ft. wide sections) provides 30% coverage when installed on 15 ft. centers and 2/3 the wall height.

- A) General contractor shall coordinate upper geogrid layers installation with paying installation.
 B) No splices shall be made within 6 feet of each other or the modular unit.
 C) Maintain the direction of drainage away from the wall face at all times during construction of the wall and finish grading as shown on plans. grading as shown on plans.

 9) Placement of geogrid shall be as per plans reference to length and elevations.

 E) The Engineer shall be an otified by the installing contractor should the embedment depth of the block be less than 6" for walls less than 7", and less than 9" for walls greater than 7" in height.

 F) The reinforced soil is assumed to be a sandy type material (pure slits and clay are not acceptable).

10.0 Qualification of Design

- A. Stability of any temporary slopes required by the installation of segmental retaining wall shall be addressed by a qualified Geotechnical Engineer. Responsibility of these temporary slopes rests with the Owner and/or Architect of this project and the slopes shall meet all OSHA standards of maximum slope steepness = 1.5H:1V.

 B. Handrail/guardrail requirements shall be determined by the Architect or General Contractor.

 C. The top of wall elevation for this design has been established by the retaining wall engineer at his discretion. The flexibility of this design allows for the top of wall to be adjusted higher of lower by 12 vartical inches and state meet acceptable foctors of soffety. Any adjustments to the wall height must include maintaining a maximum geogrid spacing of 24 inches and must be supplied to the retaining wall engineer in writing.

 D. The general contractor is responsible for integrating the retaining wall installation into the project. The general contractor is responsible for varifying that the wall configuration illustrated on these plans can be installed according to the site information provided on the civil engineer's grading plan without conflicts associated with and guitter, powers at sections, building foundations, utilities, or any other component to be installed in close proximity to this retaining wall system.

 E. All conflicts or discrepancies must be presented to the retaining wall engineer at a project menging on site before construction begins on the retaining wall. An allowable time for revision to be made and provided by the retaining wall engineer shall be established at the same meeting before construction begins.



DOMESTE NG-2446 (704) 483-5225 Fax: (704) 483-5466 SEAL 19258 4090 N. NC HWY 15 P.O. Box 2189 DENVER, NC 28037 www.WWEgeo.com MLKiser@bellsouth.net

