

Project Information

Energy Code: 2018 IECC

Project Title: 11432-187 Mavis Sanford, NC

Location: Sanford, North Carolina

Climate Zone: 4a

Project Type: New Construction

Vertical Glazing / Wall Area: 42%

Construction Site: 1585 Buffalo Road

Sanford, North Carolina 27332

Owner/Agent: Mavis Tire Supply L.L.C. 358 Saw Mill River Road

Millwood, New York 10546

9149842500

Designer/Contractor:
Alexandria Locke
Larson Design Group

3000 Westinghouse Drive, Suite

400

Cranberry Township, Pennsylvania

16066

Additional Efficiency Package(s)

Credits: 1.0 Required 1.0 Proposed Reduced Lighting Power, 1.0 credit

Building Area Floor Area

1-Automotive Facility : Nonresidential 6979

Envelope Assemblies

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor _(a)
Roof: Insulation Entirely Above Deck, [Bldg. Use 1 - Automotive Facility]	6979		30.0	0.032	0.032
Floor: Unheated Slab-On-Grade, Vertical 2 ft., [Bldg. Use 1 - Automotive Facility] (c)	352		7.5	0.560	0.540
NORTH Ext. Wall: Concrete Block, 10in., Partially Grouted, Cells Empty, Normal Density, Furring: Metal, [Bldg. Use 1 - Automotive Facility]	310	0.0	12.0	0.066	0.104
Ext. Wall: Steel-Framed, 16in. o.c., [Bldg. Use 1 - Automotive Facility]	814	21.0	8.6	0.055	0.064
Window: Metal Frame: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	441			0.290	0.380
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	42			0.670	0.770
EAST Ext. Wall: Concrete Block, 10in., Partially Grouted, Cells Empty, Normal Density, Furring: Metal, [Bldg. Use 1 - Automotive Facility]	324	0.0	12.0	0.066	0.104
Ext. Wall: Steel-Framed, 16in. o.c., [Bldg. Use 1 - Automotive Facility]	1930	21.0	8.6	0.055	0.064
Window: Metal Frame: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	318			0.290	0.380
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 -	21			0.670	0.770

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24

Data filename: Page 1 of 10

Assembly	Gross Area or Perimeter	Cavity R-Value	Cont. R-Value	Proposed U-Factor	Budget U- Factor _(a)
Automotive Facility] (b)					
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
SOUTH Ext. Wall: Concrete Block, 10in., Partially Grouted, Cells Empty, Normal Density, Furring: Metal, [Bldg. Use 1 - Automotive Facility]	1163	0.0	12.0	0.066	0.104
Door: Insulated Metal, Swinging, [Bldg. Use 1 - Automotive Facility]	21			0.370	0.610
<u>WEST</u> Ext. Wall: Concrete Block, 10in., Partially Grouted, Cells Empty, Normal Density, Furring: Metal, [Bldg. Use 1 - Automotive Facility]	318	0.0	12.0	0.066	0.104
Ext. Wall: Steel-Framed, 16in. o.c., [Bldg. Use 1 - Automotive Facility]	1930	21.0	8.6	0.055	0.064
Door: Glass (over 50% glazing): Metal Frame, Entrance Door, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	21			0.670	0.770
Window: Metal Frame: Fixed, Perf. Specs.: Product ID Kawneer, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	318			0.290	0.380
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450
Door: Glass (over 50% glazing): Metal Frame, Non-Entrance Door, Perf. Specs.: Product ID Clopay, SHGC 0.25, [Bldg. Use 1 - Automotive Facility] (b)	142			0.380	0.450

⁽a) Budget U-factors are used for software baseline calculations ONLY, and are not code requirements.

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24

Data filename:

Page 2 of 10

⁽b) Fenestration product performance must be certified in accordance with NFRC and requires supporting documentation.

⁽c) Slab-On-Grade proposed and budget U-factors shown in table are F-factors.

Envelope PASSES: Design 2% better than code

Envelope Compliance Statement

Compliance Statement: The proposed envelope design represented in this document is consistent with the building plans, specifications, and other calculations submitted with this permit application. The proposed envelope systems have been designed to meet the 2018 IECC requirements in COMcheck Version COMcheckWeb and to comply with any applicable mandatory requirements listed in the Inspection Checklist.

Benjamin Wetzel - Designer

Name - Title Signature

11/21/2024

Date

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24

Data filename: Page 3 of 10

COMcheck Software Version COMcheckWeb Inspection Checklist Energy Code: 2018 IECC

Requirements: 0.0% were addressed directly in the COMcheck software

Text in the "Comments/Assumptions" column is provided by the user in the COMcheck Requirements screen. For each requirement, the user certifies that a code requirement will be met and how that is documented, or that an exception is being claimed. Where compliance is itemized in a separate table, a reference to that table is provided.

Section # & Req.ID	Plan Review	Complies?	Comments/Assumptions
C103.2 [PR1] ¹	Plans and/or specifications provide all information with which compliance can be determined for the building envelope and document where exceptions to the standard are claimed.	□Complies □Does Not □Not Observable □Not Applicable	
C402.4.1 [PR10] ¹	The vertical fenestration area <= 30 percent of the gross above-grade wall area.	□Complies □Does Not □Not Observable □Not Applicable	
C402.4.1 [PR11] ¹	The skylight area <= 3 percent of the gross roof area.	□Complies □Does Not □Not Observable □Not Applicable	
C402.4.2 [PR14] ¹	In enclosed spaces > 2,500 ft2 directly under a roof with ceiling heights >15 ft. and used as an office, lobby, atrium, concourse, corridor, storage, gymnasium/exercise center, convention center, automotive service, manufacturing, non-refrigerated warehouse, retail store, distribution/sorting area, transportation, or workshop, the following requirements apply: (a) the daylight zone under skylights is >= half the floor area; (b) the skylight area to daylight zone is >= 3 percent with a skylight VT >= 0.40; or a minimum skylight effective aperture >= 1 percent.	□Complies □Does Not □Not Observable □Not Applicable	
C406 [PR9] ¹	Plans, specifications, and/or calculations provide all information with which compliance can be determined for the additional energy efficiency package options.	□Complies □Does Not □Not Observable □Not Applicable	

Additional Comments/Assumptions:

	1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)
--	---	----------------------	---	------------------------	---	---------------------

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 4 of 10

Section # & Req.ID	Footing / Foundation Inspection	Complies?	Comments/Assumptions
C303.2 [FO4] ²	Slab edge insulation installed per manufacturer's instructions.	\square Complies \square Does Not	
		□Not Observable □Not Applicable	
C303.2.1 [FO6] ¹	Exterior insulation protected against damage, sunlight, moisture, wind,	\square Complies \square Does Not	
	landscaping and equipment maintenance activities.	□Not Observable □Not Applicable	
C105 [FO3] ²	Installed slab-on-grade insulation type and R-value consistent with insulation	\square Complies \square Does Not	See the Envelope Assemblies table for values.
	specifications reported in plans and COMcheck reports.	□Not Observable □Not Applicable	
C402.2.4 [FO7] ²	Slab edge insulation depth/length. Slab insulation extending away from	\square Complies \square Does Not	See the Envelope Assemblies table for values.
	building is covered by pavement or >= 10 inches of soil.	□Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 5 of 10

Section # & Req.ID	Framing / Rough-In Inspection	Complies?	Comments/Assumptions
C303.1.3 [FR12] ²	Fenestration products rated in accordance with NFRC.	\square Complies \square Does Not	
		□Not Observable □Not Applicable	
C303.1.3 [FR13] ¹	Fenestration products are certified as to performance labels or certificates	□Complies □Does Not	
	provided.	□Not Observable □Not Applicable	
C402.4.3 [FR10] ¹	Vertical fenestration SHGC value.	□Complies □Does Not	See the Envelope Assemblies table for values.
		□Not Observable □Not Applicable	
C402.4.3, C402.4.3.	and SHGC consistent with label	□Complies □Does Not	See the Envelope Assemblies table for values.
4 [FR8] ¹	specifications and as reported in plans and COMcheck reports.	□Not Observable □Not Applicable	
2.1	The building envelope contains a continuous air barrier that is sealed in	□Complies □Does Not	
[FR19] ¹	an approved manner and material permeability <= 0.004 dfm/ft2. Air barrier penetrations are sealed in an approved manner.	□Not Observable □Not Applicable	
C402.5.4	Factory-built fenestration and doors are labeled as meeting air leakage	□Complies □Does Not	
[FR18] ³		□Not Observable □Not Applicable	
C402.5.7 [FR17] ³	Vestibules are installed on all building entrances. Doors have self-closing	□Complies □Does Not	
	devices.	□Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 6 of 10

Section # & Req.ID	Mechanical Rough-In Inspection	Complies?	Comments/Assumptions
C402.5.5, C403.2.4. 3 [ME3] ³	Stair and elevator shaft vents have motorized dampers that automatically close. Refernece section C403.7.7 for operational details.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
	Outdoor air and exhaust systems have motorized dampers that automatically shut when not in use and meet maximum leakage rates. Check gravity dampers where allowed. Reference section language for operational details.		

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC

Data filename: Page 7 of 10

Section # & Req.ID	Rough-In Electrical Inspection	Complies?	Comments/Assumptions
C405.6 [EL26] ²	Low-voltage dry-type distribution electric transformers meet the minimum efficiency requirements of Table C405.6.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C405.7 [EL27] ²	Electric motors meet the minimum efficiency requirements of Tables C405.7(1) through C405.7(4). Efficiency verified through certification under an approved certification program or the equipment efficiency ratings shall be provided by motor manufacturer (where certification programs do not exist).	□Complies □Does Not □Not Observable □Not Applicable	
	Escalators and moving walks comply with ASME A17.1/CSA B44 and have automatic controls configured to reduce speed to the minimum permitted speed in accordance with ASME A17.1/CSA B44 or applicable local code when not conveying passengers.	□Complies □Does Not □Not Observable □Not Applicable	
C405.9 [EL29] ²	Total voltage drop across the combination of feeders and branch circuits <= 5%.	□Complies □Does Not □Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 8 of 10

Section #	Insulation Inspection	Complies?	Comments/Assumptions
& Reg.ID	msulation inspection	Compiles:	Comments/Assumptions
C303.1 [IN3] ¹	Roof insulation installed per manufacturer's instructions. Blown or poured loose-fill insulation is installed only where the roof slope is <=3 in 12.	□Complies □Does Not □Not Observable □Not Applicable	
C402.2.1 [IN20] ¹	Insulation installed on a suspended ceiling having ceiling tiles is not being specified for roor/ceiling assemblies. Continuous insulation board installed in 2 or more layers with edge joints offset between layers.	□Complies □Does Not □Not Observable □Not Applicable	
C303.1 [IN10] ²	Building envelope insulation is labeled with R-value or insulation certificate providing R-value and other relevant data.	☐Complies ☐Does Not ☐Not Observable ☐Not Applicable	
C303.2 [IN7] ¹	Above-grade wall insulation installed per manufacturer's instructions.	□Complies □Does Not □Not Observable □Not Applicable	
C105 [IN6] ¹	Installed above-grade wall insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
C402.2.3 [IN8] ²	Installed floor insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports.	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
C402.2.6 [IN18] ³	Radiant panels and associated components, designed for heat transfer from the panel surfaces to the occupants or indoor space are insulated with a minimum of R-3.5.	□Complies □Does Not □Not Observable □Not Applicable	
C105 [IN2] ¹	Installed roof insulation type and R-value consistent with insulation specifications reported in plans and COMcheck reports. For some ceiling systems, verification may need to occur during Framing Inspection.	□Complies □Does Not □Not Observable □Not Applicable	See the Envelope Assemblies table for values.
C402.5.1. 1 [IN1] ¹	All sources of air leakage in the building thermal envelope are sealed, caulked, gasketed, weather stripped or wrapped with moisture vaporpermeable wrapping material to minimize air leakage.	□Complies □Does Not □Not Observable □Not Applicable	

1	High Impact (Tier 1)	2	Medium Impact (Tier 2)	3	Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 9 of 10

Section # & Req.ID	Final Inspection	Complies?	Comments/Assumptions
C402.5.6 [FI37] ¹	Weatherseals installed on all loading dock cargo door openings and provide direct contact along the top and sides of vehicles parked in the doorway.	□Complies □Does Not □Not Observable □Not Applicable	
C402.5.8 [FI26] ³	Recessed luminaires in thermal envelope to limit infiltration and be IC rated and labeled. Seal between interior finish and luminaire housing.	□Complies □Does Not □Not Observable □Not Applicable	
C408.1.1 [FI57] ¹	Building operations and maintenance documents will be provided to the owner. Documents will cover manufacturers' information, specifications, programming procedures and means of illustrating to owner how building, equipment and systems are intended to be installed, maintained, and operated.	□Complies □Does Not □Not Observable □Not Applicable	

1 High Impact (Tier 1) 2 Medium Impact (Tier 2) 3 Low Impact (Tier 3)

Project Title: 11432-187_Mavis Sanford, NC Report date: 11/21/24
Data filename: Page 10 of 10