

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

NOTE: The General Contractor shall obtain approval of the Wal-Mart Construction Manager before beginning the Work defined in this **Revision**. If applicable, adjustment to the Contract Summary be based only on the method described in 7.3.3.1 of the Contract.

SCOPE: The scope of this **Revision** is to revise the last issued contract documents of **Cameron, NC** dated **01-08-2025** and all subsequent contract modifications, to reflect the following:

**SUMMARY:**

**Walmart Directed Change – (WM)**

**Quality Control – (QC)**

**Code Comments – (CC)**

**CI 31769 - VE Restroom Fixtures – (CI 31769) PR#1 7/2/25**

Revised Fixtures: Faucet, Flush Value & All illuminated Mirrors with Non-illuminated Mirrors.

**CI 32293 - Update Roofing Spec Requirements – (CI 32293) PR#1 7/2/25**

Remove Holcim-Elevate (formerly Firestone), Remove requirement for Walmart Approved Subcontractors, Remove requirement of Owner Roofing Consultant.

**CI 32312 - BRAND - Rollout of New Enterprise (PTI) Paint Interior – (CI 32312) PR#1 7/2/25**

New Enterprise Brand Finishes and Signage

**CI 32442 - Refrigeration Responsibility Matrix – (CI 32442) CCD #1 12/4/25**

Create a Matrix for all Equipment needed and the responsible party for providing said equipment.

**CI 32623 - TCO2 Refrigeration Proto Content Updates – (CI 32623) CCD #1 12/4/25**

Add TCO2 Refrigeration details for TCO2 design as follow-up to CI32171.

**CI 32646 COFFEE – PY26 PROTO UPDATES – (CI 32646) CCD #1 12/4/25**

Update Layout for Dunkin Donuts tenant.

**CI 32702 Add Reflective Plastic Sleeve to Bollards in Receiving Dock Areas – (CI 32702) CCD #1 12/4/25**

Place Blue Bollard Sleeve at Receiving Truck Wells.

**CI 32749 Add Ice/Water Machine To Remodel Break Room – (CI 32749) CCD #1 12/4/25**

**GENERAL**

**SHEET C1 – COVER SHEET PR#1 7/2/25**

DRAWING INDEX

1. ADDED SR1 SEISMIC RESTRAINT SHEET TO SET PER MEP. (WM)

**SHEET C1 – COVER SHEET CCD #1 12/4/25**

DRAWING LIST

1. Added Sheet RM1 Responsibility Matrix to Drawing Set. (CI 32646)
2. Added Sheet DD1 Dunkin Tenant Plans and Elevations to Drawing Set. (CI 32646)
3. Added Sheet DD2 Dunkin Tenant Details to Drawing Set. (CI 32646)
4. Added Sheet DA2 Dunkin Signage to Drawing Set. (CI 32646)
5. Added Sheet DDP1 Dunkin Tenant Plumbing Plans and Risers to Drawing Set. (CI 32646)
6. Added Sheet DDP3 Dunkin Tenant Plumbing Schedules to Drawing Set t. (CI 32646)
7. Added Sheet DDE1 Electrical Lighting Plan to Drawing Set. (CI 32646)
8. Added Sheet DDE2 Dunkin Electrical Power Plan & Elevations to Drawing Set. (CI 32646)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

- 9. Added Sheet DDE3 Electrical Panelboard Schedules to Drawing Set. (CI 32646)
  - 10. Omitted sheet GA5 Responsibility Schedules from Drawing Set. (CI 32442)
- Omitted sheet GA5.1 Responsibility Schedules from Drawing Set. (CI 32442)

**SHEET N1 – GENERAL INFORMATION CCD #1 12/4/25**

INSECT CONTROL UNIT LEGEND

- 1. Updated Number of Units to 4 Total. (CI 32646)

**SHEET SA1 – SCHEDULES AND ALLOWANCES ADD #2 9/10/25**

BID ALLOWANCE SCHEDULE

- 1. Revised Joint Replacement to 5,000 LF per ICC Scope Assessment Report. (QC)

**ARCHITECTURAL**

**SHEET SP1 – SITE PLAN PR#1 7/2/25**

DETAIL 1 – SITE PLAN

- 1. REVISED PROPANE CAGE LOCATION BACK TO ITS ORIGINAL POSITION ON SITE. (WM)

**SHEET SP1 – SITE PLAN PR#2 7/25/25**

DETAIL 1 – SITE PLAN

- 1. Added Dimension at Propane Cages Location to Sidewalk. (CC)

**SHEET SP1 – SITE PLAN CCD #1 12/4/25**

KEYNOTES

- 1. Added Keynote 5.02 for Painted 6” Pipe Bollard. (CI 32623)
- 2. Added Keynote 6.60 for Blue Bollard Cover Installation. (CI 32702)

DETAIL 1 – SITE PLAN

- 1. Added 6.60 Keynote Tag at Receiving Bays. (CI 32702)
- 2. Added 6” Pipe Bollards at TCO2 Charging Station. (CI 32623)

DETAIL 5 – ENLARGED CHARGING STATION

- 1. Added detail for Charging Station Bollards location. (CI 32623)

**SHEET D1 – DEMOLITION PLAN PR#1 7/2/25**

DETAIL 1 – DEMOLITION PLAN

- 1. REVISED PROPANE CAGE LOCATION BACK TO ITS ORIGINAL POSITION ON SITE. (WM)
- 2. OMITTED EXISTING COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)
- 3. OMITTED EXISTING MOP SINK AT 150 CORRIDOR, 158 JANITOR, 910 DRY PRODUCE PREP & 961 MEAT UTILITY. (WM)
- 4. OMITTED EXISTING 3-COMPARTMENT SINK AT 910 DRY PRODUCE PREP. (WM)

**SHEET D1 – DEMOLITION PLAN PR#3 8/12/25**

DETAIL 1 – DEMOLITION PLAN

- 2. Revised Doors at Vision Center per Existing Condition. (QC)

**SHEET D1 – DEMOLITION PLAN CCD #1 12/4/25**

DETAIL 1 – DEMOLITION PLAN

- 1. Added Demolition Scope to White Box Tenant Space. (WM)
- 2. Added Demolition Scope to BOH Vending Machines per Final ID Plan. (WM)
- 3. Omitted Existing BOH 8’-0” Rack, per Final ID Plan. (WM)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

4. Added Trenching at Dunkin Tenant. (CI 32646)

**SHEET D1.1 – ENLARGED DEMO PLAN PR#1 7/2/25**

DETAIL 1 – CUSTOMER SERVICE DEMO ENLARGED PLAN

1. OMITTED EXISTING COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)

DETAIL 2 – FRONT GROCERY DEMOLITION PLAN

1. OMITTED EXISTING MOP SINK & 3-COMPARTMENT SINK AT 910 DRY PRODUCE PREP. (WM)

**SHEET D1.1 – ENLARGED DEMO PLAN CCD #1 12/4/25**

DETAIL 3 – DUNKIN TENANT DEMOLITION PLAN

1. Revised Detail Title per scope change. (WM)
2. Added Trenching at Dunkin Tenant. (CI 32646)

DETAIL 10 – DUNKIN TENANT TRENCHING PLAN

Added Trenching Plan to Sheet. (CI 32646)

**SHEET A1 – FLOOR PLAN PR#1 7/2/25**

DETAIL 1 – FLOOR PLAN

1. ADDED NEW COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)
2. REVISED PROPANE CAGE LOCATION BACK TO ITS ORIGINAL POSITION ON SITE. (WM)
3. ADDED NEW 3-COMPARTMENT SINK AT 910 DRY PRODUCE PREP. (WM)

**SHEET A1 – FLOOR PLAN PR#3 8/12/25**

DETAIL 1 – FLOOR PLAN

1. Added Pet & Baby Coolers per 11/12 Revised ID Plan. (QC)

**SHEET A1 – FLOOR PLAN ADD #2 9/10/25**

DETAIL 1 – FLOOR PLAN

1. Revised OGP Cooler/Freezer to flip layout. (WM)
2. Revised Side Counter at Pharmacy per Existing Pneumatic Tube Location. (QC)

**SHEET A1 – FLOOR PLAN CCD #1 12/4/25**

DETAIL 1 – FLOOR PLAN

1. Revised Garden Center & Seasonal Fixtures, per Final ID Plan. (WM)
2. Revised White Box Tenant. (WM)
3. Revised Customer Service Desk, per Final ID Plan. (WM)
4. Revised Fitting Rooms layout, per Store Planning. (WM)
5. Revised OPD Racking, per Final ID Plan. (WM)
6. Revised BOH Location of Apparel Workstation, per Final ID Plan. (WM)
7. Revised Location of Self-Contained Case at Grocery Sales, per Final ID Plan. (WM)
8. Revised Location of Ice Machin per Merch/Order Copy Plan. (WM)
9. Omitted Existing BOH Vending Machines, per Final ID Plan. (WM)
10. Added three New Vending Machines, per Final ID Plan. (WM)
11. Added 6" Pipe Bollards at TCO2 Charging Station. (CI 32623)
12. Added Dunkin Donuts Tenant to Floor Plan. (CI 32646)

DETAIL 3 – FITTING ROOM PLAN

1. Revised Fitting Rooms layout, per Store Planning. (WM)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SHEET A1.1 – FLOOR FINISH PLAN ADD #2 9/10/25**

FLOOR FINISH RESPONSIBILITY MATRIX

1. Omitted Pharmacy Health Service Room LVT2 Flooring. (WM)

DETAIL 1 – FLOOR FINISH PLAN

1. Revised OGP Cooler/Freezer to flip layout. (WM)
2. Added LVT2 Floor Pattern and Finish Tag at Vision Center Adjustment Room. (QC)
3. Omitted LVT2 Flooring and added Exposed Concrete at Pharmacy Health Service Room. (WM)

**SHEET A1.1 – FLOOR FINISH PLAN CCD #1 12/4/25**

FLOOR FINISH RESPONSIBILITY MATRIX

1. Revised Preferred Flooring Contractor to RMI per Lucernex.

DETAIL 1 – FLOOR FINISH PLAN

1. Revised Tenant spaces per White Box Scope of Work. (WM)
2. Added Gate and Kiosk Wall, per Dunkin Tenant. (CI 32646)

**SHEET A2 – EXTERIOR ELEVATIONS PR#1 7/2/25**

DETAIL 5 – REAR ELEVATION

1. ADDED CMU REPAIR NOTE. (WM)

**SHEET A2 – EXTERIOR ELEVATIONS CCD #1 12/4/25**

COLOR LEGEND

1. Added Color Name for P76U to Legend. (QC)
2. Omitted P162 duplicate from Legend. (QC)

DETAIL 1 – FRONT ELEVATION

1. Added New Tenant Signage to Elevation. (CI 32646)

**SHEET A4 – ROOF PLAN AND DETAILS PR#2 7/25/25**

DETAIL 1 – ROOF PLAN

1. Revised Location of RCU Units and Roof Penetrations. (CI 32171)

DETAIL 2 – OGP ROOF ENLARGED PLAN

1. Revised Location of RCU Units and Roof Penetrations. (CI 32171)
2. Revised RCU Units Notes. (CI 32171)
3. Added Walkway Pads and Crickets at New RCU Units. (QC)

**SHEET A4 – ROOF PLAN AND DETAILS ADD #2 9/10/25**

DETAIL 1 – ROOF PLAN

1. Revised RCU Units location per OGP Cooler/Freezer flip layout. (WM)

DETAIL 2 – OGP ROOF ENLARGED PLAN

1. Revised RCU Units location per OGP Cooler/Freezer flip layout. (WM)

**SHEET A4 – ROOF PLAN AND DETAILS CCD #1 12/4/25**

DETAIL 2 – OGP ROOF ENLARGED PLAN

1. Revised RCU to CU TCO Roof Units, per MEP. (CI 32623)

**SHEET A5 – ENLARGED PLANS, ELEVATIONS, AND DETAILS PR#1 7/2/25**

COLOR LEGEND

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

1. ADDED P218 TRUE BLUE & PS13 WM TRUE BLUE WALL FINISHES. (CI 32312)
2. REVISED P162E TO P162 PEPPERCORN WALL FINISHES. (QC)

SCOPE FINISH BOX: 105 CUSTOMER SERVICE

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)

SCOPE FINISH BOX: 101 VESTIBULE GM, 103 OTHER INCOME, 104 CART STORAGE GM, 115 VESTIBULE GR, 118 CART STORAGE GR

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 1 – FRONT TENANT WALL FLOOR PLAN

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)
2. ADDED TIRE STOP AT CUSTOMER SERVICE PER NEW ENTERPRISE LAYOUT. (CI 32312)
3. ADDED BLUE ACCENT WALL AT VESTIBULES PER NEW ENTERPRISE LAYOUT. (CI 32312)
4. ADDED NEW COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)

DETAIL 2 – CUSTOMER SERVICE FLOOR PLAN

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)
2. ADDED RECYCLED RUBBER TIRE STOP PER NEW ENTERPRISE LAYOUT. (CI 32312)
3. ADDED NEW COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)
4. ADDED HALF-HEIGHT KICK PLATE NOTE AND DOOR TAG TO REFERENCE SPESC. (WM)

DETAIL 5 – MURAL ELEVATION

1. REVISED WALL FINISHES AND NOTE PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 6 – FOOD SERVICE INTERIOR ELEVATION

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 9 – INTERIOR ELEVATION

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 10 – CUSTOMER SERVICE ELEVATION

1. ADDED INTERIOR ELEVATION FOR VINYL GRAPHIC PER NEW ENTERPRISE LAYOUT. (CI 32312)

**SHEET A5 – ENLARGED PLANS, ELEVATIONS, AND DETAIL ADD #2 9/10/25**

DETAIL 1 – FLOOR TENANT WALL FLOOR PLAN

Revised Side Counter at Pharmacy per Existing Pneumatic Tube

**SHEET A5 – ENLARGED PLANS, ELEVATIONS, AND DETAILS CCD #1 12/4/25**

SCOPE FINISH BOX: 808 BOARD UP TENANT

1. Omitted Scope Finish Box from Sheet. (CI 32646)

SCOPE FINISH BOX: 808 WHITE BOX

1. Added Scope Finish Box to Sheet. (QC)

DETAIL 1 – FRONT TENANT WALL FLOOR PLAN

1. Added Dunkin Donuts Tenant to Floor Plan. (CI 32646)
2. Revised Tenant Space per White Box Scope. (WM)
3. Revised Customer Service Desk, per Final ID Plan. (WM)

DETAIL 2 – CUSTOMER SERVICE FLOOR PLAN

1. Revised Customer Service Desk, per Final ID Plan. (WM)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

DETAIL 3 – BOARD UP TENANT SPACE PLAN

1. Omitted Detail from Sheet. (CI 32646)

DETAIL 9 – INTERIOR ELEVATION

1. Added Dunkin Donuts Tenant Entrance Elevation and Callout to Detail. (CI 32646)

**SHEET A5.1 – RESTROOM PLANS AND DETAILS PR#1 7/2/25**

CUSTOMER RESTROOM FIXTURE SCHEDULE

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)

DETAIL 1 – CUSTOMER FRONT RESTROOM

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)

DETAIL 2 – CUSTOMER REAR RESTROOM

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)

**SHEET A5.4 – ENLARGED PLANS AND DETAILS CCD #1 12/4/25**

DETAIL 1 – GR ENLARGED CHECKOUT PLAN

1. Revised Checkout Layout, per Final ID Plan. (WM)

DETAIL 2 – GM ENLARGED CHECKOUT

1. Revised Checkout Layout, per Final ID Plan. (WM)
2. Revised Location of Ice Machin, per Merch/Order Copy Plan. (WM)

**SHEET A6 – REAR OFFICE PLAN PR#1 7/2/25**

COLOR LEGEND

1. ADDED P218 TRUE BLUE & PS13 WALMART TRUE BLUE WALL FINISHES. (CI 32312)

SCOPE FINISH BOX: 172 TRAINING, 174 CBL

1. REVISED WALL FINISHES PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 1 – REAR OFFICE FLOOR PLAN

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)

DETAIL 2 – REAR OFFICE ENLARGED PLAN

1. REVISED ALL ILLUMINATED MIRRORS TO BE NON- ILLUMINATED MIRRORS. (CI 31769)
2. REVISED WALL FINISHES AT 172 TRAINING PER NEW ENTERPRISE LAYOUT. (CI 32312)

DETAIL 4 – ENLARGED MOTHER’S ROOM

1. REVISED ILLUMINATED MIRROR TO BE NON- ILLUMINATED MIRROR. (CI 31769)

**SHEET A6 – REAR OFFICE PLAN CCD #1 12/4/25**

DETAIL 1 – REAR OFFICE FLOOR PLAN

1. Omitted Existing BOH Vending Machines, per Final ID Plan. (WM)
2. Added three New Vending Machines, per Final ID Plan. (WM)
3. Revised Location of Apparel Workstation, per Final ID Plan. (WM)

**SHEET A8 – DOOR SCHEDULE AND FINISHES PR#1 7/2/25**

FINISH KEY

1. ADDED P218 TRUE BLUE & PS13 WALMART TRUE BLUE WALL FINISHES. (CI 32312)

**SHEET A8 – DOOR SCHEDULE AND FINISHES CCD #1 12/4/25**

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**DETAIL 1 – DOOR TYPES**

1. Omitted Door Hood at A3 Automatic Sliding Door. (QC)

**DOOR SCHEDULE**

1. Added Door 803A to Door Schedule for Dunkin Gate. (CI 32646)
2. Revised Door Mark from 808B to 805A per Dunkin Tenant. (CI 32646)
3. Removed Door 808A from Schedule. (CI 32646)

**SHEET AC1 – AUTOCENTER PLAN AND DETAILS PR#1 7/2/25**

**SCOPE FINISH BOX: 601 TOILET**

1. REVISED SCOPE OF WORK FOR RESTROOM FIXTURES. (QC)

**DETAIL 1 – AUTO CENTER DEMOLITION PLAN**

1. REVISED RESTROOM FIXTURE TO ETR, EXCEPT WATER CLOSET TO BE REPLACED. (QC)

**DETAIL 2 – AUTO CENTER FLOOR PLAN**

1. REVISED RESTROOM FIXTURE TO ETR. (QC)
2. ADDED NOTE TO NEW WATER CLOSET. (QC)

**DETAIL 3 – AUTO CENTER ENTRY ELEVATION**

1. REVISED AUTO CENTER ENTRY ELEVATION PER NEW ENTERPRISE LAYOUT. (CI 32312)
2. OMITTED DB5 DURO BASE BLACK, P76 WALMART BLUE PER NEW ENTERPRISE LAYOUT. (CI 32312)

**DETAIL 5 – TOILET FLOOR PLAN**

1. OMITTED DETAIL FROM SHEET. (QC)

**SHEET BR1 – BREAKROOM PLAN AND DETAILS PR#1 7/2/25**

**COLOR LEGEND**

1. ADDED P218 TRUE BLUE PER NEW ENTERPRISE LAYOUT. (CI 32312)

**DETAIL 9 – BREAKROOM ELEVATION**

1. REVISED WALL FINISH TO P218 TRUE BLUE PER NEW ENTERPRISE LAYOUT. (CI 32312)

**SHEET BR1 – BREAKROOM PLANS AND DETAILS CCD #1 12/4/25**

**DETAIL 1 - BREAKROOM DEMOLITION PLAN**

1. Added Trenching for new Floor drain, per MEP. (CI 32749)

**DETAIL 2 - ENLARGED BREAKROOM PLAN**

1. Added Ice & Water Dispenser. (CI 32749)

**DETAIL 4 – MODULAR CABINET ASSEMBLY ELEVATION**

1. Added Ice & Water Dispenser. (CI 32749)

**SHEET DD1 – DUNKIN TENANT PLANS AND ELEVATIONS CCD #1 12/4/25**

1. Added Sheet to Set for new Dunkin Tenant layout. (CI 32646)

**SHEET DD2 – DUNKIN TENANT DETAILS CCD #1 12/4/25**

1. Added Sheet to Set for new Dunkin Tenant layout. (CI 32646)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SHEET DA2 – DUNKIN SIGNAGE CCD#1 12/4/25**

1. Added Sheet to Set for new Dunkin Tenant layout. (CI 32646)

**SHEET PHM1 – MODULAR PHARMACY PLANS, ELEVATIONS AND SCHEDULES PR#1 7/2/25**

**DETAIL 4 – PHARMACY EXTERIOR ELEVATION**

1. REVISED 'PHARMACY' SIGN PER NEW ENTERPRISE LAYOUT. (CI 32312)

**SHEET PHM1 – MODULAR PHARMACY PLANS, ELEVATIONS AND SCHEDULES ADD #2 9/10/25**

**DETAIL 1 – PHARMACY PLAN**

1. Revised Side Counter at Pharmacy per Existing Pneumatic Tube Location. (QC)

**DETAIL 2 – DEMOLITION PLAN**

1. Revised Side Counter at Pharmacy per Existing Pneumatic Tube Location. (QC)

**DETAIL 6 – SIDE COUNTER ELEVATION**

1. Revised Side Counter at Pharmacy per Existing Pneumatic Tube Location. (QC)
2. Revised Notes, Dimensions for Side Counter and Millwork. (QC)

**SHEET PHM4 – PANEL PLAN ADD #2 9/10/25**

**DETAIL 1 – MODULAR PANEL PLAN**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**SHEET PHM5.1 – PHASING PLAN ADD #2 9/10.25**

**DETAIL 2 – NIGHT 3 DEMO**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**DETAIL 3 – NIGHT 3**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**SHEET PHM5.2 – PHASING PLANS ADD #2 9/10/25**

**DETAIL 1 – NIGHT 4 DEMO**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**DETAIL 2 – NIGHT 4**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**DETAIL 3 – NIGHT 5 - PART 1**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**DETAIL 4 – NIGHT 5 - PART 2**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**DETAIL 5 – NIGHT 6 AND 7**

1. Revised Side Counter and Millwork per Existing Pneumatic Tube Location. (QC)

**SHEET VC1 – VISION CENTER PR#3 8/12/25**

**DETAIL 1 – VISION CENTER DEMO PLAN**

1. Revised Doors at Vision Center per Existing Condition. (QC)
2. Added new Hardware replacement note. (QC)

**SHEET GA1 – FRONT GROCERY PLAN PR#1 7/2/25**

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**STAINLESS STEEL EQUIPMENT LEGEND**

1. ADDED LEGEND IN ITS ENTIRELY TO SHEET. (WM)

**DETAIL 1 – FRONT GROCERY FLOOR PLAN**

1. ADDED NEW 3-COMPARTMENT SINK AND MOP SINK AT 910 DRY PRODUCE PREP. (WM)

**SHEET GA1 – FRONT GROCERY PLAN PR#3 8/12/25**

**REFRIGERATED CASE LEGEND**

1. Added Pet & Baby Coolers to Legend per 11/12 Revised ID Plan. (QC)

**SHEET GA1 – FRONT GROCERY PLAN CCD #1 12/4/25**

**DETAIL 1 – FRONT GROCERY PLAN**

1. Revised Location of Self-Contained Case, per Final ID Plan. (WM)

**SHEET GA2 – REAR GROCERY PLAN PR#1 7/2/25**

**DETAIL 1 – REAR GROCERY FLOOR PLAN**

1. ADDED NEW MOP SINK AT 150 CORRIDOR & 961 MEAT UTILITY. (WM)

**SHEET GA5 - RESPONSIBILITY SCHEDULES CCD #1 12/4/25**

1. Omitted sheet from set. (CI 32442)

**SHEET GA5.1 - RESPONSIBILITY SCHEDULES CCD #1 12/4/25**

1. Omitted sheet from set. (CI 32442)

**SHEET OPA1 – ONLINE PICKUP PLANS AND DETAILS PR#2 7/25/25**

**DETAIL 4 – OPA1 - WALK-IN PLAN**

1. Added Notes, Dimensions, Keynote Tags, and Callout to Detail. (QC)

**SHEET OPA1 – ONLINE PICKUP PLANS AND DETAILS ADD #2 9/10/25**

**DETAIL 2 – ONLINE PICKUP FLOOR PLAN**

1. Revised OGP Cooler/Freezer to flip layout. (WM)

**DETAIL 3 – FREEZER UNDERSLAB PLAN**

1. Revised OGP Cooler/Freezer to flip layout. (WM)

**DETAIL 4 – WALK-IN PLAN**

1. Revised OGP Cooler/Freezer to flip layout. (WM)
2. Revised Notes and Dimensions per OGP Cooler/Freezer to flip layout. (WM)

**SHEET OPA1 – ONLINE PICKUP PLANS AND DETAILS CCD #1 12/4/25**

**DETAIL 2 – ONLINE PICKUP FLOOR PLAN**

1. Revised OPD Racking, per Final ID Plan. (WM)
2. Added 6" Pipe Bollards at TCO2 Charging Station. (CI 32623)

**SHEET OPA1.2 – ONLINE PICKUP PLANS AND DETAILS PR#2 7/25/25**

**DETAIL 14 – ENLARGED BOLLARD PLAN**

1. Added Notes, Dimensions, Keynote Tags, and Callout to Detail. (QC)

**SHEET OPA1.2 – ONLINE PICKUP DETAILS CCD #1 12/4/25**

**DETAIL 9 – ASSOCIATE CANOPY COVER SECTION**

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

1. Revised Smooth Face to 8" Split Face CMU. (QC)

DETAIL 10 – CANOPY ATTACHMENT AT CMU

1. Revised Smooth Face to 8" Split Face CMU. (QC)

**SHEET OPA1.3 – EDGE PROTECTION AT STEEL JOIST** ADD #2 9/10/25

DETAIL 1 – FLOOR PLAN

1. Revised OGP Cooler/Freezer to flip layout. (WM)

**STRUCTURAL**

**SHEET S0 – GENERAL STRUCTURAL INFORMATION** ADD #2 9/10/25

GENERAL NOTES

1. Revised soil bearing pressure in note 2.1.
2. Revised sulfate exposure class in note 3.2.

FOUNDATION SUBSURFACE PREPARATION NOTE

1. Revised foundation subsurface preparation note.

**SHEET S1 – FOUNDATION AND ROOF FRAMING PLANS** PR#2 7/25/25

DETAIL 2 – ROOF FRAMING PLAN

1. Revised sizes of RCUs.

**SHEET S1 – FOUNDATION AND ROOF FRAMING PLANS** PR#3 8/12/25

DETAIL 1 – FOUNDATION & SLAB PLAN

3. Added boxed note at new opening along grid 1.

DETAIL 2 – ROOF FRAMING PLAN

1. Removed steel lintel at new opening along grid 1.

**SHEET S1 – FOUNDATION AND ROOF FRAMING PLANS** ADD #2 9/10/25

DETAIL 1 – FOUNDATION & SLAB PLAN

1. Shifted insulated freezer slab.
2. Revised slab control joint spacing between grids B-B.9.

DETAIL 2 – ROOF FRAMING PLAN

2. Revised locations of RCUs and roof penetration.

**SHEET S2 – FOUNDATION DETAILS** ADD #2 9/10/25

DETAIL 2 – EXTERIOR COLUMN FOOTING

1. Revised footing size and reinforcing.

DETAIL 8 – NEW COLUMN AT EXISTING WALL

1. Revised footing length.

**SHEET S2.1 – NEW OPENING PLANS AND DETAILS** PR#3 8/12/25

DETAIL 3 – NEW OPENING IN EXISTING WALL

2. Revised jamb details.

DETAIL 5 – NEW OPENING IN EXISTING WALL

2. Revised detail.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SHEET S4 – GENERAL SCHEDULES AND DIAGRAMS** PR#2 7/25/25

DETAIL 5 – RTU/RCU FRAMING SUPPORT PLAN

3. Revised RCU curb width and weight in schedule.

**SHEET S5 – VENDOR CANOPY PLANS AND DETAILS** PR#3 8/12/25

DETAIL 6 – CANOPY AT CMU WALL

1. Revised/added notes.

**SHEET S5 – VENDOR CANOPY PLANS AND DETAILS** CCD #1 12/4/25

DETAIL 3 – PHARMACY CANOPY FOOTING SECTION

3. Removed notes 2 and 3.

DETAIL 5 – ASSOCIATE CANOPY COLUMN FOOTING

3. Removed notes 2 and 3.

**FIRE**

**SHEET FP1 – FIRE SPRINKLER PLAN** ADD #2 9/10/25

DETAIL 1 – FIRE SPRINKLER SITE PLAN

1. Revise Pickup Freezer and Cooler layout.

**SHEET FP1 – FIRE SPRINKLER PLAN** CCD #1 12/4/25

CONTRACTOR PROVIDED SPRINKLER SCHEDULE

2. Revise existing pendent sprinkler quantity.

DETAIL 1 – FIRE SPRINKLER SITE PLAN

1. Add detail callout 7/FP2.

**SHEET FP2 – ENLARGED FIRE SPRINKLER PLAN** ADD #2 9/10/25

DETAIL 3 – PICKUP STORAGE FIRE SPRINKLER PLAN

1. Revise sprinkler layout for Cooler and Freezer.

DETAIL 4 – PICKUP COOLER/FREEZER FIRE SPRINKLER PLAN

1. Revise sprinkler layout for Cooler and Freezer.

**SHEET FP2 – ENLARGED FIRE SPRINKLER PLAN** CCD #1 12/4/25

PROTECTION CRITERIA LEGEND

2. Add Dunkin Donuts to protection criteria.

DETAIL 7 – DUNKIN DONUTS FIRE SPRINKLER PLAN

2. Add detail to sheet.

**PLUMBING**

**SHEET P1 – OVERALL PLUMBING PLAN** PR#1 7/2/25

DETAIL 1 – OVERALL PLUMBING PLAN

1. Replace 3-comp sink in produce prep.
2. Replace mop sink in produce prep.
3. Replace mop sink in meat utility.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

4. Replace mop sink in rear hallway.

**SHEET P1 – OVERALL PLUMBING PLAN PR#2 7/25/25**

DETAIL 1 – OVERALL PLUMBING PLAN

1. Revise Breakroom sink S3.

**KEYNOTES**

1. Add keynote 15.436.
2. Remove keynote 15.448.

**SHEET P1 – OVERALL PLUMBING PLAN ADD #2 9/10/25**

DETAIL 1 – OVERALL PLUMBING PLAN

1. Extend callout 1/P1.2 plan south.

**SHEET P1 – OVERALL PLUMBING PLAN CCD #1 12/4/25**

DETAIL 1 – OVERALL PLUMBING PLAN

1. Add Dunkin callouts 1/DDP1 & 2/DDP1.
2. Add callout 5/P1.1.

**SHEET P1.1 – ENLARGED PLUMBING PLANS PR#1 7/2/25**

DETAIL 1 – FRONT GROCERY PLUMBING PLAN.

1. Add note for new faucet

**SHEET P1.1 – ENLARGED PLUMBING PLANS CCD #1 12/4/25**

DETAIL 5 – BREAKROOM PLUMBING PLAN

1. Add plan to sheet.

**SHEET P1.2 – ENLARGED PLUMBING PLANS ADD #2 9/10/25**

DETAIL 1 – PICKUP PLUMBING PLAN

1. Revise plumbing plan per freezer/cooler swap.
2. Add piping clearance box note.

**SHEET P2 – PLUMBING DETAILS AND SCHEDULES PR#1 7/2/25**

TOILET PLUMBING FIXTURE SCHEDULE

1. Revise L22 faucet.
2. Revise L24 faucet.

PLUMBING FIXTURE SCHEDULE

1. Add SS1 to schedule.

GROCERY PLUMBING EQUIPMENT CONNECTION SCHEDULE

1. Add schedule to sheet.

**SHEET P2 – PLUMBING DETAILS AND SCHEDULES PR#2 7/25/25**

PLUMBING FIXTURE SCHEDULE

2. Add S3.

**SHEET P2 – PLUMBING DETAILS AND SCHEDULES CCD #1 12/4/25**

PLUMBING FIXTURE SCHEDULE

1. Add IMB to schedule.

DETAIL 6 – ICE AND WATER DISPENSER PLUMBING CONNECTION

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

1. Add detail to sheet.

**SHEET DDP1 – DUNKIN TENANT PLUMBING PLANS AND RISERS CCD #1 12/4/25**

1. Sheet added to set.

**SHEET DDP2 – DUNKIN TENANT PLUMBING DETAILS CCD #1 12/4/25**

1. Sheet added to set.

**SHEET DDP3 – DUNKIN TENANT PLUMBING SCHEDULES CCD #1 12/4/5**

1. Sheet added to set.

**MECHANICAL**

**SHEET M1 – OVERALL MECHANICAL PLAN PR#1 7/2/25**

**SEISMIC NOTES**

1. Add note to sheet.

**SHEET SR1 – SEISMIC RESTRAINT PR#1 7/2/25**

1. Add sheet to drawing set.

**REFRIGERATION**

**SHEET RM1 – RESPONSIBILITY MATRICES CCD #1 12/4/25**

1. Sheet added to set.

**SHEET BASR1 – BUILDING AUTOMATION SYSTEM PLAN AND DETAILS PR#2 7/25/25**

**DETAIL 2 – PICKUP REFRIGERATION BUILDING AUTOMATION SYSTEM PLAN**

1. Revise RCU size and remove XCM notes.

**DETAIL 4 – REFRIGERATION BAS ONE-LINE DIAGRAM**

1. Remove XCM.

**SHEET BASR1 – BUILDING AUTOMATION SYSTEM PLAN ADD #2 9/10/25**

**DETAIL 2 – PICKUP REFRIGERATION BUILDING AUTOMATION SYSTEM PLAN**

1. Revise OGP Cooler and OGP Freezer location.
2. Revise RCU 1 and 2 locations.

**SHEET BASR1 – BUILDING AUTOMATION SYSTEM PLAN AND DETAILS CCD #1 12/4/25**

**DETAIL 2 – PICKUP REFRIGERATION BUILDING AUTOMATION SYSTEM PLAN**

1. Revise CU naming.

**DETAIL 4 – REFRIGERATION BAS ONE-LINE DIAGRAM**

1. Revise CU naming.

**DETAIL – LEAK ALARM AND CONTROL SEQUENCE OF OPERATIONS**

1. Revise notes.

**SHEET BASR2 – BUILDING AUTOMATION SYSTEM DETAILS PR#2 7/25/25**

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

DETAIL 4 – WALK-IN EVAPORATOR CONTROL DEVICE LOCATION AND INSTALLATION

1. Revise detail.

DETAIL 5 – KE2-RE2 CONTROLLER WIRING (WALK-IN, EEV, NO EEPR)

1. Revise detail.

**SHEET BASR3 – BUILDING AUTOMATION SYSTEM SCHEDULE PR#2 7/25/25**  
SYSTEM RCU1 DISCHARGE AIR TEMPERATURE AND DEFROST PARAMETERS

1. Add schedule to sheet.

SYSTEM RCU2 DISCHARGE AIR TEMPERATURE AND DEFROST PARAMETERS

1. Add schedule to sheet.

**SHEET BASR3 – BUILDING AUTOMATION SYSTEM SCHEDULE CCD #1 12/4/25**  
SCHEDULE – SYSTEM CU1 TCO2 DISCHARGE AIR TEMPERATURE AND DEFROST PARAMETERS

1. Revise CU naming.

SCHEDULE – SYSTEM CU2 TCO2 DISCHARGE AIR TEMPERATURE AND DEFROST PARAMETERS

1. Revise CU naming.

SCHEDULE – KE2-RE2 WALK-IN APPLICATION MATRIX

1. Schedule added to sheet.

SCHEDULE – KE2-RE2 DOOR SWITCH APPLICATION MATRIX

1. Schedule added to sheet.

**SHEET BASR4 – BUILDING AUTOMATION SYSTEM LEAK DETECTION DETAILS CCD #1 12/4/25**  
DETAIL 1 – LEAK DETECTION PANEL INSTALLATION AND WIRING (COPELAND)

1. Revise detail to be up to date.

DETAIL 3 – LEAK DETECTION COOLER/FREEZER DEVICE MOUNTING (COPELAND)

1. Revise detail to be up to date.

**SHEET R1.1 – REAR REFRIGERATION PLAN PR#2 7/25/25**

DETAIL 1 – REFRIGERATION OGP PLAN

1. Revise RCU size.
2. Update keynote and detail call outs.
3. Update RCU1 and 2 coil model number

PIPING SCHEDULE SYSTEM RCU1

1. Add schedule to sheet.

PIPING SCHEDULE SYSTEM RCU2

1. Add schedule to sheet.

KEYNOTES

1. Add keynote 15.661.

**SHEET R1.1 – REAR REFRIGERATION PLAN ADD #2 9/10/25**

DETAIL 1 – REFRIGERATION OGP PLAN

1. Revise OGP Cooler and OGP Freezer location.
2. Revise RCU 1 and 2 locations.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

3. Revise RCU2 piping schedule.
4. Revise MTA piping schedule.

**SHEET R1.1 – REAR REFRIGERATION PLAN CCD #1 12/4/25**

DETAIL 1 – REFRIGERATION OGP PLAN

1. Revise entire detail.

SCHEDULE – PIPING SCHEDULE SYSTEM CU1 TCO2

1. Revise CU naming.

SCHEDULE – PIPING SCHEDULE SYSTEM CU2 TCO2

1. Revise CU naming

**SHEET R2 – REFRIGERATION SCHEDULE PR#2 7/25/25**

REFRIGERATION SCHEDULE SYSTEM RCU1

1. Add schedule to sheet.

REFRIGERATION SCHEDULE SYSTEM RCU2

1. Add schedule to sheet.

**SHEET R2 – REFRIGERATION SCHEDULES CCD #1 12/4/25**

SCHEDULE – REFRIGERATION SCHEDULE SYSTEM CU1 TCO2

1. Revise CU naming.

SCHEDULE – REFRIGERATION SCHEDULE SYSTEM CU1 TCO2

1. Revise CU naming.

SCHEDULE – FAN-COIL UNIT EQUIPMENT SCHEDULE

1. Add schedule to sheet.

SCHEDULE – REFRIGERATION TCO2 CONDENSING UNIT SCHEDULE

1. Add schedule to sheet.

**SHEET R3 – REFRIGERATION DETAILS CCD #1 12/4/25**

DETAIL 1 – HORIZONTAL REFRIGERANT LINE SUPPORT

1. Revise detail to be up to date.

DETAIL 5 – REFRIGERATION PIPING SUPPORT (ON ROOF)(TCO2)

1. Revise detail title.

**SHEET R3.1 – REFRIGERATION DETAILS PR#2 7/25/25**

DETAIL 2 – CO2 DX EVAPORATOR FAN/COIL UNIT WITH CONTROL VALVES

1. Add detail to sheet.

DETAIL 3 – CO2 DX PIPING DETAILS

1. Add detail to sheet.

DETAIL 4 – CO2 VALVE STATIONS (TCO2)

1. Add detail to sheet.

**SHEET R3.1 – REFRIGERATION DETAILS CCD #1 12/4/25**

DETAIL 3 – PIPING DETAILS (TCO2)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

1. Revise detail title.

DETAIL 5 – CHARGING STATION (CO2)

1. Add detail to sheet.

DETAIL 6 – PIPING DETAILS (GENERIC)

1. Add detail to sheet.

**SHEET R4 – REFRIGERATION SUBMITTALS PR#2 7/25/25**

DETAIL 2 – CO2 DX EVAPORATOR FAN/COIL UNIT WITH CONTROL VALVES

1. Revise RCU information.

**ELECTRICAL**

**SHEET RE1 – REFRIGERATION ELECTRICAL PLAN PR#2 7/25/25**

DETAIL 1 – FRONT REFRIGERATION ELECTRICAL PLAN

1. Revise RCU1 and RCU2 disconnect size to 30A.

**SHEET RE1 – REFRIGERATION ELECTRICAL PLANS ADD #2 9/10/25**

DETAIL 1 – FRONT REFRIGERATION ELECTRICAL PLAN

1. Relocate power and devices for RCU1 & RCU2.
2. Revise power and wiring for the evaporator coils at Pickup Freezer and Cooler.
3. Relocate the leak detection panel and BAS equipment.

**SHEET E1 – LIGHTING PLAN CCD #1 12/4/25**

DETAIL 1 – LIGHTING PLAN

1. Add detail callout 1/DDE1.

**SHEET E1.1 – ENLARGED LIGHTING PLANS PR#1 7/2/25**

DETAIL 2 – FRONT OF HOUSE LIGHTING PLAN

1. Remove lighting scope of work for backlit mirrors being removed from project.

DETAIL 4 – BACK OF HOUSE LIGHTING PLAN

1. Remove lighting scope of work for backlit mirrors being removed from project.

KEYNOTES

1. Remove Keynote 16.147.

**SHEET E1.1 – ENLARGED LIGHTING PLANS ADD #2 9/10/25**

**DETAIL 9 – PICKUP LIGHTING PLAN**

1. Revise lighting layout at Pickup Freezer and Cooler.

**SHEET E1.1 – ENLARGED LIGHTING PLANS CCD #1 12/4/25**

DETAIL 8 – NOT USED

1. Remove and rename detail view from sheet.

**SHEET E1.4 – LIGHTING DETAILS AND SCHEDULES CCD #1 12/4/25**

LIGHT FIXTURE SCHEDULES

1. Update count for type 9 and 16 fixtures.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SHEET E2 – POWER PLAN PR#1 7/2/25**

DETAIL 1 – POWER PLAN

1. Revise callout number for Rear Office Power Plan.
2. Add callout 2/E2.2 for Breakroom Power Plan.
3. Add callout 9/E2.2 for Tenant Power Demo Plan.
4. Relocate power for relocated Propane Exchange.
5. Add demolition SOW for Pharmacy drive-thru and canopy.
6. Add power and devices for new Pharmacy drive-thru location.

KEYNOTES

1. Add Keynote 16.489.

**SHEET E2 – POWER PLAN CCD #1 12/4/25**

DETAIL 1 – POWER PLAN

1. Add detail callout 1/DDE2.
2. Shift electrical devices for apparel workstation.

**SHEET E2.1 – POWER DROP PLAN PR#3 8/12/25**

DETAIL 1 – POWER DROP PLAN

2. THE FOLLOWING POWER DROPS WERE DELETED FROM POWER ZONE 2:
  - a. (1) CLR
3. THE FOLLOWING POWER DROPS WERE REVISED IN POWER ZONE 2:
  - a. (1) CLR
4. Add notes identifying the Pet ID Tag and Pet Coolers in Power Zone 2.
5. Add note identifying the Baby Cooler in Power Zone 8.

**SHEET E2.1 – POWER DROP PLAN CCD #1 12/4/25**

DETAIL 1 – POWER DROP PLAN

1. THE FOLLOWING POWER DROP WERE REMOVED FROM POWER ZONE 2
  - a. (1) PET
2. THE FOLLOWING POWER DROP HAVE BEEN RELOCATED WITHIN POWER ZONE 5
  - a. (1) FTR
3. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 9
  - a. (1) MTV
4. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 9
  - a. (5) 18C
5. THE FOLLOWING POWER DROPS HAVE BEEN REMOVED FROM POWER ZONE 10
  - a. (5) 18C
6. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 10
  - a. (1) VIN
7. THE FOLLOWING POWER DROPS HAVE BEEN RELOCATED WITHIN POWER ZONE 11
  - a. (1) VIN
8. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 12
  - a. (1) VIN
9. THE FOLLOWING POWER DROP HAVE BEEN ADDED WITHIN POWER ZONE 12
  - a. (1) 11A
10. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 13
  - a. (1) VIN
11. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 13
  - a. (2) 16C
12. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 15
  - a. (1) 11A
13. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 15

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

- a. (1) 12A
- b. (1) 12B
- 14. THE FOLLOWING POWER DROPS HAVE BEEN REMOVED FROM POWER ZONE 16
  - a. (1) 12A
  - b. (1) 12B
- 15. THE FOLLOWING POWER DROP HAVE BEEN ADDED WITHIN POWER ZONE 16
  - a. (1) KEY
- 16. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 17
  - a. (1) KEY
- 17. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 17
  - a. (1) HSC
  - b. (1) 09B
- 18. THE FOLLOWING POWER DROPS HAVE BEEN REMOVED FROM POWER ZONE 18
  - a. (1) HSC
  - b. (1) 09B
- 19. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 18
  - a. (2) 07A
- 20. THE FOLLOWING POWER DROPS HAVE BEEN REMOVED FROM POWER ZONE 19
  - a. (3) 07A
- 21. THE FOLLOWING POWER DROP HAVE BEEN ADDED WITHIN POWER ZONE 19
  - a. (1) 07B
- 22. THE FOLLOWING POWER DROP HAVE BEEN ADDED WITHIN POWER ZONE 21
  - a. (1) 16C
- 23. THE FOLLOWING POWER DROP HAVE BEEN REMOVED FROM POWER ZONE 22
  - a. (1) 16C

**SHEET E2.2 – ENLARGED POWER PLANS PR#1 7/2/25**

**DETAIL 1 – REAR OFFICE POWER DEMO PLAN**

- 1. Revise power demo scope of work for updated Breakroom per latest ID plan.

**DETAIL 2 – BREAKROOM POWER PLAN**

- 1. Add detail to sheet.

**DETAIL 4 – FRONT RESTROOM POWER PLAN**

- 1. Remove power scope of work for backlit mirrors being removed from project.

**DETAIL 6 – CUSTOMER SERVICE POWER PLAN**

- 1. Show power scope of work for front counter.

**DETAIL 8 – WHITE BOX POWER PLAN**

- 1. Add box note for electrical devices on perimeter walls.

**DETAIL 9 – TENANT POWER DEMO PLAN**

- 1. Add detail to sheet.

**DETAIL 10 – REAR OFFICE POWER PLAN**

- 1. Revise detail reference number.
- 2. Revise detail to remove breakroom from the detail.
- 3. Remove power scope of work for backlit mirrors being removed from project.

**KEYNOTES**

- 1. Add Keynote 16.410.

**SHEET E2.2 – ENLARGED POWER PLANS ADD #2 9/10/25**

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**DETAIL 3 – PICKUP POWER PLAN**

1. Revise power and devices at Pickup Freezer and Cooler.
2. Revise circuits for the HCR doors.

**SHEET E2.2 – ENLARGED POWER PLANS CCD #1 12/4/25**

**DETAIL 2 – BREAKROOM POWER PLAN**

1. Show existing electrical devices for new vending machines.
2. Show power for new Ice and Water Dispenser.

**DETAIL 8 – TEMPORARY OGP POWER PLAN**

1. Revise detail view name.
2. Show power for existing temporary self contained cases.

**SHEET E2.3 – ENLARGED POWER PLANS CCD #1 12/4/25**

**DETAIL 3 – COSMETICS POWER PLAN**

1. THE FOLLOWING POWER DROPS HAVE BEEN ADDED WITHIN POWER ZONE 22
  - a. (1) 46F
2. THE FOLLOWING POWER DROPS HAVE BEEN RELOCATED WITHIN POWER ZONE 23
  - a. (6) 46E

**SHEET E4 – ELECTRICAL ONE-LINE DETAILS AND SCHEDULES CCD #1 12/4/25**

**DETAIL 1 – PARTIAL ONE-LINE DIAGRAM**

1. Show new coffee tenant panel LDU

**FEEDER SCHEDULE**

1. Add feeder 104.

**SHEET E4.1 – PANELBOARD SCHEDULES PR#1 7/2/25**

**PANELBOARD L1D1**

1. Revise description and wire size for circuits 2, 4, 6, 8, 10, 12, 14, 16, 41, 53, and 55.
2. Revise description for circuit 39.

**PANELBOARD L2D2**

1. Revise description, wire size, and breaker for circuit 1.
2. Revise description and wire size for circuits 3 and 5.

**SHEET E4.1 – PANELBOARD SCHEDULES CCD #1 12/4/25**

**PANELBOARD H2P1**

1. Circuit 23 – Revise circuit description.

**PANELBOARD L1D1**

1. Circuit 38 – Add circuit for new Ice and Water Dispenser.

**SHEET E4.2 – PANELBOARD SCHEDULES PR#1 7/2/25**

**PANELBOARD L2U**

1. Revise description and wire size for circuit 2.

**PANELBOARD L4D1**

1. Revise description, wire size, and breaker for circuit 18.
2. Revise description and wire size for circuit 20.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

PANELBOARD LRX

1. Revise description and wire size for circuit 8.
2. Revise description for circuit 16.
3. Revise description, wire size, and breaker for circuit 18.

**SHEET E4.2 – PANELBOARD SCHEDULES PR#2 7/25/25**

PANELBOARD LPU

1. Circuits 2,4,6: Revise breaker size, wire size and load.
2. Circuits 8,10,12: Revise breaker size, wire size and load.

**SHEET E4.2 – PANELBOARD SCHEDULES CCD#1 12/4/25**

PANELBOARD LMC1

1. Circuit 1,3 – Revise circuit description, load, wire size, breaker, and poles.
2. Circuit 2 – Revise circuit description, load, and wire size.
3. Circuit 5 – Revise circuit description, load, and wire size.
4. Circuit 4,6 – Revise circuit description, load, wire size, breaker, and poles.
5. Circuit 7,9 – Revise circuit description, load, wire size, breaker, and poles.
6. Circuit 8 – Revise circuit description, load, and wire size.
7. Circuit 10,12 – Revise circuit description, load, wire size, breaker, and poles.
8. Add temporary OGP SOW boxed notes.

**SHEET E4.3 – PANELBOARD SCHEDULES PR#3 8/12/25**

BUSWAY BL1B

3. Revise description for circuit 22.
4. Revise description and wire size for circuits 23 and 24.

**SHEET E4.3 – PANELBOARD SCHEDULES CCD #1 12/4/25**

BUSWAY BL1A

1. Circuit 17 – Add circuit for new 11A hardware power drop.

BUSWAY BL1B

1. Circuit 20 – Revise circuit description to Spare.

BUSWAY BL2B

1. Circuit 3 – Add power for new 16C garden center power drop.
2. Circuit 4 – Add circuit for 46E cosmetic power drop.
3. Circuit 5 – Add power for new 16C garden center power drop.
4. Circuit 6 – Revise circuit description.
5. Circuit 16 – Revise circuit description.
6. Circuit 18 – Revise circuit description.
7. Circuit 21 – Add power for new 46F cosmetics power drop.
8. Circuit 23 – Add power for new 46F cosmetics power drop.

**SHEET EPH1 – PHARMACY ELECTRICAL PLAN PR#1 7/2/25**

DETAIL 3 – PHARMACY POWER DEMO PLAN

1. Show power demo scope of work for drive-thru counter.

DETAIL 4 – PHARMACY POWER PLAN

1. Show power scope of work for Pharmacy drive-thru counter.
2. Add data outlet and note for A/V hub.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SHEET GE2 – GROCERY POWER PLANS CCD #1 12/4/25**

DETAIL 2 – GROCERY POWER PLAN

1. Revise relocation for existing self contained case.

**SHEET DDE1 – DUNKIN ELECTRICAL LIGHTING PLAN CCD #1 12/4/25**

1. Add sheet to set.

**SHEET DDE2 – DUNKIN ELECTRICAL POWER PLAN CCD #1 12/4/25**

1. Add sheet to set.

**SHEET DDE3 – DUNKIN ELECTRICAL PANELBOARD SCHEDULES CCD #1 12/4/25**

1. Add sheet to set.

**STRUCTURAL RACKING**

**SHEET FXS1 – FIXTURE ANCHORAGE PLAN AND NOTES CCD #1 12/4/25**

DETAIL 1 – RACK AND SHELVING FIXTURE ANCHOR PLAN

- Revise plan as shown due to owner requested changes.

RACK FIXTURE SCHEDULE

- Remove DD fixture from the schedule.
- Add OGP5 fixture to the schedule.
- Add YZ fixture to the schedule.

RACK FRAME & ANCHORAGE SCHEDULE

- Remove 24-72 075A frame count from the schedule.
- Updated 44-72 075A frame count.
- Added 44-120 075B frame count to the schedule.
- Update 46-90 OGP frame count.

ANCHORAGE BILL OF MATERIALS

- Update 1/2" diameter DeWalt screw bolt anchor count.
- Update 3/8" diameter DeWalt screw bolt anchor count.
- Update gondola anchor strap count.
- Update CMU wall anchor count.

TEMPORARY ANCHORAGE BILL OF MATERIALS

- Update 3/8" diameter DeWalt screw bolt temporary anchor count.
- Update temporary gondola anchor strap count.

SHELVING FIXTURE & ANCHORAGE SCHEDULE

- Add 18T half gondola to schedule.
- Remove 2490 EC from the schedule.

**SHEET FXS2 – FIXTURE ANCHORAGE DETAILS CCD #1 12/4/25**

DETAIL 5 – TYPICAL ANCHOR AT RACK FRAMES

- Added detail 5C to account for the UB frames added to the floor layout.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**CIVIL**

**SHEET C030 - OVERALL SITE PLAN PR#1 7/2/25**

1. Update sheet number.
2. Update propane cages location, moving back to their existing location in front of the bollards.

**SHEET C150-DEMOLITION PLAN ADD #2 9/10/25**

1. Additional pavement demolition to enable storm pipe install.

**SHEET C300-GRADING AND UTILITY PLAN ADD #2 9/10/25**

1. Route canopy underdrains to existing storm infrastructure.

**SHEET C500 - DEMOLITION AND SITE CONSTRUCTION PLAN PR#1 7/2/25**

1. Update propane cages location, moving back to their existing location in front of the bollards.

**SHEET C700-SITE CONSTRUCTION DETAILS ADD #2 9/10/25**

1. Add construction details for Siphonic Manhole.

**SPECIAL ELEMENTS**

**SHEET LS1 – LIFE SAFETY PLAN PR#1 7/2/25**

DETAIL 1 – LIFE SAFETY PLAN

1. ADDED NEW COUNTER & MILLWORK AT CUSTOMER SERVICE. (WM)
2. ADDED NEW 3-COMPARTMENT SINK AT 910 DRY PRODUCE PREP. (WM)

**SHEET LS1 – LIFE SAFETY PLAN PR#3 8/12/25**

DETAIL 1 – LIFE SAFETY PLAN

1. Added Pet & Baby Coolers per 11/12 Revised ID Plan. (QC)
2. Revised Fitting Room layout to omit duplicate image. (QC)

**SHEET LS1 – LIFE SAFETY PLAN ADD #2 9/10/25**

DETAIL 1 – LIFE SAFETY PLAN

1. Revised OGP Cooler/Freezer to flip layout. (WM)
2. Revised Side Counter at Pharmacy per Existing Pneumatic Tube Location. (QC)

**SHEET LS1 – LIFE SAFETY PLAN CCD #1 12/4/25**

DETAIL 1 – LIFE SAFETY PLAN

1. Revised Garden Center & Seasonal Fixtures, per Final ID Plan. (WM)
2. Revised White Box Tenant. (WM)
3. Revised Customer Service Desk, per Final ID Plan. (WM)
4. Revised Fitting Rooms layout, per Store Planning. (WM)
5. Revised OPD Racking, per Final ID Plan. (WM)
6. Revised BOH Location of Apparel Workstation, per Final ID Plan. (WM)
7. Revised Location of Self-Contained Case at Grocery Sales, per Final ID Plan. (WM)
8. Revised Location of Ice Machin per Merch/Order Copy Plan. (WM)
9. Omitted Existing BOH Vending Machines, per Final ID Plan. (WM)
10. Added three New Vending Machines, per Final ID Plan. (WM)
11. Added 6" Pipe Bollards at TCO2 Charging Station. (CI 32623)

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

12. Added Dunkin Donuts Tenant to Floor Plan. (CI 32646)

## **SPECIFICATIONS**

### **SECTION 06400 – ARCHITECTURAL WOODWORK AND MILLWORK ASSEMBLIES CCD #1 12/4/25**

1. Added Prefab Suspended Ceiling feature at Dunkin Tenant space. (CI 32646)

### **SECTION 07530 – ELASTOMERIC MEMBRANE ROOFING PR#1 7/2/25**

#### **PART 1 - GENERAL**

1. Added SECTION 1.4 ADMINISTRATIVE REQUIREMENTS. (CI 32293)
2. Added SECTION 1.6 QUALITY ASSURANCE. (CI 32293)
3. Revised SECTION 1.7 REGULATORY REQUIREMENTS. (CI 32293)
4. Omitted APPROVED ROOFING SUBCONTRACTORS SCHEDULE. (CI 32293)
5. Revised SECTION 1.8. A DELIVERY, STORAGE, AND HANDLING. (CI 32293)
6. Revised SECTION 1.10.A & B. SEQUENCING AND SCHEDULING. (CI 32293)
7. Revised SECTION 1.11.A WARRANTY. (CI 32293)

#### **PART 2 – PRODUCTS**

1. Revised SECTION 2.1.B MANUFACTURER CONTACT INFORMATION. (CI 32293)

### **SECTION 08710 – CONTRACTOR HARDWARE SCHEDULE PR#1 7/2/25**

#### **DOOR 108A - COUNTING**

1. Added Door Protection Plate K-4 to exterior side of door. (WM)

### **SECTION 08710 – CONTRACTOR HARDWARE SCHEDULE PR#3 8/12/25**

1. Added Hardware sets for existing Vision Center Vestibule doors 711A & 711C to Contractor (previously included in Owner Provided Spec in error). (QC)

### **SECTION 08710 – OWNER HARDWARE SCHEDULE PR#3 8/12/25**

1. Omitted Hardware sets for existing Vision Center Vestibule doors 711A & 711C shown by Owner in error. (QC)

### **SECTION 08710 – OWNER HARDWARE SCHEDULE CCD #1 12/4/25**

1. Added Dunkin Tenant Door 803A Hardware set. (CI 32646)
2. Omitted Board-Up Tenant Door 808A Hardware Set. (WM)
3. Revised BTS Door 808B to 805A Dunkin Tenant. (CI 32646)

### **SECTION 15480 - DOMESTIC WATER HEATERS CCD #1 12/4/25**

1. Add entire spec.

### **SECTION 15600 – REFRIGERATION SYSTEMS PR#2 7/25/25**

1. Revise specification to include TCO2 requirements.

### **SECTION 15600 – REFRIGERATION SYSTEMS CCD #1 12/4/25**

#### **SECTION 3.6 TESTING, EVACUATION, AND FILLING TRANSCRITICAL CO2 SYSTEM**

1. Add note F.

WAL-MART INC. STORE NO. 06958-1000	December 17, 2025
PROJECT: CAMERON, NC	Update to Permit No. BCOM2501-0003
PROJECT NO. 194-23-047	PR 1-3,ADD #2 & CCD #1

**SECTION 16080 – PROTECTIVE DEVICE SETTINGS REPORT CCD #1 12/4/25**

1. Add CBR-LDU to settings report.

**APPENDIX A - PRODUCTS AND WORK BY OWNER OR SEPARATE CONTRACTOR PR#1 7/2/25**

**SECTION 10810 – TOILET ACCESSORIES**

1. Omitted Lighted Mirrors from Section 2.4.H. Schedule of Accessories. (CI 31769)

**APPENDIX A – PRODUCTS AND WORK BY OWNER OR SEPARATE CONTRACTOR CCD #1 12/4/25**

**OWNERS SUPPLIERS LIST**

1. Section 06400: Added Architectural suspended ceiling feature and HJ&C Vendor. (CI 32646)
2. Section 11400: Added Ice and Water Dispenser and Scotsman Group Vendor. (CI 32749)
3. Section 15480 Added Domestic Water Heaters.
4. Section 15600 Remodel - Remote condensing units (RCU): Removed Kysor Warren. Added Carrier.

**SECTION 06065 – PLASTIC MATERIALS**

1. Omitted 'Ultratech International' from Manufacturer's list. (CI 32702)
2. Revised Paragraph 2.3.A under Products Schedule for Bollards. (CI 32702)

**SECTION 06400 – ARCHITECTURAL WOODWORK AND MILLWORK ASSEMBLIES**

1. Added Paragraph 2.4.A for Architectural Suspended Ceiling Feature. (CI 32646)

**SECTION 09720 – DECORATIVE FAUX TILE WALL PANELS**

1. Added Paragraph 2.3.B for FT2 Prefabricated wall panels. (CI 32646)
2. Added Accessories 2.4.B Trim notes 5 & 6. (CI 32646)

**SECTION 15480 - DOMESTIC WATER HEATERS**

1. Add section 15480 to spec.

**APPENDIX B - TESTING, INSPECTION, AND OBSERVATION BY OWNER PR#1 7/2/25**

**PART 1 - GENERAL**

1. OMITTED SECTION 1.7 ROOF OBSERVATION PROGRAM. (CI 32293)

**PART 2 AND PART 3 – PRODUCTS AND EXECUTION**

1. OMITTED 2.3.A.2 SECTION 07530 – ELASTOMERIC MEMBRANE ROOFING: OWNER'S INDEPENDENT ROOFING INSPECTOR (IRI). (CI 32293)
2. OMITTED SECTION 07530 ELASTOMERIC MEMBRANE ROOFING. (CI 32293)

**END OF NARRATIVE**