



**DIMENSIONAL DATA:**

CASE LENGTH	DIMENSION "A"	DIMENSION "B"	DIMENSION "C"	DIMENSION "D"	NO. HOT WELLS (IF APPLICABLE)	NO. SHELVES (IF APPLICABLE)
6 FOOT	4' - 6"	3' - 1"	5' - 9-1/4"	6' - 0-1/2"	5 - WELLS	2 - SHELVES
8 FOOT	4' - 6"	3' - 1"	7' - 9-3/8"	8' - 0-5/8"	7 - WELLS	2 - SHELVES
12 FOOT	4' - 6"	3' - 1"	11' - 9-1/4"	12' - 0-1/2"	10 - WELLS	2 - SHELVES

**ELECTRICAL DATA:**

CASE LENGTH	VOLTAGE	PHASE	AMPS	TOTAL LOAD (Kw)	BREAKER	TERMINATION	PLUG TYPE	CORD PROVIDED Y/N	UL LISTED Y/N
6 FOOT	120/208V -5 WIRE	3 PHASE	22.00	7.90	30 AMP		N/A	N	Y
8 FOOT	120/208V -5 WIRE	3 PHASE	25.68	9.22	40 AMP		N/A	N	Y
12 FOOT	120/208V -5 WIRE	3 PHASE	37.00	13.30	50 AMP		N/A	N	Y

**NOTES:**

NOTE: ELECTRICAL IS DIRECT CONNECTION HARD WIRED (NO ELECTRICAL CORD)  
 NOTE: 5 WIRE SERVICE (3 - HOTS, 1 - NEUTRAL, 1 - GROUND)  
 NOTE: ALL ZONES ARE DIGITALLY CONTROLLED THROUGH ADVANCED COMPUTER TECHNOLOGY TO ENSURE AND MAINTAIN PRODUCT TEMPERATURE AND QUALITY.  
 NOTE: ADDING A SOLID END ADDS 1/58"

ARCH	MECH	ELEC	REFR	MECH CONST	OWNER
REVIEWED	REVIEWED	REVIEWED	REVIEWED	V-APR	V-APR