



February 18, 2026

Mike Rimbey
Ph: (919) 901-2284, (919) 821-1300
3709 Auburn Church Rd,
Garner, NC 27529
Email: mike.rimbey@inlandconstructionco.com

Reference: Engineering Services
Project No.: 2401-010249_F

As requested by the client, a representative of Tyndall Engineering & Design, PA (TE&D) has reviewed the following item(s):

- 1) Absence of 6" curbs on sections of the foundation.

Based on our review and worst-case analyses, TE&D recommends the following:

- 1)
 - a) A new 6" wide x 6" tall curb and water proofing may be installed on the existing turndown footing per detail A on page 2 of this report.
 - b) Install concrete curb to 6" above finished floor monolithically per detail B on page 4 or as shown in detail A on page 3 of this report. Curb extents and dimensions are shown in plan view on page 4 of this report. Please note that the greyed-out areas on the plan view are to be raised 6" above finished floor.

We appreciate being able to assist you during this phase of the project. If you need further assistance or require additional information, please do not hesitate to contact us.

Sincerely,
Tyndall Engineering & Design

Bob Ahimbisibwe, PE
BEA/2401-010249_F

Prentice A. Tyndall Jr., P.E





