

Gary Willis Plumbing, Inc
2858 Bailey Rd
Coats, NC 27521 US
+19198942987
contact@gwplumbinginc.com

Estimate 4064

ADDRESS	SHIP TO	DATE	TOTAL	EXPIRATION DATE
Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	02/04/2025	\$4,472.70	03/21/2025

SITE ADDRESS 2649 Oak Grove Church Rd. Angie	FIELDWORKER Gary W.	PO Trench in water line
--	-------------------------------	-----------------------------------

ACTIVITY	QTY	RATE	AMOUNT
Material: Material 180'-3/4" PEX water line, Misc. connective fittings, 1-3/4" PRV, 1-3/4" wilkens backflow, 1-wye strainer, 1-air gap, insulation		2,264.88	2,264.88T
Trencher Trencher	1	200.00	200.00T
Backflow Test Backflow Test	1	125.00	125.00T
Labor: Labor_ Labor		1,600.00	1,600.00T

Please read the estimate carefully. If you choose to accept the estimate, please sign and date and email the estimate back to us. You will need to call our office at (919) 894-2987 to schedule the work. Feel free to contact us if you have any questions. We hereby submit an estimate to trench in a water line from the existing main going to the church and connect into it before it goes into the church and run it to the new building and run it upstairs in the new building. We will have it ready to connect to for the bathrooms and test it after we get it pressurized and insulated to pass code. We look forward to working with you.

SUBTOTAL	4,189.88
TAX	282.82
TOTAL	\$4,472.70

THANK YOU.

Thanks for your business!
Gary Willis Plumbing, Inc.

Accepted By

Accepted Date

Gary Willis Plumbing, Inc
2858 Bailey Rd
Coats, NC 27521 US
+19198942987
contact@gwplumbinginc.com

Estimate 4065

ADDRESS	SHIP TO	DATE	TOTAL	EXPIRATION DATE
Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	02/04/2025	\$2,533.11	03/21/2025

SITE ADDRESS 2649 Oak Grove Church Rd. Angie	FIELDWORKER Gary W.	PO Rough in plumbing
--	-------------------------------	--------------------------------

ACTIVITY	QTY	RATE	AMOUNT
Material: Material 40'-3" PVC piping, 20'-2" PVC piping, Misc. 3" and 2" PVC fittings, Misc. strapping, 3/4" and 1/2" PEX water lines, insulation		1,172.94	1,172.94T
Labor: Labor Labor		1,200.00	1,200.00T

Please read the estimate carefully. If you choose to accept the estimate, please sign and date and email the estimate back to us. You will need to call our office at (919) 894-2987 to schedule the work. Feel free to contact us if you have any questions. We hereby submit an estimate to dig the ditch's to rough in the sewer in the building and out to the septic tank. Also rough in the water lines to the fixtures and to the main water coming into the building. We will need to put a test on the system for inspection before covering the piping for concrete. Before starting any work, we will need to get at least half of the project up front.
We look forward to working with you.

SUBTOTAL	2,372.94
TAX	160.17
TOTAL	\$2,533.11

THANK YOU.

Thanks for your business!
Gary Willis Plumbing, Inc.

Accepted By

Accepted Date

Gary Willis Plumbing, Inc
2858 Bailey Rd
Coats, NC 27521 US
+19198942987
contact@gwplumbinginc.com

Estimate 4066

ADDRESS	SHIP TO	DATE	TOTAL	EXPIRATION DATE
Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	Greater Vision Fellowship Church 135 Dry Creek Rd Lillington, NC 27546 US	02/04/2025	\$5,312.80	03/21/2025

SITE ADDRESS 2649 Oak Grove Church Rd. Angie	FIELDWORKER Gary W.	PO Trim out plumbing
--	-------------------------------	--------------------------------

ACTIVITY	QTY	RATE	AMOUNT
Material: Material 2-ADA commodes, 2-wall hung lavatory, wax seals, closet bolts, p-traps, angle stop supply tubes, crab bars, 2-delta single lavatory faucets, 1-240A tankless water heater, drain pan, expansion tank		3,876.86	3,876.86T
Labor: Labor Labor		1,100.00	1,100.00T

Please read the estimate carefully. If you choose to accept the estimate, please sign and date and email the estimate back to us. You will need to call our office at (919) 894-2987 to schedule the work. Feel free to contact us if you have any questions. We hereby submit an estimate to go in and set the fixtures and hook them up after the walls are finished and painted. We will set the water heater and connect it and have water running when finished. We will put up the grab bars beside the commodes and behind them.
We look forward to working with you.

SUBTOTAL	4,976.86
TAX	335.94
TOTAL	\$5,312.80

THANK YOU.

Thanks for your business!
Gary Willis Plumbing, Inc.

Accepted By

Accepted Date

Backflow in ceiling over Bathrooms on catwalk
water heater in ceiling in catwalk

