

Glass Door FREEZERS - Manufacturer Code		DS- 205-4	DS 451-8	DS 651-12	
1.	<b>Product identification</b>				
	Product description (Chest Freezer)	Glass door freezer	Glass door freezer	Glass door freezer	
	Type of version (STD=standard / SI= Super Insulated)	STD	STD	STD	
	Cooling system (Static / No Frost)	Static	Static	Static	
	Condensing system(S=static/F=condensing with fan)	F	F	F	
	Climate class (N= + 18-32°C T=+ 18-43°C)	N	N	N	
	Freezer star rating	0 to 4	3	3	
	Certifications ( CE / ISO 9001/2 / LGA etc.)		ETL/NSF	ETL/NSF	ETL/NSF
2.	<b>Key features</b>				
	Gross capacity	l	205	365	550
	Total net capacity	l	165	310	471
	Defrosting (Manual-Automatic)		Manual	Manual	Manual
	Kind of coolant (R134a/R600a)		R290	R290	R290
	Foaming components (R141b/C-P)		C-P	C-P	C-P
3.	<b>Technical data</b>				
	Voltage / frequency	V/Hz	110-120/60	110-120/60	110-120/60
	Lenght of cable / incl. Plug	cm	180	180	180
	Cooling system: (K=Compressor / A=Absorbtion)		K	K	K
	Maximum noise level	dB(A)	50	50	50
4.	<b>Aesthetics</b>				
	Door Type		flat door	flat door	flat door
	Door (lid) Number		2	2	2
	Colours external (cabinet):		White	White	White
	Door glass		2	2	2
	Door frame		Light grey	Light grey	Light grey
	Logo (Adhesive/Painted)		Adhesive	Adhesive	Adhesive
5.	Equipment & accessories				
	Product classification (Eco / Standard)		Standard	Standard	Standard
	Inside cabinet walls ( Aluminium / Synthethic mat.)		White painted aluminum	White painted aluminum	White painted aluminum
	Type of lid (Hinge / Counter balanced / Sliding)		Sliding	Sliding	Sliding
	Walls thikness	mm	70	70	70
	Handle (Integrated/External**)		Integrated	Integrated	Integrated
	Lock (Glass door)***		With	With	With
	Number of basket (No./Trasparent plastic/White plastic/White wire)		White wire/2	White wire/4	White wire/6
	Defrost drain		with	with	with
	Interior light		with	with	with
	Temperature display		with	with	with
	Adjustable thermostat		YES	YES	YES
	Maximum loading level marking		With	With	With
	Flushback skin evaporator		YES	YES	YES
	Mobility wheels (front / rear)	n°	4	4	4
6.	<b>Product net dimensions</b>				
	Unit dimensions (W / D / H)	mm	725*675*830	1275*675*830	1805*675*830
	Unit dimensions (W / D / H)	in	28.54*26.57*32.68	50.2*26.57*32.68	71.06*26.57*32.68
7.	<b>Packing dimensions &amp; loadability</b>				
	Packing dimensions (W / D / H)	mm	770*780*870	1320*780*870	1850*780*870
	Packing dimensions (W / D / H)	in	30.31*30.71*34.25	51.97*30.71*34.25	72.83*30.71*34.25
	40 ' HC Container load	pcs	123	72	51