

Model #	K220GDR/SDR	K220SDF
Storage Volume	20 cubic feet	20 cubic feet
Specifications		
Exterior (D x W x H)	27.75" x 30.38" x 76.6"	27.75" x 30.38" x 76.6"
Interior (D x W x H)	22.2" x 25.4" x 64.8"	22.2" x 25.4" x 64.8"
Insulation	CFC-free, high density insulation	CFC-free, high density insulation
Doors	1, right-hand swing	1, right-hand swing
Shelves	6	6
Access Port	0.5" probe port	0.5" probe port
Casters	Standard	Standard
Shipping Weight	276/261 lbs	261 lbs
Certifications & Compliances	ISO: 9001:2015, CDC and VFC Compliant, EPA and SNAP Compliant	cULus, ISO: 9001:2015, Energy Star, CDC and VFC Compliant, EPA and SNAP Compliant
Performance		
Stability	+/- 2°C to 3°C	+/- 2°C to 3°C
Adjustable Set Point Range	+2°C to +8°C	-10°C to -25°C
Factory Set Point	+4°C	-20°C
Electrical Power/Current	120v 60 Hz 15 Amp	120v 60 Hz 15 Amp
Power Plug	NEMA 5-15	NEMA 5-15
Indoor/Outdoor Use	Indoor use only	Indoor use only
Application Environment	Non-corrosive, non-flammable, non-explosive	Non-corrosive, non-flammable, non-explosive
Ambient Operating Temp	20°C to 32°C	20°C to 32°C
Refrigeration		
Refrigeration System	Vapor compression system, forced-air	Vapor compression system
Compressor	Hemetically sealed compressor	Hemetically sealed compressor
Condenser Type	Hot wall condenser	Foamed in
Expansion Device	Capillary tube	Capillary tube
Evaporator Type	Forced-air	Cold wall evaporator
Defrost	Static (cycle)	Manual
Refrigerant	R600a (Isobutane)	R290 (Propane)
Controller/System Configuration		
User Interface	Microprocessor with digital display	Microprocessor with digital display
Power Switch	Plug & Play	Plug & Play
Controller Type	Digital Controller	Digital Controller
Security	Keyed lockable doors	Keyed lockable doors
Control Sensor	NTC probe	NTC probe
Remote Alarm Terminals	Standard	Standard
High/Low Alarms	Standard	Standard
Power Failure Alarm	Standard	Standard
Door Ajar Alarm	Standard	Standard
Warranty	Two-year parts, labor, or full replacement	Two-year parts, labor, or full replacement