

LOT 56 INFORMATION:

15 FELLOW DRIVE
PIN: 0680-09-2700.000
REFERENCE: DB. 4301, PG. 293
TOTAL LOT AREA = 0.369 AC = 16,066 SF
HOUSE = 2,341 SF
FRONT PORCH = 131 SF
DRIVEWAY/SIDEWALK (TO P/L) = 509 SF
COVERED PATIO = 48 SF
PATIO = 67 SF
AC PAD = 9 SF
PROPOSED IMPERVIOUS = 3,105 SF
PERCENT IMPERVIOUS = 19.3%
MAX IMPERVIOUS ALLOWED = 4,500 SF

BUILDING SETBACKS (PER REC. PLAT)
FRONT - 25'
REAR - 20'
SIDE - 10'
CORNER SIDE - 20'

BM 2025PG. 485-488



LOT 1 INFORMATION:

16 FELLOW DRIVE
PIN: 0680-09-4730.000
REFERENCE: DB. 4301, PG. 293
TOTAL LOT AREA = 0.366 AC = 15,945 SF
PARKING AREA = 3,196 SF
PROPOSED IMPERVIOUS = 3,196 SF
PERCENT IMPERVIOUS = 20.04%
MAX IMPERVIOUS ALLOWED = 4,500 SF

NOTES:

INSET SCALE: 1"=20'

1. THIS SURVEY WAS PREPARED BY BATEMAN CIVIL SURVEY CO., UNDER THE SUPERVISION OF SONYA A. WARD, PLS.
2. THIS PLAN HAS BEEN PREPARED FOR LAYOUT AND PERMITTING PURPOSES ONLY.
3. PROPERTY LINES SHOWN WERE TAKEN FROM EXISTING FIELD EVIDENCE, EXISTING DEEDS AND PLATS OF PUBLIC RECORD, AND INFORMATION SUPPLIED TO THE SURVEYOR BY THE CLIENT.
4. ALL DISTANCES ARE HORIZONTAL GROUND DISTANCES AND ALL BEARINGS ARE NORTH CAROLINA STATE PLANE COORDINATE SYSTEM UNLESS OTHERWISE SHOWN.
5. THIS MAP IS NOT FOR RECORDATION AND SHOULD BE REVIEWED BY A LOCAL GOVERNMENT AGENCY FOR COMPLIANCE WITH ANY APPLICABLE LAND DEVELOPMENT REGULATIONS.
6. THE BASIS OF NORTH AND ALL EASEMENTS, RIGHTS-OF-WAYS, BUFFERS,SETBACKS AND ADJOINERS, ETC. REFERENCED IN TITLE BLOCK.
7. NO INVESTIGATION INTO THE EXISTENCE OF JURISDICTIONAL WETLANDS, FLOOD ZONES OR RIPARIAN BUFFERS PERFORMED BY THIS FIRM. ALL LINES SHOWN, IF ANY, ARE SCALED FROM THE RECORDED PLAT.
8. SURVEYOR HAS MADE NO INVESTIGATION OR INDEPENDENT SEARCH FOR EASEMENTS OF RECORD, ENCUMBRANCES, RESTRICTIVE COVENANTS, OWNERSHIP TITLE EVIDENCE OR ANY OTHER FACTS THAT AN ACCURATE AND CURRENT TITLE SEARCH MAY DISCLOSE.
9. ZONING: RA-30
10. BUILDER/DEVELOPER: DAVIDSON HOMES
1903 NORTH HARRISON AVE
CARY, NC 27513

CURVE TABLE				
CURVE	RADIUS	LENGTH	CHORD DIRECTION	CHORD
C53	25.00'	39.27'	S46°04'26"W	35.36'
C20	25.00'	39.27'	N43°55'34"W	35.36'
C19	19.50'	0.80'	S89°53'50"W	0.80'

0 25 50
SCALE:
1" = 50 ft.

Bateman Civil Survey Company
Engineers • Surveyors • Planners
2524 Reliance Avenue, Apex, NC 27539 Ph: 919.577.1080 Fax: 919.577.1081
www.batemancivilsurvey.com info@batemancivilsurvey.com
NCBELS Firm No. C-2378



VICINITY MAP
(Not to Scale)

LEGEND

PO = COV. FRONT PORCH/PATIO
CP = COV. REAR PORCH/PATIO
WD = WOOD DECK
SW = SIDEWALK
DW = CONCRETE DRIVEWAY
SP = SCREENED PORCH/PATIO
P = CONCRETE PATIO
⊗ = COMPUTED POINT
○ = IRON PIPE FOUND (IPF)
◉ = IRON PIPE SET (IPS)
● = SCRIBE FOUND/SET (SS)
WM = WATER METER
CO = CLEAN OUT
AC = AIR CONDITIONER PAD
© = CABLE PEDESTAL
Ⓢ = SEWER MANHOLE
T = TELEPHONE PEDESTAL
CB = CATCH BASIN/CURB INLET
☼ = LIGHT POLE
HH = HAND HOLE/UTILITY VAULT
EB = ELECTRIC BOX/TRNSFRMR
= FIRE HYDRANT
DI = DRAIN INLET/YARD INLET
G = GAS METER
E = ELECTRIC METER
R/W = RIGHT OF WAY
P/L = PROPERTY LINE

I, SONYA A. WARD, CERTIFY THAT THIS PLAT WAS DRAWN UNDER MY DIRECT SUPERVISION FROM A SURVEY MADE UNDER MY SUPERVISION (PLAT BOOK REFERENCED IN TITLE BLOCK); THAT THE BOUNDARIES NOT SURVEYED ARE CLEARLY INDICATED AS DRAWN FROM INFORMATION LISTED UNDER REFERENCES; THAT THE RATIO OF PRECISION AS CALCULATED IS 1:10,000+; AND THAT THIS MAP MEETS THE REQUIREMENTS OF THE STANDARD OF PRACTICE FOR LAND SURVEYING IN NORTH CAROLINA. L-4017
DATED:

PRELIMINARY

This map is of an existing parcel of land and is only intended for the parties and purposes shown. This map not for recordation. No title report provided.

BUILDER TO VERIFY HOUSE LOCATION
DIMENSIONS AND REVIEW TOTAL
IMPERVIOUS NOTED ON THIS PLOT PLAN

PRELIMINARY PLOT PLAN
FOR
DAVIDSON HOMES

RETREAT AT NORTH MAIN - LOT 1,56
FELLOW DRIVE, LILLINGTON, NC
NEILLS CREEK TOWNSHIP, HARNETT COUNTY

DATE: 3/26/26 DRAWN BY: AHB CHECKED BY: SAW

REFERENCE: BM 2025 PG. 485-488 BCS# 250999 SCALE: 1" = 50'

P:\2025 Projects\250999 Retreat at North Main-HLWLS\dwg\250999 Retreat at North Main.dwg, 3/27/2026 12:00:28 AM, Foxit Reader PDF Printer