



- B1** 6" minimum compacted base - clean, crushed stone approximately 1" in size (AASHTO M43 Size #57 or similar) free of debris and fines.
- BL** Backfill evenly around the interceptor and risers with clean, crushed stone approximately 1" in size (AASHTO M43 Size #57 or similar) free of debris and fines.
- CL** Pedestrian rated poly cover
- FT** Floor Tile
- IN** 4" diameter inlet pipe
- OT** 4" diameter outlet pipe
- PA** Minimum 4" thick concrete pad with rebar required for pedestrian traffic or greenspace areas. Concrete to be 28 day compressive strength to 4,000 PSI.
- RI** FCR1 field cut riser to grade
- SC** 12" clear all sides

**DETAIL** Scooter's - Erwin, NC (2946)

Indoors, Below Grade

**GB2** GREASE INTERCEPTOR 35 GPM, 4" FPT CONNECTIONS W/ 3" PLAIN END ADAPTERS, PEDESTRIAN RATED POLYPROPYLENE COVER

*Disclaimer: this Detail represents manufacturer directed guidance regarding the grease interceptor system. The contents of this document are not a substitute for local jurisdiction requirements and plumbing code standards. Please follow all local ordinances when installing.*



**SCHIER**

LIFETIME GUARANTEED  
GREASE INTERCEPTORS

[schierproducts.com](http://schierproducts.com)