

MATCH INTERIOR
T.O. SUBFLOOR

VARIES
3" MIN.

12" MINIMUM

12"
MINIMUM

2" MIN. PERIMETER
SLAB INSULATION

PTD. FIBER CEMENT
SIDING ON HOUSE WRAP
ON 1/2" WOOD SHEATHING

2x6 WALL FRAMING
(NOT LOAD-BEARING)
W/ R-19 MIN BATT
INSULATION

1/2" Φ MIN. ANCHOR
BOLTS @ 6" O.C. MAX.

REINFORCED CONCRETE
FOOTING W/ (2) #5
REBAR

3" MIN. 6" 3" MIN.
3" MIN.

12"
MINIMUM



CONSTRUCTION CLARIFICATION #1

2" = 1'-0"

AFREYA'S PLAYGROUND DAY CARE

12082 NC HWY 42

FUQUAY VARINA, NC 27526



SHEET 1 OF 1

08.04.2026

