

07/16/2026



NKS Contracting LLC
390 Bumpas Creek Access
Dunn, NC 28334

GC# 99934
Phone: (919) 701-6504

Company Representative
Nick Skatell
Phone: (919) 701-6504
nkscontracting@gmail.com

Christina Maedge
1054 North Carolina 24
Cameron, NC 28326-6953
(201) 424-0832

Job: Christina Maedge

Roofing Section

- Remove existing shingles down to the roof decking.
- Remove and reset standing seam metal trim as necessary.
- Install new drip edge at eaves only.
- Install ice and water shield.
- Install synthetic underlayment over the roof decking.
- Install Owens Corning Starter Strip Shingles along all gutter lines and rake edges.
- Install Owens Corning TruDefinition Duration Limited Lifetime architectural shingles per specifications using 1 ¼" roofing nails.
- Install Owens Corning ProEdge Hip & Ridge Shingles.
- Install new ridge vent.
- Install new pipe boots and flashings where needed.
- Clean up and haul off all job related debris.
- Provide 3 yr workmanship warranty and Owens Corning Preferred Manufacturer Warranty.
- Our Crews are licensed and insured.
- Crews will maintain safety requirement at all times during the construction process.

PLEASE NOTE: For roofs with multiple layers of shingles, there is a \$35/square charge for each additional layer (includes cost of labor and debris haul off)

- Due to the steadily increasing price of materials, this estimate is only good for 30 days.

* For retail jobs, 50% is due to schedule and 50% upon completion. Insurance jobs-deductibles are due upon completion.

SPECIAL NOTES: Remove and replace all decking with 19/32 (5/8") decking; Need 10LF of black trim coil and brake; Siding issues on parapet wall as well as coping cap issues-remove and replace board and batten siding, and seal coping cap with brown JTS1; Paint siding to match-replace with PVC on board and batten. Friday-Saturday install only. Remove/Reset gutters as needed

**Rotted or broken fascia, rafters, or siding that must be replaced to ensure a waterproof system will incur additional charges between \$50-125 per piece based on size, quantity, painting, complexity, etc. Discussions with the homeowner will take place immediately upon discovery.


**Permit fees will be added to final invoice.

	Qty	Unit
Materials		
Owens Corning TruDefinition Duration AR (3 BD/SQ) - Desert Rose	54.00	SQ
Owens Corning Starter Strip Plus - 7 3/4" (105')	3.00	BD
Owens Corning ProEdge AR (33') - Desert Rose	3.00	BD
Interwrap Rhinorooft UDL Synthetic Underlayment (10 SQ)	6.00	RL
Owens Corning RhinoRoof Granulated Ice & Water Shield (2 Sq)	2.00	RL
ACM Aluminum Drip Edge - .019 - F5 - 1 1/2" (10') - Royal Brown	28.00	PC
Lomanco 750 Aluminum Slant Back Static Roof Vent	1.00	EA
Plastic Cap Nails - 1" (3000 Cnt)	2.00	BX
Roofing Coil Nails - 1 1/4" (7200 Cnt)	3.00	BX
7/16"x4"x8' OSB	169.00	BRD
Owens Corning VentSure Rigid Strip - 11 3/4" (4')	20.00	PC
ACM Painted Aluminum Trim Coil - 14"x50' - Black/Royal Brown	1.00	RL

ACM Aluminum Prebent Step Flashing - 3"x4"x7" (50 PC/BD)	1.00	BD
Neverleak Aluminum Base Pipe Flashing - 3"-4"	2.00	EA
Labor		
Tear off and Install Architectural Shingles - Walkable	54.00	SQ
Owens Corning Preferred Warranty	1.00	EA
		--


TOTAL	\$37,625.00
-------	-------------

Starting at **\$347/month** with  **Acorn** FINANCE • [APPLY](#)

DocuSigned by:

40C4931D7FC44EE...

7/16/2026

Date

Company Authorized Signature
DocuSigned by:

52D143219342402...

7/16/2026

Date

Customer Signature

Customer Signature

Date