Harnett COUNTY NORTH CAROLINA

HARNETT COUNTY ENVIROMENTAL HEALTH

File/Permit #: BCOM2608-0003, -0004, -0005, -0006

CDP #: _____

IMPROVEMENT PERMIT (IP)

■ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: Purdue Drive Investments Applicant: JCH Architecture

Property Location: 790, 792, 794, 796, 780 NC 24-87 PIN/Lot Identifier: 9586-50-1195

Subdivision: _____ Lot #: _____ Block: _____ Section: _____

Facility Type: Medical Facility Number of bedrooms: _____ Number of Occupants: _____ Other: 30 staff + patients

Design Daily Flow: 520 GPD LTAR (Initial): .6 gpd/ft² LTAR (Repair): .6 gpd/ft²

Wastewater System Type: 50% Reduction (Initial)

Pump Required: ☐ Yes ☐ No ■ May be required Usable Depth to Limiting Condition (Initial): 48"

Wastewater System Type 50% Reduction (Repair)

Pump Required: ☐ Yes ☐ No ■ May be required Usable Depth to Limiting Condition (Repair): 48"

Effluent Standard: ■ DSE ☐ HSE ☐ Other:_____ Type of Water Supply: ☐ Private well ■ Municipal Supply ☐ Other:_____

Permit conditions:

The issuance of this permit in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. *This permit is subject to revocation if the site plan, plat, or the intended use changes.* The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of 15A NCAC 18E and to the conditions of this permit.

Authorized Agent's Printed Name: Timothy Goike REHSI Date: 10/22/2026

Authorized Agent's Signature: Timothy Goike REHSI Expiration Date: 10/22/2031

CONSTRUCTION AUTHORIZATION (CA)

■ New ☐ Expansion ☐ Repair ☐ System Relocation ☐ Change of Use

Owner: Purdue Drive Investments Applicant: JCH Achitecture

Property Location: 790, 792, 794, 796, 780 NC 24-87 PIN/Lot Identifier: 9586-50-1195

Subdivision: _____ Lot #: _____ Block: _____ Section: _____

Facility Type: Medical Facility Number of bedrooms: _____ Number of Occupants: _____ Other: 30 staff + patients

Design Daily Flow: 520 GPD LTAR: .6 gpd/ft²

Effluent Standard: ■ DSE ☐ HSE ☐ Other:_____ Type of Water Supply: ☐ Private well ■ Municipal Supply ☐ Other:_____

Installation Requirements/Conditions

Wastewater System Type: 50% Reduction Pump Required: ☐ Yes ☐ No ■ May be required

Septic Tank Size: 1250 gallons Total Trench Length: 150 feet Trench Spacing: 8 feet on center

Pump Tank Size: 1250 gallons Maximum Trench Depth: 32 inches Soil Cover: 6 inches

Trench Width: 36 inches Distribution Method: ■ Serial ■ D-Box or Parallel ☐ Pressure Manifold ☐ Other: _____

Artificial Drainage Required: Yes ☐ No ■ If yes, please specify details: _____

Management Entity Required: ☐ Yes ■ No Minimum O&M Requirements: _____

Permit conditions:

Do not cut or grade septic area. MUST MEET ON SITE PRIOR TO INSTILLATION TO VERIFY FINAL LAYOUT. Space near building to be provided for non-traffic rated tanks. Gravity may be achieved if plumbing stub out is high enough and supply line is within maximum fall.

The requirements of 15A NCAC 18E are incorporated by reference into this permit and shall be met. Systems shall be installed in accordance with the attached site sketch. *This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes.* The Construction Authorization shall not be affected by a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of 15A NCAC 18E, or 15A NCAC 18A .1900, as applicable, and to the conditions of this permit.

Authorized Agent's Printed Name: Timothy Goike REHSI Date: 10/22/26

Authorized Agent's Signature: Timothy Goike REHSI Expiration Date: 10/22/2031

Owner/Legal Representative Signature: _____ Date: _____

***See attached site sketch**

Harnett County Environmental Health

SITE SKETCH

PIN 9585-50-1195 Permit Number BCOM2608-0003, -0004, -0005, -0006

JCH Architecture
Applicant's Name

Subdivision/Section/Lot Number

Timothy Goike REHSI
Authorized State Agent

10/22/2026
Date

System components represent approximate contours only. The contractor must flag the system prior to beginning the installation to ensure that the proper grade is maintained.

Scale = NTS

*No part of septic lines may be under asphalt parking lot.

*MEET ON SITE PRIOR TO INSTALL

