



ENGINEERS
PLANNERS
CONSULTANTS

305 NORTH OAKLAND AVENUE · P.O. BOX 490 · NAPPANEE, INDIANA 46550PHONE: 574-773-7975
WEB: WWW.NTAINC.COM

FAX: 574-773-2732

June 13, 2019

Mr. Mike Hamm, P.E.
State of North Carolina
Department of Insurance
Manufactured Building Division
322 Chapanoke RD.
Suite 200
Raleigh, NC 27603

RE: Clayton Homes #958

Model: SN251077-NC

Dear Mr. Hamm,

Enclosed, you will find one (1) copy of the above mentioned project for your files.


Should you have any questions or comments, please contact me at your earliest convenience.

Sincerely,

David Richter

David Richter
Account Manager

Enclosures



CMH

Manufacturing, Inc.
engineering department - modular

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

Date:
6/7/2019

TYPE : MODULAR

MODEL PLAN INDEX

Model #	SN251077	State
Manufacturer	CMH Manufacturing, Inc.	NC
Brand Name	CLAYTON	
Unit Size	29'-8" x76'-0"	
Description	4 BEDROOM / 2 BATH	

Category	Document Description	Page or Sheet #
Index	<i>Model Plan Index</i>	IX-1
Technical Sheet	<i>Light & Vent</i>	TS-1
Technical Sheet	<i>Energy Compliance</i>	Prescriptive
Technical Sheet	<i>Heat Loss Calc</i>	ATTACHED
Technical Sheet	<i>HVAC System Calc</i>	ATTACHED
Technical Sheet	<i>Electrical Load Calc</i>	TS-5
Model Plan	<i>Cover Sheet</i>	1-0
Model Plan	<i>Cross Section / Fastening Schedule</i>	1-0.2
Model Plan	<i>Master Plan</i>	1-1
Model Plan	<i>HVAC Layout</i>	4-4
Model Plan	<i>DWV Plumbing Schematic</i>	8-1
Model Plan	<i>Supply Plumbing</i>	9-1
Model Plan	<i>Electrical Plan</i>	11-1
Model Plan	<i>Exterior Elevations - Front & Right</i>	20-1
Model Plan	<i>Exterior Elevations - Rear & Left</i>	20-2
Model Plan	<i>OFF Frame Foundation</i>	21-30PSF
Technical Sheet	<i>OFF-Frame Foundation Package</i>	ATTACHED
Model Plan	<i>Dryer Installation Details</i>	4-1
Model Plan	<i>Electrical Legend</i>	TS-6
Technical Sheet	<i>Electric Furnace Chart</i>	PLN-1.5
Technical Sheet	<i>Plumbing Plan</i>	PLN-1.8
Technical Sheet	<i>Trusses</i>	ATTACHED
SEE APPROVED MODULAR MANUAL FOR ;		
1. SECTIONS		2. TYPICAL DETAILS
3. REQUIRED CONSTRUCTION METHODS		4. MATERIALS

CMH

Manufacturing, Inc.
engineering department - modular

REVISIONS		
DATE :	REVISION BY :	GCK
June 7, 2019	REVISION DATE :	

TECHNICAL SHEET FOR LIGHT / VENT DATA

MODEL NUMBER	SN251077
SIZE OF UNIT	29'-8" x76'-0"
WINDOW SQ. FTG. STD.	195.62
WINDOW SQ. FTG. W/ OPT.	
FIGURED FOR :	CLAYTON WINDOWS
PERCENTAGE OF LIGHT REQ'D.	8%
PERCENTAGE OF VENT REQ'D.	4%

Room	Area	Square Footage		Required		Percentage of		Artificial Light	Artificial Vent
		Installed	Vent	Light	Vent	Installed	Vent		
LIVING ROOM	257.0	24.4	12.4	20.6	10.3	9.5%	4.8%		
MASTER BEDROOM	236.9	24.4	12.4	19.0	9.5	10.3%	5.2%		
BEDROOM 2	149.1	12.2	6.2	11.9	6.0	8.2%	4.2%		
BEDROOM 3	152.6	12.2	6.2	12.2	6.1	8.0%	4.1%		
BEDROOM 4	142.3	12.2	6.2	11.4	5.7	8.6%	4.4%		
DINING ROOM	119.7	21.2	17.3	9.6	4.8	17.7%	14.5%		
FAMILY ROOM	245.8	24.4	12.4	19.7	9.8	9.9%	5.0%		
KITCHEN	187.4	10.1	2.2	15.0	7.5	5.4%	1.2%	YES	YES

APPROVED BY

NIA 6/13/2019
INC.

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

APPLICATION ENGINEERING FOR HEATING AND COOLING

CMH Mfg., Inc.
2225 South Holden Road
Richfield, NC 27417-0386

Manufacturer's Model #: SN251077-4710
HVAC System Type: INFLOOR STRAIGHT ALUM. WITH PER REG - **CMH DESIGN** -

Prepared By LaSalle Air Systems 6/11/2019 (Method & Output © 2019)
All rights reserved: this information proprietary to LaSalle Bristol Co. and CMH Mfg., Inc.

Calculations on this page are based on design standards set forth in ASHRAE and ACCA Manuals J Rev 8.2 and D Rev 1.1. System registers are located for best distribution based on Manual T. Design calculations are based on worst case orientation. Room loads may vary based on actual conditions.

ENTIRE HOUSE VALUES - DESIGN ZONE: NC, Region 4 NCECC (2018)/IECC (2015NC) 36N Latitude

COOLING LOAD: 37,455 Btuh for Outside Temp/Humidity of 92 ° F (33 C)/ 48% and Inside reduced to 75 ° F (23 C)/ 50%

HEATING LOAD: 41,792 Btuh based on outside temp of 16 ° F (-9 C) with inside temp raised to 72 ° F (22 C)

Crawlspace is not heated by the primary air handler.

Actual UA = 362.4 Max UA (Table R402.1.2) = 384.4

Use net wall area, not gross wall

CONSTRUCTION DETAILS & U / SHGC VALUES: (22+Non-ins Rim - 15 - 38)

Total Cond. Floor Area:	2254.67 s.f.	TRUE Outside Perimeter:	211.33 ft		
Level 1 Ceiling:	108 to 108 in.	Level 2 Ceiling:	0 to 0 in.	Level 3 Ceiling:	0 to 0 in.
Primary Wall Area:	1637.08 s.f. (Net)	Dark Roof(U):	0.027	FLOOR DUCTS (U):	0.0444 Duct TEL
Secondary Wall Area:	0.00 s.f. (Net)	Prim Wall (U):	0.070	ATTIC DUCTS (U):	0.125 452.8 ft
TOTAL Low-E window	184.43 s.f.	Sec Wall (U):	0.035	EXT. DUCTS (U):	0.125
TOTAL Atrium	42.71 s.f.	Exp Floor(U):	0.044	INFLOOR DUCT AREA:	414.83 S.F. @ 51.2 TD/ 26.6 TD
TOTAL Glass Block	0.00 s.f.	Low-E wii	0.350 / 0.28	ATTIC DUCT AREA:	144.73 S.F.(return) @ 96 TD/ 88.2 TD
TOTAL Skylite	0.00 s.f.	Atrium	0.420 / 0.29	EXT. DUCT AREA:	213.63 S.F. @ 96 TD/ 45 TD
TOTAL Door1 Area:	37.78 s.f.	Glass Blc	0.510 / 0.48	PEOPLE:	5 4119.7 Btuh Total Appliances
TOTAL Door2 Area:	0.00 s.f.	Skylite	0.460 / 0.75	FIREPLACES:	0
All Glass % of Floor:	10.07 %	Door 1:	0.140	DUCT GAIN: @ Semi-Tight	4513 Btuh
All Glass % of Wall:	11.94 %	Door 2:	0.670	DUCT LOSS:	10228 Btuh
LATENT GAIN:	8659 Btuh			Summer Infiltr (7.5 mph):	39.4 cfm
Mech. Ventilation :	118.02 c(55.7 L/s)	Altitude:	1000 ft	Winter Infiltration (15 mph):	74.4 cfm @ Semi-Tight

ROOM BY ROOM VALUES:

Heat Exiting Furnace: 102 deg A/C Exiting : 48 deg
NOTICE: Due to glass area variations, the hourly cooling loads may not be balanced by a single-zone system

1086.3 FPM, max velocity in trunk #: 6
0.31 Max pressure at A/H

ROOM NAME	HEATING LOSS (Btu)	COOLING GAIN (Btu)	CFM DIST	Cooling Air Values for 3.5 ton unit		Heating Air Values for 50 90 % Gas/Oil		15.0 KW Elec	Maximum A/C capacity Calibrated Blower Test Btuh (alt adj)
				CFM	Btuh	CFM	Btuh E		
M. Bath c	3,977	3,169	110	96	2,883	90	3,006	3,419	2,939
Kitchen c	3,042	2,774	96	95	2,841	89	2,963	3,370	2,896
Dining Room c	3,150	3,705	127	92	2,763	87	2,882	3,278	2,817
Family Room A c	4,565	4,161	133	152	4,551	143	4,747	5,399	4,638
Bath #2 h	2,821	2,272	75	121	3,618	113	3,774	4,292	3,685
Utility c	3,658	3,280	113	96	2,866	90	2,990	3,400	2,922
Bedroom #2 h	4,699	3,770	124	191	5,700	179	5,945	6,761	5,811
Bedroom #3 c	2,935	2,636	92	95	2,827	89	2,948	3,353	2,882
Bedroom #4 c	2,705	2,445	85	88	2,620	82	2,733	3,108	2,639
Living Room c	4,949	4,538	145	181	5,407	169	5,640	6,414	5,447
M. Bedroom c	5,290	4,704	151	185	5,516	173	5,753	6,543	5,556
TOTALS	41,792	37,455	1,250	1,392	41,592	1,304	43,380	49,338	42,232

APPROVED BY

NIA 6/13/2019
INC.

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

APPLICATION ENGINEERING DUCT AIR FLOW AND SIZING WORKSHEET (MANUAL D)

Manufacturer: **CMH Mfg., Inc.**
2225 South Holden Road
Richfield, NC 27417-0386

Model #: **SN251077-4710**
HVAC System Type: **INFLOOR STRAIGHT ALUM. WITH PER REG - CMH DESIGN -**
Design Zone: **NC, Region 4 NCECC (2018)/IECC (2015NC)**

Prepared by **LaSalle Air Systems** 6/11/2019 All rights reserved. This information proprietary to **LaSalle Bristol Co. and CMH Mfg., Inc.**
Calculations include factors for duct air temperature change and pressure drops through ducts. All joints are tightly fitted or sealed.

Blower CFM		1439 @		0.7 E.S.P.		TEL= 488,8774		FR= 0.0798		(A/C Coil included)		User Input				
						Altitude = 1,000 ft								Final	Final	
BRANCH DUCT LISTING ANALYSIS																
BR #	Trunk #	Metal (ft)	F. G. (ft)	Flex (ft)	Bends/Fittings(ft)	Total Eq. Length	Heat Btuh	Cool Btuh	Elec Heat cfm	(Altitude Adj.) Cool cfm	Design cfm	Round Size	Rectangle Size (i.d.) x (i.d.)	Round Size	Final Velocity fpm	
1	Family Room A	4	43	0	38	356.8	437.8	1,704	1,553	58	51	58	5.65		5.0	426.2
2	Dining Room	4	43	0	38	346.8	427.8	3,150	3,705	107	121	121	7.47		6.0	615.7
3	Kitchen	4	43	0	36	336.2	415.2	3,042	2,774	104	91	104	7.01		6.0	528.4
4	M. Bath	4	43	0	39	327.1	409.1	3,977	3,169	136	103	136	7.68		6.0	690.9
5	Family Room A	5	18	0	38	357.5	413.5	2,861	2,608	98	85	98	6.81		6.0	497.0
6	Bath #2	5	18	0	38	347.5	403.5	1,430	1,151	49	38	49	5.15		5.0	357.6
7	Bath #2	5	18	0	38	358.9	414.9	1,391	1,121	47	37	47	5.15		5.0	348.0
8	Utility	5	18	0	43	350.4	411.4	3,658	3,280	125	107	125	7.45		6.0	635.4
9	Bedroom #4	6	43	0	42	367.8	452.8	2,705	2,445	92	80	92	6.90		6.0	469.9
10	Living Room	6	43	0	42	357.8	442.8	2,448	2,245	84	73	84	6.55		6.0	425.3
11	Living Room	6	43	0	42	347.8	432.8	2,501	2,293	85	75	85	6.55		6.0	434.4
12	M. Bedroom	6	43	0	42	337.8	422.8	2,676	2,380	91	78	91	6.68		6.0	464.8
13	M. Bedroom	6	43	0	43	348	434.0	2,615	2,325	89	76	89	6.68		6.0	454.2
14	Bedroom #3	7	27	0	42	348.2	417.2	2,935	2,636	100	86	100	6.92		6.0	509.9
15	Bedroom #2	7	27	0	42	338.2	407.2	2,386	1,915	81	62	81	6.27		6.0	414.5
16	Bedroom #2	7	27	0	44	349.5	420.5	2,312	1,856	79	61	79	6.28		6.0	401.7
N/A	Other Rooms															
							41,792	37,455	1,425	1,222	1,439					

APPROVED BY
NIA INC. 6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

TRUNK DUCT LISTING ANALYSIS															
TRUNK #															
TRUNK # 1	17			55	72.0	41,792	37,455			1439	13.36	12	14	14.2	1233.3
TRUNK # 2			32	199.966	232.0	21,213	19,361			737	12.22			12.0	938.4
TRUNK # 3			36	201.166	237.2	20,579	18,094			702	12.07			12.0	893.7
TRUNK # 4	43			231.966	275.0	11,873	11,201			418	10.30	5	14	8.9	860.7
TRUNK # 5	18			231.966	250.0	9,340	8,160			319	9.08	5	14	8.9	655.3
TRUNK # 6	43			237.166	280.2	12,945	11,688			442	10.55	5	14	8.9	908.2
TRUNK # 7	27			237.166	264.2	7,634	6,407			260	8.51	5	14	8.9	535.7
TRUNK # 8										0		0	0		
TRUNK # 9										0		0	0		
TRUNK # 10										0		0	0		
TRUNK # 11										0		0	0		
TRUNK # 12										0		0	0		
TRUNK # 13										0		0	0		
TRUNK # 14			56							0					
TRUNK # 15			16							0					
LONGEST RETURN DUCT			16	20	36					1439	12.87	18	24	22.7	479.6

APPLICATION ENGINEERING EQUIPMENT SELECTION AND SIZING WORKSHEET (MANUAL S)

Manufacturer: **CMH Mfg., Inc.**
2225 South Holden Road
Richfield, NC 27417-0386

Model #: **SN251077-4710**
HVAC System Type: **INFLOOR STRAIGHT ALUM. WITH PER REG - CMH DESIGN -**
Design Zone: **NC, Region 4 NCECC (2018)/IECC (2015NC)**

Prepared by LaSalle Air Systems 6/11/2019 All rights reserved. This information proprietary to LaSalle Bristol Co. and CMH Mfg., Inc.

RESULTS FROM MANUAL-J CALCULATIONS: Worst Case Orientation

HEATING LOAD:	41,792 Btuh at 16 °	REQ'D BLOWER CFM:	1,392 cfm at altitude of 1,000 ft
SENSIBLE CLG LOAD:	28,796 Btuh at 92 °	Entering Air DRY Bulb:	76.4 ° Mech. Ventilation : 118
LATENT CLG LOAD:	8,659 Btuh at 92 °	Entering Air WET Bulb:	61.3 ° Entering Air RH: 53 %
GRAINS DIFFERENCE:	46	Outside wet bulb:	72.0 ° outside RH: 48.2 %

FILL IN BLANKS IN EACH SECTION FROM THE H.V.A.C. EQUIPMENT DATA CHARTS: (Do not use ARI Ratings!)

Air handler model #: _____ Condenser model #: _____

Blower Data Select blower speed in COOLING mode: _____
Blower CFM is between 1223 > _____ < 1655 for Total (External) Static Pressure between 0.6 > _____ < 0.8

Electric, Gas or Oil Furnace Select blower speed in HEATING mode: _____ Output Btuh is between 43882 > _____ < 58509
Blower CFM is between 757 > _____ < 895 for Temp. rise of 55-65
Blower CFM is between 895 > _____ < 1094 for Temp. rise of 45-55
Blower CFM is between 1094 > _____ < 1407 for Temp. rise of 35-45

Cooling Equipment S/T Ratio = 0.76 Leaving Temp = 49.8 ° TD = 25.2 °
At 92F outside, Total A/C output from 38204 btuh _____ to 43073 btuh is GOOD.
At 92F outside, Total A/C output from 43073 btuh _____ to 44946 btuh is MARGINAL.

Sensible Capacity is from 24466 btuh _____ to 33125 btuh
Latent Capacity is from 8485 btuh _____ to 12988 btuh

Mechanical Ventilation is 8.2 % of blower cfm. Dry bulb increases by: 1.3 ° Wet bulb increases by: 0.8 °


Heat Pump with Supplemental Heating Coils
Data from performance charts

_____ btuh at _____ F outside
_____ btuh at _____ F outside

Data from load calculation

0 btuh at 72 F outside
41,792 btuh at 16 F outside

APPROVED BY
NIA INC. 6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter



At winter design temperature of 16 F outside, the distance between the lines is _____ btuh
which is the Supplemental Heat divided by 3400 = _____ KW.

APPLICATION ENGINEERING INTERNATIONAL MECHANICAL CODE - Chapter 4 Ventilation Worksheet

Manufacturer: **CMH Mfg., Inc.**
2225 South Holden Road
Richfield, NC 27417-0386

Model #: **SN251077-4710**
HVAC System Type: **INFLOOR STRAIGHT ALUM. WITH PER REG - CMH DESIGN**
Design Zone: **NC, Region 4 NCECC (2018)/IECC (2015NC)**

Prepared by *LaSalle Air Systems* 6/11/2019 All rights reserved. This information proprietary to *LaSalle Bristol Co. and CMH Mfg., Inc.*

RESULTS FROM MANUAL-J CALCULATIONS: Worst Case Orientation

HEATING LOAD:	41,792 Btuh at 16 °	REQ'D BLOWER CFM:	1,392 cfm at altitude of 1000 ft
SENSIBLE CLG LOAD:	28,796 Btuh at 92 °	Entering Air DRY Bulb:	76.4 ° Mech. Ventilation : 118
LATENT CLG LOAD:	8,659 Btuh at 92 °	Entering Air WET Bulb:	61.3 ° Entering Air RH: 53 %
GRAINS DIFFERENCE:	46	Outside wet bulb:	72.0 ° outside RH: 48 %

Natural or Mechanical: Test the infiltration at 50 Pa should result in 596.8 CFM infiltration being 1.765 ACH (to be confirmed by testing)

(5 ACH = 1691 CFM) (3 ACH = 1014 CFM)

Mechanical ventilation is required

To Meet Natural Ventilation: Increase Openable Area by 183 %

ROOM NAME	Room Area	Openable Area		ROOM NAME	Room Area	Openable Area	
		Required	Built			Require	Built
M. Bath	246.0	9.8	3.92	Living Room	274.4	10.9	15.00
Kitchen	197.8	7.9	7.05	M. Bedroom	255.9	10.2	15.00
Dining Room	131.0	5.2	21.35		0.0	0.0	0.00
Family Room A	264.5	10.5	15.00		0.0	0.0	0.00
Bath #2	124.8	4.9	6.25		0.0	0.0	0.00
Utility	163.2	6.5	7.50		0.0	0.0	0.00
Bedroom #2	215.1	8.6	7.50		0.0	0.0	0.00
Bedroom #3	216.3	8.6	7.50		0.0	0.0	0.00
Bedroom #4	165.6	6.6	7.50		0.0	0.0	0.00
TOTAL					2254.7	89.7	113.57

Mechanical Ventilation Is Required In These Areas To Meet IMC 2012/2015 Per Table 403.3.1.1:

SPACE CLASSIFICATIONS	Occupancy	Area	Outdoor Exhaust		ZONE AIR DISTRIBUTION	Air
			Air	Air		Flow
Private Living Area	5.1	1686.1	118.0	0.0	Floor Supply of Warm Air/Floor Return	1079
Private Kitchen	0.0	197.8	0.0	25.0	Floor Supply of Warm Air/Floor Return	95.09
Private Baths	0.0	370.8	0.0	100.0	Floor Supply of Warm Air/Floor Return	217.6
	0.0	0.0	0.0	0.0		0
	0.0	0.0	0.0	0.0		0
	0.0	0.0	0.0	0.0		0
Total	5.1	2,254.7	118.0	125.0		1,392

System Ventilation Efficiency:

APPROVED BY

6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

ELECTRICAL FEEDER CALCULATION

CMH	PAGE:	1 of 1
Manufacturing, Inc.	DATE:	12-Jun-19
engineering department - modular	BY:	GCK

MODEL NO.	SN251077	
		Per NEC 220-30

1. LIGHTING LOAD:					
1st floor			2nd floor		
length =	76.00	FT.	length =	0.00	FT.
width =	29.67	FT.	width =	0.00	FT.
Total area =	2254	SQ. FT.	Minimum number of 15 Amp circuits =	4	
X	3	VA			
TOTAL	6762	VA			

2. SMALL APPLIANCE LOAD:			3. LAUNDRY LOAD:		
Number of circuits	3		Number of circuits	1	
X	1500	VA	X	1500	VA
TOTAL	4500	VA	TOTAL	1500	VA

4. APPLIANCE LOAD:		
Electric Range =	12100	VA
Electric Water Heater =	5000	VA
Electric Clothes Dryer =	5600	VA
Cooktop =	0	VA
Wall Oven =	0	VA
Freezer =	1200	VA
Dishwasher & Disposal =	2376	VA
Gas furnace motor =	0	VA
Micro-wave oven	1200	VA

5. TOTAL OF OTHER LOADS (1, 2 & 3)		
	LEG A	
Lighting load =	6762	
Small appliance load =	4500	
Laundry =	1500	
Appliance load =	27476	
Sub-Total =	40238	
10000 VA @ 100% =	10000	
Remainder @ 40% =	12095	
Total =	22095	VA
	92.06	AMPS

6. HVAC LOAD:		
Lineal feet of baseboard heaters =	0	
Number of baseboard heater circuits =	0	
Total baseboard heater load =	0.0	Amps
Use 65% w/ less than 4 or 40% w/ 4 or more circuits (*)		
Electric furnace @ 65% (*)		
Circuit 1 =	60 Amps	39.00 Amps
Circuit 2 =	30 Amps	19.50 Amps
Air conditioner (*)		Amps
Total HVAC load (*- Use largest of these only) =	58.50	Amps

7. TOTAL OF ALL LOADS =	150.56	Amps
--------------------------------	---------------	-------------

APPROVED BY

 6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
 David Richter

FURN SIZE
15KW

DOOR AND WINDOW SCHEDULE

NOTE: FLOOR PLAN WINDOW SIZES WITH AN "SG" DESIGNATION REPRESENTS SAFETY GLAZING REQUIRED PER IRC SECTION R308.4

SIZES	ROUGH OPENING	LIGHT (@ 8%)	VENT (@ 4%)
14 X 40 WDW.	14 1/4" X 40 1/4"	2.50	1.30
24 X35 WDW.	24 1/4" X 35 1/4"	4.10	2.10
24 X54 WDW.	24 1/4" X 54 1/4"	6.80	3.50
30 X 60 WDW.	30 1/4" X 60 1/4"	9.90	5.20
36 X 35 WDW.	36 1/4" X 35 1/4"	6.60	3.40
36 X 54 WDW.	36 1/4" X 54 1/4"	10.80	5.60
36 X 60 WDW.	36 1/4" X 60 1/4"	12.20	6.20
36 X 72 WDW.	36 1/4" X 72 1/4"	14.90	7.70
36 X 08 WDW.	36 1/4" X 08 1/4"	0.50	0.00
36 X 12 WDW.	36 1/4" X 12 1/4"	1.10	0.00
64 X 35 WDW.	64 1/4" X 35 1/4"	11.50	2.60
58 X 35 WDW.	58 1/4" X 35 1/4"	10.10	2.20

FASTENING REQUIREMENTS: FOR DOORS AND WINDOWS, USE EITHER # 8 X 1" SCREWS, 7/16" X 1 1/2" X 16 GA. STAPLES, OR .092 X 2 1/4" PD NAILS, AT 12" ON CENTER MAXIMUM.

DESIGN CRITERIA

FLOOR LIVE LOAD = 40 PSF
GROUND SNOW LOAD = 30 PSF
ATTIC LIVE LOAD = 20 PSF

CLASSIFICATION:
- USE GROUP = R
R3 RESIDENTIAL (NON-TRANSIENT)
- CONSTRUCTION TYPE IS V-B (UNPROTECTED)

- SEISMIC DESIGN CATEGORY "C"
- WIND EXPOSURE - "C"
DESIGN WIND SPEED = 90 MPH
ULTIMATE WIND SPEED = 117 MPH

ATTENTION LOCAL INSPECTION DEPARTMENT
SET-UP INSTRUCTIONS FOR THIS MODULAR UNIT ARE INCLUDED BY ATTACHMENT TO THESE PLANS. ANY PLAN SET WHICH DOES NOT INCLUDE AN ATTACHMENT ENTITLED "SET UP MANUAL" IS INCOMPLETE SET-UP INSTRUCTIONS

SEE SETUP MANUAL SENT WITH HOME

REQUIREMENTS FOR FIRESTOPPING
INSTALLATION OF NON-COMBUSTIBLE MATERIALS AROUND ALL OPENINGS THAT ARE VERTICAL PENETRATIONS IN THE FLR. AND CLG.

ATTENTION LOCAL INSPECTION DEPARTMENT
THE FOLLOWING ITEMS LISTED HAVE NOT BEEN COMPLETED BY CMH MFG, Inc., HAVE NOT BEEN INSPECTED BY NTA, INC AND ARE NOT CERTIFIED BY THE STATE OF NORTH CAROLINA MODULAR LABEL CODE COMPLIANCES MUST BE DETERMINED BY THE LOCAL JURISDICTION FOR THE FOLLOWING:
- HVAC SYSTEM (SITE INSTALLATION AND CONNECTIONS)
- THIS UNIT MUST BE CONNECTED TO A PUBLIC WATER SUPPLY AND SEWER SYSTEM, IF THESE ARE AVAILABLE.

NC(New)

CODE COMPLIANCE

ALL PLANS MEET OR EXCEED THE FOLLOWING:
North Carolina State Building Code Compliance:
- NC Residential Code - 2018 Edition

- NC Electrical Code - 2017

APPROVED BY



Approved by this electronic signature with digital approval and date on or subsequent to this date.

DAVID RICHTER

6/13/2019

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

DAVID RICHTER

MODULAR MANUAL REFERENCES

ITEMS BELOW ARE REFERENCED FOR NON PRESCRIPTIVE USE

ELECTRICAL APPLIANCES AND LOADS

ELECTRICAL - SEE PAGES PLN-1.0 for WH & PLN-1.5 for FURN CALCULATION - SEE TECHNICAL SHEET ATTACHED FOR MODEL SPECIFIC ELECTRICAL PANEL LOAD CALC FOR 200 AMP SERVICE

ANCHORAGE REQUIREMENTS

ANCHORAGE REQUIREMENTS FOR PERIMETER OFF FRAME: FOUNDATION SECTIONS FOR PERIMETER OFF FRAME: PER SETUP MANUAL

MARRIAGE WALLS - 2x CONSTRUCTION

DETAILS - MW-50.0, MW-30.0, MW-40.0
CALCULATIONB - SEE CMW SECTION

TRUSSES - DETAILS / CALCULATIONS

PER TRUSS PRINTS

PLUMBING FIXTURES

SEE PAGE PLN - 1.8

ALL MODELS ARE AVAILABLE WITH FLOOR PLAN REVERSED FROM LEFT TO RIGHT AND / OR FRONT TO BACK.

MARRIAGE WALL COLUMNS SPAN CHART

DETAIL - SEE MATING WALL COLUMNS (PAGE MW-20.0)
CALCULATIONS - SEE CMW SECTION

INSTRUCTIONS ON FILLING OUT PLAN SET BEFORE CONSTRUCTION

YOU MUST CHECK THE APPROPRIATE BOX OF WHAT THE STRUCTURE IS TO BE BUILT TO BEFORE PRODUCTION BEGINS. THE MARK SET MUST ACCOMPANY THE UNIT THROUGH THE PRODUCTION PROCESS.

EXTERIOR SIDEWALL HEADERS - SIZES AND MAXIMUM SPAN CHART

HEADER CHART - SEE EXTERIOR WALL PAGE EW - 20.0
CALCULATIONS - CEW SECTION

ATTENTION LOCAL INSPECTION DEPARTMENT: IF THIS STRUCTURE IS IN A THERMAL ZONE MORE STRINGENT THAN THAT LISTED ON THESE PLANS, IS SET ON PILINGS, OR IS INSTALLED AT A MOUNTAIN REGION OR COASTAL HIGH HAZARD SITE SUCH THAT WIND OR OTHER DESIGN PARAMETERS ARE INCREASED, THE DESIGN MUST BE DETERMINED TO BE ADEQUATE FOR ACTUAL SITE CONDITIONS. ALTERATIONS MAY BE REQUIRED TO BRING THE HOME INTO COMPLIANCE WITH THE MORE STRINGENT CONDITIONS.

"Service entrance conductors routed from their point of entrance into the structure, to their point of attachment to the service enclosure a distance horizontally not more than twice the nominal width of the service enclosure and vertically not more than the greater of 5 feet or twice the nominal height of the service enclosure shall be considered to be in compliance with the requirements of 230-70(a) of the current National Electrical Code. Service entrance conductors may be routed in the most direct route or at right angles. Service entrance conductors in excess of these specified limits will not be allowed unless specifically authorized by special permission from the electrical inspector having jurisdiction to accommodate adverse site conditions which would not reasonably allow installation within this criteria."

This home is NOT designed for placement in Coastal High Hazard Areas or Ocean Hazard Areas.

REVISIONS

CMH Manufacturing, Inc.

ALL MODULAR MODELS

COVER SHEET 1-0

TYPICAL FASTENING SCHEDULE:

FLOOR FASTENING

RM-JOIST TO JOIST
 FLOOR BLOCKING TO JOIST
 MULTIPLE JOIST
 DECKING TO FLOOR FRAMING

EXTERIOR WALL FASTENING

LOWER TOP PLATE & BOTTOM PLATE TO STUD
 DOUBLE TOP PLATES
 HEADER TO STUDS
 HEADER COMPONENTS
 STUDS TO SILLS
 EXTERIOR SIDING
 BOTTOM PLATE TO FLOOR
 SIDEWALL TO ENDWALL
 WALL TO WALL TOP PLATES
 EXTERIOR WALL SHEATHING
 PER

WATER/WALL FASTENING

LOWER TOP PLATE TO STUD
 BOTTOM PLATE TO STUD
 MULTIPLE STUDS
 STANDARD COLUMN
 DOUBLE TOP PLATES
 BOTTOM PLATE TO FLOOR
 MATING WALL TO ENDWALL
 WALL TO WALL TOP PLATES

INTERIOR WALL FASTENING

BOTTOM PLATE TO STUDS
 TOP PLATE TO STUD
 DOUBLE STUDS
 FLAT HEADER TO STUDS
 WALL TO FLOOR
 WALL TO WALL
 TOP PLATE TO ROOF SYSTEM
 GYPSUM TO WALL FRAMING

ROOF FASTENING

CEILING BOARD TO TRUSS
 BLOCKING TO TRUSS
 TRUSS TO SIDEWALL TOP PLATE
 TRUSS TO RIDGE BEAM
 TRUSS TO EDGE RAIL
 EDGE RAIL TO MATING WALL
 TRUSS TO ENDWALL TOP PLATE
 ROOF DECKING TO TRUSS
 SHINGLE TO ROOF BECKING
 OUTLOOKER TO TRUSS

INSTALLATION FASTENING

REFERENCE 'CFL' - FLOOR CONSTRUCTION CALCULATIONS OF THE MANUAL.

PER FL-120 IN APPROVED MANUAL
 (4) 7/16" x 2-1/2" x 15 GA. STAPLES OR (2) .131 x 3" NAILS
 7/16" x 2-1/2" x 15 GA. STAPLES OR 8" O.C. OR .131 x 3" NAILS @ 16" O.C. W/ GLUE BOX
 PER FL-10 IN APPROVED MANUAL

REFERENCE 'CEW' - EXTERIOR WALL CONSTRUCTION CALCULATIONS OF THE MANUAL.

PER EW-31 IN APPROVED MANUAL
 DOUBLE STUDS 7/16" x 2-1/2" x 15 GA. STAPLES @ 6" O.C.
 PER EW-1 IN APPROVED MANUAL
 PER EW-25 ATTACHED
 PER EW-20 ATTACHED
 PER THE MANUFACTURER'S SPECIFICATIONS
 PER EW-31 ATTACHED
 PER EW-30 FOR NON-SHEARWALL OR PER SW-35 FOR SHEARWALL OR PER EW-0.0 IN APPROVED MANUAL
 3" x 6" x .036" (20 GA.) GALVANIZED STEEL PLATE W/ (6) .131 x 3" NAILS AT EACH SIDE AT EACH
 FOR APA RATED SHEATHING, 7/16" x 1-3/4" x 15 GA. STAPLES AT 6" O.C. AT ALL EDGES & 12" O.C. FIELD. FOR
 COMPOSITE WALLS, FASTEN PER EW-40. FOR SHEARWALL FASTEN PER SW-40 OR ATTACHED. ALL OTHER SHEATHING FASTENED
 MANUFACTURER'S INSTALLATION INSTRUCTIONS.

REFERENCE 'CW' - MARRIAGE WALL CALCULATIONS OF THE MANUAL.

PER MW-40 IN APPROVED MANUAL
 PER MW-40 IN APPROVED MANUAL
 7/16" x 2-1/2" x 15 GA. STAPLES OR .131 x 3" NAILS @ 16" O.C. TO EACH MEMBER
 PER MW-20 ATTACHED
 PER MW-40 IN APPROVED MANUAL
 PER MW-31 ATTACHED
 PER EW-30 IN APPROVED MANUAL
 3" x 6" x .036" (20 GA.) GALVANIZED STEEL PLATE W/ (6) .131 x 3" NAILS AT EACH SIDE AT EACH WALL OR OVERLAPPED
 PLATE PER EW-0.

PER PT-40 IN APPROVED MANUAL

PER PT-40 IN APPROVED MANUAL
 7/16" x 2-1/2" x 16 GA. STAPLES @ 16" O.C.
 PER PT-20 IN APPROVED MANUAL
 PER PT-40 IN APPROVED MANUAL
 PER PT-30 IN APPROVED MANUAL
 PER PT-40 IN APPROVED MANUAL
 PER THE RESIDENTIAL BUILDING CODE TABLES

REFERENCE 'CRC' - ROOF CONSTRUCTION CALCULATIONS OF THE MANUAL.

FOAM-SEAL 2100 SPRAY ADHESIVE PER THE MANUFACTURER'S SPECIFICATIONS
 (2) 7/16" x 2-1/2" x 15 GA. STAPLES DIRECT
 PER RC-30 IN APPROVED MANUAL
 PER RC-85 ATTACHED
 90 MPH & 100 MPH WIND SPEED; (6) 7/16" x 2-1/2" x 15 GA. STAPLES OR (3) .131 x 3" NAILS
 120 MPH WIND SPEED; (8) 7/16" x 2-1/2" x 15 GA. STAPLES OR (4) .131 x 3" NAILS
 130 MPH & 140 MPH WIND SPEED; (9) 7/16" x 2-1/2" x 15 GA. STAPLES OR (5) .131 x 3" NAILS
 .131 x 4-1/2" MIN. NAILS @ 7" O.C. DIRECT OR 5" O.C. TOED OR #8 x 4-1/2" MIN. WOOD SCREWS @ 16" O.C. DIRECT OR
 10-7/8" O.C. TOED
 PER SW-35 IN APPROVED MANUAL
 PER RC-20 OR SW-10 IN APPROVED MANUAL, WHICH EVER IS WORST
 PER THE MANUFACTURER'S OR ARMA SPECIFICATIONS
 PER RC-70 IN APPROVED MANUAL

REFERENCE INSTALLATION PAGES PROVIDED IN APPROVAL.


(CS1) 7/16" APA RATED ROOF DECKING 24/16 SPAN RATING.
 15# MIN. ROOF UNDERLAYMENT; SINGLE LAYER W/ GREATER
 THAN 4:12 ROOF PITCH; DOUBLE LAYER W/ 4:12 OR LESS
 (CS2) MIN. 20 YEAR SHINGLES.
 (CS3) 1 1/2" WIDE ENGINEERED WOOD BEAM, EACH HALF IN OPEN
 SPAN AREAS GREATER THAN 46".
 (CS4) ENGINEERED WOOD TRUSSES; COMPONENTS & SPACING PER
 TRUSS PRINT
 * OR CONNECTION AND SET-UP OF ROOF
 SEE MODULAR SET-UP PAGES ATTACHED TO APPROVAL

(CS5) CEILING INSULATION, BLOWN OR BATT.
 (CS6) CONTINUOUS VENTED SOFFIT.
 (CS7) DOUBLE 2x4 TOP PLATE (MIN.).
 (CS8) 2x4 STUDS @ 16" O.C. STUD GRADE SPF #3 (MIN.).
 (CS9) WALL INSULATION (BATT)
 3/8" OSB SHEATHING WITH WATER RESISTIVE BARRIER
 BELOW ALL EXT. FINISH MATERIAL.
 CORROSION-RESISTANT FLASHING REQUIRED AT ALL
 LOCATIONS AS SHOWN ON APPROVED MANUAL DETAILS
 (CS10) SINGLE 2x4 BOTTOM PLATE SPF #3 (MIN.).
 (CS11) 3/8" (MIN.) GYPSUM WALL BOARD.
 (CS12) FLOOR INSULATION (BATT. OR BLANKET)
 (CS13) MIN. 19/32" RATED DECKING 16" O.C. OR 32/16 SPAN RATING.

Duct Insulation:
 1 - Min. R-8
 2 - Min. R-6
 RETARDER HAVING A MAXIMUM 0.06 PERM
 IN ACCORDANCE WITH ASTM E84, OR ALLOWABLE
 WITH A MINIMUM THICKNESS OF 2 MILLS, SHALL BE
 INSTALLED ON THE EXTERIOR OF THE INSULATION ON THE
 COULING SUPPLY DUCT THAT PASS THROUGH UNCONDITIONED
 INSULATION TO PROVIDE PROTECTION EXCEPT WHERE THE
 INSULATION IS SPRAY POLYURETHANE FOAM WITH
 A MAXIMUM WATER VAPOR PERMEANCE OF
 3 PERM PER INCH AT THE
 INSTALLED THICKNESS.

(CS16) MAIN HEAT DUCT. (MAYBE SITE INSTALLED BY OTHERS)
 (CS17) OFF-FRAME PER FL-110 IN APPROVED MANUAL
 (CS18) OFF-FRAME PER FL-110 IN APPROVED MANUAL
 (CS19) 2x4 (MIN.) MARRIAGE WALL STUDS @ 16" O.C.
 (CS20) LISTED BOTTOM BOARD, WHERE OCCURS.
 (CS21) 1/2" SHIM FOR COMPRESSION STRIP.
 (CS22) DOUBLE 2x4 (MIN.) TOP PLATE.
 (CS23) 2x4 (MIN.) BOTTOM PLATE.
 (CS24) 1/2" (MIN.) GYPSUM BOARD CEILING.
 (CS25) RESERVED

(CS27) CONTINUOUS 2x3 SPF #3 MINIMUM FOR
 TRUSS TOP RAIL FOR RIDGE CONNECTION
 (CS28) 2x FULL DEPTH BLOCKING 24" O.C. (2)
 JOIST BAY MIN. ENDWALL LOCATION ONLY.
 (CS29) LAP BOARD, WOOD OR VINYL SIDING, HARDI SIDING, OR EXPOSED
 SHEATHING FOR ON SITE EXTERIOR FINISH INSTALLATION.




CMH
 MANUFACTURING,
 INC

**TYPICAL CROSS SECTION &
 FASTENING SCHEDULE**

SERIES: IC/WA/SC/DE MODULA	MODEL NO.:	ALL
BRAND:	PLANT:	#958
DESCRIPTION:	DATE PRINTED:	12-13-16
DATE DRAWN:	DATE:	10-21-15
DRAWN BY:	SHEET:	1-0.2

APPROVED BY
NIA INC. 6/13/2019
 Signature of the document owner or authorized representative for installation of fasteners must be accompanied by a signature of the manufacturer or manufacturer's sales agent.
 David Richter



RETURN AIR MEASUREMENTS	INDICATES FREE END SHEAR WITH BLOCKING
① 20" x 18" GRILL REQUIRED	② THE # SPECIFIES THAT THERE CAN BE NO HALLS IN STUDS IN COLUMN
③ 4" x 10" DOOR UNDERCUT	
④ DOOR(S) MUST BE UNDERCUT 2 1/2" MIN.	
⑤ 4" x 8" OR 6" x 10" GRILL REQUIRED	
MODEL NAME	SR. FT.
4710-GE	2254
PLANT DESCRIPTION	MODEL NO.
32X76 4BR-2BR	SN251077
DESIGN BY	DATE PRINTED
GCK	06/12/2019
	SHEET NO.
	1-1

INSULATION FOR NORTH CAROLINA/2018 PRESCRIPTIVE METHOD
 CZ4: R=38 CEILING R=15 WALLS R=22 FLOOR
 U=0.35 / SHGC=0.28

APPROVED BY
NIA INC.
 6/13/2019
 Architectural and Structural Engineering
 David Kishler

REVISIONS	BY	DATE	GENERAL NOTES
			CEILING HEIGHT = 10'
			FLOOR FINISH SPECING = 16

320PLF EFFECTIVE LENGTHS
 288" EM / 70" SM: 320PLF
 366PLF BASED ON SW-31.10 - N.C.17 - (235).1-2
 ENGINEERED METHOD.
 UNBLOCKED SW-20-389B.1
 50 MPH WIND SPEED


BRNO SCHULT SERIES M032

CLAYTON HOME BUILDING GROUP

DRINKING TITLE
MASTER PLAN

B-SECTION HITCH END
 R-SECTION HITCH END

PIPING AND FITTING MATERIAL TYPE TO BE:
 PEX TYPE BY QUEST, CPVC OR COPPER
 PRESSURE RANGE 40-49 PSI
 80' DEVELOPED LENGTH



APPROVED BY
NIA INC.
 6/13/2019
 Approval of this document does not constitute an endorsement or approval of the quality of the work performed by the contractor.


COLD WATER SUPPLY PLUMBING

HOT WATER SUPPLY PLUMBING

PIPE LEGEND	
—	1"
—	3/4"
—	1/2"

BRAND	SCHULT	MODEL	MD32	REVISIONS	BY	DATE	GENERAL NOTES	DRAINING TITLE	MODEL NAME	4710-GE	SQ. FT.	2254		
CLAYTON HOME BUILDING GROUP								SUPPLY PLUMBING	PLANT	958	DESCRIPTION	32X75 4BR-2BR	MODEL NO.	SN251077
									DATE BY	GCK	DATE PRINTED	06/11/2019	SHEET NO.	9-1

APPROVED BY
NIA INC.
 6/13/2019
 I am a duly Licensed Electrician in the State of North Carolina and I hereby certify that I have prepared the above electrical plan in accordance with the applicable North Carolina Electrical Code and the applicable State Laws.
David Richter



NOTE: ALL FAMILY, DINING, LIVING, PRROR, LIBRARIES, DENIS, BEDROOMS, SUNROOMS, RECREATION ROOMS, CLOSETS, HALLWAYS OR SIMILAR ROOMS OR SPACES SHALL BE PROTECTED BY A LISTED ARC-FAULT INTERRUPTER IN ACCORDANCE WITH SECTION 210.12 OF THE NEC.

ELECTRICAL SCHEDULE															
NO.	DESCRIPTION	VOLTS	AMP.	PHASE	TYPE	DESCRIPTION	VOLTS	AMP.	PHASE	TYPE	DESCRIPTION	VOLTS	AMP.	PHASE	TYPE
1	PORTABLE APPLIANCES	120	15	1	1	1	120	15	1	1	1	120	15	1	1
2	PORTABLE APPLIANCES	120	15	1	1	2	120	15	1	1	2	120	15	1	1
3	PORTABLE APPLIANCES	120	15	1	1	3	120	15	1	1	3	120	15	1	1
4	GEN. LIGHTING/RECP.	120	15	1	1	4	120	15	1	1	4	120	15	1	1
5	GEN. LIGHTING/RECP.	120	15	1	1	5	120	15	1	1	5	120	15	1	1
6	ELECT. W/ITER RECP.	120	15	1	1	6	120	15	1	1	6	120	15	1	1
7	UNDER RECP.	120	15	1	1	7	120	15	1	1	7	120	15	1	1
8	DRYER RECP.	240	30	1	1	8	240	30	1	1	8	240	30	1	1
9	ELECT. W/ITER RECP.	120	15	1	1	9	120	15	1	1	9	120	15	1	1
10	ELECT. W/ITER RECP.	120	15	1	1	10	120	15	1	1	10	120	15	1	1
11	APPR. PRICE P.A.M.-3.1 FOR MD. P.A.M.-1.5 FOR MD.	120	15	1	1	11	120	15	1	1	11	120	15	1	1
12	APPR. PRICE P.A.M.-3.1 FOR MD. P.A.M.-1.5 FOR MD.	120	15	1	1	12	120	15	1	1	12	120	15	1	1
13	COOL. LIGHTING/RECP.	120	15	1	1	13	120	15	1	1	13	120	15	1	1
14	OPT. AIR-POOL	240	30	1	1	14	240	30	1	1	14	240	30	1	1
15	OPT. AIR-POOL	240	30	1	1	15	240	30	1	1	15	240	30	1	1
16	OPT. AIR-POOL	240	30	1	1	16	240	30	1	1	16	240	30	1	1
17	OPT. AIR-POOL	240	30	1	1	17	240	30	1	1	17	240	30	1	1
18	OPT. AIR-POOL	240	30	1	1	18	240	30	1	1	18	240	30	1	1
19	OPT. AIR-POOL	240	30	1	1	19	240	30	1	1	19	240	30	1	1
20	OPT. AIR-POOL	240	30	1	1	20	240	30	1	1	20	240	30	1	1
21	OPT. AIR-POOL	240	30	1	1	21	240	30	1	1	21	240	30	1	1
22	OPT. AIR-POOL	240	30	1	1	22	240	30	1	1	22	240	30	1	1
23	OPT. AIR-POOL	240	30	1	1	23	240	30	1	1	23	240	30	1	1
24	OPT. AIR-POOL	240	30	1	1	24	240	30	1	1	24	240	30	1	1
25	OPT. AIR-POOL	240	30	1	1	25	240	30	1	1	25	240	30	1	1
26	OPT. AIR-POOL	240	30	1	1	26	240	30	1	1	26	240	30	1	1
27	OPT. AIR-POOL	240	30	1	1	27	240	30	1	1	27	240	30	1	1
28	OPT. AIR-POOL	240	30	1	1	28	240	30	1	1	28	240	30	1	1
29	OPT. AIR-POOL	240	30	1	1	29	240	30	1	1	29	240	30	1	1
30	OPT. AIR-POOL	240	30	1	1	30	240	30	1	1	30	240	30	1	1
31	OPT. AIR-POOL	240	30	1	1	31	240	30	1	1	31	240	30	1	1
32	OPT. AIR-POOL	240	30	1	1	32	240	30	1	1	32	240	30	1	1
33	OPT. AIR-POOL	240	30	1	1	33	240	30	1	1	33	240	30	1	1
34	OPT. AIR-POOL	240	30	1	1	34	240	30	1	1	34	240	30	1	1
35	OPT. AIR-POOL	240	30	1	1	35	240	30	1	1	35	240	30	1	1
36	OPT. AIR-POOL	240	30	1	1	36	240	30	1	1	36	240	30	1	1
37	OPT. AIR-POOL	240	30	1	1	37	240	30	1	1	37	240	30	1	1
38	OPT. AIR-POOL	240	30	1	1	38	240	30	1	1	38	240	30	1	1
39	OPT. AIR-POOL	240	30	1	1	39	240	30	1	1	39	240	30	1	1
40	OPT. AIR-POOL	240	30	1	1	40	240	30	1	1	40	240	30	1	1

REVISIONS			
NO.	DATE	BY	DESCRIPTION

GENERAL NOTES	


ELECTRICAL PLAN	
PROJECT NO.	4710-GE
PLANT	958
DESCRIPTION	32X76 4BR-2BR
MODEL NO.	SN2S1077
DRAWN BY	GCK
DATE PRINTED	06/11/2019
SHEET NO.	11-1
DATE	06/05/2019
SCALE	AS SHOWN

SCHULT MD32
 CLAYTON HOME BUILDING GROUP

2254 SQ. FT. RITIC AREA
 1082 SQ. IN. REQUIRED
 VENTED SOFFIT - 7.38 SQ. IN. VENT/FT
 70 FT RIDGE CAP/VENT-16.00 SQ. IN. VENT/FT
 1122 SQ. IN. PROVIDED FOR SOFFIT
 1260 SQ. IN. PROVIDED FOR RIDGE VENT


7:12

ASPHALT SHINGLES



FRONT ELEVATION

VINYL LAP SIDING




RIGHT SIDE ELEVATION


APPROVED BY
NIA INC.
 6/13/2019
Approval of this drawing does not constitute an opinion or guarantee of accuracy or compliance with the requirements of applicable State laws.
David Richter

BRAND	SCHULT	SERIES	M032	REVISIONS	BY	DATE	GENERAL NOTES	DRAWING TITLE	MODEL NAME	4710-GE	SN. FT.	2254	
	CLAYTON HOME BUILDING GROUP		PLANT		958	DESCRIPTION			32X76 4BR-2BR	MODEL NO.	SN251077	DATE PRINTED	06/11/2019
								DRAWN BY		GCK	DATE PRINTED		06/11/2019

7:12



BACK ELEVATION




LEFT SIDE ELEVATION

APPROVED BY
NIA INC
 6/13/2019
Approved on their Account for the use of their name in connection with the design and construction of any building or structure. Not to be used for any other purpose without the written consent of NIA, Inc.
 David Richter

BRNO	SCHULT	SERIES	MD32	REVISIONS	BY	DATE	GENERAL NOTES	DRAWING TITLE	MODEL NAME	4710-GE	SN, FT.	2254
CLAYTON HOME BUILDING GROUP								EXTERIOR ELEVATION BACK & LEFT SIDE	PLANT	DESCRIPTION	MODEL NO.	
									958	32X76 4BR-2BR	SN251077	
									DESIGN BY	DATE PRINTED	SHEET NO.	
									GCK	06/06/2019	06/11/2019	20-2

IMPORTANT:
 THIS FOUNDATION DRAWING IS MODEL SPECIFIC AND ILLUSTRATES THE BASIC LAYOUT ONLY.
 FOR FOUNDATION CONSTRUCTION, FASTENING AND SECUREMENT DETAILS YOU MUST REFER
 TO THE MODEL SPECIFIC FOUNDATION MANUAL INCLUDED WITH THIS HOME.



NOTE: THE OVERALL FOUNDATION WIDTH SHOWN
 IS 1 1/2" LARGER THAN THE ACTUAL FLOOR WIDTH
 TO COMPENSATE FOR PRODUCTION AND ASSEMBLY TOLERANCES.

PIER LEGEND

- SUPPORT AT EXISTING COLUMN
- SUPPORT UNDER EXISTING WALL
- SUPPORT UNDER EXISTING OPENING
- SUPPORT AT PORCH-ACCESSED ENTRY
- SUPPORT UNDER MAIN 1-BEAM
- SUPPORT UNDER PERIMETER WALL
- SUPPORT AT CROSS 1-BEAM BASEMENT

FLRBT	958	MODEL NO.	4710-CE	SO. FT.	2254
DRWN BY	GCK	DESCRIPTION	32X26 4BR-2BR	DATE PRINTED	06/11/2019
		ORIG. DATE	06/06/2019		
		SHEET NO.	21-30PSF		

GENERAL NOTES

● NOTES PERTAINING TO THE FOUNDATION PACKAGE PER TABLE H AND DETAIL DS IN THE FOUNDATION PACKAGE

INSTALL SCHEDULED LIGHT AND GFI RECEPT AT CORNER SPACE ENDS WITH 18" MIN. CLEARANCE BELOW BOTTOM OF FLOOR JOIST. GROUND TO BE COVERED WITH APPROVED VAPOR RETARDER MATERIAL (EQUIPMENT FOR REC - 210-70 (C))

INSTALL SCHEDULED LIGHT AND GFI RECEPT AT CORNER SPACE ENDS WITH 18" MIN. CLEARANCE BELOW BOTTOM OF FLOOR JOIST. GROUND TO BE COVERED WITH APPROVED VAPOR RETARDER MATERIAL (EQUIPMENT FOR REC - 210-70 (C))

SEE INSTALLATION MANUAL FOR FOUNDATION GENERAL NOTES & TIE-BAR REQUIREMENTS

FOUNDATION VERT LOCATIONS ARE SHOWN TYPICAL & ARE SUBJECT TO CHANGE DUE TO PIER LOCATION, CHANGES IN EXTERIOR DOCK INSTALLATION

() - DIMENSIONS INDICATE 26 INCHES OPTION

REVISIONS	BY	DATE

APPROVED BY

NTA INC 6/13/2019

Approval of this document does not constitute an endorsement or recommendation of any product or manufacturer by NTA Inc. or its affiliates.

David Richter

2624 SQ. FT. OF CORNER SPACE AREA	2164 SQ. IN. OF VENT REQUIRED	42 VENTS NEEDED @ 32 SQ. IN. EACH	2164 SQ. IN. VENTILATION INSTALLED MINIMUM
VENTILATION IS BASED ON 144 SQ. IN. OF VENT FOR EVERY 150 SQ. FT. OF CORNER SPACE AREA WITH APPROVED VAPOR RETARDER MATERIAL. ONE SUCH VENT MUST BE WITHIN 3 FT. OF EACH CORNER			

SCHULT	MD32	CLAYTON HOME BUILDING GROUP
20/30 PSF FOUNDATION		

OFF FRAME BASEMENT & CRAWL FOUNDATION DESIGN FOR:

29' - 8 " 2-SECTION MODULAR
1 STORY- 30 PSF ATTIC LIVE

30 psf live load habitable attic and attic served with fixed stairs

PERIMETER ANCHORED SYSTEM- BUILDING IS SECURED TO FOUNDATION WALLS TO SUPPORT WIND AND SEISMIC FORCES.

SIDEWALLS ARE SUPPORTED (PERIMETER BLOCKED)

BUILDING CODE INFORMATION:

IRC (2015)

ASCE 7-10

2018 NORTH CAROLINA RESIDENTIAL CODE

BUILDING SITE INFORMATION:

*MAXIMUM ULTIMATE/DESIGN WIND SPEED & EXPOSURE: 117/ 90 MPH EXPOSURE C-enclosed

MINIMUM SOIL BEARING CAPACITY: 1500 PSF

MAXIMUM GROUND SNOW(S): 20 PSF, 30 PSF

Flat roof snow load (Pg)=20.0 PSF ,23.1 PSF

SEISMIC DESIGN CATEGORY: C

DESIGN SPECTRAL RESPONSE (S_{DS}): 0.49

SEISMIC SOIL SITE CLASS: D



HOME INFORMATION:

UNIT WIDTH: 29' - 8 "

MAX. UNIT LENGTH: 76 ft.

ROOF PITCH: 7/12 to 7/12

DESIGN LOADS: 40 PSF FL. LL., 10PSF T.C.D.L., 10PSF B.C.
D.L., 13PSF FL. DL. &, 30PSF B.C.L.L

MAX. SIDEWALL HEIGHT: 108 INCHES

TOTAL MATING WALL RIM JOIST BEAMS: (4) 2X10 #2 SPF

RIM JOIST SPLICES: 6" X 8" MiTek MT20 metal plates each side

MODEL #: SN251077

OFF FRAME FLOOR

PLANT NUMBER: 958

It is responsibility of others (retailer, builder & building official) to determine if this package is appropriate for site location by verifying design criteria and soil bearing capacity of site.

* Ultimate wind speed Vult. Per ASCE 7-10/ allowable stress design wind speed Vasd. All wind speeds are indicated as (Vasd) design speeds unless otherwise indicated.

This design is the property of CMH Manufacturing and cannot be used without authorization. This design is exclusively for use with new homes built by CMH Manufacturing. Use with homes built by other companies is strictly prohibited.

FILENAME:958I-14.S.J.C.22.22.235(_)

program version: 19.17

Page 1 of 27

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

PAGE DESCRIPTION	DETAIL	PAGE #
COVER		1
TABLE OF CONTENTS		2
PREFACE		3
INSTRUCTIONS		4
		5
GENERAL NOTES		
SOIL CLASSIFICATION (TABLE R405.1)		8
FOUNDATION WALL DESIGN		9
UNBALANCED FOUNDATIONS TABLE L	TABLE L	10
PIER AND FOOTER DESIGN TABLE M	TABLE M	11
MIN. POST CAPACITY AND FOOTER DESIGN TABLE N	TABLE N	12
KEY PLAN 7 - OFF-FRAME BASEMENT	KEY 7	13
KEY PLAN 8 - OFF-FRAME CRAWL PLAN	KEY 8	14
NON-REINFORCED PERIMETER WALL - DETAIL D1	D1	15
NON-REINFORCED MATING PIER / CRAWLSPACE ONLY (MORTAR EMBEDDED) - DETAIL D3	D3	16
REINFORCED MATING PIER / BASEMENT OR CRAWLSPACE - DETAIL D5	D5	17
MATING WALL COLUMN TIE DOWN - DETAIL D6	D6	18
ADJUSTABLE STEEL COLUMN POST / BASEMENT OR CRAWLSPACE - DETAIL D7	D7	19
SPECIAL HIGH CAPACITY SHEARWALL HOLD-DOWN	D18	20
DOUBLE MUD SILL CONSTRUCTION OPTION.	D34	21
FLOOR TO SILL PLATE FASTENING - DETAIL E	E	22
FLOOR TO SILL PLATE FASTENING - DETAIL F	F	23
FLOOR TO SILL PLATE FASTENING - DETAIL G	G	24
FLOOR TO SILL PLATE FASTENING - DETAIL H	H	25
FLOOR TO SILL & SILL TO FOUNDATION SECUREMENT WITH DETAIL H PLATES		26
FLOOR TO SILL & SILL TO FOUNDATION SECUREMENT WITHOUT DETAIL H PLATES		27

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter



Model: SN251077
 Customer: Wilson

FILENAME:958I-14.S.J.C.22.22.235()

Preface

This foundation design manual is dedicated to the ever-growing trend to place homes over basements and permanent foundations. CMH Manufacturing, Inc. has attempted to address the more common installation configurations. These may or may not be the only acceptable designs for basements or permanent foundations. If deviations are made from these details, it is the homeowner's and/or installation contractor's responsibility to obtain proper documentation and engineer's details of construction acceptable to the local authority having jurisdictions. CMH Manufacturing, Inc. will not supply any details other than what is contained in the following design manual. If an alternate design is requested it must be provided by an independent engineer subject to local approval. The owner/contractor is responsible for any additional construction details, permits, inspections and fees associated with these items.

Setting a home over a basement or permanent foundation requires special knowledge, experience and equipment to accomplish a safe and proper set. Contractors performing this type of installation must be licensed, bonded and insured to protect all aspects of this type of work.

APPROVED BY
6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

Instructions

1. Determine site soil classification, (see table R405.1).
2. The provided foundation and anchorage designs are not applicable for the following conditions. In all these cases a complete geotechnical evaluation must be performed and foundation must be designed by a professional engineer in accordance with section 1808.6 (IBC) for site specific conditions.
 - Site contains OL, OH or Pt class soils.
 - Site contains compressible or shifting soils.
 - Site contains expansive soils per IRC (R403.1.8.1) or per local authority and adopted code.
 - Site contains soils which do not provide the minimum allowable soil bearing strength as specified per the provided designs.
 - Foundation walls support unbalanced loads on opposite sides of building, such as a daylight basement or walk out basement where the building aspect ratio, L/W, exceeds the values specified in Table L.
 - Site with soils subject to liquefaction or soil containing high concentration of sulfate.
3. Determine foundation wall height for each wall of foundation. Reference Detail – D1 for wall height.
4. Determine height of backfill for each wall of foundation. Reference Table L when backfill heights along the foundation wall are unbalanced. Reference Detail – D1 for perimeter foundation wall construction.
5. Determine what type of mateline supports will be used. Reference Detail - D3, D5 or D7 for mateline columns.
6. Determine if type H connector plates will be used around the perimeter of the building. Fastening and anchoring tables have been provided with and without the use of the H connectors.
7. Find the **Floor to Sill Plate & Sill Plate to Foundation** table for site soil classification.
8. Find site wall height and backfill height line and follow this line across. Heights are listed as maximums, therefore any line beneath (greater height) may be utilized for items 10 ,11 & 12 below.
9. If type H connectors will be installed the table labeled **With Type H Plate Connectors** can be utilized. Note (6) will specify spacing for H plates along sidewalls and Note (7) will specify spacing for H plates along each endwall.
10. Select desired rim to sill connection from line in table (E, F or G for sidewalls and E or G for endwalls).
11. Select desired anchor type (4 or 5) for sill to foundation wall connection and determine anchor spacing for sidewall and endwall under corresponding column.
12. Determine if shearwall foundation holddowns are required by checking far right column within selected row. See Shearwall Foundation Holddown Detail (Detail D18) for connection requirements .

The above process may be repeated as desired for different foundation wall and backfill combinations.

General Notes

1. Foundation plans and details developed by CMH Manufacturing, Inc. are provided to our company owned sales centers and wholesale distribution partners. Alternate foundation systems may be used in lieu of these plans provided they are designed by a local professional Engineer or Architect familiar with the local soil and climate conditions, and are approved by the local authority having jurisdiction.
2. All notes stating "in field" or "by owner" are obligations pertaining to owner/contractor.
3. Owner /Contractor shall provide complete foundation, including footing drains, vapor barrier, sill plate, anchor bolts, stair area, slab and footing reinforcement along with damp proofing, waterproofing, backfill, and all finish work per Chapter 4 of IRC or per adopted local building code.
4. Owner/Contractor shall be responsible for performing all work in accordance with approved construction details and obtaining all necessary inspections as required by local or state authorities.
5. Not designed for areas likely to have collapsible, expansive, compressible, shifting, liquifaction, soil containing high concentration of sulfate or other unknown soil characteristics. In these conditions a local engineer must provide foundation design and the building official shall determine whether to require a soil test to determine the soil characteristics. This soil test shall be made by an approved testing agency using an approved method.
6. Pier spacing is dimensioned to centerline unless otherwise noted.
7. The foundation dimensions shown are nominal. An increase in module width should be expected due to module expansion, setting tolerances, etc. The foundation contractor should consult with the manufacturer of the modules prior to construction of the foundation to determine the actual width of the home and placement of anchors.
8. All steel support columns shall have protective coating and a load capacity equal to or greater than specified on foundation plan (k=1000 pounds).
9. All foundation construction materials and installation shall be in accordance with all state and local codes.
10. Backfill shall not be placed against the wall until the wall has sufficient strength and has been anchored to the floor above or has been sufficiently braced to prevent damage by the backfill. Heavy-equipment must be restricted to a minimum distance to the foundation at least equal to the depth of the foundation.
11. Solid cap block or cement fill required at top courses of all masonry piers or pilasters.
12. The foundation design has been designed to be placed in the seismic zone indicated on the cover of this document. Please note that all CMH structures have been designed for seismic (zone/category) A, B, or C only, unless otherwise noted on floor plan and cover page of these instructions.
13. All piers shall be constructed of 8"x8"x16" concrete masonry units conforming to ASTM C90 with a minimum compressive strength of 700 psi. Masonry foundation walls must be laid in type m or s mortar. When required per tables or details, piers of masonry units shall be laid in type m or s mortar. All dry stack masonry should be surfaced bonded with an approved adhesive product.


FILENAME:958I-14.S.J.C.22.22.235(_)

APPROVED BY

6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

Page 5 of 27

14. All reinforcing steel shall be Grade 60 minimum. All splices shall be lapped 24 " minimum and splices shall be offset 30 " minimum within same footer.
15. All concrete grout shall be 3000 psi at 28 days.
16. Reference the model plan drawing for specific foundation layout.
17. Concrete footings shall have a minimum compressive strength of 3000 psi at 28 days. Concrete foundation walls and other concrete exposed to weather shall have a minimum compressive strength of 3000 psi at 28 days and in moderate and severe weather areas the concrete shall be air entrained no less than 5 percent and not more than 7 percent. See table R301.2(1) and R402.2 of IRC
18. All exterior footings shall be placed at least 12 " below the undisturbed ground surface. All exterior footings shall extend below the frost line or otherwise frost protected in accordance with Sections R403.1.4.1 through R403.1.4.2 of IRC or per adopted local building code.
19. Top of foundation walls shall extend a minimum of 6-1/2 " above finished adjacent grade. Wood framing members, including wood sheathing, that rest on exterior foundation walls and are less than 8 " from exposed earth shall be of naturally durable or preservative-treated wood. Wood floor joist shall not be closer than 18 " from exposed ground in under floor space.
20. Owner/Contractor shall verify this package is applicable for use at site by verifying all site conditions including design criteria and allowable soil bearing capacity meets or exceeds those specified within this package and shall verify dimensions prior to starting foundation. Notify home manufacturer of any discrepancies immediately.
21. The foundation must be designed and built to local codes and ordinances and must be approved and inspected by local building officials.
22. Access shall be to all under floor spaces. Access shall be a minimum of 18 " by 24 ". If mechanical equipment is installed in this area, please refer to the Mechanical Code for minimum access opening. Through wall access openings shall not be located under an exterior door.
23. Under floor space shall be ventilated with a net area ratio not less than 1 square foot for each 150 square feet of under floor space area placed in accordance with local codes. Ratio may be reduced to 1/1,500 where ground is covered with a 6-mil polyethylene or approved vapor retarder.
24. Field installed wiring in basement is subject to local inspection. Basement smoke alarms must be installed at foot of stairs and interconnected with home smoke alarms and tested on site. Smoke alarms must be located, installed, and tested in conformance with local building requirements.
25. Large clear spans along mating wall require a column or pier at each end. See model specific foundation plot plan for mating wall column locations and Table M and Table N for support pier and footer size.
26. Basement stairs (widths, handrails, clearances, headroom, landings, fire protection, etc.) are the responsibility of the owner/contractor and must be constructed to comply with local building codes.
27. Owner/contractor shall not alter basement stair opening without written approval from CMH Manufacturing, Inc.

28. Lighting and receptacles in basement are the responsibility of owner/contractor.
29. Termite protection shall be provided per the building code and local requirements and are responsibility of owner/contractor.
30. Ground snow load is indicated on foundation plans. Snow load must be verified per locality. Building has not been designed to be located within a Tsunami design zone.
31. This structure has not been designed to be located within flood hazard locations or in Coastal A Zones. When site is located in a flood hazard area or in Coastal A Zones as determined by the local authority having jurisdiction or flood hazard maps. The unit shall have lowest floor elevated above the design floor elevation. Foundation and anchorage designs shall be provided by a local engineer in conformance with locally adopted building code and ASCE-24-14.
32. All connection hardware, anchor bolts, straps, hold-downs, washers and fasteners shall be minimum of ASTM A653 Type G185 zinc coated galvanized or stainless when in contact with pressure treated sill plates or other pressure treated lumber.
33. Radon control, when required by a local jurisdiction, shall be provided and installed by others in accordance with appendix F of the IRC.
34. Topographic wind effects have not been considered. Home has not been designed to be located in areas designated as having local historical data documenting structural damage to buildings caused by wind speed-up at isolated hills, ridges and escarpments.
35. Surface drainage shall be devirted to a storm sewer or other approved collection point. Lots shall be graded to drain surface water away from foundation walls. The grade shall fall a minimum of 6 inches within the first 10 feet.
- 36 A 6-mil-thick polyethylene moisture barrier shall be applied over the porous layer with the basement floor constructed over the polyethylene.
37. Concrete and Masonry Foundation walls that retain earth and enclose interior spaces and floors below grade shall be damp proofed from the top of the footing to the finished grade. Masonry walls shall have not less than 3/8" Portland cement parging applied to the exterior of the wall. The parging shall be damp proofed in accordance with one of the following.
-  a. Bituminous coating, b. 3 pound per sq. yard of arcylic modified cement, c. 1/8" coat of surface-bonding cement complying with ASTM C887, d. Material permitted for waterproofing per Section R406.2, e. Other approved methods or materials.
38. Concrete and masonry foundation walls that retain earth and enclose interior spaces and floors below grade in areas of high water table or other severe soil-water conditions shall be waterproofed from the top of the footing to the finished grade in accordance with one of the following:
- a. 2-ply hot-mopped felts, b. 55 pound rolled roofing, c. 6-mil polyvinyl chloride, 6-mil polyethylene, d. 40-mil polymer-modified asphalt., e. 60-mil flexible polymer cement, f. 1/8" cement-based, fiber-reinforced, waterproof coating, g. 60-mil solvent-free liquid-applied synthetic rubber.
39. If building is located within a wind borne debris region glazed openings shall be protected from wind borne debris. Wind Borne debris protection is the responsibility of others.
40. When Geotechnical report is required or available, all recommendations shall be followed and geotechnical engineer shall review all foundation plans to verify applicability with recommendations and engineer shall be present on regular basis during site preparation, fill placement and foundation excavation.
41. Self-closing rated doors shall be installed between garage and house (on-site by other).(R302.5.1)
- 42.Reserved.
43. A 6-mil polyethylene or approved vapor retarder with joints lapped not less than 12 inches shall be placed between the concrete floor slab and the base course or the prepared subgrade.

SOIL CLASSIFICATION

Table R405.1 W/ NC admendments(see footnote c)


LATERAL SOIL LOAD	UNIFIED SOIL CLASSIFICATION SYSTEM SYMBOL	SOIL DESCRIPTION	DRAINAGE CHARACTERISTICS ^a	FROST HEAVE POTENTIAL	VOL. CHANGE POTENTIAL EXPANSION ^b	ALLOWABLE SOIL PRESSURE
30 psf LATERAL SOIL LOAD	GW	Well-graded gravels, gravel sand mixtures, little or no fines	Good	Low	Low	5000
	GP	Poorly graded gravel or gravels sand mixtures, little or no fines	Good	Low	Low	5000
	SW	Well-graded gravels, gravelly sands, little or no fines	Good	Low	Low	3000
	SP	Poorly graded sand, or gravelly sands, little or no fines	Good	Low	Low	3000
45 psf LATERAL SOIL LOAD	GM	Silty gravels, gravel-sand-silt mixtures	Good	Medium	Low	3000
	SM	Silty sand, sand-silt mixtures	Good	Medium	Low	3000
	GC	Clayey gravels, gravel-sand-clay mixtures	Medium	Medium	Low	3000
60 psf LATERAL SOIL LOAD	SC	Clayey sands, sand-clay mixture	Medium	Medium	Low	3000
	ML	Inorganic silts and very fine sands, rock flour, silty or clayey fine sands or clayey silts with slight plasticity	Medium	High	Low	2000*
	CL	Inorganic clays of low to medium plasticity, gravelly clays, sandy clays, silty clays, lean clays	Medium	Medium	Medium to Low	2000*
	CH	Inorganic clays of high plasticity, fat clays	Poor	Medium	High	2000*
	MH	Inorganic silts, micaceous or diatomaceous fine sandy or silty soils, elastic silts	Poor	High	High	2000*
SPECIAL INSPECTION REQUIRED	OL	Organic silts and organic silty clays of low plasticity	Poor	Medium	Medium	SPECIAL INSPECTION REQUIRED
	OL	Organic clays of medium to high plasticity, organic silts	Unsatisfactory	Medium	High	
	Pt	Peat and other highly organic soils	Unsatisfactory	Medium	High	

a. The percolation rate for good drainage is over 4 inches per hour, medium drainage is 2 inches to 4 inches per hour, and poor is less than 2 inches per hour.

b. Soils with low potential expansion typically have a plasticity index (PI) of 0 to 15, soils with a medium potential expansion have a PI of 10 to 35 and soils with a high potential expansion have PI greater than 20.

c. IRC Table of same name has been used in part to derive table with additional information supplemented from other accepted engineering references.

* Where the building official determines that in place soils with an allowable bearing capacity of less than 2000 psf are likely to be present at the site, the allowable bearing capacity shall be determined by a soils investigation.

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
 David Richter

FILENAME:958I-14.S.J.C.22.22.235(_)

Page 8 of 27

TABLE R404.1.1:IRC (2015) PERIMETER FOUNDATION WALL MINIMUM REQUIREMENTS [Seismic Seismic Zone: Design]

Max. Wall Height	Maximum Unbalanced Fill*	GW, GP, SW, & SP Soil Class (30 PSF)			GM, GC, SM-SC, & ML Soil Class (45 PSF)			SC, MH, ML-CL, & Inorganic CL Soil Class (60 PSF)		
		Plain Masonry 1 Walls	8" Reinforced Masonry Walls 5.9	8" Poured Concrete Walls 6.7	Plain Masonry 1 Walls	8" Reinforced Masonry Walls 5.9	8" Poured Concrete Walls 6.7	Plain Masonry 1 Walls	8" Reinforced Masonry Walls 5.9	8" Poured Concrete Walls 6.7
0 to 5 feet	4	6 in. solid (3) or 8 in.	-	PC	6 in. solid (3) or 8 in.	-	PC	6 in. solid (3) or 8 in.	-	PC
	5	6 in. solid (3) or 8 in.	-	PC	8 in.	-	PC	10 in.	-	PC
6 feet to 7 feet	4	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	8	#4 @ 48 in. o.c.	PC	8	#4 @ 48 in. o.c.	PC
	5	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	10 in.	#4 @ 48 in. o.c.	PC	10 in.	#4 @ 48 in. o.c.	PC
	6	10 in.	#4 @ 48 in. o.c.	PC	12 in.	#5 @ 48 in. o.c.	PC	10 in. solid (3)	#5 @ 48 in. o.c.	#5 @ 48 in. o.c.
	7	12 in.	#5 @ 48 in. o.c.	PC	10 in. solid (3)	#6 @ 48 in. o.c.	PC	12 in. solid (3)	#6 @ 40 in. o.c.	#6 @ 48 in. o.c.
8 feet	4	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	8	#4 @ 48 in. o.c.	PC
	5	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	10 in.	#4 @ 48 in. o.c.	PC	12 in.	#4 @ 48 in. o.c.	PC
	6	10 in.	#4 @ 48 in. o.c.	PC	12 in.	#5 @ 48 in. o.c.	PC	12 in. solid (3)	#5 @ 48 in. o.c.	#6 @ 32 in. o.c.
	7	12 in.	#5 @ 48 in. o.c.	PC	12 in. solid (3)	#6 @ 48 in. o.c.	PC	Footnote (4)	#6 @ 40 in. o.c.	#6 @ 32 in. o.c.
	8	10 in. solid (3)	#5 @ 48 in. o.c.	#6 @ 41	12 in. solid (3)	#6 @ 48 in. o.c.	#6 @ 43 in. o.c.	Footnote (4)	#6 @ 32 in. o.c.	#6 @ 18 in. o.c.
9 feet	4	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	6 in. solid (3) or 8 in.	#4 @ 48 in. o.c.	PC	8 in.	#4 @ 48 in. o.c.	PC
	5	8 in.	#4 @ 48 in. o.c.	PC	10 in.	#4 @ 48 in. o.c.	PC	12 in.	#5 @ 48 in. o.c.	PC
	6	10 in.	#4 @ 48 in. o.c.	PC	12 in.	#4 @ 48 in. o.c.	PC	12 in. solid (3)	#6 @ 48 in. o.c.	#6 @ 35 in. o.c.
	7	12 in.	#5 @ 48 in. o.c.	PC	12 in. solid (3)	#6 @ 48 in. o.c.	#6 @ 35 in. o.c.	Footnote (4)	#6 @ 40 in. o.c.	#6 @ 32 in. o.c.
	8	12 in. solid (3)	#5 @ 48 in. o.c.	#6 @ 36 in. o.c.	Footnote (4)	#6 @ 40 in. o.c.	#6 @ 32 in. o.c.	Footnote (4)	#6 @ 24 in. o.c.	#6 @ 28 in. o.c.
	9	Footnote (4)	#6 @ 40 in. o.c.	#6 @ 35 in. o.c.	Footnote (4)	#6 @ 24 in. o.c.	#6 @ 25 in. o.c.	Footnote (4)	#6 @ 16 in. o.c.	#6 @ 24 in. o.c.
10 feet	8	NA	#6 @ 48 in. o.c.	#6 @ 35 in. o.c.	NA	#6 @ 32 in. o.c.	#6 @ 29 in. o.c.	NA	#6 @ 24 in. o.c.	#6 @ 21 in. o.c.
	9	NA	#6 @ 40 in. o.c.	#6 @ 34 in. o.c.	NA	#6 @ 24 in. o.c.	#6 @ 22 in. o.c.	NA	#6 @ 16 in. o.c.	#6 @ 16 in. o.c.
	10	NA	#6 @ 32 in. o.c.	#6 @ 27 in. o.c.	NA	#6 @ 16 in. o.c.	#6 @ 17 in. o.c.	NA	#6 @ 16 in. o.c.	#6 @ 13 in. o.c.

*Unbalanced backfill height is the difference in height between the exterior finish grade level and the top of the basement slab or crawl space grade. Backfill shall be placed only AFTER the home has been anchored to the foundation wall.

(1) - All block must conform to ASTM C90 (700 psi rated) and be laid in a running bond of Type M or S mortar with overlapping pattern. UngROUTED hollow masonry units are permitted except where otherwise indicated.

(3) - Solid grouted hollow units or solid masonry units.

(4) - Wall construction per reinforced units or design required.

(5) - Vertical reinforcement shall be Grade 60 minimum. The distance from the face of the soil side of the wall to the center of vertical reinforcement shall be at least 5".

(6) - PC = Plain Concrete (Concrete with less reinforcement than minimum for reinforced concrete)

(7) - All reinforcement shall be Grade 60 minimum. The distance from the face of the soil side of the wall to the vertical reinforcement shall be at least 6 1/16", but not more than 6 11/16".

*All information above has been extracted from the 2009 IRC Tables R404.1.1(1), Tables R404.1.1(2) Tables R404.1.2(3)

(8) Reserved

(9) Reserved




Maximum Aspect Ratio, L/W for Unbalanced Foundations

Maximum Wall Height	Maximum Unbalanced Fill	SOIL CLASS		
		GW, GP, SW, & SP (30 PSF)	GM, GC, SM-SC, & ML (45 PSF)	SC, MH, ML-CL, & Inorganic CL (60 PSF)
7 feet	4	4.0	4.0	4.0
	5	4.0	3.4	2.6
	6	3.0	2.0	1.5
	7	1.9	1.2	0.9
8 feet	4	4.0	4.0	4.0
	5	4.0	3.9	2.9
	6	3.4	2.3	1.7
	7	2.1	1.4	1.1
9 feet	8	1.4	1.0	0.7
	4	4.0	4.0	4.0
	5	4.0	4.0	3.3
	6	3.8	2.6	1.9
	7	2.4	1.6	1.2
	8	1.6	1.1	0.8
	9	1.1	0.8	0.6

Instructions:

Where foundation wall support unbalanced load on opposite sides of building such as daylight basement, the building aspect ratio, L/W, shall not exceed the value specified in Table

- 1 - Determine foundation wall height, unbalanced fill depth, and soil class to determine aspect ratio from table above.
- 2 - Multiple "W" times aspect ratio.
- 3 - Result is equal to the maximum allowable building length on the exposed side.



Example 1 - check sidewall for 26'-8" x 60'-0" home.

Basement Wall Height = 8'-0"
 Unbalanced backfill = 7'-0"
 Soil Class = SP
 Aspect Ratio from Table above = 2.1



26.67 x 2.1 = 56'-0" max. allowable length - **example fails**
 Try again using 6'-0" max. unbalanced fill with an aspect ratio of 3.4.
 26.67 x 3.4 = 90'-8" max. allowable length - **example passes**
Max. allowable backfill is 6'-0"

Example 2 - check endwall for 26'-8" x 60'-0" home.

Basement Wall Height = 8'-0"
 Unbalanced backfill = 7'-0"
 Soil Class = SP
 Aspect Ratio from Table above = 2.1
 60 x 2.1 = 126'-0" max. allowable length - **example passes**

"L" = total overall dimension of the building on the exposed side
 "W" = the total overall dimension of the building on the side adjacent to the exposed side

Required Rim Joist to Sill Plate Fastening at wall "L".
Use a 20 Gauge metal angle clip at 24" o.c. with (5) 8d nails per leg or an approved connector supplying 230 pounds per linear foot capacity.

*Page extracted from 2006 IRC section R404.1.5 & Table R404.1(3)

Clayton home building group	
UNBALANCED FOUNDATIONS (TABLE L)	
DATE: 3/27/07	FILENAME: 958I-14.S.J.C.22.22.235()
PAGE #: Page 10 of 27	

TABLE M - MINIMUM CONCRETE BLOCK PIER AND FOOTER SIZE

AT MATING WALL COLUMNS (REF. DETAILS D4 OR D5)						# of Uplift Ties
GROUND SNOW	20	30				
MAXIMUM MATING LINE SPAN BETWEEN MATING WALL COLUMN SUPPORTS	4'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			0
	6'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			0
	8'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			0
	10'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			1
	12'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			1
	14'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			1
	16'	(D) 40"x40"x12" OR 46" Dia. X 19"	(D) 40"x40"x12" OR 46" Dia. X 19"			1
	18'	(D) 40"x40"x12" OR 46" Dia. X 19"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	20'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	22'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	24'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	26'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	28'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	30'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
	32'	(T) 48"x48"x16" OR 56" Dia. X 24"	(T) 48"x48"x16" OR 56" Dia. X 24"			1
34'	(T) 48"x48"x16" OR 56" Dia. X 24"	(DR) 62"x62"x23" OR 70" Dia. X 31"			1	
36'	(T) 48"x48"x16" OR 56" Dia. X 24"	(DR) 62"x62"x23" OR 70" Dia. X 31"			1	
46'	(DR) 62"x62"x23" OR 70" Dia. X 31"	(DR) 62"x62"x23" OR 70" Dia. X 31"			1	
SUPPORTS UNDER MATING OPENING AS CLEARSPANS IN FEET						
PIER SPACING	7.9'	7.9'				
PIER CONFIG.	(S) 28"x28"x10" OR 28" Dia.	(S) 28"x28"x10" OR 28" Dia.				
SUPPORTS UNDER MATING WALLS- CLEARSPANS IN FEET						
PIER SPACING	5.5'	5.5'				
PIER CONFIG.	(D) 40"x40"x12" OR 34" Dia.	(D) 40"x40"x12" OR 34" Dia.				

Girder beams construction to be (4) 2X10 #2 SPF joists. Splices 6" X 8" MiTek MT20 metal plates each side

Chart Key:

(Pier Configuration) Min. footer width (inches) x Min. footer length (inches) x Min. footer depth (inches)

(S)= Single stack block configuration.

(D)= Double stack block configuration.

(T)= Triple stack block configuration.

(DR)=Double stack reinforced & fully grouted configuration.

IE. For 20 psf 178" box with 14' opening:Double stack pier on a 40"x 40" sq. footer 12" deep footing.

30' 1 STORY- 30 PSF ATTIC LIVE OFF FRAME BASEMENT & CRAWL With Roof Pitch of 7/12 Min. to 7/12 Max.

NOTES: 1 DESIGNED FOR 90 MPH MAX. WIND SPEED.

2 DESIGNED FOR 1500 PSF MIN. ALLOWABLE SOIL BEARING CAPACITY.

3 DESIGN TO * Ultimate wind speed Vult. Per ASCE 7-10/ allowable stress design wind speed Vasd. All wind speeds are indicated as (Vasd) design sp

4 MAX. MATING WALL OPENINGS LISTED IN CHART ASSUME OPENING IN BOTH HALVES. IF ANCHOR IS TIED TO ONLY ONE


COLUMN (ONE HALF) THEN HALF THE OPENING SIZE CAN BE USED WHEN LOOKING UP VALUE IN TABLE ABOVE. PIER

SUPPORTS REQUIRED AT EACH SIDE OF DOOR OPENINGS AND ALL EXTERIOR WALL OPENINGS GREATER THAN 4'.

5 WHEN PIER CONFIGURATION IS NOT GIVEN IN CHART THE ACTUAL LOADS EXCEED ALL PREDESIGNED PIERS AND A LOCAL ENGINEER MUST DESIGN THE SUPPORTS FOR THE GIVEN LOADS (- UPLIFT/ + GRAVITY LOADS).

6 ALL PIERS SHALL BE EMBEDDED IN TYPE M OR S MORTAR.

7.Round footers or Round Piles with diameter as required above may be used as alternate to square footing or square footing and block piers.



Model: SN251077
Customer: Wilson

FILENAME:9581-14.S.J.C.22.22.235(_)

TABLE N - STRUCTURAL STEEL POST AND FOOTER SIZE AT MATING WALL COLUMNS (REF. DETAIL D7)

GROUND SNOW		20	30				Uplift force
MAXIMUM MATING LINE SPAN BETWEEN MATING WALL COLUMN SUPPORTS	4'	(9k) 30"x30"x11"	(9k) 30"x30"x11"				0 #
	6'	(9k) 30"x30"x11"	(14k) 38"x38"x13"				0 #
	8'	(14k) 38"x38"x13"	(14k) 38"x38"x13"				0 #
	10'	(14k) 38"x38"x13"	(14k) 38"x38"x13"				14.06 #
	12'	(14k) 38"x38"x13"	(14k) 38"x38"x13"				114.06 #
	14'	(14k) 38"x38"x13"	(14k) 38"x38"x13"				214.06 #
	16'	(14k) 38"x38"x13"	(20k) 44"x44"x14"				314.06 #
	18'	(20k) 44"x44"x14"	(20k) 44"x44"x14"				414.06 #
	20'	(20k) 44"x44"x14"	(20k) 44"x44"x14"				514.06 #
	22'	(20k) 44"x44"x14"	(20k) 44"x44"x14"				614.06 #
	24'	(20k) 44"x44"x14"	(20k) 44"x44"x14"				714.06 #
	26'	(20k) 44"x44"x14"	(20k) 44"x44"x14"				814.06 #
	28'	(20k) 44"x44"x14"	(30k) 54"x54"x17"				914.06 #
	30'	(20k) 44"x44"x14"	(30k) 54"x54"x17"				1014.06 #
	32'	(30k) 54"x54"x17"	(30k) 54"x54"x17"				1114.06 #
34'	(30k) 54"x54"x17"	(30k) 54"x54"x17"				1214.06 #	
36'	(30k) 54"x54"x17"	(30k) 54"x54"x17"				1314.06 #	
46'	(30k) 54"x54"x17"	(30k) 54"x54"x17"				1814.06 #	
SUPPORTS UNDER MATING OPENING AS CLEARSPANS IN FEET							
POST SPACING	7.9'	7.9' O/C					Girder beams construction to be (4) 2X10 #2 SPF joists. Splices 6" X 8" MiTek MT20 metal plates each side.
FOOTER SIZE	(9k) 30"x30"x11"	(9k) 30"x30"x11"					
SUPPORTS UNDER MATING WALLS- CLEARSPANS IN FEET							
POST SPACING	5.5'	5.5'					
FOOTER SIZE	(9k) 30"x30"x11"	(9k) 30"x30"x11"					

Chart Key:

(Post Load)= Minimum allowable compression rating which post must be rated in kips (1000 lbs.).

(Post Capacity and Footer Size) Min. footer width (inches) x Min. footer length (inches) x Min. footer depth (inches)

Note: Steel piers must have a minimum steel base plate size of 4 inches x 5.5 inches which bears directly on footer sized per chart.

Minimum steel column top plate size of 4"x5.5"for 9000#; 6"x6"for 14000#; 6"x8"for 20000# & 6"x12"for 30000#

Minimum footer Reinforcement (Number of #4 bars each way):

Footer size	# of No. 4 bars	Footer size	# of No. 4 bars
30"x30"	3	44"x44"	6
38"x38"	5	54"x54"	9



30' 1 STORY- 30 PSF ATTIC LIVE OFF FRAME BASEMENT & CRAWL With Roof Pitch of 7/12 Min. to 7/12 Max.

NOTES: 1 DESIGNED FOR 90 MPH MAX. WIND SPEED.

2 DESIGNED FOR 1500 PSF MIN. ALLOWABLE SOIL BEARING CAPACITY.

3 DESIGN TO * Ultimate wind speed Vult. Per ASCE 7-10/ allowable stress design wind speed Vasd. All wind speeds are indicated. Model: SN251077

4 MAX. MATING WALL OPENINGS LISTED IN CHART ASSUME OPENING IN BOTH HALVES. IF ANCHOR IS TIED TO ONLY ONE Customer: Wilson

COLUMN (ONE HALF) THEN HALF THE OPENING SIZE CAN BE USED WHEN LOOKING UP VALUE IN TABLE ABOVE. PIERS


SUPPORTS REQUIRED AT EACH SIDE OF DOOR OPENINGS AND ALL EXTERIOR WALL OPENINGS GREATER THAN 4'.

5 WHEN PIER CONFIGURATION IS NOT GIVEN IN CHART THE ACTUAL LOADS EXCEED


FILENAME:9581-14.S.J.C.22.22.235()

ALL PREDESIGNED FOOTERS AND A LOCAL ENGINEER MUST DESIGN THE SUPPORTS

FOR THE GIVEN LOADS (- UPLIFT/ + GRAVITY LOADS).



KEY PLAN
OFF-FRAME BASEMENT - 2 SECTION
 NOT TO SCALE



CROSS SECTION A-A

NOTES:

- MARRIAGE LINE POSTS SHALL SUPPORT THE MARRIAGE WALL, COLUMNS AND STAIR LOADS WHERE OCCURS. REFER TO SPECIFIC FOUNDATION LAYOUT FOR LOCATION INFORMATION.
- SEE GENERAL NOTES SECTION FOR VENTILATION, DRAINAGE AND OTHER FOUNDATION REQUIREMENTS.

APPROVED BY


 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

Model: SN251077
 Customer: Wilson


Clayton home building group

KEY PLAN 7 - OFF-FRAME / BASEMENT / 2 SECTION

DATE: 05/25/07	9581-14.S.J.C.22.22.235()
PAGE #:	
Page 13 of 27	



KEY PLAN
OFF-FRAME CRAWL SPACE - 2 SECTION
 NOT TO SCALE



CROSS SECTION A-A

NOTES:

1. MARRIAGE LINE POSTS SHALL SUPPORT THE MARRIAGE WALL, COLUMNS AND STAIR LOADS WHERE OCCURS. REFER TO SPECIFIC FOUNDATION LAYOUT FOR LOCATION INFORMATION.
2. SEE GENERAL NOTES SECTION FOR VENTILATION, DRAINAGE AND OTHER FOUNDATION REQUIREMENTS.

APPROVED BY

 6/13/2019

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter

Model: SN251077
 Customer: Wilson

Clayton home building group


KEY PLAN 8 - OFF-FRAME / CRAWL SPACE / 2 SECTION

DATE: 05/25/07

958I-14.S.J.C.22.22.235(L)

PAGE #:

Page 14 of 27



TYPICAL SEE DETAIL BELOW FOR FOAM SHEATHING APPLICATION.

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

FOOTER SIZE TABLE

MAX. GROUND SNOW	MIN. FOOTER SIZE WIDTH W	DEPTH H	
		Crawl	Basement
20 PSF	16 "	10"	10"
30 PSF	16 "	10"	10"

**NON-REINFORCED PERIMETER FOUNDATION WALL
 BASEMENT OR CRAWLSPACE
 MAX. 90 MPH WIND SPEED & SEISMIC ZONE C
 30' WIDE 1 STORY- 30 PSF ATTIC LIVE**

NOTES:

- 1) MUD SILL TO FOUNDATION ANCHORS:
 TYPE 4: 1/2" DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH 2"x2"x1/8" WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO SINGLE SILL PLATE.
 TYPE 5: SIMPSON MAB OR MAS MUD SILL ANCHOR INSTALLED PER INSTALLATION INSTRUCTIONS.
- 2) RIM TO MUD SILL FASTENING AND SILL TO FOUNDATION ANCHOR SPACING SHALL BE THE MINIMUM OF:
 - a) SPACING GIVEN IN APPLICABLE TABLES FOR UNIT CONFIGURATION AND WIND SPEED.
 - b) SPACING GIVEN IN BACKFILL/ SIDEWALL TABLES FOR GIVEN UNIT CONFIGURATION, MAXIMUM BASEMENT WALL HEIGHT, BACKFILL DEPTH, AND LOCAL SOIL CLASSIFICATION.
- 3) DISTANCE FROM EDGE OF FOOTER TO FACE OF FOUNDATION WALL (P) SHALL NOT BE LESS THAN 2" AND SHALL NOT EXCEED THE FOOTER THICKNESS (H).
- 4) 1500 PSF MIN. ALLOWABLE SOIL BEARING CAPACITY.

Model: SN251077 Customer: Wilson

Clayton home building group

**NON-REINFORCED PERIMETER
 FOUNDATION WALL - DETAIL - D1**

DATE: 07/17/07 958I-14.S.J.C.22.22.235(U)

PAGE #: Page 15 of 27

APPROVED BY

NIA INC.
6/13/2019

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
David Richter

1/2" BOLTS, NUTS, AND WASHERS OR 3/8" LAG SCREWS REQUIRED THRU RIM JOIST GIRDER. SIZE AND SPACING PER HOME SETUP MANUAL.

MATING WALLS WHERE OCCURS.

SINGLE, DOUBLE OR TRIPLE 2x RIM MEMBER, EACH HALF

DECKING

2x FLOOR JOISTS, 16" O.C.

FILL ANY GAPS AT BOLT LOCATIONS WITH SOLID WOOD SHIMS FOR WOOD TO WOOD CONTACT

SHIM AS NEEDED PER NOTE 4

OPTIONAL FILLER PER NOTE 3

CAP BLOCK PER NOTE 3

MATING LINE PIERS LAID IN MORTAR PER NOTE 2. SINGLE, DOUBLE OR TRIPLE STACKED. SIZE AND SPACING REQUIREMENTS PER TABLE "M"


NOTE: FOR COLUMN TIE-DOWN REQUIREMENTS SEE DETAIL **D6**

D6

APPROVED VAPOR RETARDER OVER FINISH GRADE

67" MAX. ABOVE GRADE


CONCRETE FOOTING BELOW FROST LINE AND MIN. 12" BELOW FINISH GRADE. SIZE PER TABLE "M"



36" MAX. ABOVE GRADE

SINGLE STACKED

67" MAX. ABOVE GRADE



TRIPLE STACKED

**NON-REINFORCED MATING WALL OR COLUMN SUPPORT PIER
CRAWL SPACE ONLY**

Model: 314231077 Customer: WILSON

NOTES:

1. FOOTINGS MUST BE LEVEL IN ALL DIRECTIONS. PIERS ARE TO BE PLACED CENTERED ON THE FOOTING SO THAT THE FOOTING PROJECTION FROM THE PIER IS EQUAL FROM SIDE-TO-SIDE AND FRONT-TO-BACK. PIERS MUST BE LEVEL VERTICALLY ON ALL SIDES AND SQUARE WITH THE FOOTING.
2. CONCRETE BLOCKS FOR PIERS ARE 8" x 16" x 8" NOMINAL SIZE, HOLLOW CELL LOAD BEARING CMU's MANUFACTURED IN CONFORMANCE WITH ASTM C90, GRADE "N". OPEN CELLS ARE ALIGNED VERTICALLY. THE PIERS SHALL BE LAID IN RUNNING BOND WITH TYPE M OR S MORTAR OR APPROVED ALTERNATE (SEE GENERAL NOTE 12). SINGLE STACKED BLOCKS TO BE LAID WITH LONG SIDE PERPENDICULAR TO MATE LINE RIM JOISTS. DOUBLE STACKED BLOCK IS LAID WITH EACH LAYER AT A RIGHT ANGLE TO THE PREVIOUS LAYER. THE TOP COURSE OR THE CAP BLOCKS SHALL BE PERPENDICULAR TO THE MATE LINE RIM JOISTS.
3. CAP BLOCKS SHALL BE 4" SOLID CONCRETE OR MASONRY BLOCK. 2x NOMINAL HARDWOOD OR 1/2" STEEL MAY BE USED AS A CAP BLOCK IF THE TOP COURSE OF THE PIER IS SOLID MASONRY OR CONCRETE OR IF THE TOP COURSE OF A HOLLOW PIER IS FILLED WITH CONCRETE OR GROUT. OPTIONAL FILLER MATERIAL MAY BE 2x NOMINAL HARDWOOD OR 2" OR 4" NOMINAL SOLID CONCRETE BLOCK. ALL CAPS AND FILLER SHALL BE OF THE SAME NOMINAL DIMENSIONS AS THE PIERS THEY REST UPON. INDIVIDUAL LENGTHS OF CAP BLOCKS AND FILLER SHALL BE PERPENDICULAR TO THE MATE LINE RIM JOISTS.
4. SHIMS SHALL BE OF HARDWOOD, AT LEAST 3 1/2" WIDE AND 6" LONG AND ARE NOT TO EXCEED ONE INCH IN THICKNESS. SHIMS SHALL BE PERPENDICULAR TO MATE LINE, FITTED AND DRIVEN TIGHT BETWEEN CAP BLOCKS OR FILLER AND MATE LINE RIM JOISTS.
5. MARRIAGE LINE PIERS SHALL SUPPORT THE MARRIAGE WALL AND COLUMNS WHERE OCCURS PER MODEL SPECIFIC FOUNDATION PLAN. MAXIMUM PIER SPACING PER TABLE "M".
6. SEE GENERAL NOTES FOR DRAINAGE AND OTHER FOUNDATION REQUIREMENTS.

Clayton home building group


**NON-REINFORCED MATING
WALL COLUMN SUPPORT PIER
- CRAWLSPACE ONLY - DETAIL
- D3**

DATE: 06/13/07

9581-14.S.J.C.22.22.235()

PAGE #:

Page 16 of 27



**REINFORCED MATING WALL OR COLUMN SUPPORT PIER
BASEMENT OR CRAWL SPACE
(PIER SPACING AND FOOTER SIZE PER TABLE M)**


Model: SN251077
Customer: Wilson

- NOTES:**
1. FOOTINGS MUST BE LEVEL IN ALL DIRECTIONS. PIERS ARE TO BE PLACED CENTERED ON THE FOOTING SO THAT THE FOOTING PROJECTION FROM THE PIER IS EQUAL FROM SIDE-TO-SIDE AND FRONT-TO-BACK. PIERS MUST BE LEVEL VERTICALLY ON ALL SIDES AND SQUARE WITH THE FOOTING.
 2. CONCRETE BLOCKS FOR PIERS ARE 8" x 16" x 8" NOMINAL SIZE, HOLLOW CELL LOAD BEARING CMU'S MANUFACTURED IN CONFORMANCE WITH ASTM C90, GRADE "N". OPEN CELLS ARE ALIGNED VERTICALLY. THE PIERS SHALL BE LAID IN RUNNING BOND WITH TYPE M OR S MORTAR. SINGLE STACKED BLOCKS TO BE LAID WITH LONG SIDE PERPENDICULAR TO MATE LINE RIM JOISTS. DOUBLE STACKED BLOCK IS LAID WITH EACH LAYER AT A RIGHT ANGLE TO THE PREVIOUS LAYER. THE TOP COURSE OR THE CAP BLOCKS SHALL BE PERPENDICULAR TO THE MATE LINE RIM JOISTS.
 3. CAP BLOCKS SHALL BE 4" SOLID CONCRETE OR MASONRY BLOCK. 2x NOMINAL HARDWOOD OR 1/2" STEEL MAY BE USED AS A CAP BLOCK IF THE TOP COURSE OF THE PIER IS SOLID MASONRY OR CONCRETE OR IF THE TOP COURSE OF A HOLLOW PIER IS FILLED WITH CONCRETE OR GROUT. OPTIONAL FILLER MATERIAL MAY BE 2x NOMINAL HARDWOOD OR 2" OR 4" NOMINAL SOLID CONCRETE BLOCK. ALL CAPS AND FILLER SHALL BE OF THE SAME NOMINAL DIMENSIONS AS THE PIERS THEY REST UPON. INDIVIDUAL LENGTHS OF CAP BLOCKS AND FILLER SHALL BE PERPENDICULAR TO THE MATE LINE RIM JOISTS.
 4. SHIMS SHALL BE OF HARDWOOD, AT LEAST 3 1/2" WIDE AND 6" LONG AND ARE NOT TO EXCEED ONE INCH IN THICKNESS. SHIMS SHALL BE PERPENDICULAR TO MATE LINE, FITTED AND DRIVEN TIGHT BETWEEN CAP BLOCKS OR FILLER AND MATE LINE RIM JOISTS.
 5. MARRIAGE LINE PIERS SHALL SUPPORT THE MARRIAGE WALL AND COLUMNS WHERE OCCURS PER MODEL SPECIFIC FOUNDATION PLAN. MAXIMUM PIER SPACING PER TABLE "M".
 6. SEE GENERAL NOTES FOR DRAINAGE AND OTHER FOUNDATION REQUIREMENTS.

Clayton home building group

**REINFORCED MATING WALL OR
COLUMN SUPPORT PIER -
BASEMENT OR CRAWL SPACE
DETAIL - D5**

DATE: 06/04/07	9581- 14.S.J.C.22.22.235()
PAGE #:	
Page 17 of 27	



APPROVED BY
NIA INC. 6/13/2019

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

- NOTES:**
1. ALL MARRIAGE WALL COLUMN LOCATIONS WITH OPENINGS 4 FEET OR GREATER MAY REQUIRE THE INSTALLATION OF COLUMN BRACKETS AND TIE-DOWNS. SEE TABLE "M" FOR REQUIREMENTS.
 2. EACH BRACKET IS RATED FOR AN ALLOWABLE WORKING LOAD OF 1,719 LBS.
 3. THE CAPACITY OF BOTH THE TIE-DOWN STRAP AND ANCHOR MUST BE 3,150 LBS. WORKING LOAD (4,725 LBS. ULTIMATE)
 4. USE A RADIUS CLIP FOR ALL BRACKET APPLICATIONS BY THREADING A PIECE OF STRAP OVER THE BRACKETS BEFORE LOOPING THE TIE-DOWN STRAP AROUND THE BRACKET.
 5. GROUND ANCHORS WHICH ARE LISTED FOR THE REQUIRED CAPACITY ABOVE MAY BE USED IN LIEU OF CONCRETE ANCHOR.
 6. DISTANCE FROM EDGE OF FOOTING TO FACE OF FOUNDATION WALL (P) SHALL NOT BE LESS THAN 2" AND SHALL NOT EXCEED THE FOOTING THICKNESS (H). FOOTING THICKNESS MAY BE 10" IF GROUND ANCHORS WITH AN UPLIFT CAPACITY OF 3,150 LBS. ARE USED IN PLACE OF CONCRETE ANCHORS.
 7. FOOTING SIZES PER TABLE "M" HAVE BEEN DESIGNED ASSUMING CONCRETE ANCHORS WILL BE UTILIZED. IF GROUND ANCHORS ARE UTILIZED TO TRANSMIT UPLIFT INTO GROUND SOIL, THE DEPTH OF THE FOOTING MAY BE REDUCED TO (P). WHERE (P) IS EQUAL TO THE GREATEST DISTANCE FROM EDGE OF FOOTING TO EDGE OF PIER. MINIMUM DEPTH IS 9".

Clayton home building group

MATING WALL COLUMN TIE DOWN - DETAIL - D6

DATE: 06/29/07 9581-14.S.J.C.22.22.235(L)

PAGE #: **Page 18 of 27**

1/2" BOLTS, NUTS, AND WASHERS OR 3/8" LAG SCREWS REQUIRED THRU RIM JOIST GIRDER. SIZE AND SPACING PER HOME SETUP MANUAL

MATING WALLS WHERE OCCURS.
SINGLE, DOUBLE OR TRIPLE 2x RIM MEMBER, EACH HALF
DECKING
2x FLOOR JOISTS, 16" O.C.

FILL ANY GAPS AT BOLT LOCATIONS WITH SOLID WOOD SHIMS FOR WOOD TO WOOD CONTACT.
(2) 5/16" x 3" LAG SCREWS WITH WASHERS THROUGH POST PLATE INTO RIM JOIST. PILOT HOLES MUST BE SITE DRILLED.

11 GA., 3" DIA. MIN. ADJUSTABLE STEEL MONO POST WITH MIN. 1/4" PLATES TOP AND BOTTOM. SIZE AND SPACING PER TABLE "N".
NOTE: THE MIN. CAPACITY RATING OF EACH POST MUST BE GREATER THAN OR EQUAL TO THE SPECIFIED LOAD CAPACITY OF TABLE "N".

SECURE STEEL POST BOTTOM PLATE TO FOOTING WITH (4) 1/2" DIA. ANCHOR BOLTS OR WEDGE ANCHORS, NUTS AND WASHERS. (UTILIZE 5/8" DIA. ANCHOR BOLTS FOR SEISMIC DESIGN CATEGORY "E" OR HIGHER). MAKE POST ADJUSTMENTS BEFORE POURING SLAB.

APPROVED VAPOR RETARDER

NOTE:
FOR POST SUPPORTING MATING WALL OPENINGS, POST MUST BE RATED AND SECURED TO GIRDER BEAM AND FOOTING FOR UPLIFT FORCE SPECIFIED IN TABLE "N".

3 1/2" MIN. CONCRETE SLAB ON GRADE. IMPORTANT: ALL STEEL POSTS MUST BE INSTALLED AND FINAL ADJUSTMENTS MADE BEFORE SLAB IS POURED. POURED SLAB LOCKS POST ADJUSTMENTS PERMANENTLY.

REINFORCED CONCRETE FOOTING WITH (3) #4 REBARS EACH WAY. SIZE PER TABLE "N".

ALTERNATE POST INSTALLATION: STEEL POSTS MAY BE INSTALLED WITH SCREW JACK ASSEMBLY AT THE TOP OR BOTTOM. STEEL POSTS INSTALLED WITHOUT THE SCREW JACK ASSEMBLY AT THE BOTTOM AND ENCASED IN CONCRETE ARE SUBJECT TO LOAD REDUCTIONS. VERIFY THE CAPACITY OF THE STEEL POST BASED ON THE INSTALLATION METHOD PRIOR TO INSTALLATION OF THE POST.

APPROVED BY

NIA 6/13/2019
INC.

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

**ADJUSTABLE STEEL COLUMN POST
BASEMENT OR CRAWL SPACE
(MAXIMUM POST SPACING PER TABLE N)**

NOTES:

1. FOOTINGS MUST BE LEVEL IN ALL DIRECTIONS. STEEL POSTS ARE TO BE PLACED CENTERED ON THE FOOTING SO THAT THE FOOTING PROJECTION FROM THE POST IS EQUAL FROM SIDE-TO-SIDE AND FRONT-TO-BACK. COLUMN POSTS MUST BE LEVEL VERTICALLY ON ALL SIDES AND SQUARE WITH THE FOOTING.
2. MARRIAGE LINE STEEL POSTS SHALL SUPPORT THE MARRIAGE WALL AND COLUMNS WHERE OCCURS PER
3. SEE GENERAL NOTES FOR DRAINAGE AND OTHER FOUNDATION REQUIREMENTS.

Clayton home building group

**ADJUSTABLE STEEL COLUMN
POST - BASEMENT OR CRAWL
SPACE - DETAIL - D7**

DATE: 06/08/07

9581-14.S.J.C.22.22.235()

PAGE #:

Page 19 of 27


Model: SN251077

Customer: Wilson

APPROVED BY




Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter



SIMPSON MSTCM40 STRAP OR STHD14 STRAP IS IN ADDITION TO REQUIRED ANCHOR BOLTS AND RIM TO MUD SILL FASTENING REQUIREMENTS. (SEE HOME FLOOR TO SILL PLATE AND SILL PLATE TO FOUNDATION CHARTS FOR NUMBER OF STRAPS REQUIRED AT EACH HOLD-DOWN LOCATION.)

NOTE: STRAP MUST BE POSITIONED A MINIMUM OF 1 1/2" FROM EDGE OF FOUNDATION WALL.



SHEARWALL FOUNDATION HOLD-DOWN

Model: SN251077 Customer: Wilson

NOTES:

1. WHERE REQUIRED AT FREE-END HOLD-DOWNS (AS LOCATED ON THE FOUNDATION LAYOUT) OR AT BUILDING CORNERS PER THE FASTENING TABLES INCLUDED WITHIN THIS FOUNDATION DESIGN PACKAGE, THE FOUNDATION HOLD-DOWN STRAPS ARE THE RESPONSIBILITY OF OTHERS AND ARE NOT PROVIDED BY CLAYTON HOME BUILDING GROUP OR SUBSIDIARIES.
2. SIMPSON MSTCM40 SHALL BE FASTENED TO WALL STUD WITH (26) 16d NAILS AND TO FOUNDATION WALL WITH (14) 1/4" x 2 1/4" TITAN SCREWS.
3. SIMPSON MSTCM40 OR STHD14 STRAP MAY BE PLACED ON ENDWALL OR SIDEWALL. MINIMUM EDGE DISTANCE OF TITAN SCREW TO CONCRETE OR MASONRY BLOCK CORNER OF 1 1/2" MUST BE MAINTAINED.
4. SIMPSON MSTCM40 STRAP IS IN ADDITION TO THE REQUIRED ANCHOR BOLTS AND RIM TO MUD SILL FASTENING REQUIREMENTS.
5. SIMPSON STHD14 STRAP (POURED WALLS) MUST BE FASTENED TO WALL STUD WITH (38) .148X 3 1/4" NAILS.)
6. DESIGN STRAP CAPACITY: MSTCM40=4250# AND STHD14= 5025#

Clayton home building group

SHEARWALL FOUNDATION HOLD-DOWN - DETAIL - D18

DATE: 06/13/07

9581-14.S.J.C.22.22.235()

PAGE #:

Page 20 of 27



APPROVED BY




Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

WHEN FASTENING TABLES WITH H PLATES ARE USED SIMPSON LTP4 SHALL BE INSTALLED PER DETAIL H TO BOTH BOTTOM MUD SILL TO UPPER MUD SILL & TOP MUD SILL TO RIM JOIST. SPACING PER HOME FLOOR TO SILL PLATE & SILL WITH H PLATE TABLES.



FASTEN UPPER TOP PLATE TO BOTTOM PLATE WITH 8D (.131 x 3") NAILS SPACED PER TYPE E FASTENER TYPE SPACING FOR RIM TO SILL



FASTEN RIM JOIST TO SILL WITH 10D (.148 x 3") CORROSION RESISTANT NAILS. ON CENTER SPACING OF FASTENER TYPE "E" IN TABLES. NOTE: IF SPACING REQUIRES ADDITIONAL TYPE "H" PLATE CONNECTORS, SEE DETAIL ABOVE AND DETAIL (H)

MIN 2x6 TREATED MUD SILLS TOP PLATE ONLY MAY BE NOTCHED OR COUNTER SUNK TO RECEIVE NUTS/ WASHERS

Model: SN251077

Customer: Wilson

DOUBLE MUD SILL OPTION

NOTES:

1. MUD SILL TO FOUNDATION ANCHORS:
TYPE 4:1/2" DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH 2"x2"x1/8" WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO BOTTOM MUD SILL PLATE.
2. UPPER MUD SILL MUST BE FASTENED TO LOWER MUD SILL WITH .131"x3" NAILS SPACED PER RIM JOIST TO MUD SILL SPACING TABLE FOR TYPE E FASTENERS.
4. WHEN FASTENING TABLES WITH H PLATES ARE USED, SIMPSON LPT4 PLATES MUST BE INSTALLED FROM LOWER MUD SILL TO UPPER MUD SILL AND FROM UPPER MUD SILL TO RIM JOIST PER FASTENING SPACED PER RIM TO MUD SILL SPACING TABLES.



Clayton home building group

DOUBLE MUD SILL FOUNDATION WALL DETAIL - D34

DATE: 06/04/07

I-14.S.CC.C.42.0.235

PAGE #:



ALTERNATE FASTENER:


THE FOLLOWING ALTERNATE FASTENERS MAY BE USED WHEN SPACING IN CHART IS MULTIPLIED BY THE FOLLOWING FASTENER MULTIPLIER.

- 8D (.131 x 3") NAIL = .82
- 16D (.162 x 3 1/2") NAIL = 1.2
- #8 x 3" WOOD SCREW = .78

DETAIL A- DIRECT RIM TO SILL FASTENING

APPROVED BY
NIA INC. 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter

FASTENED THRU $\frac{7}{16}$ " MAX. EXTERIOR SHEATHING



ALTERNATE FASTENER:

FASTENERS MAY BE INSTALLED THROUGH $\frac{7}{16}$ " MAXIMUM THICK WALL SHEATHING WHEN SPACING IN CHARTS ARE REDUCED BY MULTIPLYING BY THE FOLLOWING:

- 10d (.148"x3") NAIL = .68
- 8D (.131 x 3") NAIL = .55
- 16D (.162 x 3 1/2") NAIL = .816
- #8 x 3" WOOD SCREW = .53

DETAIL B- THRU SHEATHING RIM TO SILL FASTENING

FLOOR TO SILL PLATE FASTENING -TYPE "E" -ENDWALL OR SIDEWALL

NOTES:

- 1) MUD SILL TO FOUNDATION ANCHORS:
 TYPE 4: DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO SINGLE SILL PLATE.
 TYPE 5: SIMPSON MAB OR MASA MUD SILL ANCHOR INSTALLED PER INSTALLATION INSTRUCTIONS
- 2) RIM TO MUD SILL FASTENING AND SILL TO FOUNDATION ANCHOR SPACING SHALL BE THE MINIMUM OF:
 - a) SPACING GIVEN IN APPLICABLE TABLES FOR UNIT CONFIGURATION AND WIND SPEED.
 - b) SPACING GIVEN IN BACKFILL/ SIDEWALL TABLES FOR GIVEN UNIT CONFIGURATION, MAXIMUM BASEMENT WALL HEIGHT, BACKFILL DEPTH, AND LOCAL SOIL CLASSIFICATION.

Clayton home building group


FLOOR TO SILL PLATE FASTENING - ENDWALL OR SIDEWALL - DETAIL - E

DATE: 04/17/07

958I-14.S.J.C.22.22.235()

PAGE #:

Page 22 of 27



2x12 TREATED MUD SILL REQUIRED

SILL PLATE ANCHOR (TYPE "4" OR "5")
(SEE NOTE #1)
SIZE AND SPACING PER TABLES

FASTEN OVERSIZED MUD SILL TO 16" O.C. FLOOR JOISTS WITH 10D (.148 x 3") CORROSION RESISTANT NAILS. QUANTITY OF FASTENER TYPE "F" IN TABLES. NOTE: IF TABLE QUANTITY REQUIRES ADDITIONAL TYPE "H" PLATE CONNECTORS, SEE DETAIL **H**

APPROVED BY
NIA INC. 6/13/2019
Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

ALTERNATE FASTENERS:
THE FOLLOWING ALTERNATE FASTENERS MAY BE USED WHEN QUANTITY IN TABLE IS MULTIPLIED BY THE FOLLOWING FASTENER MULTIPLIER.

8D (.131 x 3") NAIL = 1.21
16D (.162 x 3 1/2") NAIL = .83
#8 x 3" WOOD SCREW = 1.28

NOTE: THIS DETAIL FOR TYPE "F" FASTENING IS APPLICABLE TO SIDEWALL CONNECTIONS ONLY AND CAN NOT BE USED FOR ENDWALLS. SEE FASTENING TYPE "E" OR TYPE "G" FOR ENDWALL APPLICATION.

FLOOR TO SILL PLATE FASTENING - TYPE "F" - SIDEWALL ONLY

NOTES:

- 1) MUD SILL TO FOUNDATION ANCHORS:
TYPE 4: DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO SINGLE SILL PLATE.
TYPE 5: SIMPSON MAB OR MASA MUD SILL ANCHOR INSTALLED PER INSTALLATION INSTRUCTIONS
- 2) RIM TO MUD SILL FASTENING AND SILL TO FOUNDATION ANCHOR SPACING SHALL BE THE MINIMUM OF:
 - a) SPACING GIVEN IN APPLICABLE TABLES FOR UNIT CONFIGURATION AND WIND SPEED.
 - b) SPACING GIVEN IN BACKFILL/ SIDEWALL TABLES FOR GIVEN UNIT CONFIGURATION, MAXIMUM BASEMENT WALL HEIGHT, BACKFILL DEPTH, AND LOCAL SOIL CLASSIFICATION.

Clayton home building group

**FLOOR TO SILL PLATE FASTENING - SIDEWALL ONLY
DETAIL - F**

DATE: 04/17/07

958I-14.S.J.C.22.22.235()

PAGE #:


Page 23 of 27

APPROVED BY




Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.

David Richter




ENDWALL DETAIL

SIMPSON STRONG-TIE A23 ANGLE FASTENED TO FLOOR JOIST AND MUD SILL WITH (4) 10D (.148 x 1.5") NAILS. (CORROSION RESISTANT NAIL REQUIRED INTO P.T. MUD SILL) O.C. SPACING PER FASTENER TYPE "G" IN TABLES. NOTE: IF SPACING REQUIRES ADDITIONAL TYPE "H" PLATE CONNECTORS, SEE DETAIL **(H)**



SIDEWALL DETAIL

SIMPSON STRONG-TIE A23 ANGLE FASTENED TO FLOOR JOIST AND MUD SILL WITH (4) 10D (.148 x 1.5") NAILS. (CORROSION RESISTANT NAIL REQUIRED INTO P.T. MUD SILL) USE (1) OR (2) ANGLES EA. JOIST PER FASTENER TYPE "G" IN TABLES. NOTE: IF SPACING REQUIRES ADDITIONAL TYPE "H" PLATE CONNECTORS, SEE DETAIL **(H)**



SIMPSON STRONG-TIE 'A23' ANGLE

FLOOR TO SILL PLATE FASTENING - TYPE "G" -ENDWALL OR SIDEWALL

NOTES:

- 1) MUD SILL TO FOUNDATION ANCHORS:
 - TYPE 4: DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO SINGLE SILL PLATE.
 - TYPE 5: SIMPSON MAB OR MASA MUD SILL ANCHOR INSTALLED PER INSTALLATION INSTRUCTIONS
- 2) RIM TO MUD SILL FASTENING AND SILL TO FOUNDATION ANCHOR SPACING SHALL BE THE MINIMUM OF:
 - a) SPACING GIVEN IN APPLICABLE TABLES FOR UNIT CONFIGURATION AND WIND SPEED.
 - b) SPACING GIVEN IN BACKFILL/ SIDEWALL TABLES FOR GIVEN UNIT CONFIGURATION, MAXIMUM BASEMENT WALL HEIGHT, BACKFILL DEPTH, AND LOCAL SOIL CLASSIFICATION.

Clayton home building group

FLOOR TO SILL PLATE FASTENING - ENDWALL OR SIDEWALL - DETAIL - G

DATE: 05/25/07

9581-14.S.J.C.22.22.235()



PAGE #:

Page 24 of 27

SIMPSON STRONG-TIE LPT4 OR TP35 TIE PLATE FASTENED TO RIM JOIST AND MUD SILL WITH (12) 8D (.131 x 1.6") NAILS. CORROSION RESISTANT NAILS REQUIRED INTO P.T. MUD SILL.

QUANTITY, LOCATION AND O.C. SPACING PER NOTES 6 OR 7 IN TABLES.

NOTE: USE OF TIE PLATES IS FOR WIND LOAD ONLY AND MUST BE IN ADDITION TO FASTENING REQUIRED FOR BACKFILL PRESSURE PER DETAILS



SIMPSON STRONG-TIE "LPT4" TIE PLATE

SIMPSON STRONG-TIE "TP35" TIE PLATE

APPROVED BY
NIA 6/13/2019
INC.
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter

FLOOR TO SILL PLATE FASTENING - TYPE "H" - ENDWALL OR SIDEWALL

NOTES:

- 1) MUD SILL TO FOUNDATION ANCHORS:
 TYPE 4: DIAMETER STEEL ANCHOR BOLTS EMBEDDED 7" MIN. INTO CONCRETE FOUNDATION WALL OR CLOSE CELL CMU WITH WASHERS AND NUTS. BOLT HEADS SHALL NOT BE RECESSED INTO SINGLE SILL PLATE.
 TYPE 5: SIMPSON MAB OR MASA MUD SILL ANCHOR INSTALLED PER INSTALLATION INSTRUCTIONS
- 2) RIM TO MUD SILL FASTENING AND SILL TO FOUNDATION ANCHOR SPACING SHALL BE THE MINIMUM OF:
 - a) SPACING GIVEN IN APPLICABLE TABLES FOR UNIT CONFIGURATION AND WIND SPEED.
 - b) SPACING GIVEN IN BACKFILL/ SIDEWALL TABLES FOR GIVEN UNIT CONFIGURATION, MAXIMUM BASEMENT WALL HEIGHT, BACKFILL DEPTH, AND LOCAL SOIL CLASSIFICATION.

Clayton home building group

FLOOR TO SILL PLATE FASTENING - ENDWALL OR SIDEWALL - DETAIL - H

DATE: 04/17/07

958I-14.S.J.C.22.22.235(L)

PAGE #:

Page 25 of 27

Home Floor to Sill Plate & Sill Plate to Foundation WITH TYPE H PLATE CONNECTORS (See note 6 & 7)

SOIL CLASSES SC, ML-CL AND INORGANIC CL SOILS [Allowable bearing capacity of 1500 psf or less]

Unit Width: 29.67' to 29.67' Max.

Unit Length: 76' Max.

Roof Pitch: 7/12 to 7/12

Max. Roof Overhang: 12 "

Max. Sidewall Height: 9'

*Wind Speed (3s): 90

Seismic Zone C

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

Model: SN251077

Customer: Wilson

MAXIMUM FASTENER SPACING OR FASTENERS PER JOIST SPACING ^{4,5 & 6}											# REQ'D S/W HDS
SIDEWALL FASTENING SPACING ¹					END WALL FASTENING					SEE D18 /CORNER	
Foundation Wall ¹⁰		Rim to Sill ^b			Sill to Fnd. Wall		Rim to Sill ⁷		Sill to Fnd. Wall		
Wall Height	Backfill Depth	Fastener Type			Anchor Spacing		Fastener Type		Anchor Spacing		
		E	F ^a	G ^a	4	5	E	G	4	5	
24 "	16 "	14.7" o.c.	1	1	72" o.c.	72" o.c.	40" o.c.	492" o.c.	54" o.c.	29" o.c.	0
32 "	24 "	14.7" o.c.	1	1	72" o.c.	72" o.c.	16" o.c.	194" o.c.	53" o.c.	28" o.c.	0
40 "	32 "	8.4" o.c.	2	1	72" o.c.	72" o.c.	8" o.c.	102" o.c.	49" o.c.	28" o.c.	0
3.833'	3.33'	4.9" o.c.	2	1	50" o.c.	55" o.c.	5" o.c.	61" o.c.	41" o.c.	26" o.c.	0
7'	4'	5.2" o.c.	2	1	53" o.c.	59" o.c.	5" o.c.	64" o.c.	42" o.c.	26" o.c.	0
7'	5'	NA	4	1	25" o.c.	27" o.c.	NA	33" o.c.	25" o.c.	20" o.c.	0
7'	6'	NA	6	2	14" o.c.	15" o.c.	NA	19" o.c.	14" o.c.	14" o.c.	0
8'	4'	5.9" o.c.	2	1	62" o.c.	69" o.c.	6" o.c.	73" o.c.	45" o.c.	27" o.c.	0
8'	5'	3.0" o.c.	3	1	29" o.c.	32" o.c.	3" o.c.	37" o.c.	29" o.c.	21" o.c.	0
8'	6'	NA	6	2	16" o.c.	18" o.c.	NA	22" o.c.	16" o.c.	15" o.c.	0
8'	7'	NA	9	2	10" o.c.	11" o.c.	NA	14" o.c.	10" o.c.	10" o.c.	0
9'	3'	14.7" o.c.	1	1	72" o.c.	72" o.c.	16" o.c.	194" o.c.	53" o.c.	28" o.c.	0
9'	4'	6.7" o.c.	2	1	72" o.c.	72" o.c.	7" o.c.	82" o.c.	47" o.c.	27" o.c.	0
9'	5'	3.4" o.c.	3	1	33" o.c.	36" o.c.	3" o.c.	42" o.c.	32" o.c.	23" o.c.	0
9'	6'	NA	5	2	18" o.c.	20" o.c.	NA	24" o.c.	18" o.c.	17" o.c.	0
9'	7'	NA	8	2	11" o.c.	12" o.c.	NA	15" o.c.	11" o.c.	11" o.c.	0
9'	8'	NA	11	NA	7" o.c.	8" o.c.	NA	10" o.c.	7" o.c.	8" o.c.	0

NOTES:

- Foundation wall height at connector should be used at sidewalls or Max. height along sidewall for End wall fastening in table above.
- See details for additional fastener options.
- All fastener spacing must start within 12" maximum of each corner or half specified spacing (lesser of two).
- Type F & G connectors are qty. per 16" oc. Joist spacing.
- Fastener Type Key:
 - * Type E*- Fasteners toe-nailed through rim joist into sill plate (Refer to Detail E)
 - *Type F*- Fasteners direct nailed from sill plate into each floor joist (Applicable at Sidewalls only) (Refer to Detail F)
 - *Type G*- Number of Simpson A23 angles fastened to sill plate and each 16" OC. (2x8 min. sill plate) (Refer to Detail G)
 - *Type H*- Simpson LPT4 or TP35 plate fastened to rim joist and mud sill with (12) 8dx1.5" treated nails. (Refer to Detail H)
- Anchor Types:
 - *Type 4*- 1/2" x10" Anchor Bolt with 2"x2"x1/8" Washer between plate and nut.
 - *Type 5*- Simpson MAB15 (concrete) or MAB23 (concrete block) or MASA
- Fasteners are in addition to (2) Type H tie plates spaced within 6' of corners & 96" oc. elsewhere along sidewalls.(See note 3)
- Fasteners are in addition to Type H tie plates spaced at 32" oc. along endwall.
- Three options (E,F,& G) for rim to sill fastening and two options (4 & 5) for sill plate to foundation anchorage have been provided in chart. Any combination of rim sill connectors and mud sill anchors maybe used.
- All connection hardware, anchor bolts, straps, hold-downs, washers and fasteners shall be galvanized or stainless when in contact with PT sill plates or other PT lumber.
- Maximum foundation wall height and maximum unbalanced backfill.

958I-14.S.J.C.22.22.235(_)

Home Floor to Sill Plate & Sill Plate to Foundation WITHOUT TYPE H PLATE CONNECTORS (See note 6 & 7)

SOIL CLASSES SC, ML-CL AND INORGANIC CL SOILS [Allowable bearing capacity of 1500 psf or less]

Unit Width: 29.67' to 29.67' Max.

Unit Length: 76' Max.

Roof Pitch: 7/12 to 7/12

Max. Roof Overhang: 12 "

Max. Sidewall Height: 9'

***Wind Speed (3s): 20**

Seismic Zone C

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

Model: SN251077

Customer: Wilson

Foundation Wall ¹⁰		MAXIMUM FASTENER SPACING OR FASTENERS PER JOIST SPACING ^{2,3 & 5}										# REQ'D S/W HDS SEE D18 /CORNER
		SIDEWALL FASTENING SPACING ¹					END WALL FASTENING					
		Rim to Sill ^b			Sill to Fnd. Wall		Rim to Sill ^f		Sill to Fnd. Wall			
Wall Height	Backfill Depth	Fastener Type			Anchor Spacing		Fastener Type		Anchor Spacing			
		E	F ^a	G ^a	4	5	E	G	4	5		
24 "	16 "	9.2" o.c.	1	1	72" o.c.	72" o.c.	8" o.c.	29" o.c.	54" o.c.	29" o.c.	1	
32 "	24 "	9.2" o.c.	1	1	72" o.c.	72" o.c.	7" o.c.	28" o.c.	53" o.c.	28" o.c.	1	
40 "	32 "	9.2" o.c.	1	1	72" o.c.	72" o.c.	7" o.c.	25" o.c.	49" o.c.	28" o.c.	1	
3.833'	3.33'	5.8" o.c.	2	1	50" o.c.	55" o.c.	5" o.c.	20" o.c.	41" o.c.	26" o.c.	1	
7'	4'	6.2" o.c.	2	1	53" o.c.	59" o.c.	6" o.c.	20" o.c.	42" o.c.	26" o.c.	1	
7'	5'	NA	4	1	25" o.c.	27" o.c.	3" o.c.	11" o.c.	25" o.c.	20" o.c.	1	
7'	6'	NA	6	2	14" o.c.	15" o.c.	NA	6" o.c.	14" o.c.	14" o.c.	0	
8'	4'	7.3" o.c.	2	1	62" o.c.	69" o.c.	6" o.c.	22" o.c.	45" o.c.	27" o.c.	1	
8'	5'	3.4" o.c.	3	1	29" o.c.	32" o.c.	4" o.c.	13" o.c.	29" o.c.	21" o.c.	1	
8'	6'	NA	5	2	16" o.c.	18" o.c.	NA	7" o.c.	16" o.c.	15" o.c.	0	
8'	7'	NA	8	2	10" o.c.	11" o.c.	NA	4" o.c.	10" o.c.	10" o.c.	0	
9'	3'	9.2" o.c.	1	1	72" o.c.	72" o.c.	7" o.c.	28" o.c.	53" o.c.	28" o.c.	1	
9'	4'	8.4" o.c.	2	1	72" o.c.	72" o.c.	6" o.c.	23" o.c.	47" o.c.	27" o.c.	1	
9'	5'	3.8" o.c.	3	1	33" o.c.	36" o.c.	4" o.c.	14" o.c.	32" o.c.	23" o.c.	1	
9'	6'	NA	5	1	18" o.c.	20" o.c.	NA	8" o.c.	18" o.c.	17" o.c.	0	
9'	7'	NA	7	2	11" o.c.	12" o.c.	NA	5" o.c.	11" o.c.	11" o.c.	0	
9'	8'	NA	11	NA	7" o.c.	8" o.c.	NA	3" o.c.	7" o.c.	8" o.c.	0	

NOTES:

1. RESERVED
2. See details for additional fastener options.
3. All fastener spacing must start within 12" maximum of each corner or half specified spacing (lesser of two).
4. Type F & G connectors are qty. per 16" oc. Joist spacing.
5. Fastener Type Key:
 - "Type E"- Fasteners toe-nailed through rim joist into sill plate (Refer to Detail E)
 - "Type F"- Fasteners direct nailed from sill plate into each floor joist (Applicable at Sidewalls only) (Refer to Detail F)
 - "Type G"- Number of Simpson A23 angles fastened to sill plate and each 16" OC. (2x8 min. sill plate) (Refer to Detail G)
 - "Type H"- Simpson LPT4 or TP35 plate fastened to rim joist and mud sill with (12) 8dx1.5" treated nails. (Refer to Detail H)
- Anchor Types:
 - "Type 4"- 1/2" x10" Anchor Bolt with 2"x2"x1/8" Washer between plate and nut.
 - "Type 5"- Simpson MAB15 (concrete) or MAB23 (concrete block) or MASA
6. Fasteners reflected in chart do NOT require "H type" connector plates to be installed along sidewall.
7. Fasteners reflected in chart do NOT require "H type" connector plates to be installed along endwall.
8. Three options (E,F,& G) for rim to sill fastening and two options (4 & 5) for sill plate to foundation anchorage have been provided in chart. Any combination of rim sill connectors and mud sill anchors maybe used.
9. All connection hardware, anchor bolts, straps, hold-downs, washers and fasteners shall be galvanized or stainless when in contact with PT sill plates or other PT lumber.
10. Maximum foundation wall height and maximum unbalanced backfill.

9581-14.S.J.C.22.22.235(L)


GENERAL NOTES:

APPROVAL SEAL:

CMJ Engineering

DRYER VENT INSTALLATION

Drawn by: O'Neal
Date: 4/11/07/Proj #:



APPROVED BY
NIA INC.
 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements or applicable State Laws
 David Richter

INSTALLATION INSTRUCTIONS.

EXHAUST DUCTS FOR DOMESTIC CLOTHES DRYERS SHALL BE CONSTRUCTED OF METAL OR NONCOMBUSTIBLE MATERIAL OF EQUAL STRENGTH AND CORROSION RESISTANCE AND SHALL HAVE A SMOOTH INTERIOR FINISH. NO PART OF THE DRYER DUCT TO BE IN CONTACT WITH THE GROUND. THE DUCT TO RUN TO THE OUTSIDE OF THE UNIT AND SHALL NOT TERMINATE UNDERNEATH THE UNIT. A APPROVED DAMPER TO BE INSTALLED ON THE END OF THE DUCT.

ELECTRICAL FURNACE DESCRIPTION CHART

Nortek Model E Series	Supply Circuit	Total Amperes	Max Over- Current Rating	Min. Circuit Ampacity	Recommended Wire Sizes		Low Voltage Thermostat Wire Size
					NM-B	SEU*	
					60°C Copper	60°C Copper	
010	Single	44.6	60	56	4-2	4-4-6	
012	Single	51.2	70	64	4-2	4-4-6	2-Wire
	Dual	"A" 27.1	40	34	8-2	6-6-10	system max wire
		"B" 24.2	30	30	10-2	8-8-10	lengths:
015	Single	N/A	N/A	N/A			24 Ga. = 55'
	Dual	"A" 44.6	60	56	4-2	4-4-6	22 Ga. = 90'
		"B" 20.8	30	26	10-2	8-8-10	20 Ga. = 140'
017	Single	N/A	N/A	N/A			24 Ga. = 55'
	Dual	"A" 47.9	60	60	4-2	4-4-6	22 Ga. = 90'
		"B" 22.5	30	28	10-2	8-8-10	20 Ga. = 140'
020	Single	N/A	N/A	N/A			18 Ga. = 225'
	Dual	"A" 44.6	60	56	4-2	4-4-6	
		"B" 41.7	60	52	4-2	4-4-6	4 or more-Wire
023	Single	N/A	N/A	N/A			system max wire
	Dual	"A" 45.5	60	57	4-2	4-4-6	lengths:
		"B" 48.0	60	60	4-2	4-4-6	24 Ga. = 25'
							22 Ga. = 45'
							20 Ga. = 70'
							18 Ga. = 110'

ELECTRIC FURNACE MODEL NUMBER	OUTPUT CAPACITY (BTU)
E#EB-010H	35,000
E#EB-012H	41,000
E#EB-015H	53,000
E#EB-017H	57,000
E#EB-020H	70,000
E#EB-023H	75,000
# = Series Version	

*- NEC Section 338.10(B)(4)(a)

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
David Richter

ELECTRICAL LEGEND (NOT TO SCALE)			
	LIGHT		PANEL BOX
	CAN LIGHT		THERMOSTAT
	PULL CHAIN LIGHT		SWITCH
	BATH FAN		3-WAY SWITCH
	FLUORESCENT LIGHT		PHONE JACK
	CABLE JACK		CEILING MOUNT C.O. & SMOKE DETECTOR
	15 AMP RECEPT FLOOR LEVEL		CEILING MOUNT C.O. DETECTOR
	15 AMP RECEPT CABINET LEVEL		WALL MOUNT SMOKE DETECTOR
	15 AMP RECEPT SIDWAYS		CEILING MOUNT SMOKE DETECTOR
	20 AMP RECEPT FLOOR LEVEL		SWITCH LEG
	20 AMP RECEPT CABINET LEVEL		JUNCTION BOX
	20 AMP RECEPT SIDWAYS		CEILING FAN
	240 VOLT RECEPT		
	15 AMP WATERPROOF RECEPT GFI		POT & PAN RACK
	20 AMP WATERPROOF RECEPT GFI		HEAT TAPE RECEPT
	FURNACE		WATER HEATER
A DASHED SYMBOL REPRESENTS AN OPTION			
GFI-INDICATES A GROUND FAULT PROTECTED RECEPT			

PLUMBING FIXTURE DESCRIPTION CHART

APPLIANCE	MANUFACTURER	MODEL #	ANSI/ASME STANDARD
TOILET	BRISTOL BAY	VCEFB-03B	
SINKS	LYONS EL MUSTICE & SON PREMIUM FLOW CORESTONE & TEKA REVERE	KS01P4-TB #610 UTILITY SINGLE BOWL DOUBLE BOWL BAR SINK	
LAVATORIES	BRISTOL BAY	VCL-10	
TUB SHOWER	BAYMONT BATHWARE	5118 5100 5109	UL
SHOWER	BAYMONT BATHWARE	3309 3308 3304	UL
TUB	BAYMONT BATHWARE	2205 2272	UL

APPROVED BY



Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

Column Member Configuration	Ground Snow = 30 PSF								# Blocks & Min. Length
	Standard Spans (inches)		Transverse		Endwall		W/O Block	With Block	
	bearing length	W/O Block	With Block	W/O Block	With Block				
(1) 2x4 STUD SPF	82.6 "	2.34 "	98.6 "	98.6 "	47.33 "	47.33 "	47.33 "	47.33 "	(1) 0"
(2) 2x4 STUD SPF	189.23 "	5.35 "	123.72 "	205.23 "	91.72 "	155.03 "	155.03 "	155.03 "	(1) 4.2"
(3) 2x4 STUD SPF	291.84 "	8.26 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(4) 2x4 STUD SPF	394.46 "	11.16 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(5) 2x4 STUD SPF	497.07 "	14.06 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(6) 2x4 STUD SPF	599.68 "	16.96 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(7) 2x4 STUD SPF	600. "	16.97 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(4) 2x4 STUD SPF	394.46 "	11.16 "	123.72 "	247.45 "	91.72 "	215.45 "	215.45 "	215.45 "	(1) 6.4"
(1) 2x4 STUD SPF	82.6 "	2.34 "	98.6 "	98.6 "	47.33 "	47.33 "	47.33 "	47.33 "	(1) 0"
(2) 2x4 STUD SPF	189.23 "	5.35 "	123.72 "	205.23 "	91.72 "	155.03 "	155.03 "	155.03 "	(2) 4.2"

108" MAX. WALL HEIGHT.

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws.
 David Richter

MIN. ROOF LOAD WHICH STANDARD STUDS MUST BE DOUBLED:

MATING STUD:	DOUBLED @
2x4 STUD SPF	N.A.

N.A. = SINGLE STUD SPACING IS ACCEPTABLE IN ALL ROOF LOADS.



GENERAL NOTES:

- 1 178" BOX
- 2 WIND SPEED: 100 mph-enclosed (Exp. C)
- 3 1.5" MIN. RIDGE BEAM WIDTH.
- 4 RESERVED
- 5 18" MAX. STANDARD MATING STUD SPACING.
- 6 3" MIN. COMBINED TOP & BOTTOM PLATE THICKNESS. SPANS ASSUME COLUMNS ARE LOCATED IN BOTH HALFS.
- 7 RIDGE BEAM MUST BE IN FULL WOOD TO WOOD CONTACT WITH TOP PLATE FOR SPECIFIED BEARING LENGTH. BEARING LENGTH MAYBE DIVIDED AMONG MULTIPLE BEAMS EACH SIZED PER NOTE 3)
- 8 NO NOTCHES OR HOLES ALLOWED IN COLUMN MEMBERS.
- 9 COLUMN MEMBERS SHALL BE FASTENED TOGETHER WITH 15 GA X 2 1/2" STAPLES AT 16" OC. MAX.
- 10 SPANS "WITH" BLOCKS" REQUIRE RIDGE BEAM BEARING BLOCK(S) TO BE SECURED TO RIDGE BEAM OVER COLUMN LOCATION. 2x4x Length MIN. BLOCKS. SEE MW-20.8 FOR REQUIREMENT.
- 11 WHEN RIDGE BEAM BEARS DIRECTLY ON END GRAIN OF COLUMN MEMBER ALLOWABLE SPANS WITH BLOCK MAYBE USED FOR THE FOLLOWING RIDGE BEAMS:
 - a. FINNFOREST
 - b. MASTERPLANK
- 12 ISOLATED COLUMNS ARE COLUMNS THAT HAVE OPENINGS ON BOTH SIDES. ISOLATED COLUMNS ARE NOT IN A WALL SEGMENT BUT ARE STAND ALONE MEMBERS. ISOLATED COLUMNS SHALL MEET ALL THE FOLLOWING:
 - a. (3) MEMBER MINIMUM.
 - b. ALL COLUMN MEMBERS SHALL BE GLUED TOGETHER WITH 80% MIN. COVERAGE OF PVA GLUE.
 - c. SPANS SHALL BE DETERMINED FROM STANDARD COLUMN TABLES WITH BEARING LENGTH BEING THE COLUMN WIDTH AS MEASURED PARALLEL TO MATING LINE. ACTUAL BEARING LENGTH MAYBE DOUBLED WHEN BEARING BLOCK IS INSTALLED.
- 13 MAXIMUM LIVE AND DEAD LOADS:
 BOTTOM CHORD LIVE LOAD: 30 PSF Attic Storage
 TOP CHORD DEAD: 10 PSF
 BOTTOM CHORD DEAD: 10 PSF
 FLOOR LIVE LOAD: 0 PSF
- 14 COLUMN QTY'S. ARE NUMBER PER EACH END OF EACH UNIT. EACH UNIT IS DETERMINED INDEPENDENTLY.
- 15 DESIGN IN ACCORDANCE WITH THE IRC (2009)

Clayton homes building group

calc. ref. CMW-20.8.S.J.E.48.3-1.10

1 STORY W. ATTIC STORAGE
 MATE WALL COLUMN SPAN CHART

Drawn by: JWW Ver. 15.3

Date: 06/24/16

APPROVAL #:

MW-20.8.S.J.E.48.3-1

Trenco
818 Soundside Rd
Edenton, NC 27932

Re: WPL-913-1114-011_(32W)
CMH MANUFACTURING - SCHULT (Rich-NC)

The truss drawing(s) referenced below have been prepared by Truss Engineering Co. under my direct supervision based on the parameters provided by Wood Perfect, Ltd.

Pages or sheets covered by this seal: I33886338 thru I33886353

My license renewal date for the state of North Carolina is December 31, 2018.

North Carolina COA: C-0844

APPROVED BY
NIA 6/13/2019
INC.
Approval of this document does not authorize or
approve any deviation or deviations from the
requirements of applicable State Laws
David Richter



July 5, 2018

Galinski, John

IMPORTANT NOTE: Truss Engineer's responsibility is solely for design of individual trusses based upon design parameters shown on referenced truss drawings. Parameters have not been verified as appropriate for any use. Any location identification specified is for file reference only and has not been used in preparing design. Suitability of truss designs for any particular building is the responsibility of the building designer, not the Truss Engineer, per ANSI/TPI-1, Chapter 2.

Job	Truss	Truss Type	Qty	Ply	CMH MANUFACTURING - SCHULT (Rich-NC)	13886338
WPL-913-1114-011_(32W)	M478-15	HINGED ATTIC	1	1	M478 : 7/12 WIDE MOD/HUD - 15 Job Reference (optional)	
Wood Perfect, LLC, Guin, AL 33563					7.640 s Apr 22 2016 Mitek Industries, Inc. Thu Jul 05 09:29:20 2018 Page 1	

ID: Xetm8C1XFFyLhVtnAqnsTTzGw4j-S5GQ?YSEm6QPD44jXioyofYw2z_W6LgHzvUxvz79Qz




Plate Offsets (X,Y) - [2:0-1-12,0-2-0], [2:0-3-13,0-6-4], [3:0-2-12,0-1-0], [4:0-0-5,0-1-2], [5:0-0-11,0-1-2], [9:0-2-0,Edge], [13:0-0-11,0-1-2], [14:0-0-5,0-1-2], [15:0-2-12,0-1-0], [16:0-1-12,0-2-0], [16:0-3-13,0-6-4], [18:0-5-10,0-1-8], [22:0-5-10,0-1-8], [23:0-1-12,0-1-8], [24:0-1-12,0-1-8]

SPACING-: 2-0-0 LOADING (psf)	SPACING-: 1-4-0 LOADING (psf)	SPACING-: 2-0-0 LOADING (psf)	CSI.	DEFL.	in (loc)	l/defl	L/d	PLATES	GRIP
TCLL 23.1 (Ground Snow=30.0)	TCLL 34.7 (Ground Snow=45.0)	Plate Grip DOL 1.15 Lumber DOL 1.15 Rep Stress Incr YES Code IBC2015/TPI2014	TC 0.66 BC 0.70 WB 0.82 (Matrix)	Vert(LL) 0.37 Vert(CT) -0.40 Horz(CT) 0.01 Attic -0.25	21-22 18-19 16 20-21	>478 >362 n/a 590	240 180 n/a 360	MT20 MT18HS	197/144 197/144
TCDL 11.0	TCDL 16.5							Weight: 229 lb	FT = 0%
BCLL 0.0 *	BCLL 0.0 *								
BCDL 10.0	BCDL 15.0								

LUMBER-
TOP CHORD 2x6 SP No.2 *Except*
 7-9,9-11: 2x4 SPF No.2
BOT CHORD 2x10 SP No.1
WEBS 2x3 SPF Stud *Except*
 6-12,8-23,10-24: 2x6 SPF Stud, 5-21,13-19: 2x4 SPF Stud
WEDGE
 Left: 2x4 SPF Stud, Right: 2x4 SPF Stud

BRACING-
TOP CHORD Structural wood sheathing directly applied or 4-8-15 oc purlins.
BOT CHORD Rigid ceiling directly applied or 6-7-14 oc bracing.

APPROVED BY

 6/13/2019
 Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws
 David Richter

REACTIONS. (lb/size) 2=1169/0-3-8, 20=510/0-3-8, 16=1169/0-3-8
 Max Horz 2=404(LC 11)
 Max Uplift 2=550(LC 12), 20=-196(LC 12), 16=-551(LC 13)
 Max Grav 2=1270(LC 23), 20=864(LC 23), 16=1271(LC 24)

FORCES. (lb) - Maximum Compression/Maximum Tension
TOP CHORD 1-2=0/6, 2-3=-1299/349, 3-4=-1256/473, 4-5=-1238/498, 5-29=-1105/617, 6-29=-1055/637, 6-7=-475/233, 7-8=-459/259, 8-9=-259/160, 9-10=-259/160, 10-11=-457/258, 11-12=-474/231, 12-30=-1055/637, 13-30=-1105/617, 13-14=-1235/498, 14-15=-1253/473, 15-16=-1296/347, 16-17=0/6
BOT CHORD 2-22=-249/1026, 22-27=-246/1024, 21-27=-246/1024, 21-33=-246/1024, 31-33=-246/1024, 31-32=-246/1024, 32-34=-246/1024, 20-34=-246/1024, 20-37=-246/1024, 35-37=-246/1024, 35-36=-246/1024, 36-38=-246/1024, 19-38=-246/1024, 19-28=-246/1024, 18-28=-246/1024, 16-18=-247/1024
WEBS 3-22=-447/474, 15-18=-447/474, 6-23=-881/576, 23-24=-881/576, 12-24=-881/576, 5-21=-224/309, 13-19=-224/307, 8-23=-292/463, 10-24=-291/462

REQUIRED FIELD JOINT CONNECTIONS - Maximum Compression (lb)/ Maximum Tension (lb)/ Maximum Shear (lb)/ Maximum Moment (lb-in)
 6=881/578/307/0, 7=475/256/286/0, 8=292/463/47/0, 10=291/462/47/0, 11=473/255/285/0, 12=881/576/305/0, 19=224/307/0/0, 20=248/1024/531/0, 21=224/309/0/0

- NOTES-**
- 1) Dado: 0-2-10 length x 0-1-10 deep dado, 1-7-0 to right edge from joint 20 on the top face.
 - 2) Dado: 0-2-10 length x 0-1-10 deep dado, 1-7-0 to left edge from joint 20 on the top face.
 - 3) Wind: ASCE 7-10; Vu1=152mph (3-second gust) Vasd=120mph @24in o.c.; TCDL=4.4psf; BCDL=4.0psf; (Alt. 180mph @16in o.c.; TCDL=6.6psf; BCDL=6.0psf); h=22ft; Cat. II; Exp C; enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
 - 4) TCLL: ASCE 7-10; Pg=30.0 psf (ground snow); Ps=23.1 psf (roof snow); Category II; Exp C; Partially Exp.; Ct=1.1
 - 5) Roof design snow load has been reduced to account for slope.
 - 6) Unbalanced snow loads have been considered for this design.
 - 7) This truss has been designed for greater of min roof live load of 17.1 psf or 2.00 times flat roof load of 23.1 psf on overhangs non-concurrent with other live loads.
 - 8) As requested, plates have not been designed to provide for placement tolerances or rough handling and erection conditions. It is the responsibility of the fabricator to increase plate sizes to account for these factors.



July 5, 2018

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MII-7473 rev. 10/03/2015 BEFORE USE.
 Design valid for use only with Mitek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see ANSITPH Quality Criteria, DSB-89 and BCSI Building Component Safety Information available from Truss Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22304.

ENGINEERING BY

 A MITEK® AFFILIATE
 818 Soundside Road
 Edenton, NC 27932

Job	Truss	Truss Type	Qty	Ply	CMH MANUFACTURING - SCHULT (Rich-NC)	I33886338
WPL-913-1114-011_(32W)	M478-15	HINGED ATTIC	1	1	M478 : 7/12 WIDE MOD/HUD - 15 Job Reference (optional)	

Wood Perfect, LLC, Guin, AL 33563

7.640 s Apr 22 2016 MiTek Industries, Inc. Thu Jul 05 09:29:20 2018 Page 2
ID:Xetn8C1XFFyLhVtr4qnsTTzGw4j-S5GQ?YSEm6QPD44jXloyoufYw2z_W6LgHzvUxvz79Qz

NOTES-

- 9) All plates are MT20 plates unless otherwise indicated.
- 10) See HINGE PLATE DETAILS for plate placement.
- 11) Provisions must be made to prevent lateral movement of hinged member(s) during transportation.
- 12) All additional member connections shall be provided by others for forces as indicated.
- 13) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 14) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members, with BCDL = 10.0psf.
- 15) Ceiling dead load (5.0 psf) on member(s). 5-6, 12-13, 6-23, 23-24, 12-24
- 16) Bottom chord live load (30.0 psf) and additional bottom chord dead load (0.0 psf) applied only to room. 20-21, 19-20
- 17) Provide mechanical connection (by others) of truss to bearing plate capable of withstanding 550 lb uplift at joint 2, 196 lb uplift at joint 20 and 551 lb uplift at joint 16.
- 18) This truss is designed in accordance with the 2015 International Building Code section 2306.1 and referenced standard ANSI/TPI 1.
- 19) "Fix heels only" Member end fixity model was used in the analysis and design of this truss.
- 20) Attic room checked for L/360 deflection.

APPROVED BY

NIA INC. 6/13/2019

Approval of this document does not authorize or approve any deviation or deviations from the requirements of applicable State Laws

David Richter

WARNING - Verify design parameters and READ NOTES ON THIS AND INCLUDED MITEK REFERENCE PAGE MH-7473 rev. 10/03/2015 BEFORE USE.

Design valid for use only with MiTek® connectors. This design is based only upon parameters shown, and is for an individual building component, not a truss system. Before use, the building designer must verify the applicability of design parameters and properly incorporate this design into the overall building design. Bracing indicated is to prevent buckling of individual truss web and/or chord members only. Additional temporary and permanent bracing is always required for stability and to prevent collapse with possible personal injury and property damage. For general guidance regarding the fabrication, storage, delivery, erection and bracing of trusses and truss systems, see **ANSI/TPI Quality Criteria, DSB-89 and BCSI Building Component Safety Information** available from Truss Plate Institute, 218 N. Lee Street, Suite 312, Alexandria, VA 22314.


ENGINEERING BY
TRENCO
A MiTek Alliance

816 Soundside Road
Edenton, NC 27932

Symbols

PLATE LOCATION AND ORIENTATION

Center plate on joint unless x, y offsets are indicated. Dimensions are in ft-in-sixteenths. Apply plates to both sides of truss and fully embed teeth.



For 4 x 2 orientation, locate plates 0- 1/16" from outside edge of truss.

This symbol indicates the required direction of slots in connector plates.



* Plate location details available in MITek 20/20 software or upon request.

PLATE SIZE

4 X 4
The first dimension is the plate width measured perpendicular to slots. Second dimension is the length parallel to slots.


LATERAL BRACING LOCATION

Indicated by symbol shown and/or by text in the bracing section of the output. Use T or I bracing if indicated.



BEARING


Indicates location where bearings (supports) occur. Icons vary but reaction section indicates joint number where bearings occur. Min size shown is for crushing only.



Industry Standards:

- ANSI/TPI1: National Design Specification for Metal Plate Connected Wood Truss Construction.
- DSB-89: Design Standard for Bracing.
- BCSI: Building Component Safety Information, Guide to Good Practice for Handling, Installing & Bracing of Metal Plate Connected Wood Trusses.

Numbering System



JOINTS ARE GENERALLY NUMBERED/LETTERED CLOCKWISE AROUND THE TRUSS STARTING AT THE JOINT FARTHEST TO THE LEFT.

CHORDS AND WEBS ARE IDENTIFIED BY END JOINT NUMBERS/LETTERS.

PRODUCT CODE APPROVALS

ICC-ES Reports:

- ESR-1311, ESR-1352, ESR1988
- ER-3907, ESR-2362, ESR-1397, ESR-3282

Trusses are designed for wind loads in the plane of the truss unless otherwise shown.

Lumber design values are in accordance with ANSI/TPI 1 section 6.3 These truss designs rely on lumber values established by others.

© 2012 MITek® All Rights Reserved



MITek Engineering Reference Sheet: MIL-7473 rev. 10/03/2015

General Safety Notes

Failure to Follow Could Cause Property Damage or Personal Injury

- Additional stability bracing for truss system, e.g. diagonal or X-bracing, is always required. See BCSI.
- Truss bracing must be designed by an engineer. For wide truss spacing, individual lateral braces themselves may require bracing, or alternative Tor l bracing should be considered.
- Never exceed the design loading shown and never stack materials on inadequately braced trusses.
- Provide copies of this truss design to the building designer, erection supervisor, property owner and all other interested parties.
- Cut members to bear tightly against each other.
- Place plates on each face of truss at each joint and embed fully. Knots and wane at joint locations are regulated by ANSI/TPI 1.
- Design assumes trusses will be suitably protected from the environment in accord with ANSI/TPI 1.
- Unless otherwise noted, moisture content of lumber shall not exceed 19% at time of fabrication.
- Unless expressly noted, this design is not applicable for use with fire retardant, preservative treated, or green lumber.
- Camber is a non-structural consideration and is the responsibility of truss fabricator. General practice is to camber for dead load deflection.
- Plate type, size, orientation and location dimensions indicated are minimum plating requirements.
- Lumber used shall be of the species and size, and in all respects, equal to or better than that specified.
- Top chords must be sheathed or purlins provided at spacing indicated on design.
- Bottom chords require lateral bracing at 10 ft. spacing, or less, if no ceiling is installed, unless otherwise noted.
- Connections not shown are the responsibility of others.
- Do not cut or alter truss member or plate without prior approval of an engineer.
- Install and load vertically unless indicated otherwise.
- Use of green or treated lumber may pose unacceptable environmental, health or performance risks. Consult with project engineer before use.
- Review all portions of this design (front, back, words and pictures) before use. Reviewing pictures alone is not sufficient.
- Design assumes manufacture in accordance with ANSI/TPI 1 Quality Criteria.

NORTH CAROLINA

MODULAR PLANS REVIEW CHECKLIST

PAGE 1 of 3

revised May 2011

Manufacturer CMH MANUFACTURING INC.
Model number/name SM251077
3rd Party NTA INC.
Review Date
Reviewer *DAVID RICHTER* DAVID RICHTER

Plan Sheet Page # and NOTES

QC MANUAL (current and complete)

APPENDIX B (required and attached)

single family dwelling - not required

PLAN SHEETS

Each plan sheet third-party stamped with approver's name

Each plan sheet is numbered and/or indexed

IX-1

GENERAL (cover sheet)

Code References

1-0

Statement regarding connection to public utilities

1-0

Statement regarding bathrooms if not included

1-0

Construction type

1-0

Occupancy classification

1-0

Fire resistance ratings (if required)

1-0

Floor live load

1-0

Roof live load

1-0

Design wind velocity

1-0

Seismic information (commercial projects)

1-0

Thermal zones

1-0, HDD on REScheck (attached)

Notice to inspections department regarding items to be site installed

1-0

FLOOR PLANS

Interior and exterior wall layouts

1-1

Door and window schedule

1-0.2

Light and Ventilation requirements

TS-1

Attic access (size and location)

1-1

Non-prescriptive headers

Charts on 1-0, calc ref on 1-0

Safety glazing requirements

1-1

Fire rating of Exterior walls (if applicable)

EXTERIOR ELEVATIONS

Exterior materials

20-1, 20-2, 1-0.2

Attic ventilation requirements

20-1, 20-2

PLUMBING

Plan

locations on floor plan 1-1

All fixtures furnished by mfg. shown on plans

1-1

Materials (water supply & distribution, DWV, storm drainage)

DWV: 8-1; Supply: 9-1

Supply and waste risers, including DWV system (generic) beneath the building

DWV: 8-1; Supply: 9-1

Water heater (type and capacity)

ref to electrical appliances on 1-0

NORTH CAROLINA

MODULAR PLANS REVIEW CHECKLIST

PAGE 2 of 3

revised May 2011

Plan Sheet Page # and NOTES

MECHANICAL

Design calculations	attached
Installed unit capacity	attached
Supply and returns (locations and sizes)	4-4
Duct sizes	4-4
Specifications (units, ducts)	1-1, 4-4
All appliances furnished by mfg. shown on plans	1-1, exhaust fans 11-1

ELECTRICAL

Plan	11-1
Location of all electrical boxes	11-1
Electrical panel location	11-1
Note regarding main disconnect (if applicable)	
Exterior lighting and receptacles	11-1
Ground level receptacles (if applicable)	11-1
Smoke detector location(s)	11-1
Electrical load calculations	TS-5
Electrical panel layout (breaker and wire sizes, circuit schedule)	11-1
Panel and service entrance sizes	Panel: 1-0a, SE ref in set-up on 1-0
All fixtures furnished by mfg. shown on plans	11-1

ACCESSIBILITY

(for other than 1 & 2 family dwellings)

Entrances and means of egress	
Doors, doorways, and door hardware	
Stairs and handrails	
Toilet rooms, plumbing fixtures, grab bars, etc	
Bathrooms and shower rooms	
Occupancy specific requirements	
Multi-family dwellings: Type A and B units	

FLOOR X-SECTION

Joist and beam sizes and spacing	1-0.2
Materials species and grade	1-0.2
Sheathing, decking, and concrete as applicable	1-0.2
Fastening instructions	1-0.2
Insulation	1-0.2
Details as required for clarification	1-0.2, other details ref manual on 1-0.2

WALL X-SECTION

Stud and column sizes and spacing	studs: 1-0.2; column charts: 1-0.2
Materials species and grade	1-0.2
Sheathing and bracing	1-0.2
Headers and lintels	header charts: 1-0.2
Finishes	1-0.2
Fastening instructions	1-0.2
Insulation	1-0.2
Details as required for clarification	Ref manual on 1-0.2

NORTH CAROLINA

MODULAR PLANS REVIEW CHECKLIST

PAGE 3 of 3

revised May 2011

Plan Sheet Page # and NOTES

CEILING/ROOF X-SECTION

Truss, rafter, and beam spacing	1-0.2
Lumber species and grade	1-0.2
Sheathing and decking	1-0.2
Finishes	1-0.2
Fastening instructions	1-0.2
Insulation	1-0.2
Details including NC sealed truss designs or manual reference	man ref to trusses 1-0.2, other details man ref 1-0.2

FOUNDATION PLAN

Footings, pier, and curtain wall locations and specifications	21-30 PSF (OFF FRAME)
X-sections with dimensions	21-30 PSF (OFF FRAME)
Anchorage - sill plate to piers and curtain wall	21-30 PSF (OFF FRAME)
Anchorage - building to sill plate	21-30 PSF (OFF FRAME)
Anchorage - tie downs (lateral and longitudinal)	21-30 PSF (OFF FRAME)
Soil bearing capacity	21-30 PSF (OFF FRAME)
Minimum concrete compressive strength	21-30 PSF (OFF FRAME)
Mortar type	21-30 PSF (OFF FRAME)
Ventilation requirements (with and without vapor barrier)	21-30 PSF (OFF FRAME)
Crawl space access requirements	21-30 PSF (OFF FRAME)

ENERGY COMPLIANCE

Demonstrate compliance	PRESCRIPTIVE
------------------------	--------------

SET-UP INSTRUCTIONS

Floor and ceiling connections	ref to set-up manual on 1-0.2
Marriage wall connections	ref to set-up manual on 1-0.2
Roof set-up connections	ref to set-up manual on 1-0.2
Plumbing connections	ref to set-up manual on 1-0.2
Mechanical connections	ref to set-up manual on 1-0.2
Electrical connections	ref to set-up manual on 1-0.2
Fire stopping	1-0.2
Air infiltration elimination	ref to set-up manual on 1-0.2
Notice to inspections department attachment if set-up instructions are by attachment	1-0.2

ITEMS NOT INSPECTED IN PLANT

List of items not inspected by 3rd. Party	1-0.2
Notice to inspections department	1-0.2