



JS CONSULTING & DESIGN
STRUCTURAL ENGINEERING
1535 N FAYETTEVILLE ST
ASHEBORO, NC 27203
336-521-9787 (f) 336-521-9789

CERTIFICATE NUMBER: P-1513

Client:

L&G Buildings and Concrete

1535 N Fayetteville St

Asheboro, NC 27203

336-521-9787 (f) 336-521-9789

Project:

30'x40'x14' w/ 12'x40'x11' lean to

Jonathan Weaver

3020 Old Stage Rd

Coats, NC 27521

Job No:



1801-1277

Date:

10/25/18

Sheet:

S1




(A) SLAB TURN DOWN
NOT TO SCALE

FOUNDATION PLAN

NOT TO SCALE

DRAINAGE NOTE:
OWNER TO PROVIDE POSITIVE
DRAINAGE AWAY FROM BLDG. PAD.






JS CONSULTING & DESIGN
 STRUCTURAL ENGINEERING
 11703 DURHAM RD
 RALEIGH, NC 27614
 P (919) 925-1980
 F (919) 228-1081

CERTIFICATE NUMBER: P-1513

Client:
 L&G Buildings and Concrete
 1535 N Fayetteville St
 Asheboro, NC 27703
 336-521-9787 (F) 336-521-9789


Project:
 30' x 40' x 14' w/ 12' x 40' x 11' lean to
 Jonathan Weaver
 3020 Old Stage Rd
 Coats, NC 27521

Job No:
 1801-1277
 Date:
 10/25/18
 Sheet:
 S3



LEAN TO

TYPICAL CROSS SECTION C-C
 NOT TO SCALE



TYP. WIND COLLAR/BRACE
 NOT TO SCALE

GABLE END WALL FRAMING
 GABLE END WALLS SHALL BE FRAMED @ 4' O.C. USING 2-1/4" 14ga SQUARE TUBES TO THE BOTTOM RAIL AND RAFTERS W/ L-CLIPS AND (2) SCREWS IN EACH LEG OF THE CLIP. ANY STUDS OVER 13'-0" IN LENGTH SHALL BE (2) 2-1/4" 14ga AND ATTACHED W/ (2) L-CLIPS AND (2) SCREWS IN EACH LEG OF THE CLIP.





JS CONSULTING & DESIGN
 STRUCTURAL ENGINEERING
 11703 DURANT RD
 RALEIGH, NC 27614
 P | 919 | 476-1480
 F | 919 | 224-1881

CERTIFICATE NUMBER: P-1513

Client:

L&G Buildings and Concrete
 1535 N Fayetteville St
 Asheboro, NC 27203
 336-521-9787 (F) 336-521-9789


Project:

30'x40'x14' w/ 12'x40'x11' lean to
 Jonathan Weaver
 3020 Old Stage Rd
 Coats, NC 27521

Job No:
1801-1277

Date:
10/25/18

Sheet:
S4



SIDE ELEVATION
NOT TO SCALE

ALL ANGLE CLIPS TO HAVE (2) SCREWS
 INSTALLED IN EACH LEG OF ANGLE. TYP.

DOOR OPENING NOTE:
 FOR DOORS PLACED IN GABLE END WALLS
 ONLY. EXACT LOCATION TO BE DETERMINED BY
 BUILDER. MINIMUM HEADER SIZE (2) 2-1/4"
 14ga SQUARE TUBES ATTACHED TOGETHER W/
 CLIPS AND SCREWS @ 1'-0" O.C. MINIMUM (1)
 2-1/4" KING STUD EACH SIDE FOR DOORS
 LESS THAN 10' WIDE AND (2) 2-1/4" KING
 STUD EACH SIDE FOR DOORS 12' AND WIDER.
 ATTACH USING ANGLE CLIPS AND SCREWS



Client:
 L&G Buildings and Concrete
 1535 N Fayetteville St
 Asheboro, NC 27203
 336-521-9787 (f) 336-521-9789

Project:
 30'x40'x14' w/ 12'x40'x11' lean to
 Jonathan Weaver
 3020 Old Stage Rd
 Coats, NC 27521

Job No:
 1801-1277
Date:
 10/25/18
Sheet:
 S5

NOTES

DESIGN CRITERIA

1. BUILDING CODE.....2012 NORTH CAROLINA BUILDING CODE
2. IMPORTANCE FACTORS

WIND (Iw)	0.87
SNOW (Is)	0.80
SEISMIC (Iw)	1.0
3. GROUND SNOW LOAD.....15 PSF
4. ROOF LL.....5 PSF (NO FOOT TRAFFIC)
5. WIND
 - A) BASIC WIND SPEED (ASCE 7-05)100 MPH
 - B) WIND HAZARD EXPOSURE CATEGORY.....B
 - C) WIND BASE SHEARS (for MWFRS) $V_x = 2.4\text{ k}$ $V_y = 2.4\text{ k}$ (PER FRAME)
6. SEISMIC
 - A) SEISMIC DESIGN CATEGORY A
 COMPLIANCE WITH SECTION 1616.4 ONLY? YES NO
 - B) SEISMIC DESIGN CATEGORY B C D

SEISMIC USE GROUP 1
 SPECTRAL RESPONSE ACCELERATION S_s 17.1 %g S_1 6.9 %g
 SITE CLASSIFICATION D FIELD TEST PRESUMPTIVE HISTORICAL DATA
 BASIC STRUCTURAL SYSTEM (CHECK ONE)
 BEARING WALL DUAL W/SPECIAL MOMENT FRAME
 BUILDING FRAME DUAL W/INTERMEDIATE R/C OR SPECIAL STEEL
 MOMENT FRAME INVERTED PENDULUM
 SEISMIC BASE SHEAR $V_x = 0.5\text{ k}$ $V_y = 0.5\text{ k}$ (PER FRAME)

ANALYSIS PROCEDURE SIMPLIFIED EQUIVALENT LATERAL FORCE MODAL
 ARCHITECTURAL, MECHANICAL, COMPONENTS ANCHORED? NO
 LATERAL DESIGN CONTROL: EARTHQUAKE WIND

OTHER NOTES

1. PRESUMPTIVE SOIL PRESSURE = 2,000 PSF.
2. WHERE A DETAIL IS SHOWN ON STRUCTURAL DRAWINGS FOR ONE CONDITION, IT SHALL APPLY TO ALL SIMILAR OR LIKE CONDITIONS, UNLESS NOTED OR SHOWN OTHERWISE.
3. IF CONTRACTOR FINDS A DIFFERENCE BETWEEN THESE DRAWINGS AND EXISTING ELEVATIONS, OR OTHER CONDITIONS WHICH PROHIBIT EXECUTION OF THE WORK AS DIRECTED ON THESE DRAWINGS, CONTRACTOR SHALL NOTIFY ENGINEER IMMEDIATELY.
4. ALL ITEMS SHALL BE TIGHTLY ANCHORED OR ATTACHED SQUARE, PLUMB AND TRUE, OR IN OTHER PLANES OR SHAPES AS SHOWN ON THE DRAWINGS. JOINTS SHALL BE TIGHT, EVEN, AND FREE OF OFFSETS. NO FIELD ALTERING OF ANY MEMBERS WILL BE ALLOWED THAT WILL CAUSE THEM NOT TO BE IN ACCORDANCE WITH THE DRAWINGS AND THEM NOT TO BE IN ACCORDANCE WITH THE DRAWINGS AND SPECIFICATIONS, WITHOUT WRITTEN APPROVAL OF THE DESIGN ENGINEER.
5. GENERAL CONTRACTOR IS RESPONSIBLE TO PROVIDE ADEQUATE SHORING, BRACING OR SUPPORT TO PREVENT MOVEMENT, SETTLEMENT, OR DAMAGE TO THE STRUCTURE DURING CONSTRUCTION PROCEDURES ASSOCIATED WITH THIS PROJECT.
6. CONCRETE: CONCRETE MINIMUM COMPRESSIVE STRENGTH AT 28 DAYS SHALL BE 3000 PSI.
7. CONCRETE WORK SHALL COMPLY WITH ACI "SPECIFICATIONS FOR STRUCTURAL CONCRETE FOR BUILDING (ACI 301) AND APPLICABLE PROVISIONS OF ACI 318. KEEP A COPY OF ACI FIELD REFERENCE MANUAL (ACI-SP-15) WHICH INCLUDES ACI 301 AND OTHER ACI AND ASTM REFERENCES ON THE JOB.
8. ALL FOOTING FOUNDATIONS SHALL BE PLACED ON COMPETENT SOIL.
9. FIBER MESH MAY BE SUBSTITUTED FOR WWM PER MANUFACTURER'S RECOMMENDATIONS.
10. REINFORCING STEEL: ASTM A615, GRADE 60. PROVIDE 3" CLEARANCE TO EARTH SURFACES. LAP BARS 30 DIAMETERS.
11. ALL GALVANIZING SHALL BE PERFORMED AFTER FABRICATION, AND IN ACCORDANCE WITH ASTM A123 AND/OR A153.
12. THE MINIMUM YIELD STRENGTH OF THE STEEL USED IN THE LIGHT GAUGE METAL FRAMES SHALL BE 55,000 PSI, FOR RAW OR GALVANIZED TUBES.
13. THE MINIMUM YIELD STRENGTH OF THE STEEL USED FOR THE LIGHT GAUGE METAL DECK SHALL BE 80,000 PSI, DECKING PANELS SHALL COVER THREE SPANS, MINIMUM.
14. THE LIGHT GAUGE METAL FRAMES AND DECK SHALL BE OF THE GAUGE INDICATED ON THE PLAN/DETAILS.
15. ALL SCREWS FOR ASSEMBLING FRAMES SHALL BE #12 SIZE.
16. ALL WELDING SHALL BE IN ACCORDANCE WITH AWS D1.1.
17. ALL WELDS SHALL BE COATED WITH GALVANIZE PRIMER & PAINT AFTER WELDING.

