

# HERITAGE BUILDING SYSTEMS



Established 1979



## BUILDER/CONTRACTOR RESPONSIBILITIES

**Drawing Validity** - These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

**Builder Acceptance of Drawings** - Approval of the manufacturer's drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice Sept 86 Section 4.2.1) (Mar 05 Section 4.4.1)

**Code Official Approval** - It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

**Builder is responsible for State, Federal and OSHA safety compliance** - The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

**Building Erection** - The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice Sept 86 Section 7.9.1) (Mar 05 Section 7.10.3)

**Discrepancies** - Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice Sept 86 Section 3.3) (Mar 05 Section 3.3)

**Materials by Others** - All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturer's assumptions will govern.

**Modification of the Metal Building from Plans** - The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

**Foundation Design** - The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA 06 Sections 3.2.2 and A3)

## PROJECT NOTES

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, ASTM A1011 SS, or ASTM A1011 HSLAS with a minimum yield point of 50 ksi. Material properties of hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with a minimum specified yield point of 50 ksi. Hot rolled angles, or other than flange braces, conform to ASTM 36 minimum. Hollow structural shapes conform to ASTM A500 grade b, minimum yield point is 42 ksi for round HSS and 46 ksi for rectangular HSS. Material properties of cold form light gage steel members conform to the requirements of ASTM A1011 S3 Grade 55 or ASTM A1011 HSLAS Class 1 Grade 55, with a minimum yield point of 55 ksi.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special Inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record. Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacturer nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer's Engineer's certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacturer's standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

This metal building system is designed as enclosed. All exterior components (i.e. doors, windows, vents, etc.) must be designed to withstand the specified wind loading for the design of components and cladding in accordance with the specified building code. Doors are to be closed when a maximum of 50% of design wind velocity is reached.

## DESIGN LOADING

THIS STRUCTURE IS DESIGNED UTILIZING THE LOADS INDICATED AND APPLIED AS REQUIRED BY:  
NCBC 2018

THE BUILDER IS TO CONFIRM THAT THESE LOADS COMPLY WITH THE REQUIREMENTS OF THE LOCAL BUILDING DEPARTMENT.

FRAME / ROOF DEAD LOAD	2.010 PSF
SUPERIMPOSED	
COLLATERAL (LIGHTS)	1 PSF
FRAME / ROOF LIVE LOAD	20.00 PSF (REDUCIBLE)
RISK CATEGORY	II - Normal
SNOW LOAD	
GROUND SNOW LOAD (Pg)	15.0000PSF
SNOW LOAD IMPORTANCE FACTOR (Is)	1.0000
FLAT ROOF SNOW LOAD (Pf)	10.5 PSF
SNOW EXPOSURE FACTOR (Ce)	1.0
THERMAL FACTOR (Ct)	1.00

WIND LOAD	
ULTIMATE WIND SPEED	117 MPH
NOMINAL WIND SPEED (Vnom)	90.63 MPH (IBC SECTION 1609.3.1)
WIND EXPOSURE CATEGORY	C
TOPOGRAPHICAL FACTOR	1.0

INTERNAL PRESSURE COEFFICIENT (Cp)	0.18 / -0.18
ZONE 4, COMPONENT WIND LOAD ≤ 10ft <sup>2</sup>	
29.877 PSF PRESSURE -32.409 PSF SUCTION	
ZONE 5, COMPONENT WIND LOAD < 10ft <sup>2</sup>	
29.877 PSF PRESSURE -39.928 PSF SUCTION	
ZONES PER ASCE 7-10; FIG. 30.4-1	
ZONES PRESSES SHOWN ARE UN-FACTORED	
RAIN INTENSITY	
5-MINUTE DURATION, 5-YEAR	7.0600 IN/HOUR
RECURRENT (R)	

SEISMIC LOAD	
SEISMIC IMPORTANCE FACTOR (Im)	1.00
Ss	0.1710
SDs	0.1824
S1	0.0820
S01	0.1312
SITE CLASS	D
SEISMIC DESIGN CATEGORY	B

ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE	TRANSVERSE	LONGITUDINAL
	H	FRONT BACK
BASIC FORCE RESISTING SYSTEM*	3	1.25 3
RESPONSE MODIFICATION COEFFICIENT(R)	3	1.25 3
SYSTEM OVER-STRENGTH FACTOR(Os)	2.5000	1.25 2.5000
SEISMIC RESPONSE COEFFICIENT(Cs)	0.061	0.148 0.061
BLOG DESIGN BASE SHEAR (V)	0.66 (k)	0.99 (k)

THE TRANSVERSE DIRECTION IS PARALLEL TO THE ROOF FRAMES  
THE LONGITUDINAL DIRECTION IS PERPENDICULAR TO THE ROOF FRAMES

BASIC FORCE RESISTING SYSTEM*
G4. STEEL ORDINARY MOMENT FRAME
B3. STEEL ORDINARY CONCENTRIC BRACED FRAMES
H. STRUCTURAL STEEL SYSTEMS NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE
G2. INVERTED PENDULUM SYSTEMS
CANTILEVERED COLUMN SYSTEMS

## DRAWING INDEX

PAGE	DESCRIPTION
C1	COVER SHEET
F1	ANCHOR BOLT PLAN
F2	ANCHOR BOLT REACTIONS
F3	ANCHOR BOLT DETAILS
E1	ROOF FRAMING PLAN
E2	ROOF SHEETING PLAN
E3	FRONT SIDEWALL
E4	BACK SIDEWALL
E5	LEFT ENDWALL
E6	RIGHT ENDWALL
E7	FRAME CROSS SECTION
DET-11	STANDARD DETAILS

## DRAWING STATUS

FOR APPROVAL  
THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION PERMIT  
THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

FOR ERECTOR INSTALLATION  
FINAL DRAWINGS FOR CONSTRUCTION.

FOR QUESTIONS OR ASSISTANCE CONCERNING ERECTION CALL:  
1-800-643-5555  
MONDAY - FRIDAY 7:30AM TO 5:00PM

## ENGINEERING SEAL

THIS CERTIFICATION COVERS PARTS MANUFACTURED AND DELIVERED BY THE MANUFACTURER ONLY, AND EXCLUDES PARTS SUCH AS DOORS, WINDOWS, FOUNDATION DESIGN AND ERECTION OF THE BUILDING.  
THESE DRAWINGS AND THE METAL BUILDING SYSTEM THEY REPRESENT ARE THE PRODUCT OF AN AFFILIATE OF NCI GROUP, INC. - 10943 N. SAM HOUSTON PARKWAY W., HOUSTON, TX 77064. THE PROFESSIONAL ENGINEER WHOSE SEAL APPEARS HEREON IS EMPLOYED BY AN AFFILIATE OF NCI GROUP, INC. AND IS NOT THE ENGINEER-OF-RECORD FOR THE OVERALL PROJECT.




1/2" A325 BOLT GRIP TABLE		BOLT LENGTH	NOTE: FULL THREAD ENGAGEMENT IS DEEMED TO HAVE BEEN MET WHEN THE END OF THE BOLT IS FLUSH WITH THE FACE OF THE NUT.
GRIP	LENGTH		
0 TO 9/16"	1 1/4" F.T.		WASHER REQUIRED ONLY WHEN SPECIFIED. WASHER MAY BE LOCATED UNDER HEAD OF BOLT, UNDER NUT, OR AT BOTH AT LOCATIONS NOTED ON ERECTION DRAWINGS. ADD 5/32" FOR EACH WASHER TO MATERIAL THICKNESS TO DETERMINE GRIP.
Over 9/16" TO 1 1/16"	1 3/4" F.T.		
Over 1 1/16" TO 1 5/16"	2"		
Over 1 5/16" TO 1 9/16"	2 1/4"		
Over 1 9/16" TO 1 13/16"	2 1/2"		
Over 1 13/16" TO 2 1/16"	2 3/4"		
LOCATIONS OF BOLTS LONGER THAN 2 3/4" NOTED ON ERECTION DRAWINGS			
F.T. DENOTES FULLY THREADED			

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJG	HPD	MS



2612 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH				
CUSTOMER:	JUSTIN SMITH						
LOCATION:	ANGIER, NC 27501						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	C1	A



ANCHOR BOLT PLAN

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/28/19	FOR ERECTOR INSTALLATION	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979

2612 GRIDDLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANGER, NC 27501

OWNER: JUSTIN SMITH

Mar 04 2019

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	F1	0





**GENERAL NOTES**

- THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAKING ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE CHANGES.
- REACTIONS ARE PROVIDED AS UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FOUNDATION ENGINEER WILL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS TO DETERMINE BEARING PRESSURES AND CONCRETE DESIGN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN.
- THE MANUFACTURER DOES NOT PROVIDE "MAXIMUM" LOAD COMBINATION REACTIONS. HOWEVER, THE INDIVIDUAL LOAD REACTIONS PROVIDED MAY BE USED BY THE FOUNDATION ENGINEER TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMICAL FOUNDATION DESIGN.
- THE METAL BUILDING MANUFACTURER IS RESPONSIBLE FOR THE DESIGN OF THE ANCHOR BOLT DIAMETER ONLY TO PREVENT THE TRANSFER OF FORCES BETWEEN THE BASE PLATE AND THE ANCHOR BOLT IN SHEAR, BEARING AND TENSION, BUT IS NOT RESPONSIBLE FOR THE ANCHOR BOLT EMBEDMENT FOR TRANSFER OF FORCES TO THE FOUNDATION. THE METAL BUILDING MANUFACTURER DOES NOT DESIGN AND IS NOT RESPONSIBLE FOR THE DESIGN, MATERIAL AND CONSTRUCTION OF THE FOUNDATION EMBEDMENTS. THE END USER CUSTOMER SHOULD ASSURE HIMSELF THAT ADEQUATE PROVISIONS ARE MADE IN THE FOUNDATION DESIGN FOR LOADS IMPOSED BY COLUMN REACTIONS OF THE BUILDING. OTHER IMPOSED LOADS, AND BEARING CAPACITY OF THE SOIL AND OTHER CONDITIONS OF THE BUILDING SITE. IT IS RECOMMENDED THAT THE ANCHORAGE AND FOUNDATION OF THE BUILDING BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER EXPERIENCED IN THE DESIGN OF SUCH STRUCTURES. (SECTION A3 MENA 2006 METAL BUILDING SYSTEMS MANUAL).
- BOTTOM OF ALL BASE PLATES ARE AT THE SAME ELEVATION. (UNLESS NOTED)
- ANCHOR RODS ARE ASTM F1554 GRADE 36 MATERIAL UNLESS NOTED OTHERWISE.

**BUILDING BRACING REACTIONS**

Reactions in plane of wall ± Reactions(k)

Wall Loc	Col Line	Horz	Vert	Panel Shear (lb/ft)	Note
L_EW	1 C/D	Bracing, see EW reactions			(g)
F_SW	A 2				
R_EW	3 B/C	Bracing, see EW reactions			
B_SW	D 3/2	2.0	0.3		

(g) Wind column at column line

\*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

**WIND COLUMN REACTIONS**

Wall Loc	Col Line	R/L	Load ID	Horz (k)	Vert (k)	Moment (ft-k)	Anc. Bolt Qty	Base Plate Width	Base Plate Length	Thick	
F_SW	A	2	R Wind	2.0	21.5	22.4	4	0.750	6.000	8.000	0.625
			Semiac	0.7	7.6						

**ENDWALL COLUMN:**

**BASIC COLUMN REACTIONS (k)**

Frm Line	Col Line	Dead Vert	Collot Vert	Live Vert	Snow Vert	Wind_Left1 Horz	Wind_Right1 Horz	Wind_Left2 Horz	Wind_Right2 Horz	Wind_Press Horz
1	D	0.1	0.0	0.4	0.2	0.0	-0.5	0.0	-0.7	0.0
1	C	0.4	0.2	3.4	1.8	1.6	-5.6	0.0	-1.5	1.6
1	B	0.4	0.2	3.4	1.8	0.0	-1.5	1.6	-4.3	0.0
1	A	0.1	0.0	0.4	0.2	0.0	-0.7	0.0	-0.2	0.0

Frm Line	Col Line	Wind_Suct Horz	Wind_Long1 Horz	Wind_Long2 Horz	Seis_Left1 Horz	Seis_Right1 Horz	-MIN_SNOW- Horz	EUNB_SL_L- Horz	EUNB_SL_R- Horz
1	D	0.0	-0.7	0.0	-0.3	0.0	0.0	0.0	0.1
1	C	1.8	0.0	-3.8	0.5	-3.3	0.2	-0.1	0.0
1	B	1.8	0.5	-3.3	0.0	-3.6	0.1	0.2	-0.1
1	A	0.8	0.0	-0.3	0.0	-0.7	0.0	0.0	0.0

Frm Line	Col Line	EUNB_SL_R- Horz	EUNB_SL_L- Horz	EUNB_SL_R- Vert	EUNB_SL_L- Vert
1	D	0.0	-0.1	0.0	0.0
1	C	0.0	1.0	0.0	1.0
1	B	0.0	2.2	0.0	2.2
1	A	0.0	0.1	0.0	0.1

Frm Line	Col Line	Dead Vert	Collot Vert	Live Vert	Snow Vert	Wind_Left1 Horz	Wind_Right1 Horz	Wind_Left2 Horz	Wind_Right2 Horz	Wind_Press Horz
3	B	0.4	0.2	3.4	1.8	1.6	-5.6	0.0	-1.5	1.6
3	C	0.4	0.2	3.4	1.8	0.0	-1.5	1.6	-4.3	0.0
3	D	0.1	0.0	0.4	0.2	0.0	-0.7	0.0	-0.2	0.0

Frm Line	Col Line	Wind_Press Horz	Wind_Suct Horz	Wind_Long1 Horz	Wind_Long2 Horz	Seis_Left1 Horz	Seis_Right1 Horz	Seis_Long1 Horz	Seis_Long2 Horz
3	A	0.0	0.0	0.4	0.2	0.0	-0.7	0.0	0.0
3	B	-1.6	0.0	1.8	0.0	-3.6	0.5	-3.3	0.2
3	C	-1.6	0.0	1.8	0.0	-3.6	0.0	-3.6	0.1
3	D	0.0	-0.8	0.0	0.8	0.0	-0.3	0.0	0.0

Frm Line	Col Line	-MIN_SNOW- Horz	EUNB_SL_L- Horz	EUNB_SL_R- Horz	EUNB_SL_L- Vert	EUNB_SL_R- Vert
3	A	0.0	0.3	0.0	0.1	0.0
3	B	0.0	2.6	0.0	2.2	0.0
3	C	0.0	2.6	0.0	1.0	0.0
3	D	0.0	0.3	0.0	-0.1	0.0


**NOTES FOR REACTIONS**

- BUILDING REACTIONS ARE BASED ON THE FOLLOWING BUILDING DATA:
- WIDTH (FT) = 30
  - LENGTH (FT) = 50
  - EWG HEIGHT (FT) = 12 / 12
  - ROOF SLOPE (IN/12) = 3.0:12 / 3.0:12
  - DEAD LOAD (psf) = 2.010
  - COLLATERAL LOAD (psf) = 1
  - ROOF LIVE LOAD (psf) = 20.00
  - FRAME LIVE LOAD (psf) = 12
  - ROOF SNOW LOAD (psf) = 10.5
  - GROUND SNOW LOAD (psf) = 15.0000
  - WIND SPEED (MPH) = 117
  - WIND CODE = IBC 15
  - EXPOSURE = C
  - CLOSED/OPEN = Closed
  - IMPORTANCE - WIND = 1.00
  - IMPORTANCE - SEISMIC = 1.00
  - SEISMIC ZONE = B

**REACTION KEY:**

- WIND Left/Right 1 = (with +GCj Internal Pressure)
- WIND Left/Right 2 = (with -GCj Internal Pressure)
- Wind\_Long 1 = Wind Load Case B at Left EW
- Wind\_Long 2 = Wind Load Case B at Right EW
- MIN\_SNOW = Minimum Snow (Psf) per code
- EUNB\_SL\_L = Endwall Unbalanced Snow Left
- EUNB\_SL\_R = Endwall Unbalanced Snow Right
- FUNB\_SL\_L = Rigid Frame Unbalanced Snow Left
- FUNB\_SL\_R = Rigid Frame Unbalanced Snow Right

**FRAME LINES:**



**RIGID FRAME: ANCHOR BOLTS & BASE PLATES**

Frm Line	Col Line	Anc. Bolt Qty	Base Plate Dia	Base Plate Length	Thick	Grout (in)
2	D	4	0.750	6.000	10.50	0.375
2	A	4	0.750	6.000	10.50	0.625

**RIGID FRAME: BASIC COLUMN REACTIONS (k)**

Frame Line	Column	Dead Horz	Collateral Horz	Live Horz	Snow Horz	Wind_Left1 Horz	Wind_Right1 Horz	Wind_Left2 Horz	Wind_Right2 Horz	Wind_Press Horz
2	D	0.4	1.3	0.2	0.5	1.8	5.6	1.6	4.9	-5.8
2	A	-0.4	1.3	-0.2	0.5	-1.9	5.6	-1.6	4.9	-1.5

Frame Line	Column	Wind_Left2 Horz	Wind_Right2 Horz	Wind_Long1 Horz	Wind_Long2 Horz	Seismic_Left Horz	Seismic_Right Horz
2	D	-6.2	-6.7	1.1	-2.3	0.9	-8.8
2	A	-1.1	-2.3	6.2	6.7	0.1	-29.4

Frame Line	Column	Seismic_Long Horz	-MIN_SNOW- Horz	EUNB_SL_L- Horz	EUNB_SL_R- Horz
2	D	0.0	-0.1	2.3	7.0
2	A	0.0	-7.6	-2.3	7.0

**ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES**

Frm Line	Col Line	Anc. Bolt Qty	Base Plate Dia	Base Plate Length	Thick	Grout (in)
1	D	2	0.625	7.000	8.000	0.250
1	C	2	0.625	7.000	8.000	0.250
1	B	2	0.625	7.000	8.000	0.250
1	A	2	0.625	7.000	8.000	0.250
3	A	2	0.625	7.000	8.000	0.250
3	B	2	0.625	7.000	8.000	0.250
3	C	2	0.625	7.000	8.000	0.250
3	D	2	0.625	7.000	8.000	0.250

**ANCHOR BOLT SUMMARY**

Qty	Locate	Dia (in)	Type	Proj (in)
12	Jamb	5/8"	F1554	2.00
16	Endwall	5/8"	F1554	2.00
88	Frame	3/4"	F1554	2.50
88	WindCol	3/4"	F1554	2.50
88	WindSuct	3/4"	F1554	2.50

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	2/28/19	FOR ERECTOR INSTALLATION	GJO	HPD	MS

**HERITAGE BUILDING SYSTEMS**  
Established 1979



2812 GRIDDLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5656

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH
CUSTOMER:	JUSTIN SMITH	DATE:	Mar 01 2019
LOCATION:	ANGIER, NC 27501	SHEET NUMBER:	23122
CAD:	DATE:	SCALE:	PHASE:
	2/28/19	N.T.S.	1
BUILDING ID:	A	JOB NUMBER:	16-B-92135
SHEET NUMBER:	F2	ISSUE:	0






\*\* = SAME FLANGE



The large leg of the Zee must be alternated from top to bottom in order to nest the member correctly. A triangle has been added to the end of the Zee near the connection holes, that will point to the large leg of the member.

MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
P-1	8X25Z14	28'-1 1/2"
P-2	8X25Z14	28'-1 1/2"
E-1	BES3L14	24'-11 1/2"
E-2	BES3L14	24'-11 1/2"
E-3	BES3L14	24'-11 1/2"
CB-4	1/4" CABLE	26'-6"
CB-5	1/4" CABLE	25'-8"



ROOF FRAMING PLAN

- GENERAL NOTES:
1. INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
  2. ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
  3. STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
  4. DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
  5. DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
  6. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Since 1979

2612 GRIDDLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH	DATE:	Mar 05 2019
CUSTOMER:	JUSTIN SMITH	JOB NUMBER:	16-B-92135	SHEET NUMBER:	E1
LOCATION:	ANDER, NC 27501	PHASE:	1	ISSUE:	A
CAD:	DATE: 2/28/19	SCALE:	N.T.S.	BUILDING ID:	A











MEMBER TABLE		
FRAME LINE D		
MARK	PART	LENGTH
E-2	BESS L14	24'-11 1/2"
E-3	BESS L14	24'-11 1/2"
G-9	8X25Z16	26'-5 1/2"
G-10	8X25Z16	26'-5 1/2"
CB-2	1/4" CABLE	26'-3"
CB-3	1/4" CABLE	27'-7"



SIDEWALL FRAMING: FRAME LINE D



SIDEWALL SHEETING & TRIM: FRAME LINE D

PANELS: 26 Gauge PBR - Ash Gray

FB PANELS: 26 Gauge PBR - Charcoal Gray

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979

2812 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5655

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANDLER, NC 27501

OWNER: JUSTIN SMITH

Mar 04 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-921.35	E4	A



GENERAL NOTES:

1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.




**BEARING FRAME ONLY**  
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLTY TABLE				
FRAME LINE 1				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2	4	A325	5/8"	1 3/4"
Columns/Raft	4	A325	1/2"	1 1/4"


MEMBER TABLE			
FRAME LINE 1			
MARK	PART	LENGTH	
EC-1	8F25C14	10'-8 1/4"	
EC-2	8F25C16	12'-4 3/4"	
EC-3	8F25C16	12'-4 3/4"	
EC-4	8F25C14	10'-8 1/4"	
ER-1	8F35C14	15'-5 5/16"	
ER-2	8F35C14	15'-5 5/16"	
G-1	8X25Z16	6'-2"	
G-2	8X25Z16	14'-11 1/2"	
CB-1	1/4" CABLE	19'-4"	

FLANGE BRACE TABLE		
FRAME LINE 1		
V ID	PART	LENGTH
FB29.3	L2X2X14G	2'-5 1/4"

CONNECTION PLATES	
FRAME LINE 1	
WID	MARK/PART
1	156-5



ENDWALL FRAMING: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Gauge PBR - Ash Gray  
 PANELS: 26 Gauge PBR - Charcoal Gray


**GENERAL NOTES:**  
 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.  
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.  
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.  
 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CHK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPO	MS

**HERITAGE**  
 BUILDING SYSTEMS  
 Established 1979

2612 GRIDDLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-643-5655

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH	DATE:	Mar 06 2019
CUSTOMER:	JUSTIN SMITH	JOB NUMBER:	16-B-92135	SHEET NUMBER:	E5
LOCATION:	ANDLER, NC 27501	ISSUE:	A		
CAD:	DATE:	SCALE:	PHASE:	BUILDING ID:	
	2/28/19	N.T.S.	1	A	



**BEARING FRAME ONLY**

WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON GLP SIDE.


**BOLT TABLE**

LOCATION	QUAN	TYPE	DIA	LENGTH
ER-3/ER-4	4	A325	5/8"	1 3/4"
Column/Raft	4	A325	1/2"	1 1/4"


MEMBER TABLE		
FRAME LINE 3		
MARK	PART	LENGTH
EC-1	8F25C14	10'-8 1/4"
EC-2	8F25C16	12'-4 3/4"
EC-3	8F25C16	12'-4 3/4"
ER-3	8F35C14	15'-5 5/16"
ER-4	8F35C14	15'-5 5/16"
G-1	8X25Z16	6'-2"
G-2	8X25Z16	14'-11 1/2"
CB-1	1/4" CABLE	18'-4"

FLANGE BRACE TABLE		
FRAME LINE 3		
V ID	PART	LENGTH
FB29.3	1L2X2X14G	2'-5 1/4"

CONNECTION PLATES	
FRAME LINE 3	
CHD MARK/PART	QTY
1 SC-5	1



ENDWALL FRAMING: FRAME LINE 3



ENDWALL SHEETING & TRIM: FRAME LINE 3

PANELS: 26 Gauge PBR - Ash Gray  
 PANELS: 26 Gauge PBR - Charcoal Gray

**GENERAL NOTES:**

1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
 BUILDING SYSTEMS  
Established 1979

2612 GRIBBLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-843-5555

PROJECT: JUSTIN SMITH  
 CUSTOMER: JUSTIN SMITH  
 LOCATION: ANGER, NC 27501  
 OWNER: JUSTIN SMITH

Mar 06 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	E6	A




SPUCE PLATE & BOLT TABLE									
Mark	Qty Top	Qty Bot	Int	Type	Dia	Length	Width	Thick	Length
SP-1	4	4	0	A325	3/4"	1 3/4"	6"	3/8"	1'-7 1/8"

STIFFENER TABLE				
Mark	Stiff Mark	Width	Plate Size Thick	Length
RF1-1	SI-1	2 1/2"	1/4"	17"
RF1-3	SI-1	2 1/2"	1/4"	17"

BASE PLATE TABLE			
Col Mark	Width	Plate Size Thick	Length
BP-1	6"	3/8"	10 1/2"
BP-2	6"	5/8"	10 1/2"

FLANGE BRACES: BOTH SIDES (UNLESS NOTED)  
 FBxxA(1): xx=length(in)  
 A = L2X2X14G

MEMBER TABLE								
Mark	Web Depth		Web Plate		Outside Flange		Inside Flange	
	Start	End	Thick	Length	W x Thk	Length	W x Thk	Length
RF1-1	10.0	17.0	0.134	141.2	5 x 1/4"	136.9	5 x 1/4"	125.8
RF1-2	12.0	12.0	0.134	161.1	5 x 1/4"	26.2	5 x 1/4"	158.0
RF1-3	17.0	10.0	0.134	141.0	5 x 1/4"	26.2	5 x 1/4"	125.5



FRAME CROSS SECTION: FRAME LINE 2

**GENERAL NOTES:**

1. SNUG TIGHT - ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG-TIGHTENED JOINTS IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, DECEMBER 31, 2009. PRE-TENSIONING METHODS, INCLUDING TURN-OF-NUT, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT TENSION INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.
2. ALL FIELD WELDED CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 MACHINE BOLTS
3. INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSM
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS


**HERITAGE**  
 BUILDING SYSTEMS  
Established 1979

2812 GRIBBLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-643-5655

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH	DATE:	2/28/19	SCALE:	N.T.S.	PHASE:	I	BUILDING ID:	A	JOB NUMBER:	16-B-92135	SHEET NUMBER:	E7	ISSUE:	A
----------	--------------	--------	--------------	-------	---------	--------	--------	--------	---	--------------	---	-------------	------------	---------------	----	--------	---








ANTI


PURLIN ANTI-ROLL CLIP



A5

Purlin To Bearing Frame Single Cold Form Rafter


Date Jun '17 Rev 00 Page MB-A5



B4

Cold Form Endwall Column To Rafter


Date Jun '17 Rev 00 Page MB-B4



C4

Girt To Cold Form Column


Date Jun '17 Rev 00 Page MB-C4



C13

Girt To Cold Form Endwall Column - Partially Open

Date Jun '17 Rev 00 Page MB-C13



D4

Girt To Cold Form Corner Column

Date Dec '17 Rev 00 Page MB-D4

Sheeting Clip	
Member	Piece Mark
8"	SC5
10"	SC54
12"	SC55

ISSUE	DATE	DESCRIPTION	BY	CHK'D	DSN
A	2/26/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE BUILDING SYSTEMS**  
Established 1979


2612 ORRIBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANGER, NC 27501  
OWNER: JUSTIN SMITH


Mar 04 2019

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/26/19	N.T.S.	I	A	16-B-92135	DET1	A





E5	Door Jamb Base Plate	Date Dec '18	E8	Cold Form Endwall Column Base Plate	Date Dec '18	F10	Endwall Bearing Frame - Cold Form Rafter Splice At Ridge	Date Jun '17
Page MB-E5		Rev 01	Page MB-E8		Rev 01	Page MB-F10		Rev 00



G2	Purlin To Rigid Frame	Date Jun '17	H2	Girt To Rigid Frame	Date Jun '17	H9	Portal Frame To Rigid Frame Column	Date Jun '17
Page MB-G2		Rev 00	Page MB-H2		Rev 00	Page MB-H9		Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979


2813 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555




PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANGER, NC 27501

OWNER: JUSTIN SMITH

Mar 04 2019

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET2	A








16 Low Side Eave Strut To Bearing Frame - Cold Form  
 Date: Jun '17  
 Rev: 00  
 Page: MB-16

J2 Eave Strut To By-Pass Rigid Frame At Interior  
 Date: Dec '17  
 Rev: 00  
 Page: MB-J2

K3 Girt To Single Cold Form Jamb/Sub Jamb  
 Date: Dec '17  
 Rev: 00  
 Page: MB-K3



L8 Single Cold Form Jamb/Sub Jamb To Girt  
 Date: Jun '17  
 Rev: 00  
 Page: MB-L8

M3 Header To Cold Form Jamb/Sub Jamb  
 Date: Dec '17  
 Rev: 00  
 Page: MB-M3

Q2 Cable Brace Attachment At Web  
 Date: Mar '18  
 Rev: 01  
 Page: MB-Q2

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
 BUILDING SYSTEMS  
 Established 1979

2612 GRIDDLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-643-5555




PROJECT: JUSTIN SMITH  
 CUSTOMER: JUSTIN SMITH  
 LOCATION: ANGIER, NC 27501  
 OWNER: JUSTIN SMITH

Mar 04 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET3	A










Q6  
 Diagonal Brace Clip To Floor  
 Date Jun '17  
 Rev 00  
 Page MB-Q6

R2  
 Anchor Rods At Frame Column  
 Date Dec '17  
 Rev 00  
 Page MB-R2

T18  
 TRANSITION FROM WALL PANEL TO  
 WAINSOT WITH PANELS NOT LAPPED



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSH
A	2/28/19	FOR CONSTRUCTION PERMIT	CJD	HPD	MS

**HERITAGE**  
 BUILDING SYSTEMS  
 Established 1979




2612 GREVILLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-643-5555

PROJECT: JUSTIN SMITH  
 CUSTOMER: JUSTIN SMITH  
 OWNER: JUSTIN SMITH  
 LOCATION: ANCHER, NC 27501

Mar 08 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET4	A








Standard Grade		
Description	Fastener Number	Application
1/4"-14 x 7/8"	4A	Stitch & Trim Screw
12-14 x 1 1/4"	17A	Member Screw
12-14 x 1 1/2"	17B	Member Screw
12-14 x 2"	2B	Member Screw

Note: Standard details call for 1 1/4" fasteners as member screws by default. Member screws may be 1 1/4", 1 1/2", or 2" depending on insulation, application, or customer request.

Long Life		
Description	Fastener Number	Application
1/4"-14 x 7/8"	4	Stitch & Trim Screw
12-14 x 1 1/4"	3	Member Screw
12-14 x 1 1/2"	3A	Member Screw
12-14 x 2"	5B	Member Screw

Self-Drilling Screw Application SCR1



Page MB-U2	Date Jun '17	Page MB-U3	Date Jun '17
Rev 00	Rev 00	Rev 00	Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE BUILDING SYSTEMS**  
Established 1979

2612 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555


PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANDER, NC 27501  
OWNER: JUSTIN SMITH

Mar 05 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DETS	A









Three Sided Framed Opening Jamb Trim Field Cut Details

Note: Trim installation can be done by Field Notch Panel as shown on PW07022 & PW07023 or with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




Three Sided Framed Opening Trim Installation with Field Notch Panel at Head Trim

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.




Three Sided Framed Opening "Optional" Channel Closure Trim

Note: Trim installation can be done by Field Notch Panel as shown on PW07022 & PW07023 or with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




Three Sided Framed Opening Field Notch Panel at Head Trim

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.




Three Sided Framed Opening Jamb Trim Installation

Note: Trim installation can be done by Field Notch Panel as shown on PW07022 & PW07023 or with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.




Three Sided Framed Opening Trim Installation with Field Notch and Bend Tabs at Head Trim

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.



Three Sided Framed Opening Head Trim Installation

Note: Trim installation can be done by Field Notch Panel as shown on PW07022 & PW07023 or with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Three Sided Framed Opening Field Notch and Bend Tabs at Head Trim

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979

2812 GRUBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555


PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANCHER, NC 27501

OWNER: JUSTIN SMITH


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET6	A









All Roof Members Except As Noted Below



At Eave Strut, Panel End Lap, and Peak Purlin



Fastener Location for "PBR" Roof Panel

TRM\_175

ISSUE	DATE	DESCRIPTION	BY	CHK'D	DSH
A	2/26/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979


2012 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
OWNER: JUSTIN SMITH  
LOCATION: ANGER, NC 27501

Mar 07 2019 23122

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/26/19	N.T.S.	I	A	16-B-92135	DET7	A





TRIM\_174

ISSUE	DATE	DESCRIPTION	BY	CHK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
 BUILDING SYSTEMS  
Established 1979

2012 GRIBBLE STREET  
 NORTH LITTLE ROCK, AR 72114  
 1-800-843-5555

PROJECT:	JUSTIN SMITH	OWNER:	JUSTIN SMITH	DATE:	Mar 05 2019		
CUSTOMER:	JUSTIN SMITH						
LOCATION:	ANDER, NC 27501						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET8	A









PBR Wall Panel - Pre-Assembled Walk Door & Glass-Front Walk Door  
Jamb Trim Installation

PW09029  
Nov '17 '03




PBR Wall Panel - Pre-Assembled Walk Door & Glass-Front Walk Door  
Head Trim Installation

PW09030  
Mar '15 '02




PBR Wall Panel - Knock Down Walk Door  
Jamb Trim Installation

PW09031  
Nov '17 '03



PBR Wall Panel - Knock Down Walk Door  
Head Trim Installation

PW09032  
Mar '15 '02



ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPD	MS

**HERITAGE**  
BUILDING SYSTEMS  
Established 1979


2812 CRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-843-5555

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANGIER, NC 27501  
OWNER: JUSTIN SMITH


Mar 06 2019 23122

CD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	I	A	16-B-92135	DET10	A







Door Elevation




Walk Door Clip To Jamb Isometric




Door Jamb Extension Isometric



Section A




Section B




The Adequacy Of The 1/2" Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer.  
Verify Door Jamb Base Clip Dimensions With Patterns Shown Prior To Placement Of Door Anchors And Adjust Patterns If Needed.  
Note: 12" Frames May Not Have Kerf Door Frame Feature Depending On Door Manufacturer.

Knock Down Door Anchor Placement



Section C



Section D

ISSUE	DATE	DESCRIPTION	BY	CHK'D	DSN
A	2/28/19	FOR CONSTRUCTION PERMIT	GJO	HPO	MS

**HERITAGE BUILDING SYSTEMS**  
Established 1979

2812 GRIBBLE STREET  
NORTH LITTLE ROCK, AR 72114  
1-800-643-5555

PROJECT: JUSTIN SMITH  
CUSTOMER: JUSTIN SMITH  
LOCATION: ANDLER, NC 27501

Mar 04 2019



Knock Down Door - With Girt At 7'-6" And With Low / Base Girt  
Walk Door Frame Attaching To Welded Clip Jamb

Proj: ACO5220  
Date: Nov '18  
Rev: 00

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	2/28/19	N.T.S.	1	A	16-B-92135	DET11	A