

HTE# BRES1812-0037

Harnett County Department of Public Health

30335

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Clayton Homes - Raleigh PROPERTY LOCATION: 3543 Johnston County Rd. (SR1537)

NEW REPAIR EXPANSION SUBDIVISION _____ LOT # _____

Type of Structure: 432 28'x76' MOD Site Improvements required prior to Construction Authorization Issuance: _____

Proposed Wastewater System Type: 25% Reduction (Pump)

Projected Daily Flow: 480 GPD

Number of bedrooms: 4 Number of Occupants: 8 max

Basement Yes No

Pump Required: Yes No May be required based on final location and elevations of facilities

Type of Water Supply: Community Public Well Distance from well 50+ feet Permit valid for: Five years No expiration

Permit conditions: _____

Authorized State Agent: [Signature] Date: 01/16/2019 SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Clayton Homes - Raleigh PROPERTY LOCATION: 3543 Johnston County Rd. (SR1537)

Facility Type: 432 28'x76' MOD New Expansion Repair SUBDIVISION _____ LOT # _____

Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** Pump to 25% Reduction (Initial) Wastewater Flow: 480 GPD

(See note below, if applicable Pump to 25% Reduction (Repair))

Installation Requirements/Conditions

Septic Tank Size <u>1000</u> gallons	Number of trenches <u>3</u>	Trench Spacing: <u>9</u> Feet on Center
Pump Tank Size <u>1000</u> gallons	Exact length of each trench <u>90</u> feet	Soil Cover: <u>20-26</u> inches
	Trenches shall be installed on contour at a Maximum Trench Depth of: <u>32-26</u> inches (Maximum soil cover shall not exceed 36" above the trench bottom)	
	(Trench bottoms shall be level to +/-1/4" in all directions)	

Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: NA inches below pipe NA inches above pipe NA inches total

Conditions: D-Box Equal Distribution Required; Deep (32IN) to Shallow (16IN) install required w/ stepdown required

WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.

***If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 01/16/2019

ANDREW CURRIN Construction Authorization Expiration Date: 01/16/2024

HTE# BUES1812-0037

Permit # 30335

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: 3543 Johnston County Rd (SL 1551)

ISSUED TO: Clayton Homes - Raleigh SUBDIVISION _____ LOT # _____

Authorized State Agent: Andrew Curran Date: 01/16/2019
ANDREW CURRAN

- * NO DRIVING OVER PROPOSED SEPTIC AREA; DUCTILE IRON PIPE OR DOT EQUIVALENT REQ. UNDED DRIVEWAY
- * MEET ONSITE MAY BE REQUIRED
- * PUMP TO D-BOX EQUAL DISTRIBUTION
- * DEEP (32IN) TO SHALLOW (16IN) INSTALL REQUIRED W/ STEPDOWN TO KEEP SYS TIGHT TO ESMT/TREE LINE TO JOHNSTON CO RD (SL 1551)

