

HTE# BRES1901-0002R

Harnett County Department of Public Health

30486

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Glenn Jones, Inc.
 NEW REPAIR EXPANSION
 Type of Structure: Pole Barn 50'x80' w/ Bath
 Proposed Wastewater System Type: 25% Reduction Sys.
 Projected Daily Flow: 240 GPD
 Number of bedrooms: NA Number of Occupants: NA max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well NA feet
 Permit conditions: _____

PROPERTY LOCATION: 4011 Sheriff Johnson Rd. (S21516)
 SUBDIVISION _____ LOT # _____

Site Improvements required prior to Construction Authorization Issuance: _____

Permit valid for: Five years
 No expiration

Authorized State Agent: [Signature]

Date: 03/14/2019

SEE ATTACHED SITE SKETCH

The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Glenn Jones, Inc.

PROPERTY LOCATION: 4011 Sheriff Johnson Rd. (S21516)
 SUBDIVISION _____ LOT # _____

Facility Type: Pole Barn 50'x80' w/ Bath New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No

Type of Wastewater System** 25% Reduction System (Initial) Wastewater Flow: 240 GPD
 (See note below, if applicable)

Pump to 25% Red. Sys. (Repair) OR FOUR (4) SOFT #10-BOX

Installation Requirements/Conditions

Septic Tank Size 1000 gallons
 Pump Tank Size _____ gallons

Number of trenches 1
 Exact length of each trench 200 feet
 Trenches shall be installed on contour at a
 Maximum Trench Depth of: 18 inches
 (Trench bottoms shall be level to +/-1/4"
 in all directions)

Trench Spacing: 9 Feet on Center
 Soil Cover: 6 inches
 (Maximum soil cover shall not exceed
 36" above the trench bottom)

Pump Requirements: _____ ft. TDH vs. _____ GPM

Aggregate Depth: NA inches below pipe
NA inches above pipe
NA inches total

Conditions: SOFT Creek and wetland setback

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

**If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit.

SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature]
ANDREW CURRIN

Date: 03/14/2019
 Construction Authorization Expiration Date: 03/14/2024

HTE# BRES1901-0002R

Permit # 30486

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: 4011 Sheriff Johnson Rd. (S21516)

ISSUED TO: Glenn Jones, Inc.

SUBDIVISION

LOT #

Authorized State Agent:

[Signature]

Date: 03/14/2019

