

Improvement Permit

A building permit cannot be issued with only an Improvement Permit

ISSUED TO: Justina del Carmen Garcia PROPERTY LOCATION: 748 Johnsonville School Rd. (521202)
 NEW REPAIR EXPANSION SUBDIVISION _____ LOT # _____
 Type of Structure: 4BR 72'x28' DUMH Site Improvements required prior to Construction Authorization Issuance: _____
 Proposed Wastewater System Type: 25% reduction
 Projected Daily Flow: 4800 GPD
 Number of bedrooms: 4 Number of Occupants: 8 max
 Basement Yes No
 Pump Required: Yes No May be required based on final location and elevations of facilities
 Type of Water Supply: Community Public Well Distance from well NA feet Permit valid for: Five years
 Permit conditions: _____ No expiration

Authorized State Agent: [Signature] Date: 01/18/2019 SEE ATTACHED SITE SKETCH
 The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.

Construction Authorization

(Required for Building Permit)

The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout.

ISSUED TO: Justina del Carmen Garcia PROPERTY LOCATION: 748 Johnsonville School Rd. (521202)
 Facility Type: 4BR 28'x92' DUMH New Expansion Repair
 Basement? Yes No Basement Fixtures? Yes No
 Type of Wastewater System** 25% Reduction System (PUMP) (Initial) Wastewater Flow: 4800 GPD
 (See note below, if applicable 50% PPBPS SYS.
25% reduction sys. (Repair)
Installation Requirements/Conditions
 Septic Tank Size 1000 gallons Number of trenches 3
 Pump Tank Size 1000 gallons Exact length of each trench 90 feet Trench Spacing: 9 Feet on Center
 Trenches shall be installed on contour at a Soil Cover: 8-16 inches
 Maximum Trench Depth of: 20-16 inches (Maximum soil cover shall not exceed
 (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom)
 in all directions)
 Pump Requirements: _____ ft. TDH vs. _____ GPM Aggregate Depth: NA inches below pipe
 _____ inches above pipe
 _____ inches total
 Conditions: D-Box Equal Distribution; Deep (20IN) to shallow (16IN) may be required

**WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA.
 NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA.**

***If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit.*

Owner/Legal Representative Signature: _____ Date: _____

This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH

Authorized State Agent: [Signature] Date: 01/18/2019 01/23/2019
ANDREW CURRIN Construction Authorization Expiration Date: 01/18/2024 01/23/2024

HTE# BRES1901-0005

Permit # 30343

Harnett County Department of Public Health Site Sketch

PROPERTY LOCATOR: 748 Johnsonville School Rd. (SL1203)

ISSUED TO: Justinel Casmen Garcia SUBDIVISION _____ LOT # _____

Authorized State Agent: *[Signature]* Date: 01/23/2019
ANDREW CURTIS

- * 25% REDUCTION SYSTEM
- * PUMP TO D-BOX EQUAL DISTRIBUTION REQUIRED
- * DEEP (20 IN) TO SHALLOW (16 IN) MAY BE REQUIRED
- [DEEP (20 IN) ONLY ALLOWED AT START. SHALL BE 18 IN OR LESS BY FRONT OF DUMH]

