

**STRUCTURAL NOTES**

1) ALL CONSTRUCTION SHALL CONFORM TO THE LATEST REQUIREMENTS OF "NORTH CAROLINA STATE 2012 RESIDENTIAL BUILDING CODE", IN ADDITION TO ALL LOCAL CODES AND REGULATIONS.

2) DESIGN LOADS:

|                           | LIVE LOAD (PSF)               | DEAD LOAD (PSF) | DEFLECTION |       |
|---------------------------|-------------------------------|-----------------|------------|-------|
|                           |                               |                 | LL         | TL    |
| ALL FLOORS                | 40                            | 10              | L/360      | L/240 |
| ATTIC (w/ walk up stairs) | 30                            | 10              | L/360      | L/240 |
| ATTIC (pull down access)  | 20                            | 10              | L/240      | L/180 |
| ATTIC (no access)         | 10                            | 5               | L/240      | L/180 |
| EXTERNAL BALCONY          | 40                            | 10              | L/360      | L/240 |
| ROOF                      | 20                            | 10              | L/240      | L/180 |
| ROOF TRUSS                | 20                            | 20              | L/240      | L/180 |
| WIND LOAD                 | BASED ON 100 MPH (EXPOSURE B) |                 |            |       |
| SEISMIC                   | SEISMIC ZONES A, B & C        |                 |            |       |

3) MINIMUM ALLOWABLE SOIL BEARING PRESSURE = 2000 PSF

4) CONCRETE SHALL HAVE A MINIMUM 28 DAY COMPRESSIVE STRENGTH OF 3000 PSI AND A MAXIMUM SLUMP OF FIVE INCHES UNLESS NOTED OTHERWISE. (U.N.O.)

5) MAXIMUM DEPTH OF UNBALANCED FILL AGAINST FOUNDATION WALLS TO BE LESS THAN 4'-0" WITHOUT USING SUFFICIENT WALL BRACING. REFER TO SECTION R404 OF 2012 NC BUILDING CODE FOR BACKFILL LIMITATIONS BASED ON WALL HEIGHT, WALL THICKNESS, SOIL TYPE, AND UNBALANCED BACKFILL HEIGHT.

6) ALL FRAMING LUMBER SHALL BE SPF #2 (Fb = 1000 PSI) UNO. ALL FRAMING LUMBER EXPOSED TO THE ELEMENTS SHALL BE TREATED MATERIAL. ALL LVL LUMBER TO BE 1.75" WIDE NOMINAL EACH SINGLE MEMBER AND Fb = 2600 PSI, E = 1.9M PSI (U.N.O.) ALL LSL LUMBER TO BE 3.5" WIDE NOMINAL EACH SINGLE MEMBER AND Fb = 2325 PSI, E = 1.6M PSI (U.N.O.) ALL PSL LUMBER TO BE 3.5" WIDE NOMINAL EACH SINGLE MEMBER AND Fb = 2400 PSI, E = 1.8M PSI (U.N.O.)

7) ALL LOAD BEARING EXTERIOR HEADERS SHALL BE AT (2) 2x10. (U.N.O.) REFER TO TABLE R502.5(1) & (2) FOR JACK STUD REQUIREMENTS FOR HEADER SPANS FOR INTERIOR AND EXTERIOR LOAD CONDITIONS UNLESS SPECIFICALLY NOTED ON PLANS.

8) ALL STRUCTURAL STEEL W-SHAPES (I-BEAMS) SHALL BE ASTM A992 GRADE 50. ALL STEEL ANGLES, PLATES, AND C-CHANNELS SHALL BE ASTM A36. ALL STEEL PIPE SHALL BE ASTM A53 GRADE B.

9) STEEL BEAMS SHALL BE SUPPORTED AT EACH END WITH A MINIMUM BEARING LENGTH OF 3-1/2" AND FULL FLANGE WIDTH. PROVIDE SOLID BEARING FROM BEAM SUPPORT TO FOUNDATION. BEAMS SHALL BE ATTACHED TO EACH SUPPORT WITH TWO (2) LAG SCREWS (1/2" x 4" LONG). LATERAL SUPPORT IS CONSIDERED ADEQUATE PROVIDED THE JOISTS ARE TOE NAILED TO THE SOLE PLATES, AND THE SOLE PLATES ARE NAILED OR BOLTED TO THE BEAM FLANGES @ 48" O.C.

10) PROVIDE ANCHOR BOLT PLACEMENT PER SECTION 403.1.6; 1/2" Ø ANCHOR BOLTS SPACED AT 6'-0" O.C. AND PLACED 12" FROM THE END OF EACH PLATE SECTION. ANCHOR BOLTS SHALL BE SPACED AT 3'-0" O.C. FOR BASEMENTS. ANCHOR BOLT SHALL EXTEND 7" INTO CONCRETE OR MASONRY. THERE SHALL BE A MINIMUM TWO ANCHOR BOLTS PER PLATE SECTION.

11) FOUNDATION DRAINAGE-DAMP PROOFING OR WATERPROOFING PER SECTION 405 AND 406 OF NC BUILDING CODE.

12) WALL AND ROOF CLADDING VALUES:  
WALL CLADDING SHALL BE DESIGNED FOR 24.1 POUNDS PER SQUARE FOOT (LBS/SQFT) OR GREATER POSITIVE AND NEGATIVE PRESSURE. ROOF VALUES BOTH POSITIVE AND NEGATIVE SHALL BE AS FOLLOWS:  
45.5 LBS/SQFT FOR ROOF PITCHES 0/12 TO 2.25/12  
34.8 LBS/SQFT FOR ROOF PITCHES 2.25/12 TO 7/12  
21.0 LBS/SQFT FOR ROOF PITCHES 7/12 TO 12/12  
\*\*MEAN ROOF HEIGHT 30'-0" OR LESS

13) FOR ROOF SLOPES FROM 2/12 THROUGH 4/12, BUILDER TO INSTALL 2 LAYERS OF 15# FELT PAPER.

14) REFER TO SECTION R602.3 FOR FRAMING OF ALL WALLS OVER 10'-0" IN HEIGHT.

15) PROVIDE CONTINUOUS SHEATHING PER SECTION 602.10.4 OF THE 2012 IRC.

16) UPLIFT LOADS GREATER THAN 500# SHALL BE CONTINUOUSLY ANCHORED TO THE FOUNDATION.

17) REFER TO TABLE N1102.1 FOR PRESCRIPTIVE BUILDING ENVELOPE THERMAL COMPONENT CRITERIA.

18) PSL COLUMNS DESIGNED WITH MAXIMUM HEIGHT OF 9'-0" (U.N.O.)

19) PROVIDE A MINIMUM OF 500# UPLIFT & LATERAL CONNECTION AT TOP AND BOTTOM OF PORCH COLUMNS. (U.N.O.)


20) MAXIMUM MASONRY PEIR HEIGHT SHALL NOT EXCEED FOUR TIMES ITS LEAST HORIZONTAL DIMENSION.

21) IT IS THE CONTRACTORS RESPONSIBILITY TO VERIFY ALL DIMENSIONS AND SQUARE FOOTAGE PRIOR TO CONSTRUCTION. TYNDALL ENGINEERING & DESIGN, PA IS NOT RESPONSIBLE FOR DIMENSION OR SQUARE FOOTAGE ERRORS ONCE CONSTRUCTION BEGINS.


**DEFINITIONS FOR COMMON ABBREVIATIONS**

|       |   |                       |       |   |                        |
|-------|---|-----------------------|-------|---|------------------------|
| ALT   | = | ALTERNATE             | MAX   | = | MAXIMUM                |
| CANT  | = | CANTILEVER            | MIN   | = | MINIMUM                |
| CJ    | = | CEILING JOIST         | NOM   | = | NOMINAL                |
| CMU   | = | CONCRETE MASONRY UNIT | O.C.  | = | ON CENTER              |
| COL   | = | COLUMN                | PL    | = | PLATE                  |
| CONC  | = | CONCRETE              | PT    | = | PRESSURE TREATED       |
| CONT  | = | CONTINUOUS            | REINF | = | REINFORCED             |
| CT    | = | COLLAR TIE            | REQD  | = | REQUIRED               |
| DBL   | = | DOUBLE                | RJ    | = | ROOF JOIST             |
| DIA   | = | DIAMETER              | RS    | = | ROOF SUPPORT           |
| DJ    | = | DOUBLE JOIST          | SC    | = | STUD COLUMN            |
| DR    | = | DOUBLE RAFTER         | SCH   | = | SCHEDULE               |
| EA    | = | EACH                  | SPEC  | = | SPECIFIED              |
| EE    | = | EACH END              | THK   | = | THICK                  |
| FJ    | = | FLOOR JOIST           | TJ    | = | TRIPLE JOIST           |
| FND   | = | FOUNDATION            | TRTD  | = | TREATED                |
| FTG   | = | FOOTING               | TYP   | = | TYPICAL                |
| GALV  | = | GALVANIZED            | UNO   | = | UNLESS NOTED OTHERWISE |
| HORIZ | = | HORIZONTAL            | W     | = | WIDE FLANGE BEAM       |
| HT    | = | HEIGHT                | WWF   | = | WELDED WIRE FABRIC     |
| MANUF | = | MANUFACTURER          | XJ    | = | EXTRA JOIST            |

**Approved**  
by *bsutton* 02/13/2019




**PARTIAL FOUNDATION PLAN**  
1/4" = 1'-0"




**ADDED HEATED/HABITABLE SQUARE FOOTAGE**  
Second Floor **285**

**I-JOIST HANGER SCHEDULE**  
EXISTING 14" BCI 6000s (SINGLE): SIMPSON IUS2.37/14  
EXISTING 14" BCI 6000s (DOUBLE): SIMPSON MIU4.75/14  
NEW 14 BCI 4500s (SINGLE): SIMPSON IUS1.81/14  
NEW 14" BCI 4500s (DOUBLE): SIMPSON MIU3.56/14  
USE HANGERS NOTED ABOVE (OR EQUIV.) UNLESS NOTED OTHERWISE



**PARTIAL FIRST FLOOR PLAN**  
1/4" = 1'-0"



**PARTIAL SECOND FLOOR PLAN**  
1/4" = 1'-0"

\*Engineers seal does not include construction means, methods, techniques, sequences, procedures or safety precautions. Any deviation or discrepancies on plans are to be brought to the immediate attention of Tyndall Engineering & Design, P.A. Failure to do so will void Tyndall Engineering & Design, P.A. liability. Please review these documents carefully. Tyndall Engineering & Design, P.A. will interpret that all dimensions, recommendations, etc. presented in these documents were deemed acceptable once construction begins.



**TYNDALL ENGINEERING & DESIGN, P.A.**  
1801-020622 • 1801-020622  
400 Blaylock Drive • Cary, NC 27513  
www.tyndallengineering.com

Client: **RAY WICKER**  
Project: **TRACY RESIDENCE**

**1ST & 2ND FLOOR PLAN FOUNDATION PLAN**

Project #: 1801-020622  
Date: 10/19/18  
Drawn/Design By: PSE  
DWG. Checked By: PAT  
Scale: SEE PLAN

**REVISIONS**

| No. | Date | Remarks |
|-----|------|---------|
|     |      |         |
|     |      |         |
|     |      |         |

Sheet Number **S1**  
1 of 1