## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 76 Virginia Ln ISSUED TO: Darlene Leon SUBDIVISION Heritage Village NEW [ REPAIR | EXPANSION X Site Improvements required prior to Construction Authorization Issuance: Type of Structure: SFD Addition (20'x30') Proposed Wastewater System Type: 25% Reduction System Projected Daily Flow: 600 GPD Number of Occupants: 10 Number of bedrooms: 5 Basement Yes X No Pump Required: Yes X No May be required based on final location and elevations of facilities Type of Water Supply: Community Public Well Distance from well \_\_\_\_\_\_feet Permit valid for: X Five years Permit conditions: No expiration Date: 6/24/2019 SEE ATTACHED SITE SKETCH Authorized State Agent:: The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1950, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Darlene Leon PROPERTY LOCATION: 76 Virginia Ln SUBDIVISION Heritage Village LOT # Facility Type: SFD Addition (20'x30') X No No Basement? Yes Basement Fixtures? Yes 25% Reuction System Type of Wastewater System\*\* (Initial) Wastewater Flow: 600 GPD (See note below, if applicable ) Pump 25% Red Sys Number of trenches 2 Installation Requirements/Conditions Trench Spacing: 9 Feet on Center Septic Tank Size 1250 gallons Exact length of each trench 70 Pump Tank Size \_\_\_\_\_gallons Trenches shall be installed on contour at a Soil Cover: 6-24 inches Maximum Trench Depth of: 18-36 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_ ft. TDH vs. \_\_\_\_ inches below pipe Aggregate Depth: \_\_\_\_\_\_ inches above pipe Conditions: Abandon first line inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This SEE ATTACHED SITE SKETCH Construction Authorization to the compliance with the previsions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. OCPU Date: 6/24/2019 Authorized State Agent: Construction Authorization Expiration Date: 6/24/2024

HTE#	BRES1904-007	OR
$\Pi \sqcup H$	DRUDI I O CI	

Permit # \_\_\_\_\_

## Harnett County Department of Public Health Site Sketch

		PROPERTY LOCATON:_	76	VIRGINIA	LN	
ISSUED TO: DAZZENE	LEON	SUBDIVISION				_ LOT #
Authorized State Agent:	200	COLINER TOLKS	was)	Date: 6)2	4/19	
Authorized State Agent:	ABANDON THING S	DEN DINES	2501	Date: 6 3	74   16 <u>1</u>	
	->@					
	Viesi	VIA LN				