## Harnett County Department of Public Health

## Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 210 Koerner Ln ISSUED TO: Hadwin, Larry Allen SUBDIVISION EXPANSION REPAIR NEW X Site Improvements required prior to Construction Authorization Issuance: Type of Structure: Man Home (14'x56') Proposed Wastewater System Type: Pump 25% Reduction Projected Daily Flow: 360 Number of bedrooms: 3 Number of Occupants: 6 Basement Yes No Pump Required. May be required based on final location and elevations of facilities Type of Water Supply: Community Dublic Well Distance from well feet ★ Five years Permit valid for: No expiration Permit conditions: Date: 6/28/2019 Authorized State Agent:: The issuance of this permit by the Health Department in no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The intended use changes affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit.. 8/12/19 Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1950, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Hadwin, Larry Allen PROPERTY LOCATION: 210 Koerner Ln LOT # SUBDIVISION Facility Type: Man Home (14'x56') Expansion Repair Basement? Yes × No Basement Fixtures? Yes ☐ No •Pump-tp 25% Reduction System (Initial) Wastewater Flow: 360 GPD Type of Wastewater System\*\* (See note below, if applicable ) Pump 25% Reduction System (Repair) Number of trenches 2 Installation Requirements/Conditions Septic Tank Size 1000 gallons Exact length of each trench 75 Trench Spacing: 9 Feet on Center Pump Tank Size \_\_\_\_\_gallons Trenches shall be installed on contour at a Soil Cover: 6 inches (Maximum soil cover shall not exceed Maximum Trench Depth of: 18 inches (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_\_ ft. TDH vs. \_\_\_\_\_GPM \_\_ inches below pipe Aggregate Depth: inches above pipe inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: 1 understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is Tobject to compliance with the protections of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Age Date: 6/28/2019 8/11/19 Construction Authorization Expiration Date: 6/28/2024

## Harnett County Department of Public Health Site Sketch

Authorized State Agent:	PROPERTY LOCATON: 210 KOER ALLEN SUBDIVISION  CONTO TOLKSDORE)  Date:	LOT #
1 3 1	80	

- . THIS DRAWING IS FOR ILLUSTRATIVE PURPOSES ONLY
- . SYSTEM INSTALLATION MUST MEET ALL PERTINENT LAWS, RULES