

12:45 PM 6/10/2019 RAY AND MISTY PARKER
206 EAST D STREET
ERWIN, NC

MUD ROOM 8X8 MATERIALS AND LABOR \$9,700

- 1- FOOTING 16 INCH WIDE 12 IN DEEP
- 2- BLOCK FOUNDATION OUTSIDE COVERED WITH BRICK
- 3- 2X6 TREATED MUD PLATE
- 4- BAND WILL BE 2X8 AND FLOOR JOISTS ON 16 INCH CENTERS WITH JOISTS HANGERS
- 5- 3/4 TONGUE AND GROOVE PLYWOOD SUB-FLOOR
- 6- 2X8 WALLS ON 16 INCH CENTERS
- 7- OUTSIDE WALLS COVERED WITH PLYWOOD 7/16 AND HOUSE WRAP
- 8- RAFTERS WILL BE 2X6 AND CEILING JOISTS WILL BE 2X6 ON 7X16 PLYWOOD ON TOP
- 9- DOOR ENTRANCE 36 INCH
- 10- 1/2 INCH SHEETROCK ON INSIDE AND NO WINDOWS
- 11- HURRICANE TIES ON ALL RAFTERS
- 12- OUTSIDE COVERED IN VINYL SIDING AND VINYL SOFFIT
- 13- ONE LIGHT IN CENTER OF ROOM AND CLOSET ON RIGHT HAND SIDE ENTERING MUD ROOM

TOMMY CORE'S RESIDENTIAL CONSTRUCTION LLC
PHONE: 910-985-2340
EMAIL: TOMMYCORESRESIDENTIALCONSTRLLC@GMAIL.COM

12:45 PM 6/10/2019 RAY AND MISTY PARKER
206 EAST D STREET
ERWIN, NC

CARPORT 24X24 MATERIALS AND LABOR \$10,500

- 1- 6X6 POSTS BURIED 3FT AND CONCRETED EVERY 12FT
- 2- 2X10 DOUBLE BAND WITH OSB BOARD IN THE MIDDLE
- 3- TRUSS 24FT LONG WITH 1FT OVERHANG 5/12 PITCH AND TRUSS WILL BE BRACED AS BLUE PRINT SHOWS *TRUSS ON 16" CENTERS*
- 4- 7/16 OSB BOARD FOR DECKING
- 5- BLACK METAL ROOF AND BLACK DRIP EDGE AND BLACK GABLE RAKE
- 6- BOXING COVERED WITH VINYL SOFFIT AND METAL TRIM AND CEILING JOISTS COVERED VINYL
- 7- 2 LIGHTS UNDER CARPORT, 1 FLOOD LIGHT ON CORNER FACING DRIVEWAY
- 8- ALL RAFTERS WILL BE TIED DOWN WITH HURRICAN STRAPS
- 9- BAND WILL BE BOLTED TO 6X6 POSTS

Tommy Core's Residential Construction LLC

910-985-2340

email: TommyCoresresidentialconstrllc@gmail.com

