

HTE 04-5-8692

# IMPROVEMENT PERMIT

20710

Be it ordained by the Harnett County Board of Health as follows: Section III, Item B. "No Person shall begin construction of any building at which a septic tank system is to be used for disposal of sewage without first obtaining a written permit from the Harnett County Health Department."

Name: (owner) STRONG BUILT HOMES INC  New Installation  Septic Tank  
Property Location: SR# 1415 RAWLS CHURCH RD  Repairs  Nitrification Line

Subdivision WYNDHAM BLAKE Lot # 20

Tax ID # \_\_\_\_\_ Quadrant # \_\_\_\_\_

Number of Bedrooms Proposed: 3 Lot Size: 25005sqft

Basement with Plumbing:  Garage:

Water Supply:  Well  Public  Community

Distance From Well: 100 ft.

**Following is the minimum specifications for sewage disposal system on above captioned property. Subject to final approval.**

Type of system:  Conventional  Other \_\_\_\_\_

Size of tank: Septic Tank: 1000 gallons Pump Tank: \_\_\_\_\_ gallons

Subsurface Drainage Field No. of 4 exact length of each ditch 100 ft. width of ditches 3 ft. depth of ditches 20 in. <sup>MAX!</sup>

French Drain Required: \_\_\_\_\_ Linear feet

Date: 3/1/04

Signed: [Signature] RS (OLIVER TOLKSDORF)  
Environmental Health Specialist

**This permit is subject to revocation if site plans or intended use change.**

