

Enoch Engineers, P.A.

Consulting Engineers & Surveyors

1403 NC Highway 50 South
Benson, North Carolina 27504

Phone: (919) 894-5731
(919) 894-7765

Fax: (919) 894-8190

Email: general@enochengineers.com

Joe E. Godwin Sr., P.E., P.L.S.

Fleet Temple, P.E.

Jason E. Godwin, P.L.S.

April 9, 2020

Stephenson Builders, Inc.
1187 North Raleigh Street
Angier, North Carolina 27501

Attn: Mr. Phil Stephenson

RE: Site/footing inspection
House footprint (Permit No. SFD1906-0016)
Garage footprint (Permit No. BRES1911-0001)

Subject: 155 Bombo Drive
Lillington, North Carolina

To Whom It May Concern:

Enoch Engineers conducted a footing inspection on April 8th, 2020 of the soil material for the subject property above. We observed the removal of organics including tree roots within the footing spaces. In addition we recommended undercutting the soils a minimum of 24" or to suitable soils whichever is greater and backfilling these areas with washed No. 57 stone to grade. We observed the undercut footing soils, depth and width and approve they are suitable for construction and meet the minimum requirements in accordance with the 2018 North Carolina Building Code including a minimum allowable bearing capacity of 2,000 lb/ft². If we may be of further assistance, please feel free to call.

Respectfully,

Joe E. Godwin, Sr., P.E.
Enoch Engineers, P.A.

4/9/20

jeg,sr/jeg