## Harnett County Department of Public Health

Improvement Permit

A building permit cannot be issued with only an Improvement Permit PROPERTY LOCATION: 22 Haynes St, Cameron (SR#1155) ISSUED TO: Shirlene Walker SUBDIVISION REPAIR EXPANSION | Site Improvements required prior to Construction Authorization Issuance: Type of Structure: DWMH 28'x52' Proposed Wastewater System Type: 25% Reduction Projected Daily Flow: 360 \_\_\_\_\_ Number of Occupants: 6 max Number of bedrooms: 3\_\_\_ Basement Yes Pump Required: Yes No May be required based on final location and elevations of facilities Type of Water Supply: Community Public Well Distance from well X Five years Permit valid for: Permit conditions: No expiration MA KEHS Date: 12/5/2019 The issuance of this permit by the Health Department no way guarantees the issuance of other permits. The permit holder is responsible for checking with appropriate governing bodies in meeting their requirements. This site is subject to revocation if the site plan, plat, or the intended use changes. The Improvement Permit shall not be affected by a change in ownership of the site. This permit is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to conditions of this permit. Construction Authorization (Required for Building Permit) The construction and installation requirements of Rules .1950, .1952, .1954, .1955, .1956, .1957, .1958, and .1959 are incorporated by references into this permit and shall be met. Systems shall be installed in accordance with the attached system layout. ISSUED TO: Shirlene Walker PROPERTY LOCATION: 22 Haynes St, Cameron (SR#1155) SUBDIVISION Facility Type: DWMH 28'x52' Expansion Basement? Yes Basement Fixtures? Yes 25% Reduction (Initial) Wastewater Flow: 360 GPD Type of Wastewater System\*\* (See note below, if applicable ) 25% Reduction Installation Requirements/Conditions Number of trenches 1 Septic Tank Size 1000 gallons Exact length of each trench 200 feet Trench Spacing: 9 Feet on Center Pump Tank Size \_\_\_\_\_gallons Trenches shall be installed on contour at a Soil Cover: 6 \_\_\_\_\_inches Maximum Trench Depth of: 18 inches (Maximum soil cover shall not exceed (Trench bottoms shall be level to +/-1/4" 36" above the trench bottom) in all directions) Pump Requirements: \_\_\_\_\_\_ft. TDH vs. \_\_\_\_\_GPM \_\_\_\_\_ inches below pipe Aggregate Depth: inches above pipe inches total WATER LINES (INCLUDING IRRIGATION) MUST BE 10FT. FROM ANY PART OF SEPTIC SYSTEM OR REPAIR AREA. NO UTILITIES ALLOWED IN INITIAL OR REPAIR DRAIN FIELD AREA. \*\*If applicable: I understand the system type specified is different from the type specified on the application. I accept the specifications of this permit. Owner/Legal Representative Signature: \_ This Construction Authorization is subject to revocation if the site plan, plat, or the intended use changes. The Construction Authorization shall not be transferred when there is a change in ownership of the site. This Construction Authorization is subject to compliance with the provisions of the Laws and Rules for Sewage Treatment and Disposal and to the conditions of this permit. SEE ATTACHED SITE SKETCH Authorized State Agent: Date: 12/5/2019 Construction Authorization Expiration Date: 12/5/2024

## Harnett County Department of Public Health Site Sketch

Property Location:	22 Hayr	VES ST Can Subdivis	rern (:	SP#1155)	Lot#
Authorized State Age	1	1 1 1	REHS	Da	te: 12 5 19
					1
		1200			
	+5	Reduction Repair	n	1	
	Haymes St	( Àvec	~ ( ( (		
	Ha	200 500			
	75'	3BR DW1			
	Dell Dell				
	Oe)	180			
		Brooks N	Nangum Ro	1	
			J		

This drawing is for illustrative purposes only. System installation must meet all pertinent laws, rules, and regulations.