



- Install $\frac{1}{2}$ drywall walls and $\frac{5}{8}$ ceilings
- Install 8" flex duct to a ceiling register (30' from attic unit)
- Install R13 insulation walls and blown insulation ceiling
- Install laminate flooring