

BUILDER/CONTRACTOR RESPONSIBILITIES

Drawing Validity - These drawings, supporting structural calculations and design certification are based on the order documents as of the date of these drawings. These documents describe the material supplied by the manufacturer as of the date of these drawings. Any changes to the order documents after the date on these drawings may void these drawings, supporting structural calculations and design certification. The Builder/Contractor is responsible for notifying the building authority of all changes to the order documents which result in changes to the drawings, supporting structural calculations and design certification.

Builder Acceptance of Drawings - Approval of the manufacturer's drawings and design data affirms that the manufacturer has correctly interpreted and applied the requirements of the order documents and constitutes Builder/Contractor acceptance of the manufacturer's interpretations of the order documents and standard product specifications, including its design, fabrication and quality criteria standards and tolerances. (AISC code of standard practice Sept 86 Section 4.2.1) (Mar 05 Section 4.4.1)

Code Official Approval - It is the responsibility of the Builder/Contractor to ensure that all project plans and specifications comply with the applicable requirements of any governing building authority. The Builder/Contractor is responsible for securing all required approvals and permits from the appropriate agency as required.

Builder is responsible for State, Federal and OSHA safety compliance - The Builder/Contractor is responsible for applying and observing all pertinent safety rules and regulations and OSHA standards as applicable.

Building Erection - The Builder/Contractor is responsible for all erection of the steel and associated work in compliance with the Metal Building Manufacturers drawings. Temporary supports, such as temporary guys, braces, false work or other elements required for erection will be determined, furnished and installed by the erector. (AISC Code of Standard Practice Sept 86 Section 7.9.1) (Mar 05 Section 7.10.3)

Discrepancies - Where discrepancies exist between the Metal Building plans and plans for other trades, the Metal Building plans will govern. (AISC Code of Standard Practice Sept 86 Section 3.3) (Mar 05 Section 3.3)

Materials by Others - All interface and compatibility of any materials not furnished by the manufacturer are the responsibility of and to be coordinated by the Builder/Contractor or A/E firm. Unless specific design criteria concerning any interface between materials if furnished as a part of the order documents, the manufacturers assumptions will govern.

Modification of the Metal Building from Plans - The Metal Building supplied by the manufacturer has been designed according to the Building Code and specifications and the loads shown on this drawing. Modification of the building configuration, such as removing wall panels or braces, from that shown on these plans could affect the structural integrity of the building. The Metal Building Manufacturer or a Licensed Structural Engineer should be consulted prior to making any changes to the building configuration shown on these drawings. The Metal Building Manufacturer will assume no responsibility for any loads applied to the building not indicated on these drawings.

Foundation Design - The Metal Building Manufacturer is not responsible for the design, materials and workmanship of the foundation. Anchor rod plans prepared by the manufacturer are intended to show only location, diameter and projection of the anchor rods required to attach the Metal Building System to the foundation. It is the responsibility of the end customer to ensure that adequate provisions are made for specifying rod embedment, bearing values, tie rods and or other associated items embedded in the concrete foundation, as well as foundation design for the loads imposed by the Metal Building System, other imposed loads, and the bearing capacity of the soil and other conditions of the building site. (MBMA 06 Sections 3.2.2 and A3)

PROJECT NOTES

Material properties of steel bar, plate, and sheet used in the fabrication of built-up structural framing members conform to ASTM A529, ASTM A572, ASTM A1011 SS, or ASTM A1011 HSLAS with a minimum yield point of 50 ksi. Material properties of hot rolled structural shapes conform to ASTM A992, ASTM A529, or ASTM A572 with a minimum specified yield point of 50 ksi. Hot rolled angles, or other than flange braces, conform to ASTM 36 minimum. Hollow structural shaped conform to ASTM A500 grade b, minimum yield point is 42 ksi for round HSS and 46 ksi for rectangular HSS. Material properties of cold form light gage steel members conform to the requirements of ASTM A1011 SS Grade 55 or ASTM A1011 HSLAS Class 1 Grade 55, with a minimum yield point of 55 ksi.

The manufacturer does not assume any responsibility for the erection nor field supervision of the structure and or any special inspections that may be required by the local building authority during erection (including inspection of the high strength bolts or field welds) as required during erection. The coordination and the costs associated for setting up and Special Inspections are the responsibility of the Erector, Owner, Architect, or Engineer of Record.

Design is based upon the more severe loading of either the roof snow load or the roof live load.

Loads, as noted, are given within order documents and are applied in general accordance with the applicable provisions of the model code and/or specification indicated. Neither the manufacture nor the certifying engineer declares or attests that the loads as designated are proper for the local provisions that may apply or for site specific parameters. The manufacturer's Engineer's certification is limited to design loads supplied by an Architect and/or engineer of record for the overall construction project.

This project is designed using manufacture's standard serviceability standards. Generally this means that all stresses and deflections are within typical performance limits for normal occupancy and standard metal building products. If special requirements for deflections and vibrations must be adhered to, then they must be clearly stated in the contract documents.

This metal building system is designed as enclosed. All exterior components (i.e. doors, windows, vents, etc.) must be designed to withstand the specified wind loading for the design of components and cladding in accordance with the specified building code. Doors are to be closed when a maximum of 50% of design wind velocity is reached.

DESIGN LOADING

THIS STRUCTURE IS DESIGNED UTILIZING THE LOADS INDICATED AND APPLIED AS REQUIRED BY:

NCBC 18

THE BUILDER IS TO CONFIRM THAT THESE LOADS COMPLY WITH THE REQUIREMENTS OF THE LOCAL BUILDING DEPARTMENT.

FRAME / ROOF DEAD LOAD 1.870 PSF
SUPERIMPOSED
COLLATERAL (LIGHTS) 0.5 PSF

FRAME / ROOF LIVE LOAD 12 /20.00 PSF

RISK CATEGORY II - Normal

SNOW LOAD
GROUND SNOW LOAD (Pg) 15.00 PSF
SNOW LOAD IMPORTANCE FACTOR (Is) 1.0000
FLAT ROOF SNOW LOAD (Pf) 10.5 PSF
SNOW EXPOSURE FACTOR (Ce) 1.0
THERMAL FACTOR (Ct) 1.00

WIND LOAD
ULTIMATE WIND SPEED 120 MPH
NOMINAL WIND SPEED (VASD) 93 MPH (IBC Section 1609.3.1)

WIND EXPOSURE CATEGORY B
TOPOGRAPHICAL FACTOR 1.0
INTERNAL PRESSURE COEFFICIENT (Gcpi) 0.18 /-0.18
ZONE 4, COMPONENT WIND LOAD ≤ 10FT²
25.882 PSF PRESSURE -28.076 PSF SUCTION
ZONE 5, COMPONENT WIND LOAD < 10FT²
25.882 PSF PRESSURE -34.590 PSF SUCTION
ZONES PER ASCE 7-10; FIG. 30.4-1
ZONES PRESSURES SHOWN ARE UN-FACTORED

RAIN INTENSITY
5-MINUTE DURATION, 5-YEAR RECURRENCE (I1) 7.1000 IN/HOUR

SEISMIC LOAD
SEISMIC IMPORTANCE FACTOR (Ie) 1.00
Ss 0.2471 Sds 0.2635
S1 0.0907 SD1 0.1440
SITE CLASS D
SEISMIC DESIGN CATEGORY C

ANALYSIS PROCEDURE: EQUIVALENT LATERAL FORCE

BASIC FORCE RESISTING SYSTEM*	TRANSVERSE	LONGITUDINAL	
	H	FRONT	BACK
RESPONSE MODIFICATION COEFFICIENT(R)	3	3	3
SYSTEM OVER-STRENGTH FACTOR(Qd)	2.5000	2.5000	2.5000
SEISMIC RESPONSE COEFFICIENT(Cs)	0.088	0.088	0.088
BLDG DESIGN BASE SHEAR (V)	1.66 (k)	1.67 (k)	

THE TRANSVERSE DIRECTION IS PARALLEL TO THE RIGID FRAMES
THE LONGITUDINAL DIRECTION IS PERPENDICULAR TO THE RIGID FRAMES

BASIC FORCE RESISTING SYSTEM*
C4. STEEL ORDINARY MOMENT FRAME
B3. STEEL ORDINARY CONCENTRIC BRACED FRAMES
H. STRUCTURAL STEEL SYSTEMS NOT SPECIFICALLY DETAILED FOR SEISMIC RESISTANCE
G2. INVERTED PENDULUM SYSTEMS
CANTILEVERED COLUMN SYSTEMS

DRAWING INDEX

PAGE	DESCRIPTION
C1	COVER SHEET
F1	ANCHOR BOLT PLAN
F2	ANCHOR BOLT REACTIONS
F3	ANCHOR BOLT DETAILS
E1	ROOF FRAMING PLAN
E2	ROOF SHEETING PLAN
E3	FRONT SIDEWALL
E4	BACK SIDEWALL
E5	LEFT ENDWALL
E6	RIGHT ENDWALL
E7	FRAME CROSS SECTION
DET1-15	STANDARD DETAILS

DRAWING STATUS

FOR APPROVAL
THESE DRAWINGS, BEING FOR APPROVAL, ARE BY DEFINITION NOT FINAL, AND ARE FOR CONCEPTUAL REPRESENTATION ONLY. THEIR PURPOSE IS TO CONFIRM PROPER INTERPRETATION OF THE PROJECT DOCUMENTS. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

FOR CONSTRUCTION PERMIT
THESE DRAWINGS, BEING FOR PERMIT, ARE BY DEFINITION NOT FINAL. ONLY DRAWINGS ISSUED "FOR ERECTOR INSTALLATION" CAN BE CONSIDERED AS COMPLETE.

FOR ERECTOR INSTALLATION
FINAL DRAWINGS FOR CONSTRUCTION.

FOR QUESTIONS OR ASSISTANCE CONCERNING ERECTION CALL:
817-462-4029
MONDAY - FRIDAY 7:30AM TO 5:00PM

ENGINEERING SEAL

THIS CERTIFICATION COVERS PARTS MANUFACTURED AND DELIVERED BY THE MANUFACTURER ONLY, AND EXCLUDES PARTS SUCH AS DOORS, WINDOWS, FOUNDATION DESIGN AND ERECTION OF THE BUILDING.

THESE DRAWINGS AND THE METAL BUILDING SYSTEM THEY REPRESENT ARE THE PRODUCT OF AN AFFILIATE OF NCI GROUP, INC. - 10943 N. SAM HOUSTON PARKWAY W., HOUSTON, TX 77064. THE PROFESSIONAL ENGINEER WHOSE SEAL APPEARS HEREON IS EMPLOYED BY AN AFFILIATE OF NCI GROUP, INC. AND IS NOT THE ENGINEER-OF-RECORD FOR THE OVERALL PROJECT.



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

1/2"Ø A325 BOLT GRIP TABLE

GRIP	LENGTH	BOLT LENGTH
0 TO 9/16"	1 1/4" F.T.	
Over 9/16" TO 1 1/16"	1 3/4" F.T.	
Over 1 1/16" TO 1 5/16"	2"	
Over 1 5/16" TO 1 9/16"	2 1/4"	
Over 1 9/16" TO 1 13/16"	2 1/2"	
Over 1 13/16" TO 2 1/16"	2 3/4"	


LOCATIONS OF BOLTS LONGER THAN 2 3/4" NOTED ON ERECTION DRAWINGS
F.T. DENOTES FULLY THREADED

BUILDING SIZE: 40'-0" x 75'-0" x 16'-0" 4.0:12

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY					
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082					
PROJECT: THOMAS SANDERS		OWNER: THOMAS SANDERS			
LOCATION: LILLINGTON, NC 27546					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER
	1/13/20	N.T.S.	1	A	17-B-48481
					SHEET NUMBER
					C1
					ISSUE
					A

○ Dia= 5/8"
 ⊗ Dia= 3/4"



ANCHOR BOLT PLAN


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	1/13/20	FOR ERECTOR INSTALLATION	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	F1	0



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

GENERAL NOTES

1. THE REACTIONS PROVIDED ARE BASED ON THE ORDER DOCUMENTS AT THE TIME OF MAILING. ANY CHANGES TO BUILDING LOADS OR DIMENSIONS MAY CHANGE THE REACTIONS. THE REACTIONS WILL BE SUPERSEDED AND VOIDED BY ANY FUTURE MAILING.
2. REACTIONS ARE PROVIDED AS UN-FACTORED FOR EACH LOAD GROUP APPLIED TO THE COLUMN. THE FOUNDATION ENGINEER WILL APPLY THE APPROPRIATE LOAD FACTORS AND COMBINE THE REACTIONS IN ACCORDANCE WITH THE BUILDING CODE AND DESIGN SPECIFICATIONS TO DETERMINE BEARING PRESSURES AND CONCRETE DESIGN. THE FACTORS APPLIED TO LOAD GROUPS FOR THE STEEL COLUMN DESIGN MAY BE DIFFERENT THAN THE FACTORS USED IN THE FOUNDATION DESIGN.
3. THE MANUFACTURER DOES NOT PROVIDE "MAXIMUM" LOAD COMBINATION REACTIONS. HOWEVER, THE INDIVIDUAL LOAD REACTIONS PROVIDED MAY BE USED BY THE FOUNDATION ENGINEER TO DETERMINE THE APPLICABLE LOAD COMBINATIONS FOR HIS/HER DESIGN PROCEDURES AND ALLOW FOR AN ECONOMICAL FOUNDATION DESIGN.
4. THE METAL BUILDING MANUFACTURER IS RESPONSIBLE FOR THE DESIGN OF THE ANCHOR BOLT DIAMETER ONLY TO PERMIT THE TRANSFER OF FORCES BETWEEN THE BASE PLATE AND THE ANCHOR BOLT IN SHEAR, BEARING AND TENSION, BUT IS NOT RESPONSIBLE FOR THE ANCHOR BOLT EMBEDMENT FOR TRANSFER OF FORCES TO THE FOUNDATION. THE METAL BUILDING MANUFACTURER DOES NOT DESIGN AND IS NOT RESPONSIBLE FOR THE DESIGN, MATERIAL AND CONSTRUCTION OF THE FOUNDATION EMBEDMENTS. THE END USE CUSTOMER SHOULD ASSURE HIMSELF THAT ADEQUATE PROVISIONS ARE MADE IN THE FOUNDATION DESIGN FOR LOADS IMPOSED BY COLUMN REACTIONS OF THE BUILDING, OTHER IMPOSED LOADS, AND BEARING CAPACITY OF THE SOIL AND OTHER CONDITIONS OF THE BUILDING SITE. IT IS RECOMMENDED THAT THE ANCHORAGE AND FOUNDATION OF THE BUILDING BE DESIGNED BY A REGISTERED PROFESSIONAL ENGINEER EXPERIENCED IN THE DESIGN OF SUCH STRUCTURES, (SECTION A3 MBMA 2006 METAL BUILDING SYSTEMS MANUAL).
5. BOTTOM OF ALL BASE PLATES ARE AT THE SAME ELEVATION. (UNLESS NOTED)
6. ANCHOR RODS ARE ASTM F1554 GRADE 36 MATERIAL UNLESS NOTED OTHERWISE.

ENDWALL COLUMN: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Anc. Dia	Base_Plate Width (in)	Base_Plate Length (in)	Thick	Grout (in)
1	D	2	0.625	7.000	8.000	0.250	0.0
1	C	4	0.625	7.000	8.000	0.250	0.0
1	B	2	0.625	7.000	8.000	0.250	0.0
1	A	2	0.625	7.000	8.000	0.250	0.0
4	A	2	0.625	7.000	8.000	0.250	0.0
4	B	4	0.625	7.000	8.000	0.250	0.0
4	C	2	0.625	7.000	8.000	0.250	0.0
4	D	2	0.625	7.000	8.000	0.250	0.0

NOTES FOR REACTIONS

BUILDING REACTIONS ARE BASED ON THE FOLLOWING BUILDING DATA:

WIDTH (FT)	=	40
LENGTH (FT)	=	75
EAVE HEIGHT (FT)	=	16 / 16
ROOF SLOPE (rise/12)	=	4.0:12 / 4.0:12
DEAD LOAD (psf)	=	1.870
COLLATERAL LOAD (psf)	=	0.5
ROOF LIVE LOAD (psf)	=	20.00
FRAME LIVE LOAD (psf)	=	12
ROOF SNOW LOAD (psf)	=	10.5
GROUND SNOW LOAD (psf)	=	15.0000
WIND SPEED (MPH)	=	120
WIND CODE	=	IBC 15
EXPOSURE	=	B
CLOSED/OPEN	=	Closed
IMPORTANCE - WIND	=	1.00
IMPORTANCE - SEISMIC	=	1.00
SEISMIC ZONE	=	C

REACTION KEY:

WIND Left/Right 1 = (with +GCpi Internal Pressure)
 WIND Left/Right 2 = (with -GCpi Internal Pressure)
 Wind_Long 1 = Wind Load Case B at Left EW
 Wind_Long 2 = Wind Load Case B at Right EW
 MIN_SNOW = Minimum Snow (Pm) per code
 E#UNB_SL_L = Endwall Unbalanced Snow Left
 E#UNB_SL_R = Endwall Unbalanced Snow Right
 F#UNB_SL_L = Rigid Frame Unbalanced Snow Left
 F#UNB_SL_R = Rigid Frame Unbalanced Snow Right

ANCHOR BOLT SUMMARY


Qty	Locate	Dia (in)	Type	Proj (in)
4	Jamb	5/8"	F1554	2.00
20	Endwall	5/8"	F1554	2.00
16	Frame	3/4"	F1554	2.50

BUILDING BRACING REACTIONS

Loc	Wall Line	Col Line	Reactions in plane of wall ± Reactions(k)				Panel Shear (lb/ft)	
			Wind Horiz	Wind Vert	Seismic Horiz	Seismic Vert	Wind	Seis
L_EW	1	D,C	Bracing, see EW reactions					
F_SW	A	2,3	3.2	*	0.8	*		
R_EW	4	A,B	Bracing, see EW reactions					
B_SW	D	3,2	3.2	*	0.8	*		

*See RF reactions table for vertical and horizontal reactions in plane of the rigid frame.

FRAME LINES: 2 3



RIGID FRAME: ANCHOR BOLTS & BASE PLATES

Frm Line	Col Line	Anc. Bolt Qty	Anc. Dia	Base_Plate Width (in)	Base_Plate Length (in)	Thick	Grout (in)
2*	D	4	0.750	6.000	9.500	0.375	0.0
2*	A	4	0.750	6.000	9.500	0.375	0.0

2* Frame lines: 2 3

RIGID FRAME: BASIC COLUMN REACTIONS (k)

Frame Line	Column Line	Dead Horiz	Dead Vert	Collateral Horiz	Collateral Vert	Live Horiz	Live Vert	Snow Horiz	Snow Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert
2*	D	0.4	1.4	0.1	0.3	1.8	6.0	1.6	5.3	-5.5	-10.3	2.2	-6.2
2*	A	-0.4	1.4	-0.1	0.3	-1.8	6.0	-1.6	5.2	-2.2	-6.2	5.5	-10.3

Frame Line	Column Line	Wind_Left2 Horiz	Wind_Left2 Vert	Wind_Right2 Horiz	Wind_Right2 Vert	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seismic_Left Horiz	Seismic_Left Vert	Seismic_Right Horiz	Seismic_Right Vert
2*	D	-6.2	-6.4	1.6	-2.3	1.4	-9.9	0.2	-9.3	-0.2	-0.2	0.2	0.2
2*	A	-1.6	-2.3	6.2	-6.4	-0.2	-9.3	-1.4	-9.9	-0.2	0.2	0.2	-0.2

Frame Line	Column Line	Seismic_Long Horiz	Seismic_Long Vert	F1UNB_SL_L Horiz	F1UNB_SL_L Vert	F1UNB_SL_R Horiz	F1UNB_SL_R Vert
2*	D	0.0	-0.5	1.3	5.0	1.3	3.0
2*	A	0.0	-0.5	-1.3	3.0	-1.3	5.0

2* Frame lines: 2 3

ENDWALL COLUMN:

BASIC COLUMN REACTIONS (k)

Frm Line	Col Line	Dead Vert	Collat Vert	Live Vert	Snow Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert	Wind_Left2 Horiz	Wind_Left2 Vert	Wind_Right2 Horiz	Wind_Right2 Vert	Wind Press Horiz
1	D	0.1	0.0	0.5	0.3	2.3	-5.2	0.0	4.1	2.3	-4.6	0.0	4.9	0.0
1	C	0.8	0.1	4.5	2.4	0.0	-0.5	2.3	-8.5	0.0	0.8	2.3	-7.2	-2.7
1	B	0.6	0.1	4.5	2.4	0.0	-3.0	0.0	-5.2	0.0	-1.7	0.0	-3.9	-2.7
1	A	0.1	0.0	0.5	0.3	0.0	-1.4	0.0	-0.5	0.0	-0.7	0.0	0.2	0.0

Frm Line	Col Line	Wind Suct Horiz	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seis_Left Horiz	Seis_Left Vert	Seis_Right Horiz	Seis_Right Vert	E1UNB_SL_L Horiz	E1UNB_SL_L Vert	E1UNB_SL_R Horiz	E1UNB_SL_R Vert
1	D	0.0	0.0	0.8	0.8	-2.1	0.4	-0.7	0.0	0.8	0.0	0.2	0.0	-0.1
1	C	3.0	0.8	-6.5	0.0	-1.8	0.0	0.7	0.3	-0.8	0.0	2.7	0.0	1.3
1	B	3.0	0.0	-3.4	0.0	-4.6	0.0	0.0	0.0	0.0	0.0	1.3	0.0	2.7
1	A	0.0	0.0	-0.4	0.0	-1.1	0.0	0.0	0.0	0.0	0.0	-0.1	0.0	0.2

Frm Line	Col Line	Dead Vert	Collat Vert	Live Vert	Snow Vert	Wind_Left1 Horiz	Wind_Left1 Vert	Wind_Right1 Horiz	Wind_Right1 Vert	Wind_Left2 Horiz	Wind_Left2 Vert	Wind_Right2 Horiz	Wind_Right2 Vert	Wind Press Horiz
4	A	0.1	0.0	0.5	0.3	2.3	-5.2	0.0	4.1	2.3	-4.6	0.0	4.9	0.0
4	B	0.8	0.1	4.5	2.4	0.0	-0.5	2.3	-8.5	0.0	0.8	2.3	-7.2	-2.7
4	C	0.6	0.1	4.5	2.4	0.0	-3.0	0.0	-5.2	0.0	-1.7	0.0	-3.9	-2.7
4	D	0.1	0.0	0.5	0.3	0.0	-1.4	0.0	-0.5	0.0	-0.7	0.0	0.2	0.0

Frm Line	Col Line	Wind Suct Horiz	Wind_Long1 Horiz	Wind_Long1 Vert	Wind_Long2 Horiz	Wind_Long2 Vert	Seis_Left Horiz	Seis_Left Vert	Seis_Right Horiz	Seis_Right Vert	E2UNB_SL_L Horiz	E2UNB_SL_L Vert	E2UNB_SL_R Horiz	E2UNB_SL_R Vert
4	A	0.0	0.0	0.8	0.8	-2.1	0.4	-0.7	0.0	0.8	0.0	0.2	0.0	-0.1
4	B	3.0	0.8	-6.5	0.0	-1.8	0.0	0.7	0.3	-0.8	0.0	2.7	0.0	1.3
4	C	3.0	0.0	-3.4	0.0	-4.6	0.0	0.0	0.0	0.0	0.0	1.3	0.0	2.7
4	D	0.0	0.0	-0.4	0.0	-1.1	0.0	0.0	0.0	0.0	0.0	-0.1	0.0	0.2


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	1/13/20	FOR ERECTOR INSTALLATION	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY








MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	F2	0




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




AR Dia 5/8" Framed Opening AR Layout AR Dia 1/2" Walk Door AR Layout

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
0	1/13/20	FOR ERECTOR INSTALLATION	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY							
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082							
PROJECT: THOMAS SANDERS				OWNER: THOMAS SANDERS			
CUSTOMER: THOMAS SANDERS							
LOCATION: LILLINGTON, NC 27546							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	F3	0



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION



MEMBER TABLE		
ROOF PLAN		
MARK	PART	LENGTH
P-1	8X25Z14	28'-1 1/2"
P-2	8X25Z16	31'-3 1/2"
P-3	8X25Z14	28'-1 1/2"
E-1	8ES4L14	24'-11 1/2"
E-2	8ES4L14	24'-11 1/2"
E-3	8ES4L14	24'-11 1/2"
CB-5	1/4" CABLE	26'-10"
CB-6	1/4" CABLE	27'-4"



ROOF FRAMING PLAN

- GENERAL NOTES:**
1. INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
 2. ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
 4. DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
 5. DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
 6. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 OWNER: THOMAS SANDERS


LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E1	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

PBR ROOF SHEETING NOTE:
 PBR ROOF PANELS ARE TO BE FIELD CUT IF THE PANELS EXTEND OUTSIDE OF THE ROOF PLANE, PANELS ARE NOT TO BE BACK LAPPED.



ROOF SHEETING PLAN
 PANELS: 26 Gauge PBR - Polar White

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS


LOCATION: LILLINGTON, NC 27546

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E2	A


GENERAL NOTES:

- INSTALL ALL PURLIN AND FLANGE BRACES (FB) AS SHOWN.
- ROOF PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
- STRUT PURLINS, IF PROVIDED, MUST BE INSTALLED AND FASTENED TO ROOF SHEETING PER "PBR" PANEL ROOF DETAIL.
- DO NOT ADD ANY ADDITIONAL ROOF OPENINGS WITHOUT BUILDING MANUFACTURER APPROVAL OR PROFESSIONAL ENGINEER APPROVAL.
- DO NOT STACK SHEET BUNDLES ON ROOF. ONLY RAISE INDIVIDUAL SHEETS AS NEEDED.
- AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

MEMBER TABLE		
FRAME LINE A		
MARK	PART	LENGTH
E-1	8ES4L14	24'-11 1/2"
E-2	8ES4L14	24'-11 1/2"
E-3	8ES4L14	24'-11 1/2"
G-7	8X25Z14	26'-5 1/2"
G-8	8X25Z16	26'-5 1/2"
G-9	8X25Z16	27'-11 1/2"
G-10	8X25Z14	26'-5 1/2"
G-11	8X25Z16	26'-5 1/2"
CB-4	1/4" CABLE	29'-3"



SIDEWALL FRAMING: FRAME LINE A



SIDEWALL SHEETING & TRIM: FRAME LINE A

PANELS: 26 Gauge PBR - Saddle Tan

- GENERAL NOTES:
1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082


PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E3	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

MEMBER TABLE		
FRAME LINE D		
MARK	PART	LENGTH
E-1	8ES4L14	24'-11 1/2"
E-2	8ES4L14	24'-11 1/2"
E-3	8ES4L14	24'-11 1/2"
G-7	8X25Z14	26'-5 1/2"
G-8	8X25Z16	26'-5 1/2"
G-9	8X25Z16	27'-11 1/2"
G-10	8X25Z14	26'-5 1/2"
G-11	8X25Z16	26'-5 1/2"
CB-4	1/4" CABLE	29'-3"



SIDEWALL FRAMING: FRAME LINE D




SIDEWALL SHEETING & TRIM: FRAME LINE D
PANELS: 26 Gauge PBR - Saddle Tan

GENERAL NOTES:

1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY							
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082							
PROJECT: THOMAS SANDERS		CUSTOMER: THOMAS SANDERS		OWNER: THOMAS SANDERS			
LOCATION: LILLINGTON, NC 27546							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E4	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION


BEARING FRAME ONLY:
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 1				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2	4	A325	5/8"	1 3/4"
Columns/Raf	4	A325	1/2"	1 1/4"


MEMBER TABLE FRAME LINE 1		
MARK	PART	LENGTH
EC-1	8F35C14	14'-6 7/16"
EC-2	8F70D12	17'-7 3/4"
EC-3	8F25C12	17'-7 3/4"
EC-4	8F25C14	14'-6 7/16"
ER-1	10F35C13	21'-0 3/4"
ER-2	10F35C13	21'-0 3/4"
DJ-1	8F35C14	12'-0"
DH-1	8F35C14	10'-0"
G-1	8X25Z16	8'-8"
G-2	8X25Z16	4'-4 1/4"
G-3	8X35Z13	19'-7 3/4"
G-4	8X25Z14	19'-7 3/4"
G-5	8X25Z16	4'-8"
CB-1	1/4" CABLE	12'-1"
CB-2	1/4" CABLE	13'-5"
CB-3	1/4" CABLE	11'-6"

FLANGE BRACE TABLE FRAME LINE 1		
▽ ID	PART	LENGTH
FB30	L2X2X1/4G	2'-6"
FB6-1	L2X2X1/8	2'-6"

CONNECTION PLATES FRAME LINE 1	
□ ID	MARK/PART
1	SC-5



ENDWALL FRAMING: FRAME LINE 1



ENDWALL SHEETING & TRIM: FRAME LINE 1

PANELS: 26 Gauge PBR - Saddle Tan

GENERAL NOTES:


1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT:	THOMAS SANDERS						
CUSTOMER:	THOMAS SANDERS						
OWNER:	THOMAS SANDERS						
LOCATION:	LILLINGTON, NC 27546						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E5	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION


BEARING FRAME ONLY:
 WASHER TO BE USED AT ENDWALL COLUMN TO ENDWALL RAFTER CONNECTION. USE ONE WASHER ON COLUMN SIDE. WASHER NOT NEEDED ON CLIP SIDE.

BOLT TABLE FRAME LINE 4				
LOCATION	QUAN	TYPE	DIA	LENGTH
ER-1/ER-2 Columns/Rof	4	A325	5/8"	1 3/4"
	4	A325	1/2"	1 1/4"


MEMBER TABLE FRAME LINE 4		
MARK	PART	LENGTH
EC-1	8F35C14	14'-6 7/16"
EC-2	8F70D12	17'-7 3/4"
EC-3	8F25C12	17'-7 3/4"
EC-4	8F25C14	14'-6 7/16"
ER-1	10F35C13	21'-0 3/4"
ER-2	10F35C13	21'-0 3/4"
G-1	8X25Z16	8'-8"
G-4	8X25Z14	19'-7 3/4"
G-6	8X35Z14	19'-7 3/4"
CB-1	1/4" CABLE	12'-1"
CB-2	1/4" CABLE	13'-5"
CB-3	1/4" CABLE	11'-6"

FLANGE BRACE TABLE FRAME LINE 4		
▽ ID	PART	LENGTH
FB30	L2X2X1/4	2'-6"
FB6-1	L2X2X1/8	2'-6"

CONNECTION PLATES FRAME LINE 4	
ID	MARK/PART
1	SC-5



ENDWALL FRAMING: FRAME LINE 4



ENDWALL SHEETING & TRIM: FRAME LINE 4
 PANELS: 26 Gauge PBR - Saddle Tan

GENERAL NOTES:
 1. INSTALL ALL GIRTS AND FLANGE BRACES (FB) AS SHOWN.
 2. WALL PANEL PROVIDES STRUCTURAL STABILITY TO THE BUILDING.
 3. OTHER THAN FOR WALK DOORS AND WINDOWS SHOWN ON THE CONTRACT, DO NOT ADD ADDITIONAL WALL OPENINGS WITHOUT APPROVAL OF BUILDING MANUFACTURER OR PROFESSIONAL ENGINEER.
 4. AFTER INSTALLATION, WIPE ALL PANELS CLEAN OF METAL SHAVINGS CAUSED BY DRILLING.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	E6	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION


SPLICE PLATE & BOLT TABLE										
Mark	Qty	Top	Bot	Int	Type	Dia	Length	Width	Thick	Length
SP-1	4	4	0		A325	3/4"	2"	6"	1/2"	1'-4 1/4"
SP-2	4	4	0		A325	3/4"	1 3/4"	6"	3/8"	1'-4 1/4"

STIFFENER TABLE				
Mark	Stiff Mark	Width	Thick	Length
RF1-1	St- 1	2 1/2	1/4"	9"

BASE PLATE TABLE			
Col Mark	Plate Size	Width	Length
BP-1	6"	3/8"	9 1/2"

FLANGE BRACES: BOTH SIDES (UNLESS NOTED)
 FBxxA(1): xx=length(in)
 A - L2X2X14G

MEMBER TABLE					
Mark	Web Depth		Web Plate		Outside Flange W x Thk x Length
	Start/End	Thick	Thick	Length	
RF1-1	9.0/ 9.0	0.134	175.4		5 x 1/4" x 185.4
	9.0/ 9.0	0.250	13.1		5 x 1/4" x 18.4
RF1-2	9.0/ 9.0	0.134	236.1		5 x 1/4" x 233.0




FRAME CROSS SECTION: FRAME LINE 2 3

GENERAL NOTES:


- SNUG TIGHT - ALL BOLTED JOINTS WITH A325 TYPE 1 BOLTS ARE SPECIFIED AS SNUG-TIGHTENED JOINTS IN ACCORDANCE WITH THE SPECIFICATION FOR STRUCTURAL JOINTS USING ASTM A325 OR A490 BOLTS, DECEMBER 31, 2009. PRE-TENSIONING METHODS, INCLUDING TURN-OF-NUT, CALIBRATED WRENCH, TWIST-OFF-TYPE TENSION-CONTROL BOLTS OR DIRECT TENSION INDICATOR ARE NOT REQUIRED. INSTALLATION INSPECTION REQUIREMENTS FOR SNUG TIGHT BOLTS (SPECIFICATION FOR STRUCTURAL JOINTS SECTION 9.1) IS SUGGESTED.
- ALL FIELD WELDED CONNECTIONS OF SECONDARY FRAMING SHALL BE BOLTED WITH A325 MACHINE BOLTS
- INSTALL ALL FLANGE BRACES ON COLUMN AND RAFTER AS SHOWN

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY					
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082					
PROJECT: THOMAS SANDERS		OWNER: THOMAS SANDERS			
CUSTOMER: THOMAS SANDERS					
LOCATION: LILLINGTON, NC 27546					
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER
	1/13/20	N.T.S.	1	A	17-B-48481
					SHEET NUMBER
					E7
					ISSUE
					A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




A5 Purlin To Bearing Frame Single Cold Form Rafter
 Date Nov '19
 Rev 01
 Page MB-A5



B4 Cold Form Endwall Column To Rafter
 Date Jun '17
 Rev 00
 Page MB-B4



Page CF02035
 Date Dec '14 Rev 04



Page PW02101
 Date Apr '18 Rev 02

Wall panel must be held off of base trim a minimum of 1/4" to prevent bottom of wall panel from rusting.

Base Trim
F406
F407
F408


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY


MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET1	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




C4
 Page MB-C4
 Girt To Cold Form Column
 Date Jun '17
 Rev 00



C5
 Page MB-C5
 Girt To Double Cee Cold Form Endwall Column
 Date Dec '17
 Rev 00




C13
 Page MB-C13
 Girt To Cold Form Endwall Column - Partially Open
 Date Jun '17
 Rev 00




C14
 Page MB-C14
 Girt To Double Cee Cold Form Endwall Column - Partially Open
 Date Jun '17
 Rev 00

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY							
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082							
PROJECT: THOMAS SANDERS				OWNER: THOMAS SANDERS			
CUSTOMER: THOMAS SANDERS							
LOCATION: LILLINGTON, NC 27546							
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET2	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




D4 Girt To Cold Form Corner Column
 Date: Oct '19
 Rev: 01
 Page: MB-D4



E4 Double Cee Cold Form Endwall Column Or Door Jamb Base Plate
 Date: Dec '18
 Rev: 01
 Page: MB-E4



E5 Door Jamb Base Plate
 Date: Dec '18
 Rev: 01
 Page: MB-E5




E8 Cold Form Endwall Column Base Plate
 Date: Dec '18
 Rev: 01
 Page: MB-E8

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082


PROJECT:	THOMAS SANDERS	OWNER:	THOMAS SANDERS				
CUSTOMER:	THOMAS SANDERS						
LOCATION:	LILLINGTON, NC 27546						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET3	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




F10 Endwall Bearing Frame – Cold Form Rafter Splice At Ridge
 Date Jun '17
 Rev 00
 Page MB-F10




G2 Purlin To Rigid Frame
 Date Sep '19
 Rev 01
 Page MB-G2

Purlin Lap Dimensions	
*	**
1'-5 ³ / ₄ "	2'-11 ¹ / ₂ "
2'-5 ³ / ₄ "	4'-11 ¹ / ₂ "
3'-1 ³ / ₄ "	6'-3 ¹ / ₂ "



H2 Girt To Rigid Frame
 Date Sep '19
 Rev 01
 Page MB-H2

Girt Lap Dimensions	
*	**
1'-5 ³ / ₄ "	2'-11 ¹ / ₂ "
2'-5 ³ / ₄ "	4'-11 ¹ / ₂ "
3'-1 ³ / ₄ "	6'-3 ¹ / ₂ "



16 Low Side Eave Strut To Bearing Frame – Cold Form
 Date Jun '17
 Rev 00
 Page MB-16


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY


MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET4	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION





Q2 Cable Brace Attachment At Web
 Date Mar '18
 Rev 01
 Page MB-Q2



R2 Anchor Rods At Frame Column
 Date Dec '17
 Rev 00
 Page MB-R2

PBR Wall Panel
 Panel Side Lap

Page PW05002
 Date Mar '19
 Rev 03



Screw Application

Page TH06006
 Date May '19
 Rev 01

Standard Grade

Description	Fastener Number	Application
1/4"-14 x 7/8" Type 2	4A	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	17A	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	17B	Member Screw (Up To 6" Insulation)

Long Life

Description	Fastener Number	Application
1/4"-14 x 7/8" Type 1	4	Stitch & Trim Screw
12-14 x 1 1/4" Type 2	3	Member Screw (Up To 4" Insulation)
12-14 x 1 1/2" Type 2	3A	Member Screw (Up To 6" Insulation)


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET6	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

PBR Roof Panel
Fastener And Tape Sealant Location

Page
GPR00011
Date
Apr '19
Rev
01



All Roof Members Except As Noted Below




At Eave Strut, Panel End Lap And Peak Purlin

Note:
Screw patterns shown satisfy U.L. 90
requirements for roof.


PBR Roof Panel
Side Lap And End Lap Details

Page
GPR04016
Date
Apr '19
Rev
04



PBR Wall Panel
Fastener Location

Page
PW05003
Date
Aug '15
Rev
04




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
642 OAKBEND DRIVE
COPPEL TX. 75019
PH. 972-571-7082

PROJECT: THOMAS SANDERS
CUSTOMER: THOMAS SANDERS
OWNER: THOMAS SANDERS
LOCATION: LILLINGTON, NC 27546


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET7	A



THIS DOCUMENT WAS
PRODUCED BY AND/OR
UNDER MY DIRECT SUPERVISION

Single Skin Wall Panel Outside Closure Requirements at Eave

Page
GD06002
Date
Feb '19
Rev
02



Detail at Foam Closure
(Low Eave Shown High Eave Similar)


Detail at Optional Metal Closure
For PBR Panel Only
(Low Eave Shown High Eave Similar)

Note:
Foam Closures Are Required When Job Requires Air Infiltration
Or Sealed Wall Requirements, See GD16002.

Wall Panel	Foam Closure
PBR	HW456
AVP	HW465
PBU	HW460
VistaShadow	HW465
NuWall	HW424
PBC	HW462
PBD	HW463
ShadowRib	HW412
Designer Series (Fluted Only)	HW4037
RBR (Reverse Rolled PBR)	HW455
RBU (Reverse Rolled PBU)	HW459
7.2	HW461

Single Skin Wall Panel Outside Closure Requirements at Rake


Page
GD06003
Date
Feb '19
Rev
02



Detail at Foam Closure

Detail at Optional Metal Closure
For PBR Panel Only

- Notes:
1. Outside Panel Closures are Required at all Sheeted Endwalls.
 2. PBR Wall Panel Outside Foam Closures HW456 Required for Roof Slope 4:12 or Less and HW422 for Roof Slope Greater Than 4:12. Field Form/Notch HW422 to Panel Profile.
 3. PBR Wall Panel Outside Metal Closure HW429 for Roof Slope 0 :12 Thru 1 1/2 :12 and HW429A for Roof Slope Greater Than 3 1/2 :12 Thru 4 1/2 :12.
 4. Rake Slide Trim Required for All Standing Seam Roofs and at Screw Down Roof Runs Greater Than 100'-0"
 5. Foam Closures are Required when Job Requires Air Infiltration or Sealed Wall Requirements, See GD16002.




Detail at Rake Slide Trim

Wall Panel	Foam Closure
PBR	HW456/HW422
AVP	HW465
PBU	HW460
VistaShadow	HW465
NuWall	HW424
PBC	HW462
PBD	HW463
ShadowRib	HW412
Designer Series (Fluted Only)	HW4037
RBR (Reverse Rolled PBR)	HW455
RBU (Reverse Rolled PBU)	HW459
7.2	HW461

PBR Roof Panel
Fixed Ridge Detail


Page
GPR06003
Date
Apr '19
Rev
04





Note:
Install optional ridge insulation trim F684
as insulation and roof sheeting is being
applied. Temporary attachment, if required,
is not by metal building manufacturer.

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


BUILDING IS MANUFACTURED BY SW STEEL FACTORY							
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082							
PROJECT: THOMAS SANDERS				OWNER: THOMAS SANDERS			
CUSTOMER: THOMAS SANDERS				LOCATION: LILLINGTON, NC 27546			
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET8	A





THIS DOCUMENT WAS
PRODUCED BY AND/OR
UNDER MY DIRECT SUPERVISION



Standard
For Roof Runs 100'-0" Or Less




Alternate
For Roof Runs Greater Than 100'-0"



Trim Profile	Peak Box			
	Southern Standard	Southern Large	Northern Standard	Northern Large
Cascading	F1519	F1585	F1672	F1760
Classic	F160	F4153	F381	F1024
Contoured	F2219	F2285	F2372	F2460
Signature	F916	F3853	F236	F1018

Note:
Flashing profile varies dependent on the building order. Attachment as illustrated is applicable for all profiles.




BUILDING IS MANUFACTURED BY SW STEEL FACTORY


MICHAEL W. CUSTER, P.E.
642 OAKBEND DRIVE
COPPEL TX. 75019
PH. 972-571-7082

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM


PROJECT:	THOMAS SANDERS						
CUSTOMER:	THOMAS SANDERS						
OWNER:	THOMAS SANDERS						
LOCATION:	LILLINGTON, NC 27546						
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET9	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




U2 Bolts At Rigid Frame Ridge Rafter Connection Date Jun '17 Rev 00



U3 Bolts At Rigid Frame Rafter To Column Connection Date Jun '17 Rev 00


PBR Wall Panel Outside Corner - On Module

Page PW03001 Date Apr '19 Rev 08



PBR Roof Panel - Southern Standard and Southern Large Low Eave Rake Corner with Flat Eave Trim - 1 1/4\"/>

Page WPR04006 Date Jul '17 Rev 05




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY





MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET10	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
642 OAKBEND DRIVE
COPPEL TX. 75019
PH. 972-571-7082

PROJECT: THOMAS SANDERS
CUSTOMER: THOMAS SANDERS
OWNER: THOMAS SANDERS
LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET11	A







THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.

Note: Trim Installation can be done by Field Notch Panel as shown on PW07022 & PW07023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW07024 & PW07025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
 Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
 Note: Panel position is shown with Panel Rib and Opening on 1'-0 module. Location of Rib may vary depending on the Opening Width and location. Field measure before cutting Panel and Trim.

Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
 Note: Field measure Opening Width and Height before making field cuts and adjust cut dimensions accordingly.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY


MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS
 OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET12	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION




Note: Field measure Door Height before making field cuts and adjust cut dimensions accordingly so that Jamb Trim fits to Head Trim & at 1/2" below Finish Floor Line.

Jamb Trim F482 and Alternate Jamb Trim F484
Front View
Right Jamb Trim as shown
Left Jamb Trim opposite hand




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.

Note: Panel position is shown with Panel Rib and Door on 1'-0" module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.




Note: All Trim is To Be Installed BEFORE Blanket Insulation Is Applied To Walls.

Note: Location Of Panel Rib May Vary Depending On Door Width, Door Location And Panel Starting Location. Refer To Erection Drawings For Panel Layout. Field Measure Before Cutting Panel And Trim.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY							
MICHAEL W. CUSTER, P.E. 642 OAKBEND DRIVE COPPEL TX. 75019 PH. 972-571-7082							
PROJECT: THOMAS SANDERS				OWNER: THOMAS SANDERS			
CUSTOMER: THOMAS SANDERS				LOCATION: LILLINGTON, NC 27546			
CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET13	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.




Note: Panel position is shown with Panel Rib and Door on 1'-0 module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Field measure Door Width and Height before making field cuts and adjust cut dimensions accordingly.

Note: Trim Installation can be done by Field Notch Panel as shown on PW09022 & PW09023 OR with Field Notch and Bend Tabs at Head Trim as shown on PW09024 & PW09025.



Note: All trim is to be installed BEFORE blanket insulation is applied to walls.
Note: Panel position is shown with Panel Rib and Door on 1'-0 module. Location of Rib may vary depending on the Door Width and location. Field measure before cutting Panel and Trim.


ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

BUILDING IS MANUFACTURED BY SW STEEL FACTORY


MICHAEL W. CUSTER, P.E.
642 OAKBEND DRIVE
COPPEL TX. 75019
PH. 972-571-7082

PROJECT: THOMAS SANDERS
CUSTOMER: THOMAS SANDERS
OWNER: THOMAS SANDERS
LOCATION: LILLINGTON, NC 27546


CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET14	A




THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION



Door Elevation




Walk Door Clip/Strike Reinforcement Angle Isometric




Door Jamb Extension Isometric

(2) Door Jamb Extensions Are Required For All Knock Down Doors.
 Extend Door Jamb Extension To The 7'-6" Girt Elevation And Attach To The Web Of The Girt With (4) Fastener #12A, Attach Door Jamb Extension Channel To Door Jamb With (6) Fastener #12A.
 For Girt Elevations Above 7'-6" Refer To AC05132 For Door Jamb Extension Requirements.
 Note:
 If Girt Has A 3/4" Flange, Field Notch Jamb Extension Channel To Clear Girt Lip. Do Not Notch Girt Lip.




Knock Down Door Anchor Placement

The Adequacy Of The 3/8" Base Anchor Is Not The Responsibility Of The Building Manufacturer. The Adequacy Of These Base Anchors Should Be Determined By A Qualified Foundation Engineer.
 Verify Door Jamb Base Clip Dimensions With Patterns Shown Prior To Placement Of Door Anchors And Adjust Patterns If Needed.
 Note: 12 1/4" Frames May Not Have Kerf Door Frame Feature Depending On Door Manufacturer.



Section A



Section B

Section C


BUILDING IS MANUFACTURED BY SW STEEL FACTORY

MICHAEL W. CUSTER, P.E.
 642 OAKBEND DRIVE
 COPPEL TX. 75019
 PH. 972-571-7082

PROJECT: THOMAS SANDERS
 CUSTOMER: THOMAS SANDERS OWNER: THOMAS SANDERS
 LOCATION: LILLINGTON, NC 27546

ISSUE	DATE	DESCRIPTION	BY	CK'D	DSN
A	1/13/20	FOR CONSTRUCTION PERMIT	FXD	HPD	CM

CAD	DATE	SCALE	PHASE	BUILDING ID	JOB NUMBER	SHEET NUMBER	ISSUE
	1/13/20	N.T.S.	1	A	17-B-48481	DET15	A



THIS DOCUMENT WAS PRODUCED BY AND/OR UNDER MY DIRECT SUPERVISION