## RJB, P.E., P.A.

C-0269

## ROBERT J. BRACKEN ENGINEER + SURVEYOR

3768 Carbonton Road • Sanford, North Carolina 27330

July 6, 2020

Harnett Co. Inspections P.O. Box 65 Lillington, NC 27546

REF: Single wide Mobile Home
Winding Ridge Properties, Inc Owner
Over height Inspection
King Charles Ave
Cameron, NC 28326

Dear Sir/Madam,

I made an onsite inspection of the above referenced Single wide M/H on July 3, 2020. The purpose of the visit was to inspect the reported "over height" foundation setup for a mobile home.

The home was anchored with the approved Minute Man Model LLBS Longitudinal and Lateral Bracing FlexTube System. The flex tubes were anchored to 24x24 inch steel plates placed under the 16x16 inch piers. With reference to the specifications provided by Minute Man Anchors, Inc.; the amount of and the placement of the Minute Man Bracing Systems complies with the requirements of the State of North Carolina Regulations For Manufactured Homes 2004 ed.

If you have any questions call 919-774-6074.

Sincerely,

Robert J. Bracken, PE