



360 spillway with 8 therapy jets and 4 spa returns. Raised 18"

Bistro table with 6" pedestal and 24" round table 2" thick with umbrella sleeve.

46' 11"

Tanning ledge with 9" of water.
(2) umbrella sleeves

232' 2"

Scale: 1/8" = 1 ft

Pool Specs

Perimeter: 116 Area: 843
Envelope: 27'-4" x 42'-5"
Depth: 7' to 10' deep RTNS: 9
Drains: Lights: 5- 2" LED
Skim: 4 P.C.:
Dig Type Volume: 18000
Spillover Length(s):
Coping Material:
Interior Finish:
Notes:

Spa Specs

Perimeter: 28 Area: 38
Jets: 8 Height: + 18"
Lights: 1- 2" led RTNS:
Drains: Spillover Length(s): 360 degree
Coping Material:
Interior Finish: Pebble
Notes:

Tile Specs

Raised Beams:
Pool Tile Material:
Spa Tile Material:
Notes:

Deck Specs

Perimeter: Area: 1232 sq ft
Coping Area:
Coping Material:
Surface Material: Concrete
Turn Down: Riser:
NOTES:

Equipment

Circ Pumps: 2.7 HP-VS Control Panel: RSPS-6
Pump #2: Remote: Aqua-Link
Pump #3: Sanitizer: 1800
Filter: CV-340 Blower: 2HP
Heater: 400k LP Fill Line: AutoFill
Cleaner: 7240 Other:
Pool Light: 5- 2" led Other:
Spa Light: 1- 2" led Other:
Other: Other:
NOTES:

Approval

I, we (the undersigned) have reviewed this plan and approve it as correct within reasonable tolerance. I, we understand that any changes made to a shape or to a location may delay the project and/or result in additional cost.

X



Project Name: Young
Client Name: Jim & Lisa
Client Email:
Client Phone:
Address: 618 Ballard Road
City: Fuquay Varina
State/Province: NC
Zip/Postal Code: 27
Designer Name: Joe Navarrete

Block:
Subdivision:
Lot #: Gate Code:
PG: PB:
Notes:

Pool Depth Profile

