

SOIL/SITE EVALUATION for ON-SITE WASTEWATER SYSTEM

(Complete all fields in full)

OWNER: Robin Johnson DATE EVALUATED: 4/20/2026  
 ADDRESS: 4485 Old Stage Rd, Angier  
 PROPOSED FACILITY: EMFH Single Use PROPOSED DESIGN FLOW (.0400): 360 gpd PROPERTY SIZE: \_\_\_\_\_  
 LOCATION OF SITE: \_\_\_\_\_ PROPERTY RECORDED: \_\_\_\_\_  
 WATER SUPPLY: Public Single Family Well Shared Well Spring Other \_\_\_\_\_ WATER SUPPLY SETBACK: \_\_\_\_\_  
 EVALUATION METHOD: Auger Boring Pit Cut TYPE OF WASTEWATER: Domestic High Strength IPWW

P R O F I L E #	.0502 LANDSCAPE POSITION/ SLOPE %	HORIZON DEPTH (IN.)	SOIL MORPHOLOGY		OTHER PROFILE FACTORS				.0509 PROFILE CLASS & LTAR*	.0503 SLOPE CORRE CTION
			.0503 STRUCTURE/ TEXTURE	.0503 CONSISTENCE/ MINERALOGY	.0504 SOIL WETNESS/ COLOR	.0505 SOIL DEPTH	.0506 SAPRO CLASS	.0507 RESTR HORIZ		
1	Side 2%	0-22	Gr/LS	Lc/NS/NP/SEXP	41  10yr 6/2				S .4	
		22-41	SBR/SCL	NFR/SS/NP/SEXP						
2	Side 2%	0-26	Gr/LS	Lc/NS/NP/SEXP	48				S.4	
		26-48	SBR/SCL	NFR/SS/NP/SEXP						
3	Side 2%	0-24	Gr/LS	Lc/NS/NP/SEXP	40  10yr 6/2				S.4	
		24-40	SBR/SCL	NFR/SS/NP/SEXP						
4	Side 2%	0-15	Gr/LS	" "	43  10yr 6/2				S .4	
		15-43	SBR/SCL	" "						

DESCRIPTION	INITIAL SYSTEM	REPAIR SYSTEM	SITE CLASSIFICATION (.0509): <u>S</u> EVALUATED BY: <u>Maggie</u> OTHER(S) PRESENT: _____
Available Space (.0508)	✓	✓	
System Type(s)	25% red	25% red	
Site LTAR	.4	.4	
Maximum Trench Depth	28	28	

Comments: \_\_\_\_\_  
 \_\_\_\_\_  
 \_\_\_\_\_

# LEGEND

LANDSCAPE POSITION	SOIL GROUP	SOIL TEXTURE	CONVENTIONAL LTAR (gpd/ft <sup>2</sup> )	SAPROLITE LTAR (gpd/ft <sup>2</sup> )	LPP LTAR (gpd/ft <sup>2</sup> )	MINERALOGY/CONSISTENCE		STRUCTURE	
						MOIST	WET		
CC (Concave slope)	I	S (Sand)	0.8 - 1.2	0.6 - 0.8	0.4 - 0.6	Lo (Loose)	NS (Non-sticky)	SG (Single grain)	
CV (Convex Slope)		LS (Loamy sand)		0.5 - 0.7		M (Massive)			
D (Drainage way)	II	SL (Sandy loam)	0.6 - 0.8	0.4 - 0.6	0.3 - 0.4	VFR (Very friable)	SS (Slightly sticky)	GR (Granular)	
FP (Flood plain)		L (Loam)		0.2 - 0.4		S (Sticky)	SBK (Subangular blocky)		
FS (Foot slope)	III	SiL (Silt loam)	0.3 - 0.6	0.1 - 0.3	0.15 - 0.3	FI (Firm)	VS (Very sticky)	ABK (Angular blocky)	
H (Head slope)		SCL (Sandy clay loam)		0.05 - 0.15**		VFI (Very firm)	NP (Non-plastic)	PR (Prismatic)	
L (Linear Slope)		CL (Clay loam)		None		0.15 - 0.3	EFI (Extremely firm)	SP (Slightly plastic)	PL (Platy)
N (Nose slope)		SiCL (Silty clay loam)					P (Plastic)		
R (Ridge/summit)		Si (Silt)					VP (Very plastic)		
S (Shoulder slope)		SC (Sandy clay)					SEXP (Slightly expansive)		
T (Terrace)		SiC (Silty clay)		0.1 - 0.4		0.05 - 0.2	EXP (Expansive)		
TS (Toe Slope)	C (Clay)								
		O (Organic)	None						

\* Adjust LTAR due to depth, consistence, structure, soil wetness, landscape, position, wastewater flow and quality.

\*\*Sandy clay loam saprolite can only be used with advanced pretreatment in accordance with 15A NCAC 18E .1200.

**HORIZON DEPTH**

In inches below natural soil surface

**DEPTH OF FILL**

In inches from land surface

**RESTRICTIVE HORIZON**

Thickness and depth from land surface

**SAPROLITE**

S(suitable) or U(unsuitable); Evaluation of saprolite shall be by pits.

**SOIL WETNESS**

Inches from land surface to free water or inches from land surface to soil colors with chroma 2 or less - record Munsell color chip designation

**CLASSIFICATION**

S (Suitable) or U (Unsuitable)

Show profile locations and other site features (dimensions, reference or benchmark, and North).

