

CONCRETE FOOTING

BRICK FOUNDATION ON TOP

4" INCH CONCRETE PAD

NOTICE TO CONTRACTOR
All construction must comply with current NC Building Codes and is subject to field inspection and verification.

APPROVED


Limited building only review
Permit holder responsible for full compliance with the code

02/04/2021

Barbara





24 ft



GENERAL NOTES:

1. NOTE: ALL CONSTRUCTION SHALL BE IN ACCORDANCE WITH CURRENT NORTH CAROLINA RESIDENTIAL BUILDING CODE REQUIREMENTS EVEN IF NOT SPECIFICALLY INDICATED ON THESE PLANS.
2. IT IS THE SOLE RESPONSIBILITY OF THE CONTRACTOR AND/ OR BUILDER TO CONFORM TO ALL STANDARDS, PROVISIONS, REQUIREMENTS, METHODS OF CONSTRUCTION AND USES OF MATERIALS, IN BUILDING CODES ANY OTHER LOCAL AGENCIES AND IN ACCORDANCE WITH GOOD ENGINEERING AND CONSTRUCTION PRACTICES.
3. R-15 INSULATION IN WALLS
6. 2"X6" RAFTERS 16" ON CENTER (2X4 STUDS)
7. TYPE OF FRAMING SYSTEM IS CATHEDRAL CEILING
8. (FOUNDATIONS) R401.2 Requirements
9. REFER TO CODE ABOUT CONCRETE (R402.2 Concrete)
10. FOOTINGS (R403 Footings)
11. ROOFING REFER TO CODE(R801.2 Requirements)
12. R802.1.3.5.2 Lumber




PROPERTY OF J. LEWIS
 DRAWINGS AND SPECIFICATIONS AS INSTRUMENTS OF SERVICE ARE AND SHALL REMAIN PROPERTY OF THE
 DESIGNER WHETHER THE PROJECT FOR WHICH THEY ARE MADE FOR IS EXECUTED OR NOT. THE DRAWINGS
 AND SPECIFICATIONS SHALL NOT BE USED BY THE OWNER OR OTHER PROJECTS FOR ADDITIONS TO THIS
 PROJECT OR FOR COMPLETION OF THIS PROJECT BY OTHERS EXCEPT BY AGREEMENT IN WRITING WITH THE
 APPROPRIATE COMPENSATION TO THE DESIGNER.

ERWIN DESIGN PROJECT
 Fayetteville, North Carolina
 Sections

AMMONS GROUP
DRAFTER: Lewis Jackson
SCALE: 1/4"
DATE: 1/22/2021

1.0

THIS LAYOUT IS INTENDED FOR THE PURPOSE OF TRUSS LOCATION AND PLACEMENT ONLY. REFER TO THE BUILDING PLANS FOR ACTUAL BUILDING CONSTRUCTION.



DEDICATED TO QUALITY AND EXCELLENCE
 200 EMMETT ROAD
 DUNN, NORTH CAROLINA 28334
 PHONE: 910-892-8400

PROJECT:	JONATHAN VANN		
CUSTOMER:	2383-Dunn		
MODEL:			
QUOTE #:	2100164	PRINT DATE:	2/4/2021
		DRAWN BY:	Jason Kindle
		SCALE:	N.T.S

TOP LIVE LOAD: 20.000 lb/ft ²
TOP DEAD LOAD: 10.000 lb/ft ²
BOTTOM DEAD LOAD: 10.000 lb/ft ²
WIND SPEED: 130.0 mph

GENERAL NOTES:
 - DO NOT CUT OR MODIFY TRUSSES
 - TRUSSES ARE SPACED 24" ON CENTER UNLESS OTHERWISE NOTED
 - REFER TO THE INDIVIDUAL TRUSS DESIGN DRAWINGS FOR THE LOCATION OF LATERAL BRACING AND MULTI-PLY CONNECTION REQUIREMENTS.
 - PER ANSI TPI 1-2002 THE TRUSS ENGINEER IS RESPONSIBLE FOR TRUSS TO TRUSS CONNECTIONS AND TRUSS PLY TO PLY CONNECTIONS. THIS TRUSS PLAN RECOMMENDS TRUSS TO BEARING CONNECTIONS AND TRUSS TO BEAM CONNECTIONS WHICH SHALL BE REVIEWED BY THE BUILDING DESIGNER. IT IS THE RESPONSIBILITY OF THE BUILDING DESIGNER TO RESOLVE ALL ROOF FORCES ADEQUATELY TO THE FOUNDATION.


Job 2100164-2100164A	Truss S1	Truss Type GABLE	Qty 1	Ply 1	JONATHAN VANN
-------------------------	-------------	---------------------	----------	----------	---------------

84 Components, Dunn, NC 28334

Job Reference (optional)

8.400 s Apr 7 2020 MiTek Industries, Inc. Thu Feb 4 07:33:22 2021 Page 1

ID:vGwN7Ka7AT2xVsNZUzNwAzobnf-DVX?ZP69VAw3cDQBsReT2lxqyleeOrrzzIYi?jzoblh



Scale = 1:69.9

Plate Offsets (X,Y)-- [2:0-1-4,Edge], [6:0-1-4,Edge]					
LOADING (psf)	SPACING-	CSI.	DEFL.	PLATES	GRIP
TCLL 20.0	2-0-0	TC 0.34	in (loc) l/defl L/d	MT20	197/144
TCDL 10.0	Plate Grip DOL 1.15	BC 0.69	Vert(LL) -0.15 8-20 >999 240		
BCLL 0.0 *	Lumber DOL 1.15	WB 0.68	Vert(CT) -0.33 8-17 >613 180		
BCDL 10.0	Rep Stress Incr YES	Matrix-MS	Horz(CT) 0.34 6 n/a n/a		
	Code IRC2015/TPI2014			Weight: 97 lb	FT = 20%

LUMBER-
 TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
 BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
 WEBS 2x4 SP No.3
 OTHERS 2x4 SP No.3

BRACING-
 TOP CHORD
 Structural wood sheathing directly applied or 4-1-4 oc purlins.
 BOT CHORD
 Rigid ceiling directly applied or 9-10-14 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size)

2	=	740/0-3-8 (min. 0-1-8)
6	=	740/0-3-8 (min. 0-1-8)
Max Horz		
2	=	-235(LC 10)
Max Uplift		
2	=	-73(LC 12)
6	=	-73(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
 TOP CHORD
 2-3=-1972/330, 3-4=-1488/13, 4-5=-1519/55, 5-6=-1889/169
 BOT CHORD
 2-8=-341/1824, 6-8=-68/1564
 WEBS
 4-8=0/1798, 5-8=-513/439, 3-8=-524/403

NOTES-
 1) Unbalanced roof live loads have been considered for this design.


- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Gable studs spaced at 2-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 6. This connection is for uplift only and does not consider lateral forces.
- 9) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
 Standard

Job 2100164-2100164A	Truss S2	Truss Type Scissor	Qty 12	Ply 1	JONATHAN VANN
-------------------------	-------------	-----------------------	-----------	----------	---------------

84 Components, Dunn, NC 28334

Job Reference (optional) 8.400 s Apr 7 2020 MiTek Industries, Inc. Thu Feb 4 07:33:24 2021 Page 1
ID:vGwN7Ka7AT2xVsnzUzNwxAzobnf-9ufm_58Q0oAnsXaZ_sgx7A0AS6J6slLGQc1p4bzoblf



Scale = 1:69.9

Plate Offsets (X,Y)-- [2:0-1-4,Edge], [6:0-1-4,Edge]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.34	Vert(LL) -0.15 8-14 >999 240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.69	Vert(CT) -0.33 8-11 >613 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.68	Horz(CT) 0.34 6 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-MS		Weight: 89 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
Structural wood sheathing directly applied or 4-1-4 oc purlins.
BOT CHORD
Rigid ceiling directly applied or 9-10-14 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size)
2 = 740/0-3-8 (min. 0-1-8)
6 = 740/0-3-8 (min. 0-1-8)
Max Horz
2 = -235(LC 10)
Max Uplift
2 = -73(LC 12)
6 = -73(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD
2-3=-1972/330, 3-4=-1488/13, 4-5=-1519/55, 5-6=-1889/169
BOT CHORD
2-8=-341/1824, 6-8=-68/1564
WEBS
4-8=0/1798, 5-8=-513/439, 3-8=-524/403

NOTES-
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 6. This connection is for uplift only and does not consider lateral forces.
- 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard


Job 2100164-2100164A	Truss S1	Truss Type GABLE	Qty 1	Ply 1	JONATHAN VANN
-------------------------	-------------	---------------------	----------	----------	---------------

84 Components, Dunn, NC 28334

Job Reference (optional)

8.400 s Apr 7 2020 MiTek Industries, Inc. Thu Feb 4 07:33:22 2021 Page 1

ID:vGwN7Ka7AT2xVsuzNwAzobnf-DVX?ZP69VAw3cDQBsReT2lxqyleeOrrzzIYi?jzoblh



Scale = 1:69.9

Plate Offsets (X,Y)-- [2:0-1-4,Edge], [6:0-1-4,Edge]	
LOADING (psf)	SPACING- 2-0-0
TCLL 20.0	Plate Grip DOL 1.15
TCDL 10.0	Lumber DOL 1.15
BCLL 0.0 *	Rep Stress Incr YES
BCDL 10.0	Code IRC2015/TPI2014
CSI.	DEFL in (loc) l/defl L/d
TC 0.34	Vert(LL) -0.15 8-20 >999 240
BC 0.69	Vert(CT) -0.33 8-17 >613 180
WB 0.68	Horz(CT) 0.34 6 n/a n/a
Matrix-MS	
PLATES	GRIP
MT20	197/144
Weight: 97 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3
OTHERS 2x4 SP No.3

BRACING-
TOP CHORD
Structural wood sheathing directly applied or 4-1-4 oc purlins.
BOT CHORD
Rigid ceiling directly applied or 9-10-14 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size)

2	=	740/0-3-8 (min. 0-1-8)
6	=	740/0-3-8 (min. 0-1-8)
Max Horz		
2	=	-235(LC 10)
Max Uplift		
2	=	-73(LC 12)
6	=	-73(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD
2-3=-1972/330, 3-4=-1488/13, 4-5=-1519/55, 5-6=-1889/169
BOT CHORD
2-8=-341/1824, 6-8=-68/1564
WEBS
4-8=0/1798, 5-8=-513/439, 3-8=-524/403

NOTES-
1) Unbalanced roof live loads have been considered for this design.


- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) Truss designed for wind loads in the plane of the truss only. For studs exposed to wind (normal to the face), see Standard Industry Gable End Details as applicable, or consult qualified building designer as per ANSI/TPI 1.
- 4) Gable studs spaced at 2-0-0 oc.
- 5) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 6) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 7) Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 8) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 6. This connection is for uplift only and does not consider lateral forces.
- 9) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

Job 2100164-2100164A	Truss S2	Truss Type Scissor	Qty 12	Ply 1	JONATHAN VANN
-------------------------	-------------	-----------------------	-----------	----------	---------------

84 Components, Dunn, NC 28334

8.400 s Apr 7 2020 MiTek Industries, Inc. Thu Feb 4 07:33:24 2021 Page 1
ID:vGwN7Ka7AT2xVsnzUzNwxAzobnf-9ufm_58Q0oAnsXaZ_sgx7A0AS6J6slLGQc1p4bzoblf



Scale = 1:69.9

Plate Offsets (X,Y)-- [2:0-1-4,Edge], [6:0-1-4,Edge]					
LOADING (psf)	SPACING- 2-0-0	CSI.	DEFL. in (loc) l/defl L/d	PLATES	GRIP
TCLL 20.0	Plate Grip DOL 1.15	TC 0.34	Vert(LL) -0.15 8-14 >999 240	MT20	197/144
TCDL 10.0	Lumber DOL 1.15	BC 0.69	Vert(CT) -0.33 8-11 >613 180		
BCLL 0.0 *	Rep Stress Incr YES	WB 0.68	Horz(CT) 0.34 6 n/a n/a		
BCDL 10.0	Code IRC2015/TPI2014	Matrix-MS		Weight: 89 lb	FT = 20%

LUMBER-
TOP CHORD 2x4 SP No.2 or 2x4 SPF No.2
BOT CHORD 2x4 SP No.2 or 2x4 SPF No.2
WEBS 2x4 SP No.3

BRACING-
TOP CHORD
Structural wood sheathing directly applied or 4-1-4 oc purlins.
BOT CHORD
Rigid ceiling directly applied or 9-10-14 oc bracing.

MiTek recommends that Stabilizers and required cross bracing be installed during truss erection, in accordance with Stabilizer Installation guide.

REACTIONS. (lb/size)

2	=	740/0-3-8 (min. 0-1-8)
6	=	740/0-3-8 (min. 0-1-8)
Max Horz		-235(LC 10)
2	=	
Max Uplift		-73(LC 12)
2	=	
6	=	-73(LC 13)

FORCES. (lb) - Max. Comp./Max. Ten. - All forces 250 (lb) or less except when shown.
TOP CHORD
2-3=-1972/330, 3-4=-1488/13, 4-5=-1519/55, 5-6=-1889/169
BOT CHORD
2-8=-341/1824, 6-8=-68/1564
WEBS
4-8=0/1798, 5-8=-513/439, 3-8=-524/403

NOTES-
1) Unbalanced roof live loads have been considered for this design.

- 2) Wind: ASCE 7-10; Vult=130mph (3-second gust) Vasd=103mph; TCDL=6.0psf; BCDL=6.0psf; h=30ft; Cat. II; Exp B; Enclosed; MWFRS (envelope) gable end zone and C-C Exterior(2) zone; cantilever left and right exposed; end vertical left and right exposed; C-C for members and forces & MWFRS for reactions shown; Lumber DOL=1.60 plate grip DOL=1.60
- 3) This truss has been designed for a 10.0 psf bottom chord live load nonconcurrent with any other live loads.
- 4) * This truss has been designed for a live load of 20.0psf on the bottom chord in all areas where a rectangle 3-6-0 tall by 2-0-0 wide will fit between the bottom chord and any other members.
- 5) Bearing at joint(s) 2, 6 considers parallel to grain value using ANSI/TPI 1 angle to grain formula. Building designer should verify capacity of bearing surface.
- 6) One H2.5A Simpson Strong-Tie connectors recommended to connect truss to bearing walls due to UPLIFT at jt(s) 2 and 6. This connection is for uplift only and does not consider lateral forces.
- 7) This truss is designed in accordance with the 2015 International Residential Code sections R502.11.1 and R802.10.2 and referenced standard ANSI/TPI 1.

LOAD CASE(S)
Standard

